

Line No.	ITEM	TYPE	TOTALS (FT)
1	20/20	1/C 500 KCMIL (35W MIN) CPT CU 0.420" EPR, 133% INSUL. LEVEL, 105C INSULATION DIAMETER: MIN: 1.570" MAX: 1.675" 15X0.025"X0.175" CU CN FLAT STRAPS 0.080" LLDPE JKT 35 KV RATED, EMPOWR® CUSTOMER NAME: INDUSTRY STANDARD CUSTOMER SPEC: INDUSTRY STANDARD CUST PART NO.: NONE INDUSTRY SPEC: AEIC CS8-20, ICEA S-94-649	57,009
2	30/30	1/C 750 KCMIL (58W MIN) CPT CU  0.220" EPR, 133% INSUL. LEVEL, MV-105  INSULATION DIAMETER: MIN: 1.370" MAX: 1.460"  24X10 AWG CU CN WIRES, SEP TAPE  0.080" PVC JKT	25,334
3	NEW	Cable, 35kV, 1/C 350KCMIL CU, CN Flat Strap	930

BHMG/ City of Rochelle MV Cable

Wesco/ Anxiter Inc. Sourcewell Contract 091422-WES

51 Prairie Parkway Gilberts, IL 60136

Aaron Formanek - 630-338-6977

aaron.formanek@anixter.com/ Yari.Hatulla@anixter.com

\* All quoted pricing is subject to metals adjustments upon the discretion of the manufacturer.

\* Availability is subject to change due to prior sales

Wesco Terms and Conditions of Sale published at [wesco.com/termsofsale](http://wesco.com/termsofsale) are e:

PROJECT USE	Wesco/Anixter	Description	Cost/FT
Sub 35kV UG Feeder Exits, 35kV UG dips (RR/hwy crossings)	<b>61658501 (Southwire) ( 57 x 1000' reels +5%/-0% Tolerances)</b>	1/C 35kv 500 mcm 35 strand Moisture Blocked Copper Conductor 100% EPR Insulation Concentric Neutral Longitudinally Blocked lldPE Jacket 1000' Reels	\$ 20.24
Sub 15kV UG Feeder Exits, 15kV UG dips (RR/hwy crossings), 15kV UG Switchgear-transformer low side ties, Multiple In House Distribution Projects	<b>Southwire 62149815 (+/-10% tolerances)</b>	MVI 750CR MBCu 15KV220E 11x14 PE 750-61 MB CPRESS CU 15KV 220 mils 133% EPR 105C 11x14CN POLY JACKET	\$ 27.76
35kV UG Switchgear Transformer high side ties	<b>512698 (Prysmian) (1 reel x 1000' +/-10%)</b>	3x1/C 46kv PowerPak 350 Cu, 100% EPR Insul. 21 x .030"x.175" Tinned Cu Flat Stap, PP Jacket	\$ 46.53

specs attached

xpressly incorporated into and shall govern this transaction

Extended	Lead time	Reel Deposit
\$ 1,153,862.16	In Stock: 2-6 Weeks or as needed & can be invoiced as needed. No Esc/De-escalations ARO. Frt. Allowed	No Reel Deposit; Deferred 1 year
\$ 703,271.84	26-28 weeks ARO plus transit. Firm until 1/14/26. Frt Allowed	None
\$ 46,530.00	In Stock: 2-4 Weeks as Is. Could be re reeled as Single Conductor in Alsip to 3 x 1000' 6-8 weeks + Cut/Reel Charges & frt +. No Escalation/De-escalations ARO.	None if returned within 1 year in good condition. REEL Deposit \$2,880

frt allowed