

UPPER PLAYGROUND RETAINING



Demo Work:

- Remove 50 LF of existing stone wall and gabions

Earth Work:

- Partially level upper area, combo of DG and exist'g grass; maintain access for maintenance to back fields.

Rock Work:

- Provide roughly 125 LF of 6-10" limestone quarry "pancake" boulders for retaining, incorporate two sets of gradual steps; consider tiering between upper and lower levels; overall distance about 85ft.
- Create two shallow rock basins (min 8" depth, 3'- 5' dia.) with river rock fill to capture and filter water from downspouts.

Plants:

- Provide 15 1 gal. native plantings that do well in semi-shade: muhly, rosemary, soft yucca, artemisia, golden groundsel, bulbine, etc.
- Drip irrigation for new plants

