

KMI Sports Construction

7070 US 290

Dripping Springs, TX, 78620

512-962-3955

info@kmisportsconstruction.com

www.KMIconnect.com

Instagram: @KMITurf - Facebook: @KMIIsports



| | | | | | |
|--|--|----------|---------------------------------|-----------|-------------|
| Date | 1/3/2023 | | Quote# | 11171VCv3 | |
| Bill to Address: | | | Remit to Address: | | |
| Name | WHLL - Hatley Infield Dirt/Grass | | 7070 US 290 | | |
| Address | 1314 Exposition Blvd Austin TX 78703 | | Dripping Springs, TX, 78620 | | |
| Email & Phone | 512-695-6709 - atxbta@gmail.com - Brandon Aghamalian | | info@kmisportsconstruction. com | | |
| Payment Terms: Deposit required to secure a spot on our schedule, remaining balance due at the time the job is completed | | | | | |
| Item # | Materials | Quantity | UOM | | |
| | Hatley Infield Dirt - Phase 1 - After Approved Jan 18th, 2023 | | | | |
| 1 | Clean and remove all of the overgrown grass from the existing dirt infield area and the home plate circle. | | | | |
| 2 | Re-shape / clean up the infield/outfield dirt and grass radius | | | | |
| 3 | Re-shape / clean up all of the lines on the infield dirt/grass edges | | | | |
| 4 | Nail drag all of the dirt surfaces | | | | |
| 5 | Add needed baseball field dirt (Elgin Facility), groom, roll and regrade the infield Sandy loam and red clay, mixed at the factory | | | | |
| 6 | Remove any lips from the grass to dirt areas | | | | |
| | Total Phase 1 - After Approved Jan 18th, 2023 | | | | \$13,929.44 |
| | | | | | |
| | Hatley Infield Dirt - Phase 2 After the 2023 Spring Season | | | | |
| 7 | Remove all of the infield grass | | | | |
| 8 | Add new soil conditioner, regrade and compact | | | | |

| | | | | | |
|----------------------------------|--|--|----------------------------|--------------------------|--------------------------|
| 9 | Add new Bermuda sod to the infield | | | | |
| 10 | Add sand to top dress the sod and seams | | | | |
| | Total Phase 2 - After the 2023 Spring Season | | | Approx Range | \$6,850 - \$7,850 |
| | | | | | |
| | Please Note - Phase 2 work is an estimate based on today's pricing. | | | | |
| | | | | | |
| Mobilization | If KMI is scheduled and confirmed to work on a project site and travels to the site and the site is not ready and/or other trades are in the project area preventing work to start, there will be a remobilization charge. | | | Subtotal | \$21,779.44 |
| 15 day expiration | This quote expires in 15 days. After which, we will need to reassess costs, supplies, and material available. | | | Deposit | \$13,067.66 |
| Financing | KMI now offers financing for all commercial projects, ask us today for more details | | | Due at Completion | \$8,711.78 |
| Customer Signature: _____ | | | Total Project Price | | \$21,779.44 |