



We Love Trees

Rollingwood - Oak wilt trenching proposal (phase one)

#9242

Trenching	\$25/ foot	450 ft	\$11,250
Trencher Delivery			\$1200
Curb cut and repair	\$1200	x3	\$3600
Wrought iron remove and install	\$500	x1	\$500
Remove and haul trees (clear path)	\$2000	x4	\$8000
Backyard sprinkler locate and repair	\$2500	x1	\$2500
Front fence remove and replace	\$2500	x1	\$2500
Traffic director	\$500	x1	\$500
		Subtotal	\$30,050
Hand dig utilities 48" (pothole)	\$1500 ea	TBD	
Saw teeth (estimate 50)	\$8.75 ea	TBD	
		Tax 8.25%	

Operation of the rubber tire rock saw trencher will be completed by Matt Sanders, owner. Trench depth will be 54" and auto backfilled. I will also oversee the project from start to finish. Utilities and sprinklers will be located and pre-dug (each yard to demonstrate working system). No grass, plant or spoil removal/restoration is included, but WLT can offer these services as well. It is recommended the soil has a chance to compact before repairing grass, etc. At completion the actual trench footage will be measured and billed for. Lead time is 4-6 weeks from contracting. Installation will take approximately ten business days, weather permitting. Pricing valid for 30 days. We do not require any deposit. Final payment by check.

Proof of GL insurance will be provided.