

# KMI Sports Construction

7070 Hwy 290 W

Dripping Springs, TX, 78620

512-962-3955

info@kmisportsconstruction.com

[www.KMIconnect.com](http://www.KMIconnect.com)

Instagram: @KMITurf - Facebook: @KMIsports



Date	5/12/2022
<b>Bill to Address:</b>	
Name	Chris Smith
Address	1200 W. Cesar Chavez St, Austin TX 78703
Email & Phone	512-922-5431 - chad.smith@streamrealty.com

<b>Quote# 2022-04051222</b>
<b>Remit to Address:</b>
7070 US HWY 290 W.
Dripping Springs, TX, 78620
info@kmisportsconstruction.com

**Payment Terms:** Deposit required to secure a spot on our schedule, remaining balance due at the time the job is completed

Item #	Materials	Quantity	UOM		
<b>Hatley Infield Turf Project</b>					
1	KMI to excavate and remove all of the existing dirt and grass from the field, approx 10,849 sq ft	10849	Square Feet		
2	KMI to provide and install 2"x2" composite nailer boards around the perimeter of the infield, this nailer board is used to secure the turf down around the edges	400	Linear Feet		
3	KMI to provide and install a 4" perforated drainage system throughout the infield, the pipe will exist the field at the lowest point and daylight drain	750	Linear Feet		
4	KMI to provide and install 6mil Plastic Barrier on the sub-base	10849	Square Feet		
5	KMI to provide #57 & #67 clean aggregate for the drainage ditches and the field final grade rock	23	Tons		
6	KMI to install, level and compact the #57 & #67 aggregate into the drainage ditches and on the field	170	Tons		
7	KMI to provide and install SBR rubber and sand mixture as the infill	32547	Lbs		
8	KMI to provide and install Power House 40oz Green and Terra-Cotta Power House 2" pile height White inlaid foul lines and batters boxes	10849	Square Feet		
9	One set of base anchors and bases, one home plate, one pitching rubber	1	Each		
10	Build a permanent artificial turf mound. If you would like a portable mound, I can provide you with our recommendations on which mound to purchase	1	Each		
11	Cleanup the site of all debris and garbage	1	Each		
Warranty	KMI provides warranty that covers seams, base work, perimeter edging and nailer boards for 3 years. The turf is covered for 8 years for the date of the install.			<b>Sub Total</b>	<b>\$97,212.87</b>
Maintanace	Mainanace of Artificial turf is as simple as making sure there is enough infill in high traffic areas. Neglecting to maintain high traffic areas voids warranty of turf. Fill with sand when necessary.			<b>Deposit</b>	<b>\$48,606.44</b>
15 day expiration	This quote expires in 15 days. After which, we will need to reaccess costs, supplies, and material available.			<b>Due at Start of Construction</b>	<b>\$11,665.54</b>
Financing	<b>KMI now offers financing for all commerical projects, ask us today for more details</b>			<b>Due at Completion</b>	<b>\$36,940.89</b>
<b>Customer Signature: _____</b>				<b>Total Project Price</b>	<b>\$97,212.87</b>