

MICHAEL WILLIAMS MASONRY, LLC

3409 El Dorado Trail

Austin, Texas 78739

TO: Kevin Glasheen

RE: Rollingwood Park, Austin, Tx. 78746

For the work we discussed, I will supply labor, tools, and materials to remove the flat stone in the path and install a drain pipe from the wall to the outside of the path, then relay the stone on the path.

I will prep the ground for approximately seventy (70) linear feet of boulder stones, approximately 2' tall x 18" wide x 44" long and lay the stones.

I will install a French drain the full length of the wall, wrap the pipe with filter cloth then cover with gravel. Demo the stone basket and rebuild it about fifty (50) ft. down the wall, then backfill the wall to grade with sandy loam the full length of the wall. This is for a total of \$31,600.00.