

**Northern Contracting, Inc.**  
**1851 Coltonville Rd.**  
**Sycamore, IL 60178**  
**Ph: 815-895-5855 Fax: 815-895-2117**  
 richard@northerncontracting.net

# Quotation

**Quotation for: Village of Roscoe**  
 attn: Ms. Christine King  
 Re: Guardrail damage on Willowbrooke Rd north of McCurry Rd. Repair  
 damaged SKT, TBT-TIS terminal.

**Date** 1/29/2026  
**Quotation #**  
**Quotation valid until:** 2/23/2026

Page # 1

*Northern Contracting, Inc. is pleased to quote the following cost necessary  
 to provide materials, labor & equipment to complete this project.*

Item #	Description	UM	Qty	Cost	Total
	Material:				
	12 ga. X 12'-6" SKT anchor panel		1	\$ 201.67	\$ 201.67
	12'-6" x 12 ga panel		1	\$ 104.27	\$ 104.27
	SKT extruder		1	\$ 1,112.15	\$ 1,112.15
	5 1/2 x 7 1/2 x 45" wood breakaway post		2	\$ 34.00	\$ 68.00
	6 x 8 x 14" non-routed block		1	\$ 8.50	\$ 8.50
	5/8 x 10" post bolt nut and washer		2	\$ 4.02	\$ 8.04
	3/8 x 4" galvanized lag bolt		2	\$ 1.20	\$ 2.40
	5/8 x 1 1/4" splice bolt		16	\$ 0.49	\$ 7.84
	5/8" hex nut		19	\$ 0.50	\$ 9.50
	5/8 x 18" post bolt		1	\$ 4.75	\$ 4.75
	18 x 18" terminal marker DA		1	\$ 22.20	\$ 22.20
	Materials total:				\$ 1,549.32
	Labor to remove the cable anchor assembly and salvage for reuse.				
	Remove the damaged extruder, bent panels and wood post plus cut the broken off wood stubs from the steel ground sleeves. Install new wood breakaway post into the steel sleeves, hang and bolt up all components plus reinstall the cable anchor assembly and tension same, complete repair of the damage.				\$ 1,357.60
	Equipment:				
	Two ton truck				\$ 105.00
	Chain saw and blade				\$ 55.00
	signage				\$ 25.00
	Equipment total:				\$ 185.00
	Quote total for repair:				\$ 3,091.92