

---

# Durascape Improvements

177 Flora Church Rd  
Kirkland, IL 60146

Jesus Esquivel      A.J. Esquivel  
(815) 997-6229      (815) 520-0327

## Proposal

**March 20, 2025**

Village of Roscoe  
10631 Main St.  
Roscoe, IL 61073

**We hereby submit specifications and estimates to:**

1. Remove & Replace retaining wall approximately 60ft x 5 ft.
2. Address Gravel (Road Stone) base as needed approximately 4 inches. Excavate & compact as needed.
3. Haul away old brick and dispose.
4. Install new retaining wall with 80 lb block 5-6 layers, as needed along with down step effect as needed, finish with wall with caps.
5. Install plastics, geogrids and drain tile as needed.
6. Back fill with stone chips for better drainage.
7. Clean site from project debris, haul and dispose.
8. Install & provide dirt around the project area for restoration, as needed.
9. Install seed & straw blanket, as needed, and clean the site.

**We propose hereby to furnish material and labor - complete in accordance with the above specifications for the sum of:**

\$ 3,500 ( three thousand five hundred)(1 & 3 ( Removal.) \$ 16,000( sixteen thousand )(2-6 Rebuild,) \$2,500 (two thousand five hundred)(7-9 Project Restoration.)

Total: \$22,000 ( Twenty two thousand).

Any additional work will be extra and added to the final sum. Signing of this Document acts as a binding Contract

## Acceptance of Proposal

Signature:\_\_\_\_\_ Date:\_\_\_\_\_ Print\_\_\_\_\_

Signature:\_\_\_\_\_ Date:\_\_\_\_\_ Print\_\_\_\_\_