



***Fritzel's Landscaping***

13416 Farm School Rd.  
Durand, IL 61024  
**815-248-2601**

Village of Roscoe  
Anthony Ford  
10631 Main St.  
Roscoe, IL 61073

3/18/2025

Take down the existing limestone retaining wall on the north/east side of the building. We will stack the limestone pieces on pallets provided by the customer.

4,980.00

4,980.00

Excavate for the new block retaining wall. Remove any existing base rock, haul away and dispose of the material.

2,300.00

2,300.00

Please sign and return.

**Subtotal**

\$7,280.00

\$7,280.00

Date: \_\_\_\_\_

Accepted By: \_\_\_\_\_



**Fritzel's Landscaping**

13416 Farm School Rd.  
Durand, IL 61024  
**815-248-2601**

Village of Roscoe  
Anthony Ford  
10631 Main St.  
Roscoe, IL 61073

3/18/2025

Install a minimum of 8" of gravel base for the new block retaining wall and compact. Install the retaining wall to match the same footprint as the existing wall. The blocks and caps will be Rochester Cement Products Classic 8" DOT straight face blocks with 4" Universal caps adhered to the top. Behind the wall we will install clean gravel chips, a filter fabric and 4" perforated drain tile with a sock. Total length of the wall is 105', ranging from 1' to 40" in height.

23,190.00

23,190.00

Install topsoil as needed to repair any damage done during construction. Finish grade, seed and cover all areas with straw netting.

1,775.00

1,775.00

Note: Winnebago County prevailing wage rate's will be paid to employees.

50% deposit due on delivery of materials, balance due on completion.

**Subtotal**

\$24,965.00

\$24,965.00

Date: \_\_\_\_\_

Accepted By: \_\_\_\_\_