

Prepared for:



City of Sanger

---

# ROADWAY IMPACT FEE STUDY

July 2024

City of Sanger  
Roadway Impact Fee Study



July  
2024

Prepared for the City of Sanger

Prepared by:

**Kimley»Horn**

Kimley-Horn and Associates, Inc.

801 Cherry Street, Suite 1300, Unit 11

Fort Worth, TX 76102

Phone 817 335 6511

TBPE Firm Registration Number: F-928

Project Number: 061322303

© Kimley-Horn and Associates, Inc.



7/12/24

*Brandon Forsythe*





## TABLE OF CONTENTS

|           |                                                                 |           |
|-----------|-----------------------------------------------------------------|-----------|
| <b>1.</b> | <b>Executive Summary .....</b>                                  | <b>1</b>  |
| A.        | Introduction.....                                               | 1         |
| B.        | Impact Fee Basics.....                                          | 1         |
| C.        | Impact Fee Calculation.....                                     | 3         |
| D.        | Chapter 395 Required Adoption Process.....                      | 4         |
| E.        | Collection and Use of Roadway Impact Fees.....                  | 4         |
| <b>2.</b> | <b>Introduction .....</b>                                       | <b>5</b>  |
| <b>3.</b> | <b>Land Use Assumptions.....</b>                                | <b>7</b>  |
| A.        | Purpose and Overview.....                                       | 7         |
| B.        | Land Use Assumptions Methodology.....                           | 8         |
| C.        | Impact Fee Service Area.....                                    | 8         |
| D.        | Data Format.....                                                | 10        |
| E.        | 10-Year Growth Summary .....                                    | 10        |
| F.        | Land Use Assumptions Summary .....                              | 11        |
| <b>4.</b> | <b>Capital Improvements Plan .....</b>                          | <b>12</b> |
| <b>5.</b> | <b>Methodology For Roadway Impact Fees.....</b>                 | <b>15</b> |
| A.        | Service Area .....                                              | 15        |
| B.        | Service Units.....                                              | 15        |
| C.        | Cost Per Service Unit.....                                      | 16        |
| D.        | Capital Improvements Plan Costing Methodology.....              | 16        |
| E.        | Summary of Capital Improvements Plan.....                       | 19        |
| F.        | Service Unit Calculation.....                                   | 21        |
| <b>6.</b> | <b>Roadway Impact Fee Calculation.....</b>                      | <b>25</b> |
| A.        | Maximum Assessable Impact Fee Per Service Unit.....             | 25        |
| B.        | Plan for the Roadway Impact Fee Credit.....                     | 27        |
| C.        | Service Unit Demand Per Unit of Development.....                | 29        |
| <b>7.</b> | <b>Sample Calculations.....</b>                                 | <b>32</b> |
| <b>8.</b> | <b>Adoption and Administration of Roadway Impact Fees .....</b> | <b>33</b> |
| A.        | Adoption Process.....                                           | 33        |
| B.        | Collection and Use of Roadway Impact Fees.....                  | 33        |
| <b>9.</b> | <b>Conclusions.....</b>                                         | <b>34</b> |



## LIST OF EXHIBITS

|            |                                |    |
|------------|--------------------------------|----|
| Exhibit 1. | Roadway Service Area Map ..... | 9  |
| Exhibit 2. | Capital Improvements Plan..... | 14 |

## LIST OF TABLES

|           |                                                                               |    |
|-----------|-------------------------------------------------------------------------------|----|
| Table 1.  | Residential and Non-Residential Growth Projections (2024 – 2034) .....        | 10 |
| Table 2.  | Capital Improvements Plan.....                                                | 13 |
| Table 3.  | Service Volumes for Proposed Facilities .....                                 | 15 |
| Table 4.  | Service Volumes for Existing Facilities.....                                  | 16 |
| Table 5.  | 10-Year Capital Improvements Plan with Conceptual Level Cost Projections..... | 20 |
| Table 6.  | Transportation Demand Factor Calculations .....                               | 23 |
| Table 7.  | 10-Year Growth Projections.....                                               | 24 |
| Table 8.  | Maximum Assessable Roadway Impact Fee Computation.....                        | 25 |
| Table 9.  | Maximum Assessable Roadway Impact Fee Computation (continued) .....           | 27 |
| Table 10. | Maximum Assessable Roadway Impact Fee .....                                   | 28 |
| Table 11. | Land Use / Vehicle-Mile Equivalency Table (LJVMET) .....                      | 30 |
| Table 12. | Maximum Assessable Roadway Impact Fee Per Service Unit (Vehicle-Mile) .....   | 34 |

## LIST OF APPENDICES

|                                                                |
|----------------------------------------------------------------|
| Appendix A – Conceptual Level Project Cost Projections         |
| Appendix B – Capital Improvements Plan Service Units of Supply |
| Appendix C – Existing Roadway Facilities Inventory             |



# 1. EXECUTIVE SUMMARY

## A. INTRODUCTION

Impact fees are a mechanism for funding the public infrastructure necessitated by new development. Across the country, they are used to fund police and fire facilities, parks, schools, roads, and utilities. In Texas, the legislature has allowed their use for water, wastewater, roadway, and drainage facilities. Historically, they have been used to fund both public water, wastewater, and roadway improvements in the City of Sanger.

In the most basic terms, impact fees are meant to recover the incremental cost of the impact of each new unit of development creating new infrastructure needs. In the case of roadway impact fees, the infrastructure need is the increased capacity on arterial and collector roadways that serve the overall transportation system. The purpose of the 2024 Roadway Impact Fee Study is to identify the fee per unit of new development necessary to fund these improvements in accordance with the enabling legislation, Chapter 395 of the Texas Local Government Code.

## B. IMPACT FEE BASICS

Roadway impact fees are determined by several key variables, each described below in greater detail.

### Impact Fee Study

The primary purpose of the 2024 Roadway Impact Fee Study is to determine the maximum impact fee per unit of new development chargeable as allowed by the state law. This determination is not a recommendation; the actual fee amount ultimately assessed is at the discretion of the Sanger City Council, so long as it does not exceed the maximum assessable allowed by law. The study looks at a period of 10 years to project new growth and corresponding capacity needs, as required by state law. The study (and corresponding maximum fees) must be restudied at least every five years. However, the study can be updated at any time to accommodate significant changes in any of the key variables of the impact fee equation.

### Service Areas

A service area is a geographic area within which a unique maximum impact fee is determined. All fees collected within the service area must be spent on eligible improvements within the same service area. For roadway impact fees, the service area may not exceed 6 miles. Considering this restriction, the entire corporate boundary of the City of Sanger is proposed to be evaluated as one (1) service area.



## Land Use Assumptions

The maximum roadway impact fee determination is required to be based on the projected growth and corresponding capacity needs in a 10-year window. This study considers the years 2024-2034.

To project future development in the 10-year window, growth assumptions were made based on the City of Sanger 2040 Comprehensive plan, parcel data, historical census data, existing and future known development characteristics, and input from City of Sanger staff. Acknowledging that development is ongoing and changing constantly, this study is based on conditions as they were on December 20, 2023.

In order to arrive at a reasonable projection of growth, existing residential and non-residential estimates were obtained using parcel data and aerial survey of existing developments. For the remaining undeveloped areas, assumptions were utilized based upon City of Sanger 2040 Comprehensive Plan, historical growth projections, and known planned developments. Consultation with City staff helped with finalizing the growth assumptions.

## Capital Improvements Plan

The Capital Improvements Plan (CIP) is the list of projects eligible for funding through impact fees. Only those capacity improvements included in the City's Future Thoroughfare Plan are included in the CIP. Capacity improvements may include the widening of an existing roadway, addition of lanes, or the construction of a new roadway. Resurfacing or other maintenance activities do not qualify as capacity improvements under impact fee laws in Texas.

The cost of the CIP is one of the fundamental factors in the calculation of the per-unit maximum impact fee. The CIP's cost was calculated through systematic evaluation of each eligible project. The presence of any special conditions (such as the need for significant drainage improvements or railroad crossings) and whether various additional construction costs were applicable (such as construction phase traffic control) were considered. In determining project limits, the team identified roadway segments with uniform need. The team utilized a standard methodology for estimating construction costs. Referencing multiple roadway projects in Sanger's vicinity, uniform costs were determined for the major items of work, additional construction items, and project delivery costs. Chapter 4 provides a listing of the 10-Year CIP in **Table 2** and map of the CIP in **Exhibit 2**. Finally, detailed cost projections by project can be found in **Appendix A**. It should be noted that these cost projections are based on conceptual level planning and are subject to refinement upon final design.

Only the projects listed in the CIP are eligible to utilize impact fee funds. Only the costs associated with providing the additional capacity necessitated by 10 years of growth can be used to calculate the maximum impact fee.





In order to calculate the maximum impact fee, the total cost of the CIP was reduced to account for:

- The portion of new capacity that will address existing needs, and
- The portion of new capacity that will not be necessitated until beyond the 10-year growth window.

A ratio that compares 10 years' demand for capacity to the net supply of capacity (total new capacity in the CIP minus existing needs) can be calculated. This ratio, which may not exceed 100%, is then applied to the cost of the net capacity supplied. The result is a determination of the costs attributable to the next 10 years' growth, which is then used to calculate the maximum impact fee in accordance with state law. The result is known as the Cost of the CIP Attributable to New Growth Between 2024-2034 (i.e. recoverable portion of the CIP):

| SERVICE AREA:                                     | SANGER         |
|---------------------------------------------------|----------------|
| COST OF CAPACITY ADDED ATTRIBUTABLE TO NEW GROWTH | \$ 220,690,065 |

### Service Units

The impact fee law defines a service unit as follows: "Service Unit means a standardized measure of consumption attributable to an individual unit of development calculated in accordance with generally accepted engineering or planning standards and based on historical data and trends applicable to the political subdivision in which the individual unit of development is located during the previous 10 years"

The 2024 Roadway Impact Fee Study defines vehicle-miles as the service unit. Based on the City's 10-year growth projections, the associated demand (consumption) value in vehicle-miles is as follows:

| SERVICE AREA:                            | SANGER |
|------------------------------------------|--------|
| TOTAL VEH-MI OF NEW DEMAND OVER 10 YEARS | 47,852 |

### C. IMPACT FEE CALCULATION

The maximum impact fee allowable in the service area is then calculated by dividing the Cost of the CIP Attributable to New Growth by the projected vehicle-miles of demand in the service area in the above table. The resulting value is multiplied by 50% to account for ad valorem credits.

Below is the listing of the 2024 Roadway Impact Fee Study's Maximum Assessable Impact Fee Per Service Unit (Vehicle-Mile):

| SERVICE AREA:                                       | SANGER   |
|-----------------------------------------------------|----------|
| MAX ASSESSABLE FEE PER SERVICE UNIT (\$ PER VEH-MI) | \$ 2,305 |



## **D. CHAPTER 395 REQUIRED ADOPTION PROCESS**

Chapter 395 of the Texas Local Government Code stipulates a specific process for the adoption of roadway impact fees. A Capital Improvements Advisory Committee (CIAC) is required to review the Land Use Assumptions and CIP used in calculating the maximum fee, and to provide the Committee's findings for consideration by the City Council. This CIAC also reviews the roadway impact fee ordinance and provides its findings to the City Council. The composition of the CIAC is required to adequately represent the building and development communities. The City Council then conducts a public hearing on the Land Use Assumptions, CIP, and roadway impact fee ordinance.

Following policy adoption, the CIAC is tasked with advising the City Council of the need to update the Land Use Assumptions or the CIP at any time within five years of adoption. Finally, the CIAC oversees the proper administration of the roadway impact fee, once in place, and advises the City Council as necessary.

## **E. COLLECTION AND USE OF ROADWAY IMPACT FEES**

Roadway impact fees are assessed when a final plat is recorded. The assessment defines the impact of each unit at the time of platting, according to land use, and may not exceed the maximum impact fee allowed by law. Roadway impact fees are collected when a building permit is issued. Therefore, funds are not collected until development-impacts are introduced to the transportation system. Funds collected within a service area can be used only within the same service area. Finally, fees must be utilized within 10 years of collection, or must be refunded with interest.



## 2. INTRODUCTION

Chapter 395 of the Texas Local Government Code describes the procedure political subdivisions must follow in order to create and implement impact fees. Chapter 395 defines an Impact Fee as “a charge or assessment imposed by a political subdivision against new development in order to generate revenue for funding or recouping the costs of capital improvements or facility expansions necessitated by and attributable to the new development.”

Accordingly, the City of Sanger has developed its Land Use Assumptions and Capital Improvements Plan with which to implement roadway impact fees. The City has retained Kimley-Horn and Associates to provide professional transportation engineering services for the 2024 Roadway Impact Fee Study. This report includes details of the roadway impact fee calculation methodology in accordance with Chapter 395, the applicable Land Use Assumptions, development of the Capital Improvements Plan, and refinement of the Land Use / Vehicle-Mile Equivalency Table.

This report introduces and references two of the basic inputs to the roadway impact fee:

1. **Land Use Assumptions**
2. **Capital Improvements Plan**

Information from the Land Use Assumptions and Capital Improvements Plan are used extensively throughout the remainder of the report.

There is a detailed discussion of the methodology for the computation of impact fees. This discussion is broken into three components:

1. **Methodology for Roadway Impact Fees**
2. **Roadway Impact Fee Calculation**
3. **Plan for the Roadway Impact Fee Credit**

The components of the **Methodology for Roadway Impact Fees** include development of:

- Service Area
- Service Units
- Cost Per Service Unit
- Capital Improvements Plan Costing Methodology
- Summary of Capital Improvements Plan
- Service Unit Calculation





The **Roadway Impact Fee Calculation** includes the determination of the:

- Maximum Assessable Impact Fee Per Service Unit
- Service Unit Demand Per Unit of Development

The **Plan for the Roadway Impact Fee Credit** outlines a 50% reduction of the Capital Improvements Plan as outlined in Chapter 395 of the Texas Local Government Code.

The final chapter of the report is the Conclusion, which presents the findings of the analysis and summarizes the report.



### 3. LAND USE ASSUMPTIONS

#### A. PURPOSE AND OVERVIEW

Chapter 395 of the Texas Local Government Code describes the procedure Texas political subdivisions must follow in order to assess impact fees for new development. The first step required in updating impact fees is the development of Land Use Assumptions. These Land Use Assumptions, which include both residential and non-residential estimates, form the basis for the development of impact fees for roadway facilities.

Reasonable future growth estimates are necessary in order to aid the City of Sanger in establishing the need for roadway projects required to serve future development. In accordance with Chapter 395, Kimley-Horn has compiled the information required to complete the Land Use Assumptions using the following sources:

- City of Sanger 2040 Comprehensive Plan;
- Parcel Data Information from Denton Central Appraisal District;
- Historical Census Data;
- Aerial Overview of City Development Potential; and
- City of Sanger Staff.

The Land Use Assumptions include the following components:

1. **Land Use Assumptions Methodology** – Overview of the general methodology used to generate the land use assumptions.
2. **Impact Fee Service Area** – Determination of the Sanger service area for roadway impact fees.
3. **Data Format** – Discussion into the categorical groupings assumed for roadway impact fees.
4. **10-Year Growth Summary** – Data on residential and non-residential growth within each service area over the next 10 years (2024-2034).
5. **Land Use Assumptions Summary** – Synopsis of the land use assumptions.



## **B. LAND USE ASSUMPTIONS METHODOLOGY**

The residential and non-residential growth projections formulated in this chapter were done using reasonable and generally accepted planning principles. The following factors were considered in developing these projections:

- Character, type, density, and quantity of existing development;
- Known planned developments;
- Location of vacant land;
- Historical population growth; and
- Input from City of Sanger staff.

Existing residential and non-residential data was compiled using parcel data and aerial survey of existing developments. For the remaining undeveloped areas, assumptions were utilized based upon City of Sanger 2040 Comprehensive Plan, historical growth projections, and known planned developments. Consultation with City staff helped with finalizing the growth assumptions.


## **C. IMPACT FEE SERVICE AREA**

According to Chapter 395 of the Local Government Code, a service area refers to the area within the corporate boundaries or extraterritorial jurisdiction of the political subdivision to be served by the capital improvements or facilities specified in the impact fee. Funds collected in the specific service areas must be spent in the service area collected.


The geographic boundary of the proposed impact fee service area for roadway facilities is shown in **Exhibit 1**. The roadway service area covers the entire corporate boundary of the City of Sanger. Chapter 395 of the Texas Local Government Code specifies that “the service area is limited to an area within the corporate boundaries of a political subdivision and shall not exceed six (6) miles”

The City of Sanger is proposed to be considered as one (1) service area for roadway impact fee purposes. For roadway facilities, the service area is limited to those areas within the current corporate limits. Therefore, areas within the extraterritorial jurisdiction (ETJ) are excluded from the study.





# **Exhibit 1** **Roadway Service Area Map**



## **Legend**

- Service Area
- ETJ
- Railroads

- Thoroughfare Plan Network
- Local Roads





## D. DATA FORMAT

The residential and non-residential estimates were all compiled in accordance with the following categories and format:

- Residential Units – Number of dwelling units, both single-family and multifamily.
- Non-Residential Units – Square feet of building area based on three (3) different classifications:
  - Basic: Land use activities that produce goods and services, including those that are exported outside the local economy (i.e. manufacturing, construction, transportation, wholesale, trade, warehousing, and other industrial uses).
  - Service: Land use activities which provide personal and professional services such as government and other professional and administrative offices.
  - Retail: Land use activities which provide for the retail sale of goods that primarily serve households and whose location choice is oriented toward the household sector (i.e. grocery stores and restaurants).

## E 10-YEAR GROWTH SUMMARY

**Table 1** summarizes the residential and non-residential 10-year growth projections within the roadway service area. These projections were prepared based upon existing land use, anticipated future land use, and consultation with City staff.

**Table 1. Residential and Non-Residential Growth Projections (2024 – 2034)**

| Condition                     | Residential<br>(Dwelling Units) |              | Non-Residential<br>(Square Feet) |                |                  |
|-------------------------------|---------------------------------|--------------|----------------------------------|----------------|------------------|
|                               | Single-Family                   | Multifamily  | Basic                            | Service        | Retail           |
| 2023 (Existing)               | 3,228                           | 805          | 1,113,500                        | 978,500        | 1,620,000        |
| 2033 (3% Annual Growth)       | 4,338                           | 1,082        | 1,496,500                        | 1,315,000      | 2,177,000        |
| <b>Net Growth</b>             | <b>1,110</b>                    | <b>277</b>   | <b>383,000</b>                   | <b>336,500</b> | <b>557,000</b>   |
| Known Planned Developments    | 2,138                           | 1,160        | 2,071,000                        | 152,000        | 608,000          |
| <b>Total Projected Growth</b> | <b>3,248</b>                    | <b>1,437</b> | <b>2,454,000</b>                 | <b>488,500</b> | <b>1,165,000</b> |



## F. LAND USE ASSUMPTIONS SUMMARY

The following is a summary of the land use assumptions for roadway impact fees. The roadway land use assumptions are confined to growth projected within the City Limits. The 10-year (2024-2034) growth projections are:

- Residential
  - Single-Family = 3,248 Dwelling Units
  - Multifamily = 1,437 Dwelling Units
- Non-residential
  - Basic = 2,454,000 ft<sup>2</sup>
  - Service = 488,500 ft<sup>2</sup>
  - Retail = 1,165,000 ft<sup>2</sup>



## 4. CAPITAL IMPROVEMENTS PLAN

The City has identified the roadway projects needed to accommodate the projected growth within the City. The City of Sanger Future Thoroughfare Plan is the ultimate plan for the infrastructure within the City Limits. Only capacity improvements still needed to build out the Future Thoroughfare Plan to accommodate the expected growth within the next 10 years are included in the Capital Improvements Plan. The Capital Improvements Plan includes arterial and collector roadway facilities and consists of four (4) categories of projects. They are as follows:

- New – Any future roadway identified by the City to be included in the Capital Improvements Plan.
- Widening – Existing roadways not currently built to the ultimate classification in the Future Thoroughfare Plan and must be completely reconstructed.
- 1/3 Widening – Existing roadways that only have one-third of the ultimate cross section to be built.
- Construction – Roadway currently under construction which the City has contributed funds towards.

All the roadway facilities identified are part of the currently adopted Future Thoroughfare Plan. For costing purposes, four-lane divided cross sections are assumed for principal arterial facilities, four-lane undivided cross sections are assumed for minor arterial facilities, and two-lane undivided cross sections are assumed for collector facilities. A thoroughfare's costing assumptions may be assumed with an alternative cross section depending on existing adjacent facilities.


The proposed Capital Improvements Plan is listed in **Table 2** and mapped in **Exhibit 2**. The table shows the length of each project as well as the facility's impact fee classification. The Capital Improvements Plan was developed in conjunction with input from City of Sanger staff and represents those projects that will be needed to accommodate the growth projected in Chapter 3. Land Use Assumptions.




**Table 2. Capital Improvements Plan**

| Service Area | Proj. # | Roadway                       | Limits                                              | Project Type | Length (mi) | % In Service Area |
|--------------|---------|-------------------------------|-----------------------------------------------------|--------------|-------------|-------------------|
| Sanger       | 1       | North Metz to I-35 Connector  | 3,030' W of I-35 SBFR to I-35 SBFR                  | New          | 0.57        | 100%              |
|              | 2       | Chisam Rd                     | I-35 NBFR to 4,375' E of I-35 NBFR                  | Widening     | 0.83        | 100%              |
|              | 3       | Lois Rd W                     | 3,645' W of I-35 SBFR to I-35 SBFR                  | Widening     | 0.69        | 100%              |
|              | 4       | Lois Rd E (1)                 | I-35 NBFR to 525' E of I-35 NBFR                    | Widening     | 0.10        | 100%              |
|              | 5       | Lois Rd E (2)                 | 525' E of I-35 NBFR to 775' E of I-35 NBFR          | New          | 0.05        | 100%              |
|              | 6       | Lois Rd E (3)                 | 775' E of I-35 NBFR to 2,255' E of I-35 NBFR        | Widening     | 0.28        | 100%              |
|              | 7       | South Metz to I-35 Connector  | 4,935' W of I-35 SBFR to I-35 SBFR                  | New          | 0.93        | 100%              |
|              | 8       | Utility Rd                    | I-35 NBFR to 1,920' E of I-35 NBFR                  | Widening     | 0.36        | 100%              |
|              | 9       | Belz Rd                       | Metz Rd to I-35 SBFR                                | Widening     | 0.91        | 100%              |
|              | 10      | Indian Ln (1)                 | I-35 SBFR to FM 455                                 | New          | 1.07        | 100%              |
|              | 11      | Indian Ln (2)                 | 1,290' N of McReynolds Rd to McReynolds Rd          | Widening 1/3 | 0.24        | 100%              |
|              | 12      | Indian Ln (3)                 | McReynolds Rd to 3,365' S of McReynolds Rd          | New          | 0.64        | 100%              |
|              | 13      | FM 455 (1)                    | FM 2450 to 830' E of Marion Rd                      | Construction | 5.47        | 100%              |
|              | 14      | FM 455 (2)                    | 830' E of Marion Rd to 2,110' S of FM 2164          | Widening     | 2.84        | 100%              |
|              | 15      | Willow St                     | Cowling Rd to Indian Ln                             | Widening     | 0.95        | 100%              |
|              | 16      | McReynolds Rd                 | Indian Ln to 600' E of PR 6630                      | Widening     | 1.08        | 100%              |
|              | 17      | 5th St                        | Keaton Rd to I-35 SBFR                              | Widening     | 0.17        | 100%              |
|              | 18      | Cowling to Railroad Connector | Cowling Rd to Railroad Ave                          | New          | 0.52        | 100%              |
|              | 19      | Rector Rd                     | 2,730' W of Railroad Ave to Railroad Ave            | New          | 0.52        | 100%              |
|              | 20      | N Tejas Dr                    | 1,245' S of FM 455 to 1,490' N of Duck Creek Rd     | New          | 0.25        | 100%              |
|              | 21      | Jennifer Cir (1)              | Lois Rd W to Belz Rd                                | New          | 1.54        | 100%              |
|              | 22      | Jennifer Cir (2)              | Belz Rd to 1,555' S of Belz Rd                      | Widening     | 0.29        | 100%              |
|              | 23      | Jennifer Cir (3)              | 1,555' S of Belz Rd to Keith Dr                     | New          | 0.13        | 100%              |
|              | 24      | Keith Dr                      | Jennifer Cir to FM 455                              | Widening     | 0.27        | 100%              |
|              | 25      | Cowling Rd                    | 5th St to 3,335' S of Cowling to Railroad Connector | Widening     | 1.06        | 100%              |
|              | 26      | 2nd St                        | Indian Ln to FM 455                                 | New          | 0.69        | 100%              |
|              | 27      | Marion Rd                     | 270' N of Avion Dr to FM 455                        | Widening     | 0.60        | 100%              |
|              | 28      | Union Hill Rd                 | FM 455 to McReynolds Rd                             | New          | 1.04        | 100%              |





## Exhibit 2 Capital Improvements Plan



### Legend

- Service Area
- ETJ
- Floodplain
- Railroads
- Local Roads

### Project Type

- New
- Widening
- Widening 1/3
- Construction
- Thoroughfare Plan Network





## 5. METHODOLOGY FOR ROADWAY IMPACT FEES

### A. SERVICE AREA

The one (1) service area used in the 2024 Roadway Impact Fee Study is shown in the previously referenced **Exhibit 1**. This service area covers the entire corporate boundary of the City of Sanger. Chapter 395 of the Texas Local Government Code specifies that “the service area is limited to an area within the corporate boundaries of the political subdivision and shall not exceed six (6) miles.” The service area in the 2024 Roadway Impact Fee Study is consistent with the specification of Chapter 395 of the Texas Local Government Code.

### B. SERVICE UNITS

The “service unit” is a measure of consumption or use of the roadway facilities by new development. In other words, it is the unit of measure used in the 2024 Roadway Impact Fee Study to quantify the supply and demand for roads in the City. For transportation purposes, the service unit is defined as a vehicle-mile as explained below:

- Vehicle-Mile: The capacity consumed in a single lane in the PM peak hour by a vehicle making a trip one mile in length. The PM peak hour is used as the basis for transportation planning and the estimation of trips caused by new development.
- Total Vehicle-Miles of Supply: Based on the total length (miles), number of lanes, and capacity (vehicles per hour) (see **Appendix B**).
- Total Vehicle-Miles of Demand: Based on the 10-year growth projections. The demand is equal to PM Trip Rate (trips) \* Trip Length (miles).

The hourly service volumes used in the 2024 Roadway Impact Fee Study are based upon thoroughfare capacity criteria published by the North Central Texas Council of Governments (NCTCOG) and applied to the City of Sanger’s thoroughfare classifications. **Table 3** and **Table 4** show the service volumes as a function of the Impact Fee classification and existing cross sections, respectively.

**Table 3. Service Volumes for Proposed Facilities**

| Roadway Type<br>(Impact Fee<br>Classifications) | Description         | Hourly Vehicle-Mile Capacity per<br>Lane-Mile of Roadway Facility |
|-------------------------------------------------|---------------------|-------------------------------------------------------------------|
| Principal Arterial                              | Four-Lane Divided   | 650                                                               |
| Minor Arterial                                  | Four-Lane Undivided | 525                                                               |
| Collector                                       | Two-Lane Undivided  | 425                                                               |



**Table 4. Service Volumes for Existing Facilities**

| Roadway Type | Description                            | Hourly Vehicle-Mile Capacity per Lane-Mile of Roadway Facility |
|--------------|----------------------------------------|----------------------------------------------------------------|
| 3U           | Three-Lane Undivided                   | 525                                                            |
| 2U           | Two-Lane Undivided                     | 425                                                            |
| 2U-G         | Two-Lane Undivided<br>(Gravel or Dirt) | 150                                                            |

### **C. COST PER SERVICE UNIT**

A fundamental step in the impact fee process is to establish the cost for each service unit. In the case of roadway impact fees, this is the cost for each vehicle-mile of travel. Thus, it is the cost to construct a roadway (lane-mile) needed to accommodate a vehicle-mile of travel. The cost per service unit is calculated for each service area based on the roadway projects within that service area.

The second component of the cost per service unit is the determination of the number of service units in each service area. This number is the measure of the growth in transportation demand that is projected to occur in the 10-year period. Chapter 395 requires that roadway impact fees be assessed only to pay for growth projected to occur in the City Limits within the next 10 years. As noted earlier, the units of demand are vehicle-miles of travel.

### **D. CAPITAL IMPROVEMENTS PLAN COSTING METHODOLOGY**

All of the project costs for a facility which serves the overall transportation system are eligible to be included in the Capital Improvements Plan. Chapter 395 of the Texas Local Government Code specifies that the allowable costs are "...including and limited to the:

1. Construction contract price;
2. Surveying and engineering fees;
3. Land acquisition costs, including land purchases, court awards and costs, attorney's fees, and expert witness fees; and
4. Fees actually paid or contracted to be paid to an independent qualified engineer or financial consultant preparing or updating the Capital Improvements Plan who is not an employee of the political subdivision."

The engineer's opinion of the probable costs of the projects in the Capital Improvements Plan is based, in part, on the calculation of a unit cost of construction. This means that a cost per linear foot of roadway is calculated based on an average price for the various components of roadway construction. This allows the probable cost to be determined by the type of facility being constructed, the number of lanes, and the







- Limits – Represents the beginning and ending location for each project.
- Impact Fee Class – The costing class to be used in the analysis. The impact fee class provides the width for the various elements in the roadway. The construction costs are variable based on the proposed Future Thoroughfare Plan classification of the roadway. An additional classification is utilized for Indian Lane (2) where a portion of the facility currently exists and the road is only to be partially widened. The following notation is used for this project:
  - “(1/3)” for facilities where one additional lane is to be constructed to match the existing, adjacent section of Indian Lane.
- Length (ft) – The distance measured in feet that is used to cost out the project.
- Service Area – Represents the service area where the project is located.
- Description – Used to describe the project type assumed in the costing such as a widening or a new project.

### Roadway Construction Pay Items

A typical roadway project consists of several costs, including planning, survey, design engineering, permitting, right-of-way acquisition, construction, and inspection. While the construction cost component of a project may actually consist of hundreds of various pay items, a simplified approach was used for developing the conceptual level project costs. The roadway construction components pay items are listed below:

- |                                 |                                  |
|---------------------------------|----------------------------------|
| • Undersized Roadway Excavation | • Curb & Gutter                  |
| • Lime-Treated Subgrade         | • Topsoil                        |
| • Reinforced Concrete           | • Turn Lanes and Median Openings |
| • Concrete Sidewalk             |                                  |

### Major Construction Component Allowances

A percentage of the paving construction cost is allotted for various major construction component allowances, as appropriate. These allowances include traffic control, pavement markings, roadway drainage, utility adjustments, landscaping, and illumination.

Lump sum dollar allowances are provided for special drainage structures and railroad crossings where needs are anticipated.

The paving and allowance subtotal is given a fifteen percent (15%) contingency, five percent (5%) mobilization, and either five (5%) or one percent (1%) preparation of right-of-way (ROW) based on whether the project is new or existing to determine the construction cost total.



## Project Cost Summary

To determine the total Impact Fee Project Cost, sixteen percent (16%) of the construction cost total is added for engineering, surveying, and testing.

Percentages are also allotted for ROW/ easement acquisition. ROW/ easement acquisition was based on whether the project was an existing alignment or future alignment. For an existing alignment, the ROW/ easement acquisition cost was provided an allotment equal to ten percent (10%) of the construction cost total. For a new alignment, the ROW/ easement acquisition cost was equal to twenty percent (20%) of the construction cost total. The value for ROW/ easement acquisition is an estimated contribution allocation and does not represent actual ROW/ easement acquisition needs. TxDOT facilities and partial widening projects assumed no ROW/ easement acquisition.

The Impact Fee Project Cost Total is the Construction Cost Total plus engineering, surveying, testing, and inspection, plus ROW/ easement acquisition. Based upon discussions with City of Sanger staff, state highway projects were included with a projected City contribution of twenty percent (20%) of the total project cost.

## E SUMMARY OF CAPITAL IMPROVEMENTS PLAN

**Table 5** provides the Capital Improvements Plan list for the service area with planning level project costs. Individual project cost worksheets are provided in **Appendix A**, Conceptual Level Project Cost Projections. It should be noted that these tables reflect only conceptual-level opinions or assumptions regarding the portions of future project costs that are potentially recoverable through impact fees. Actual project costs are likely to change with time and are dependent on market and economic conditions that cannot be precisely predicted.

The Capital Improvements Plan establishes the list of projects for which Roadway Impact Fees may be utilized. Projects not included in the Capital Improvements Plan are not eligible to receive impact fee funding. The cost projections utilized in this study should not be utilized for the City's building program or construction CIP.



**Table 5. 10-Year Capital Improvements Plan with Conceptual Level Cost Projections**

| Service Area | Proj. # | Roadway                       | Limits                                              | Project Type | Length (mi) | % In Service Area | Total Project Cost                   | Total Cost in Service Area |
|--------------|---------|-------------------------------|-----------------------------------------------------|--------------|-------------|-------------------|--------------------------------------|----------------------------|
| Sanger       | 1       | North Metz to I-35 Connector  | 3,030' W of I-35 SBFR to I-35 SBFR                  | New          | 0.57        | 100%              | \$ 6,251,000                         | \$ 6,251,000               |
|              | 2       | Chisam Rd                     | I-35 NBFR to 4,375' E of I-35 NBFR                  | Widening     | 0.83        | 100%              | \$ 10,309,000                        | \$ 10,309,000              |
|              | 3       | Lois Rd W                     | 3,645' W of I-35 SBFR to I-35 SBFR                  | Widening     | 0.69        | 100%              | \$ 11,535,000                        | \$ 11,535,000              |
|              | 4       | Lois Rd E (1)                 | I-35 NBFR to 525' E of I-35 NBFR                    | Widening     | 0.10        | 100%              | \$ 1,549,000                         | \$ 1,549,000               |
|              | 5       | Lois Rd E (2)                 | 525' E of I-35 NBFR to 775' E of I-35 NBFR          | New          | 0.05        | 100%              | \$ 745,000                           | \$ 745,000                 |
|              | 6       | Lois Rd E (3)                 | 775' E of I-35 NBFR to 2,255' E of I-35 NBFR        | Widening     | 0.28        | 100%              | \$ 6,333,000                         | \$ 6,333,000               |
|              | 7       | South Metz to I-35 Connector  | 4,935' W of I-35 SBFR to I-35 SBFR                  | New          | 0.93        | 100%              | \$ 9,509,000                         | \$ 9,509,000               |
|              | 8       | Utility Rd                    | I-35 NBFR to 1,920' E of I-35 NBFR                  | Widening     | 0.36        | 100%              | \$ 4,448,000                         | \$ 4,448,000               |
|              | 9       | Belz Rd                       | Metz Rd to I-35 SBFR                                | Widening     | 0.91        | 100%              | \$ 15,788,000                        | \$ 15,788,000              |
|              | 10      | Indian Ln (1)                 | I-35 SBFR to FM 455                                 | New          | 1.07        | 100%              | \$ 19,659,000                        | \$ 19,659,000              |
|              | 11      | Indian Ln (2)                 | 1,290' N of McReynolds Rd to McReynolds Rd          | Widening 1/3 | 0.24        | 100%              | \$ 725,000                           | \$ 725,000                 |
|              | 12      | Indian Ln (3)                 | McReynolds Rd to 3,365' S of McReynolds Rd          | New          | 0.64        | 100%              | \$ 6,484,000                         | \$ 6,484,000               |
|              | 13      | FM 455 (1)                    | FM 2450 to 830' E of Marion Rd                      | Construction | 5.47        | 100%              | \$ 7,850,949                         | \$ 7,850,949               |
|              | 14      | FM 455 (2)                    | 830' E of Marion Rd to 2,110' S of FM 2164          | Widening     | 2.84        | 100%              | \$ 11,020,000                        | \$ 11,020,000              |
|              | 15      | Willow St                     | Cowling Rd to Indian Ln                             | Widening     | 0.95        | 100%              | \$ 18,725,000                        | \$ 18,725,000              |
|              | 16      | McReynolds Rd                 | Indian Ln to 600' E of PR 6630                      | Widening     | 1.08        | 100%              | \$ 21,576,000                        | \$ 21,576,000              |
|              | 17      | 5th St                        | Keaton Rd to I-35 SBFR                              | Widening     | 0.17        | 100%              | \$ 489,000                           | \$ 489,000                 |
|              | 18      | Cowling to Railroad Connector | Cowling Rd to Railroad Ave                          | New          | 0.52        | 100%              | \$ 8,167,000                         | \$ 8,167,000               |
|              | 19      | Rector Rd                     | 2,730' W of Railroad Ave to Railroad Ave            | New          | 0.52        | 100%              | \$ 8,141,000                         | \$ 8,141,000               |
|              | 20      | N Tejas Dr                    | 1,245' S of FM 455 to 1,490' N of Duck Creek Rd     | New          | 0.25        | 100%              | \$ 2,545,000                         | \$ 2,545,000               |
|              | 21      | Jennifer Cir (1)              | Lois Rd W to Belz Rd                                | New          | 1.54        | 100%              | \$ 16,029,000                        | \$ 16,029,000              |
|              | 22      | Jennifer Cir (2)              | Belz Rd to 1,555' S of Belz Rd                      | Widening     | 0.29        | 100%              | \$ 2,965,000                         | \$ 2,965,000               |
|              | 23      | Jennifer Cir (3)              | 1,555' S of Belz Rd to Keith Dr                     | New          | 0.13        | 100%              | \$ 1,359,000                         | \$ 1,359,000               |
|              | 24      | Keith Dr                      | Jennifer Cir to FM 455                              | Widening     | 0.27        | 100%              | \$ 2,679,000                         | \$ 2,679,000               |
|              | 25      | Cowling Rd                    | 5th St to 3,335' S of Cowling to Railroad Connector | Widening     | 1.06        | 100%              | \$ 19,706,000                        | \$ 19,706,000              |
|              | 26      | 2nd St                        | Indian Ln to FM 455                                 | New          | 0.69        | 100%              | \$ 9,052,000                         | \$ 9,052,000               |
|              | 27      | Marion Rd                     | 270' N of Avon Dr to FM 455                         | Widening     | 0.60        | 100%              | \$ 10,573,000                        | \$ 10,573,000              |
|              | 28      | Union Hill Rd                 | FM 455 to McReynolds Rd                             | New          | 1.04        | 100%              | \$ 16,773,000                        | \$ 16,773,000              |
|              |         |                               |                                                     |              |             |                   | <b>Project Cost Subtotal</b>         | <b>\$ 250,984,949</b>      |
|              |         |                               |                                                     |              |             |                   | <b>Roadway Impact Fee Study Cost</b> | <b>\$ 50,000</b>           |
|              |         |                               |                                                     |              |             |                   | <b>Total Cost</b>                    | <b>\$ 251,034,949</b>      |





## **F. SERVICE UNIT CALCULATION**

The basic service unit for the computation of the City of Sanger's roadway impact fee is the vehicle-mile of travel during the PM peak hour. To determine the cost per service unit, it is necessary to project the growth in vehicle-miles of travel for the service area for the 10-year period.

The growth in vehicle-miles from 2024 to 2034 is based upon projected changes in residential and non-residential growth for the period. These growth projections are discussed in Chapter 3. Land Use Assumptions.

The residential and non-residential statistics in the Land Use Assumptions provide the "independent variables" that are used to calculate the existing (2024) and projected (2034) transportation service units (vehicle-miles) used to establish the roadway impact fee maximum rates within the service area. The roadway demand service units (vehicle-miles) for the service area are the sum of the vehicle-miles "generated" by each category of land use in the service area.

For the purpose of impact fees, all developed and developable land is categorized as either residential or non-residential. For residential land uses, the number of dwelling units in each service area is multiplied by a transportation demand factor to compute the vehicle-miles of travel that occur during the PM peak hour. This factor computes the average amount of demand caused by the residential land uses in the service area. The transportation demand factor is discussed in more detail later in this section.

For non-residential land uses, the process is similar. The Land Use Assumptions provide the projected number of building square footages for three (3) categories of non-residential land uses – basic, service, and retail. These categories correspond to an aggregation of other specific land use categories based on the North American Industry Classification System (NAICS).

Building square footage is the most common independent variable for the estimation of non-residential trips in the Institute of Transportation Engineers' (ITE) Trip Generation Manual, 11<sup>th</sup> Edition. This characteristic is more appropriate than the number of employees because building square footage is tied more closely to trip generation and is known at the time of application for any development, or development modification, that would require the assessment of an impact fee.

The existing and projected Land Use Assumptions for the dwelling units and the square footage of basic, service, and retail land uses provide the basis for the projected increase in vehicle-miles of travel. As noted earlier, a transportation demand factor is applied to these values and then summed to calculate the total peak hour vehicle-miles of demand for the service area.

The transportation demand factors are aggregate rates derived from three sources – the ITE Trip Generation Manual, 11<sup>th</sup> Edition, NCTCOG, and open-source data specific to Sanger.



ITEs Trip Generation Manual, 11<sup>th</sup> Edition provides the number of trips that are produced or attracted to the land use for each dwelling unit, square foot of building, or other corresponding unit. For the retail category of land uses, the rate is adjusted to account for the fact that a percentage of retail trips are made by people who would otherwise be traveling past that particular establishment anyway, such as a trip between work and home. These trips are called pass-by trips, and since the travel demand is accounted for in the land use calculations relative to the primary trip, it is necessary to discount the retail rate to avoid double counting trips.

The next component of the transportation demand factor accounts for the length of each trip. The average trip length for each category is based on the region-wide travel characteristics survey conducted by NCTCOG, open-source data specific to Sanger, and other generally accepted planning principles.

The computation of the transportation demand factor is based on the following equation:

$$TDF = T * (1 - P_b) * L_{\max}$$

$$\text{where... } L_{\max} = \min(L * OD \text{ or } SA_L)$$

Variables

|                  |                                       |
|------------------|---------------------------------------|
| TDF              | = Transportation Demand Factor,       |
| T                | = Trip Rate (peak hour trips / unit), |
| P <sub>b</sub>   | = Pass-By Discount (% of trips),      |
| L                | = Average Trip Length (miles),        |
| L <sub>max</sub> | = Maximum Trip Length (miles),        |
| OD               | = Origin-Destination Reduction (50%)  |
| SA <sub>L</sub>  | = Maximum Service Area Trip Length    |

The maximum trip length was limited to six (6) miles based on the maximum trip length within the City Limits. Chapter 395 of the Texas Local Government Code allows for a service area of six (6) miles.

The adjustment made to the average trip length statistic in the computation of the maximum trip length is the origin-destination reduction. This adjustment is made because the roadway impact fee is charged to both the origin and destination end of the trip. For example, impact fee methodology will account for a trip from home to work within Sanger to both residential and non-residential land uses. To avoid counting these trips as both residential and non-residential trips, a 50% origin-destination (OD) reduction factor is applied. Therefore, only half of the trip length is assessed to each land use, and the total trip is only counted once.

**Table 6** shows the derivation of the Transportation Demand Factor for the two (2) residential land uses and the three (3) non-residential land use categories. The values utilized for all variables shown in the transportation demand factor equation are also shown in the table.



Table 6. Transportation Demand Factor Calculations

| Variable           | Residential   |             | Basic       | Service     | Retail       |
|--------------------|---------------|-------------|-------------|-------------|--------------|
|                    | Single-Family | Multifamily |             |             |              |
| T                  | 0.94          | 0.51        | 0.65        | 1.44        | 3.40         |
| P <sub>b</sub>     | 0%            | 0%          | 0%          | 0%          | 29%          |
| L <sub>max</sub> * | 5.17          | 5.17        | 6.00        | 6.00        | 5.15         |
| <b>TDF</b>         | <b>4.86</b>   | <b>2.64</b> | <b>3.90</b> | <b>8.64</b> | <b>12.43</b> |

The application of the demographic projections and the transportation demand factors are presented in the 10-Year Growth Projections in **Table 7**. This table shows the total growth projected in total vehicle-miles by service area between the years 2024 and 2034. These estimates and projections lead to the Vehicle-Miles of Travel for the 10-year period.



Table 7. 10-Year Growth Projections

2024 - 2034 Growth Projections<sup>1</sup>

| SERVICE<br>AREA | RESIDENTIAL VEHICLE-MILES |                               |                      |                               |                               | NON-RESIDENTIAL SQUARE FEET <sup>5</sup> |         |           | TRANS. DEMAND FACTOR <sup>6</sup> |                      |                     | NON-RESIDENTIAL VEHICLE-MILES <sup>10</sup> |         |        |        | TOTAL<br><br>VEHICLE<br>MILES <sup>11</sup> |
|-----------------|---------------------------|-------------------------------|----------------------|-------------------------------|-------------------------------|------------------------------------------|---------|-----------|-----------------------------------|----------------------|---------------------|---------------------------------------------|---------|--------|--------|---------------------------------------------|
|                 | SINGLE-<br>FAMILY UNITS   | Trip Rate<br>TDF <sup>2</sup> | MULTIFAMILY<br>UNITS | Trip Rate<br>TDF <sup>3</sup> | VEHICLE<br>MILES <sup>4</sup> | BASIC                                    | SERVICE | RETAIL    | BASIC <sup>7</sup>                | SERVICE <sup>8</sup> | RETAIL <sup>9</sup> | BASIC                                       | SERVICE | RETAIL | TOTAL  |                                             |
|                 |                           | 0.94                          |                      | 0.51                          |                               |                                          |         |           |                                   |                      |                     |                                             |         |        |        |                                             |
|                 |                           | 0.94                          |                      | 0.51                          |                               |                                          |         |           |                                   |                      |                     |                                             |         |        |        |                                             |
| SANGER          | 3,248                     | 4.86                          | 1,437                | 2.64                          | 19,579                        | 2,454,000                                | 488,500 | 1,165,000 | 3.90                              | 8.64                 | 12.43               | 9,571                                       | 4,221   | 14,481 | 28,273 | 47,852                                      |

VEHICLE-MILES OF INCREASE (2024 - 2034)

| SERVICE AREA | VEH-MILES |
|--------------|-----------|
| SANGER       | 47,852    |

Notes:

<sup>1</sup> From Chapter 3: Land Use Assumptions

<sup>2</sup> Transportation Demand Factor (from LUVMET) using Single-Family Detached Housing land use and trip generation rate

<sup>3</sup> Transportation Demand Factor (from LUVMET) using Multifamily Housing (Low-Rise) land use and trip generation rate

<sup>4</sup> Calculated by multiplying TDF by the number of dwelling units

<sup>5</sup> From Chapter 3: Land Use Assumptions

<sup>6</sup> Trip generation rate and Transportation Demand Factors from LUVMET for each land use

<sup>7</sup> 'Basic' corresponds to General Light Industrial land use and trip generation rate

<sup>8</sup> 'Service' corresponds to General Office Building land use and trip generation rate

<sup>9</sup> 'Retail' corresponds to Shopping Center (>150k SF) land use and trip generation rate

<sup>10</sup> Calculated by multiplying Transportation Demand Factor by the number of thousand square feet for each land use

<sup>11</sup> Residential plus non-residential vehicle-mile totals





## 6. ROADWAY IMPACT FEE CALCULATION

### A. MAXIMUM ASSESSABLE IMPACT FEE PER SERVICE UNIT

This chapter presents the maximum assessable impact fee rate calculated for the service area. The maximum assessable impact fee is the sum of the eligible Capital Improvements Plan costs for the service area divided by the growth in travel attributable to new development projected to occur within the 10-year period. A majority of the components of this calculation have been described and presented in previous chapters. The purpose of this section is to document the computation and to demonstrate that the guidelines provided by Chapter 395 of the Texas Local Government Code have been addressed.

**Tables 8-9** illustrate the computation of the maximum assessable impact fee. Each row in the tables is numbered to simplify explanation of the calculation. The calculation of the maximum assessable impact fee is shown in **Table 10**.

**Table 8. Maximum Assessable Roadway Impact Fee Computation**

| Line | Title                                                                         | Description                                                                                                                                                                                                  |
|------|-------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1    | <i>Total Vehicle-Miles of Capacity Added by the Capital Improvements Plan</i> | The total number of vehicle-miles added to the service area based on the capacity, length, and number of lanes in each project (from <b>Appendix B – Capital Improvements Plan Service Units of Supply</b> ) |

Each project identified in the Capital Improvements Plan will add a certain amount of capacity to the City's roadway network based on its length and classification. This line displays the total amount added within each service area.

|   |                                               |                                                                                                                                                                                             |
|---|-----------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 2 | <i>Total Vehicle-Miles of Existing Demand</i> | A measure of the amount of traffic currently using the roadway facilities upon which capacity is being added. (from <b>Appendix B – Capital Improvements Plan Service Units of Supply</b> ) |
|---|-----------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

A number of facilities identified in the Capital Improvements Plan have traffic currently utilizing a portion of their existing capacity. This line displays the total amount of capacity along these facilities currently being used by existing traffic.

|   |                                                     |                                                                                                                                                              |
|---|-----------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 3 | <i>Total Vehicle-Miles of Existing Deficiencies</i> | Number of vehicle-miles of travel that are not accommodated by the existing roadway system (from <b>Appendix C – Existing Roadway Facilities Inventory</b> ) |
|---|-----------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|

In order to ensure that existing deficiencies on the City's roadway network are not recoverable through impact fees, this line is based on the entire roadway network within the service area. Any thoroughfare within the service area that is deficient, even those not identified on the Capital Improvements Plan, will have these additional vehicle-miles removed from the calculation.



|   |                                                      |                                                                                                                                                                     |
|---|------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 4 | <i>Net Amount of Vehicle-Miles of Capacity Added</i> | A measurement of the amount of vehicle-miles added by the Capital Improvements Plan that will not be utilized by existing demand. <b>(Line 1 – Line 2 – Line 3)</b> |
|---|------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|

This calculation identifies the portion of the Capital Improvements Plan (in vehicle-miles) that may be recoverable through the collection of impact fees.

|   |                                                                            |                                                                                                                                                                                    |
|---|----------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 5 | <i>Total Cost of the Capital Improvements Plan within the Service Area</i> | The total cost of the Capital Improvements Plan projects within each service area (from <b>Table 5: 10-Year Capital Improvements Plan with Conceptual Level Cost Projections</b> ) |
|---|----------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

This line simply identifies the total cost of all of the roadway projects identified in the service area.

|   |                                      |                                                                                                                                                                                                      |
|---|--------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 6 | <i>Cost of Net Capacity Supplied</i> | The total Capital Improvements Plan cost <b>(Line 5)</b> prorated by the ratio of Net Capacity Added <b>(Line 4)</b> to Total Capacity Added <b>(Line 1)</b> . <b>[(Line 4 / Line 1) * (Line 5)]</b> |
|---|--------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Using the ratio of vehicle-miles added by the Capital Improvements Plan available to serve future growth to the total vehicle-miles added, the total cost of the Capital Improvements Plan is reduced to the amount available for future growth (i.e. excluding existing usage and deficiencies).

|   |                                              |                                                                                                                                                                                                     |
|---|----------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 7 | <i>Cost to Meet Existing Needs and Usage</i> | The difference between the Total Cost of the Capital Improvements Plan within the Service Area <b>(Line 5)</b> and the Cost of the Net Capacity supplied <b>(Line 6)</b> . <b>(Line 5 – Line 6)</b> |
|---|----------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

This line is provided for information purposes only – it is to present the portion of the total cost of the Capital Improvements Plan that is required to meet existing demand.

|   |                                                        |                                                                                                                                                                                                             |
|---|--------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 8 | <i>Total Vehicle-Miles of New Demand over 10 Years</i> | Based upon the growth projection provided in <b>Chapter 3: Land Use Assumptions</b> , an estimate of the number of new vehicle-miles within the service area over the next ten years (from <b>Table 7</b> ) |
|---|--------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

This line presents the amount of growth (in vehicle-miles) projected to occur within each service area over the next 10 years.

|    |                                                             |                                                                                                                                                                                                                                                                                       |
|----|-------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 9  | <i>Percent of Capacity Added Attributable to New Growth</i> | The result of dividing Total Vehicle-Miles of New Demand <b>(Line 8)</b> by the Net Amount of Capacity Added <b>(Line 4)</b> , limited to 100%. This calculation is required by Chapter 395 to ensure capacity added is attributable to new growth. <b>(Line 8 / Line 4) ≤ (100%)</b> |
| 10 | <i>Chapter 395 Check</i>                                    |                                                                                                                                                                                                                                                                                       |

In order to ensure that the vehicle-miles added by the Capital Improvements Plan do not exceed the amount needed to accommodate growth beyond the 10-year window, a comparison of the two values is performed. If the amount of vehicle-miles added by the Capital Improvements Plan exceeds the growth projected to occur in the next ten years, the Capital Improvements Plan cost is reduced accordingly.





|           |                                                          |                                                                                                                                                                                                            |
|-----------|----------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>11</b> | <i>Cost of Capacity Added Attributable to New Growth</i> | The result of multiplying the Cost of Net Capacity Supplied ( <b>Line 6</b> ) by the Percent of Capacity Added Attributable to New Growth, limited to 100% ( <b>Line 10</b> ). ( <b>Line 6 * Line 10</b> ) |
|-----------|----------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

This value is the total Capital Improvements Plan project costs (excluding financial costs) that may be recovered through impact fees. This line considers the limitations to impact fees required by the Texas legislature.

|           |                                                |                                                                                                                                                                                                  |
|-----------|------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>12</b> | <i>Pre-Credit Maximum Fee Per Service Unit</i> | Found by dividing the Cost of Capacity Added Attributable to New Growth ( <b>Line 11</b> ) by the Total Vehicle-Miles of New Demand Over 10 Years ( <b>Line 8</b> ). ( <b>Line 11 / Line 8</b> ) |
|-----------|------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

This value is the total pre-credit maximum fee per service unit that may be recovered through impact fees.

## B. PLAN FOR THE ROADWAY IMPACT FEE CREDIT

Chapter 395 of the Texas Local Government Code requires the Capital Improvements Plan to contain specific enumeration of a plan for awarding the impact fee credit. Section 395.014 of the Code requires:

- “(A) a credit for the portion of ad valorem tax and utility service revenues generated by new service units during the program period that is used for the payment of improvements, including the payment of debt, that are included in the capital improvements plan; or
- (B) In the alternative, a credit equal to 50 percent of the total projected cost of implementing the capital improvements plan...”

The City of Sanger has determined the maximum assessable impact fee per service unit shall be 50% of the total projected cost of implementing the Capital Improvements Plan. Therefore, the Credit Calculation (Line 13) is assumed to be half of the Cost of the Capacity Added Attributable to Growth (Line 11). The sum of these values represents the Recoverable Cost of the Capital Improvements Plan (Line 14). The Maximum Assessable Fee Per Service Unit (Line 15) is then found dividing the Recoverable Cost of the Capital Improvements Plan (Line 14) by the Total Vehicle-Miles of Demand over 10 Years (Line 8). **Table 9** summarizes the additional computations carried out to provide the maximum assessable impact fee.

**Table 9. Maximum Assessable Roadway Impact Fee Computation (continued)**

| Line      | Title                                                | Description                                                                                                                                                                                      |
|-----------|------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>13</b> | <i>Credit Calculation</i>                            | Assumed to be 50% of the Cost of Capacity Added Attributable to New Growth ( <b>Line 11</b> ) as allowed by Chapter 395. ( <b>Line 11 * 50%</b> )                                                |
| <b>14</b> | <i>Recoverable Cost of Capital Improvements Plan</i> | The sum of the Cost of Capacity Added Attributable to New Growth ( <b>Line 11</b> ) and the Credit Calculation ( <b>Line 13</b> ). ( <b>Line 11 + Line 13</b> )                                  |
| <b>15</b> | <i>Maximum Assessable Fee Per Service Unit</i>       | Found by dividing the Recoverable Cost of the Capital Improvements Plan ( <b>Line 14</b> ) by the Total Vehicle-Miles of New Demand Over 10 Years ( <b>Line 8</b> ). ( <b>Line 14 / Line 8</b> ) |



**Table 10** summarizes the calculations walked through in **Tables 8 – 9** and provides the maximum assessable impact fee for the service area.

**Table 10. Maximum Assessable Roadway Impact Fee**

| <b>SERVICE AREA:</b> |                                                                                                           | <b>SANGER</b>    |
|----------------------|-----------------------------------------------------------------------------------------------------------|------------------|
| <b>1</b>             | TOTAL VEH-MI OF CAPACITY ADDED BY CIP<br>(FROM CIP UNITS OF SUPPLY, <b>APPENDIX B</b> )                   | 45,591           |
| <b>2</b>             | TOTAL VEH-MI OF EXISTING DEMAND<br>(FROM CIP UNITS OF SUPPLY, <b>APPENDIX B</b> )                         | 5,455            |
| <b>3</b>             | TOTAL VEH-MI OF EXISTING DEFICIENCIES<br>(FROM EXISTING ROADWAY FACILITIES INVENTORY, <b>APPENDIX C</b> ) | 56               |
| <b>4</b>             | NET AMOUNT OF VEH-MI OF CAPACITY ADDED<br>(LINE 1 - LINE 2 - LINE 3)                                      | 40,080           |
| <b>5</b>             | TOTAL COST OF CIP WITHIN SERVICE AREA<br>(FROM <b>TABLE 5</b> )                                           | \$ 251,034,949   |
| <b>6</b>             | COST OF NET CAPACITY SUPPLIED<br>(LINE 4 / LINE 1) * (LINE 5)                                             | \$ 220,690,065   |
| <b>7</b>             | COST TO MEET EXISTING NEEDS AND USAGE<br>(LINE 5 - LINE 6)                                                | \$ 30,344,884    |
| <b>8</b>             | TOTAL VEH-MI OF NEW DEMAND OVER 10 YEARS<br>(FROM <b>TABLE 7</b> AND <b>LAND USE ASSUMPTIONS</b> )        | 47,852           |
| <b>9</b>             | PERCENT OF CAPACITY ADDED ATTRIBUTABLE TO GROWTH<br>(LINE 8 / LINE 4)                                     | 119.4%           |
| <b>10</b>            | CHAPTER 395 CHECK<br>(IF LINE 8 > LINE 4, REDUCE LINE 9 TO 100%,<br>OTHERWISE NO CHANGE)                  | 100.0%           |
| <b>11</b>            | COST OF CAPACITY ADDED ATTRIBUTABLE TO NEW GROWTH<br>(LINE 6 * LINE 10)                                   | \$ 220,690,065   |
| <b>12</b>            | PRE-CREDIT MAX FEE PER SERVICE UNIT<br>(\$ PER VEH-MI)<br>(LINE 11 / LINE 8)                              | \$ 4,611         |
| <b>13</b>            | CREDIT CALCULATION<br>(50% OF LINE 11)                                                                    | \$ (110,345,033) |
| <b>14</b>            | RECOVERABLE COST OF CIP<br>(LINE 11 + LINE 13)                                                            | \$ 110,345,032   |
| <b>15</b>            | MAXASSESSABLE FEE PER SERVICE UNIT (\$ PER VEH-MI)<br>(LINE 14 / LINE 8)                                  | \$ 2,305         |



### C. SERVICE UNIT DEMAND PER UNIT OF DEVELOPMENT

The roadway impact fee is determined by multiplying the impact fee rate by the number of service units projected for the proposed development. For this purpose, the City will utilize the Land Use/ Vehicle-Mile Equivalency Table (LUVMET), presented in **Table 11**. This table lists the predominant land uses that may occur within the City of Sanger. For each land use, the development unit that defines the development's magnitude with respect to transportation demand is shown. Although every possible use cannot be anticipated, the majority of local uses are found in this table. If the exact use is not listed, one similar in trip-making characteristics can serve as a reasonable proxy. The individual land uses are grouped into categories, such as residential, office, commercial, and industrial.

The trip rates presented for each land use are a fundamental component of the LUVMET. The trip rate is the average number of trips generated during the PM peak hour by each land use per development unit. The next column, if applicable to the land use, presents the number of trips to and from certain land uses reduced by pass-by trips, as previously discussed.

The source of the trip generation and pass-by statistics is the ITE Trip Generation Manual, 11th Edition, the latest edition. This manual utilizes trip generation studies for a variety of land uses throughout the United States, and is the standard used by traffic engineers and transportation planners for traffic impact analysis, site design, and transportation planning. However, for land uses not contained within the 11th Edition of the ITE Trip Generation Manual, an alternative service unit demand could be calculated by completing a trip generation study based on the procedure identified in the ITE Trip Generation Handbook.

To convert vehicle trips to vehicle-miles, it is necessary to multiply trips by trip length. The trip length values are based on land use, as explained in Section 5.F. Service Unit Calculation.

The remaining column in the LUVMET shows the vehicle-miles per development unit. This number is the product of the trip rate and the maximum trip length. This number, previously referred to as the Transportation Demand Factor, is used in the impact fee to compute the number of service units attributed to each land use category. The number of service units is multiplied by the impact fee rate (established by City ordinance) in order to determine the impact fee for a development.





**Table 11. Land Use / Vehicle-Mile Equivalency Table (LUVMET)**

| Land Use Category                    | ITE Land Use Code | Development Unit | Trip Gen Rate (PM) | Pass-by Rate | Pass-by Source | Trip Rate | Trip Length (mi) | Adj. For O-D | Adj. Trip Length (mi) | Max Trip Length (mi) | Veh-Mi Per Dev-Unit |
|--------------------------------------|-------------------|------------------|--------------------|--------------|----------------|-----------|------------------|--------------|-----------------------|----------------------|---------------------|
| <b>PORT AND TERMINAL</b>             |                   |                  |                    |              |                |           |                  |              |                       |                      |                     |
| Truck Terminal*                      | 030               | Acres            | 6.55               |              |                | 6.55      | 19.33            | 50%          | 9.66                  | 6.00                 | <b>39.30</b>        |
| <b>INDUSTRIAL</b>                    |                   |                  |                    |              |                |           |                  |              |                       |                      |                     |
| General Light Industrial             | 110               | 1,000 SF GFA     | 0.65               |              |                | 0.65      | 19.33            | 50%          | 9.66                  | 6.00                 | <b>3.90</b>         |
| Industrial Park                      | 130               | 1,000 SF GFA     | 0.34               |              |                | 0.34      | 19.33            | 50%          | 9.66                  | 6.00                 | <b>2.04</b>         |
| Warehousing                          | 150               | 1,000 SF GFA     | 0.18               |              |                | 0.18      | 19.33            | 50%          | 9.66                  | 6.00                 | <b>1.08</b>         |
| Mini-Warehouse                       | 151               | 1,000 SF GFA     | 0.15               |              |                | 0.15      | 19.33            | 50%          | 9.66                  | 6.00                 | <b>0.90</b>         |
| <b>RESIDENTIAL</b>                   |                   |                  |                    |              |                |           |                  |              |                       |                      |                     |
| Single-Family Detached Housing       | 210               | Dwelling Units   | 0.94               |              |                | 0.94      | 10.34            | 50%          | 5.17                  | 5.17                 | <b>4.86</b>         |
| Single-Family Attached Housing       | 215               | Dwelling Units   | 0.57               |              |                | 0.57      | 10.34            | 50%          | 5.17                  | 5.17                 | <b>2.95</b>         |
| Multifamily Housing (Low-Rise)       | 220               | Dwelling Units   | 0.51               |              |                | 0.51      | 10.34            | 50%          | 5.17                  | 5.17                 | <b>2.64</b>         |
| Mobile Home Park                     | 240               | Dwelling Units   | 0.58               |              |                | 0.58      | 10.34            | 50%          | 5.17                  | 5.17                 | <b>3.00</b>         |
| Senior Adult Housing - Single-Family | 251               | Dwelling Units   | 0.30               |              |                | 0.30      | 10.34            | 50%          | 5.17                  | 5.17                 | <b>1.55</b>         |
| Senior Adult Housing - Multifamily   | 252               | Dwelling Units   | 0.25               |              |                | 0.25      | 10.34            | 50%          | 5.17                  | 5.17                 | <b>1.29</b>         |
| Congregate Care Facility             | 253               | Dwelling Units   | 0.18               |              |                | 0.18      | 10.34            | 50%          | 5.17                  | 5.17                 | <b>0.93</b>         |
| Assisted Living                      | 254               | Beds             | 0.24               |              |                | 0.24      | 10.34            | 50%          | 5.17                  | 5.17                 | <b>1.24</b>         |
| <b>LODGING</b>                       |                   |                  |                    |              |                |           |                  |              |                       |                      |                     |
| Hotel                                | 310               | Rooms            | 0.59               |              |                | 0.59      | 5.78             | 50%          | 2.89                  | 2.89                 | <b>1.71</b>         |
| Motel                                | 320               | Rooms            | 0.36               |              |                | 0.36      | 5.78             | 50%          | 2.89                  | 2.89                 | <b>1.04</b>         |
| <b>RECREATIONAL</b>                  |                   |                  |                    |              |                |           |                  |              |                       |                      |                     |
| Golf Course                          | 430               | Acres            | 0.28               |              |                | 0.28      | 12.36            | 50%          | 6.18                  | 6.00                 | <b>1.68</b>         |
| Miniature Golf Course                | 431               | Holes            | 0.33               |              |                | 0.33      | 12.36            | 50%          | 6.18                  | 6.00                 | <b>1.98</b>         |
| Golf Driving Range                   | 432               | Tees             | 1.25               |              |                | 1.25      | 12.36            | 50%          | 6.18                  | 6.00                 | <b>7.50</b>         |
| Movie Theater                        | 445               | Movie Screens    | 13.96              |              |                | 13.96     | 12.36            | 50%          | 6.18                  | 6.00                 | <b>83.76</b>        |
| Ice Skating Rink                     | 465               | 1,000 SF GFA     | 1.33               |              |                | 1.33      | 12.36            | 50%          | 6.18                  | 6.00                 | <b>7.98</b>         |
| Racquet / Tennis Club                | 491               | Tennis Courts    | 3.82               |              |                | 3.82      | 12.36            | 50%          | 6.18                  | 6.00                 | <b>22.92</b>        |
| Recreational Community Center        | 495               | 1,000 SF GFA     | 2.50               |              |                | 2.50      | 12.36            | 50%          | 6.18                  | 6.00                 | <b>15.00</b>        |
| <b>INSTITUTIONAL</b>                 |                   |                  |                    |              |                |           |                  |              |                       |                      |                     |
| Elementary School                    | 520               | Students         | 0.16               |              |                | 0.16      | 10.43            | 50%          | 5.21                  | 5.21                 | <b>0.83</b>         |
| Middle School / Junior High School   | 522               | Students         | 0.15               |              |                | 0.15      | 10.43            | 50%          | 5.21                  | 5.21                 | <b>0.78</b>         |
| High School                          | 525               | Students         | 0.14               |              |                | 0.14      | 10.43            | 50%          | 5.21                  | 5.21                 | <b>0.73</b>         |
| Junior / Community College           | 540               | Students         | 0.11               |              |                | 0.11      | 10.43            | 50%          | 5.21                  | 5.21                 | <b>0.57</b>         |
| University / College                 | 550               | Students         | 0.15               |              |                | 0.15      | 10.43            | 50%          | 5.21                  | 5.21                 | <b>0.78</b>         |
| Church                               | 560               | 1,000 SF GFA     | 0.49               |              |                | 0.49      | 10.43            | 50%          | 5.21                  | 5.21                 | <b>2.55</b>         |
| Day Care Center                      | 565               | 1,000 SF GFA     | 11.12              | 44%          | C              | 6.23      | 10.43            | 50%          | 5.21                  | 5.21                 | <b>32.44</b>        |
| <b>MEDICAL</b>                       |                   |                  |                    |              |                |           |                  |              |                       |                      |                     |
| Hospital                             | 610               | Beds             | 1.69               |              |                | 1.69      | 19.49            | 50%          | 9.74                  | 6.00                 | <b>10.14</b>        |
| Nursing Home                         | 620               | Beds             | 0.14               |              |                | 0.14      | 19.49            | 50%          | 9.74                  | 6.00                 | <b>0.84</b>         |
| Clinic                               | 630               | 1,000 SF GFA     | 3.69               |              |                | 3.69      | 19.49            | 50%          | 9.74                  | 6.00                 | <b>22.14</b>        |
| Animal Hospital / Veterinary Clinic  | 640               | 1,000 SF GFA     | 3.53               |              |                | 3.53      | 19.49            | 50%          | 9.74                  | 6.00                 | <b>21.18</b>        |
| <b>OFFICE</b>                        |                   |                  |                    |              |                |           |                  |              |                       |                      |                     |
| General Office Building              | 710               | 1,000 SF GFA     | 1.44               |              |                | 1.44      | 19.98            | 50%          | 9.99                  | 6.00                 | <b>8.64</b>         |
| Corporate Headquarters Building      | 714               | 1,000 SF GFA     | 1.30               |              |                | 1.30      | 19.98            | 50%          | 9.99                  | 6.00                 | <b>7.80</b>         |
| Single Tenant Office Building        | 715               | 1,000 SF GFA     | 1.76               |              |                | 1.76      | 19.98            | 50%          | 9.99                  | 6.00                 | <b>10.56</b>        |
| Medical-Dental Office Building       | 720               | 1,000 SF GFA     | 3.93               |              |                | 3.93      | 19.98            | 50%          | 9.99                  | 6.00                 | <b>23.58</b>        |
| Office Park                          | 750               | 1,000 SF GFA     | 1.30               |              |                | 1.30      | 19.98            | 50%          | 9.99                  | 6.00                 | <b>7.80</b>         |

\*Uses data from ITE Trip Generation Manual 8th Edition

**Key to Sources of Pass-by Rates:**

- A: ITE Trip Generation Handbook 3rd Edition (September 2017)
- B: Estimated by Kimley-Horn based on ITE rates for similar categories
- C: 2021 Pass-By Tables for ITETripGen Appendices



Table 11 (continued).

Land Use / Vehicle-Mile Equivalency Table (LUVMET)

| Land Use Category                                               | ITE Land Use Code | Development Unit          | Trip Gen Rate (PM) | Pass-by Rate | Pass-by Source | Trip Rate | Trip Length (mi) | Adj. For O-D | Adj. Trip Length (mi) | Max Trip Length (mi) | Veh-Mi Per Dev-Unit |
|-----------------------------------------------------------------|-------------------|---------------------------|--------------------|--------------|----------------|-----------|------------------|--------------|-----------------------|----------------------|---------------------|
| <b>COMMERCIAL</b>                                               |                   |                           |                    |              |                |           |                  |              |                       |                      |                     |
| <b>Automobile Related</b>                                       |                   |                           |                    |              |                |           |                  |              |                       |                      |                     |
| Automobile Sales (New)                                          | 840               | 1,000 SF GFA              | 2.42               |              |                | 2.42      | 11.32            | 50%          | 5.66                  | 5.66                 | 13.70               |
| Automobile Sales (Used)                                         | 841               | 1,000 SF GFA              | 3.75               |              |                | 3.75      | 11.32            | 50%          | 5.66                  | 5.66                 | 21.23               |
| Automobile Parts Sales                                          | 843               | 1,000 SF GFA              | 4.90               | 43%          | C              | 2.79      | 11.32            | 50%          | 5.66                  | 5.66                 | 15.81               |
| Tire Store                                                      | 848               | 1,000 SF GFA              | 3.75               | 25%          | C              | 2.81      | 11.32            | 50%          | 5.66                  | 5.66                 | 15.92               |
| Quick Lubrication Vehicle Shop                                  | 941               | Servicing Positions       | 4.85               | 20%          | B              | 3.88      | 11.32            | 50%          | 5.66                  | 5.66                 | 21.96               |
| Automobile Care Center                                          | 942               | 1,000 SF GFA              | 3.11               |              |                | 3.11      | 11.32            | 50%          | 5.66                  | 5.66                 | 17.60               |
| Gasoline / Service Station                                      | 944               | Vehicle Fueling Positions | 13.91              | 57%          | C              | 5.98      | 1.20             | 50%          | 0.60                  | 0.60                 | 3.59                |
| Convenience Store / Gas Station                                 | 945               | Vehicle Fueling Positions | 18.42              | 56%          | C              | 8.10      | 1.20             | 50%          | 0.60                  | 0.60                 | 4.86                |
| Self-Service Car Wash                                           | 947               | Wash Stalls               | 5.54               | 40%          | B              | 3.32      | 1.20             | 50%          | 0.60                  | 0.60                 | 1.99                |
| Automated Car Wash                                              | 948               | Car Wash Tunnels          | 77.50              | 40%          | B              | 46.50     | 1.20             | 50%          | 0.60                  | 0.60                 | 27.90               |
| <b>Dining</b>                                                   |                   |                           |                    |              |                |           |                  |              |                       |                      |                     |
| Fine Dining Restaurant                                          | 931               | 1,000 SF GFA              | 7.80               | 44%          | C              | 4.37      | 9.62             | 50%          | 4.81                  | 4.81                 | 21.01               |
| High Turnover (Sit-Down) Restaurant                             | 932               | 1,000 SF GFA              | 9.05               | 43%          | C              | 5.16      | 9.62             | 50%          | 4.81                  | 4.81                 | 24.81               |
| Fast-Food Restaurant without Drive-Thru Window                  | 933               | 1,000 SF GFA              | 33.21              | 55%          | B              | 14.94     | 9.62             | 50%          | 4.81                  | 4.81                 | 71.88               |
| Fast-Food Restaurant with Drive-Thru Window                     | 934               | 1,000 SF GFA              | 33.03              | 55%          | C              | 14.86     | 9.62             | 50%          | 4.81                  | 4.81                 | 71.49               |
| Fast-Food Restaurant with Drive-Thru Window (No Indoor Seating) | 935               | Drive-Thru Lanes          | 59.50              | 31%          | C              | 41.06     | 9.62             | 50%          | 4.81                  | 4.81                 | 197.47              |
| Coffee/Donut Shop with Drive-Thru Window                        | 937               | 1,000 SF GFA              | 38.99              | 70%          | B              | 11.70     | 9.62             | 50%          | 4.81                  | 4.81                 | 56.26               |
| <b>Other Retail</b>                                             |                   |                           |                    |              |                |           |                  |              |                       |                      |                     |
| Construction Equipment Rental Store                             | 811               | 1,000 SF GFA              | 0.99               | 26%          | B              | 0.73      | 10.31            | 50%          | 5.15                  | 5.15                 | 3.77                |
| Free-Standing Discount Store                                    | 815               | 1,000 SF GFA              | 4.86               | 20%          | C              | 3.89      | 10.31            | 50%          | 5.15                  | 5.15                 | 20.02               |
| Nursery (Garden Center)                                         | 817               | 1,000 SF GFA              | 6.94               | 30%          | B              | 4.86      | 10.31            | 50%          | 5.15                  | 5.15                 | 25.02               |
| Shopping Center (>150k)                                         | 820               | 1,000 SF GLA              | 3.40               | 29%          | C              | 2.41      | 10.31            | 50%          | 5.15                  | 5.15                 | 12.43               |
| Shopping Plaza (40-150k)                                        | 821               | 1,000 SF GLA              | 5.19               | 40%          | C              | 3.11      | 10.31            | 50%          | 5.15                  | 5.15                 | 16.04               |
| Strip Retail Plaza (<40k)                                       | 822               | 1,000 SF GLA              | 6.59               | 40%          | B              | 3.95      | 10.31            | 50%          | 5.15                  | 5.15                 | 20.36               |
| Supermarket                                                     | 850               | 1,000 SF GFA              | 8.95               | 24%          | C              | 6.80      | 10.31            | 50%          | 5.15                  | 5.15                 | 35.03               |
| Convenience Store                                               | 851               | 1,000 SF GFA              | 49.11              | 51%          | A              | 24.06     | 10.31            | 50%          | 5.15                  | 5.15                 | 123.93              |
| Home Improvement Superstore                                     | 862               | 1,000 SF GFA              | 2.29               | 42%          | C              | 1.33      | 10.31            | 50%          | 5.15                  | 5.15                 | 6.84                |
| Toy / Children's Superstore                                     | 864               | 1,000 SF GFA              | 5.00               | 30%          | B              | 3.50      | 10.31            | 50%          | 5.15                  | 5.15                 | 18.03               |
| Department Store                                                | 875               | 1,000 SF GFA              | 1.95               | 30%          | B              | 1.37      | 10.31            | 50%          | 5.15                  | 5.15                 | 7.03                |
| Pharmacy / Drugstore without Drive-Thru Window                  | 880               | 1,000 SF GFA              | 8.51               | 53%          | C              | 4.00      | 10.31            | 50%          | 5.15                  | 5.15                 | 20.60               |
| Pharmacy / Drugstore with Drive-Thru Window                     | 881               | 1,000 SF GFA              | 10.25              | 49%          | C              | 5.23      | 10.31            | 50%          | 5.15                  | 5.15                 | 26.92               |
| <b>SERVICES</b>                                                 |                   |                           |                    |              |                |           |                  |              |                       |                      |                     |
| Walk-in Bank                                                    | 911               | 1,000 SF GFA              | 12.13              | 35%          | B              | 7.88      | 3.39             | 50%          | 1.69                  | 1.69                 | 13.32               |
| Drive-in Bank                                                   | 912               | Drive-in Lanes            | 27.07              | 35%          | C              | 17.60     | 3.39             | 50%          | 1.69                  | 1.69                 | 29.74               |
| Hair Salon                                                      | 918               | 1,000 SF GFA              | 1.45               | 30%          | B              | 1.02      | 3.39             | 50%          | 1.69                  | 1.69                 | 1.72                |

\*Uses data from ITE Trip Generation Manual 8th Edition

**Key to Sources of Pass-by Rates:**

- A: ITE Trip Generation Handbook 3rd Edition (September 2017)
- B: Estimated by Kimley-Horn based on ITE rates for similar categories
- C: 2021 Pass-By Tables for ITETripGen Appendices



## 7. SAMPLE CALCULATIONS

The following section details two (2) examples of maximum assessable Roadway Impact Fee calculations.

### Example 1:

#### Development Type - One (1) Unit of Single-Family Housing

| Determine Development Unit and Vehide-Miles Per Development Unit       |                                                                                                                                                                                                                   |
|------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Step 1</b>                                                          | <i>From Table 11 [Land Use / Vehide-Mile Equivalency Table]</i><br>Development Type: 1 Dwelling Unit of Single-Family Detached Housing<br>Development Units: 1 Dwelling Unit<br>Veh-Mi Per Development Unit: 4.86 |
| Determine Maximum Assessable Impact Fee Per Service Unit (Vehide-Mile) |                                                                                                                                                                                                                   |
| <b>Step 2</b>                                                          | <i>From Table 10, Line 15 [Maximum Assessable Fee Per Service Unit]</i><br>Sanger Service Area: \$2,305                                                                                                           |
| Determine Maximum Assessable Impact Fee                                |                                                                                                                                                                                                                   |
| <b>Step 3</b>                                                          | Impact Fee = # of Development Units * Veh-Mi Per Development Unit * Max. Fee Per Service Unit<br>Impact Fee = 1 * 4.86 * \$2,305<br>Maximum Assessable Impact Fee = \$11,202                                      |

### Example 2:

#### Development Type - 150,000 Square Foot Home Improvement Superstore

| Determine Development Unit and Vehide-Miles Per Development Unit       |                                                                                                                                                                                                                                          |
|------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Step 1</b>                                                          | <i>From Table 11 [Land Use / Vehide-Mile Equivalency Table]</i><br>Development Type: 150,000 square feet of Home Improvement Superstore<br>Development Units: 1,000 square feet of Gross Floor Area<br>Veh-Mi Per Development Unit: 6.84 |
| Determine Maximum Assessable Impact Fee Per Service Unit (Vehide-Mile) |                                                                                                                                                                                                                                          |
| <b>Step 2</b>                                                          | <i>From Table 10, Line 15 [Maximum Assessable Fee Per Service Unit]</i><br>Sanger Service Area: \$2,305                                                                                                                                  |
| Determine Maximum Assessable Impact Fee                                |                                                                                                                                                                                                                                          |
| <b>Step 3</b>                                                          | Impact Fee = # of Development Units * Veh-Mi Per Development Unit * Max. Fee Per Service Unit<br>Impact Fee = 150 * 6.84 * \$2,305<br>Maximum Assessable Impact Fee = \$2,364,930                                                        |





## 8. ADOPTION AND ADMINISTRATION OF ROADWAY IMPACT FEES

### A. ADOPTION PROCESS

Chapter 395 of the Texas Local Government Code stipulates a specific process for the adoption of Roadway Impact Fees. A Capital Improvements Advisory Committee (CIAC) is required to review the Land Use Assumptions and Roadway Impact Fee Capital Improvements Plan used in calculating the maximum fee, and to provide the Committee's findings for consideration by the City Council. The CIAC also reviews the calculation and resulting maximum fees and provides its findings to the City Council. The composition of the CIAC is required to adequately represent the building and development communities. The City Council then conducts a public hearing on the roadway impact fee assumptions (Land Use Assumptions and Capital Improvements Plan) and Roadway Impact Fee Ordinance.

Following policy adoption, the CIAC is tasked with advising the City Council of the need to update the Land Use Assumptions or the Capital Improvements Plan at any time within five years of adoption. Finally, the CIAC oversees the proper administration of the impact fee, once in place, and advises the City Council as necessary.

### B. COLLECTION AND USE OF ROADWAY IMPACT FEES

Roadway impact fees are assessed when a final plat is recorded. The assessment defines the impact of each unit at the time of platting, according to land use, and may not exceed the maximum impact fee allowed by law. Roadway impact fees are collected when a building permit is issued. Therefore, funds are not collected until development-impacts are introduced to the transportation system. Funds collected within a service area can only be used within the same service area. Finally, fees must be utilized within 10 years of collection, or must be refunded with interest.



## 9. CONCLUSIONS

The City of Sanger has established a process to implement the assessment and collection of roadway impact fees through the adoption of an impact fee ordinance that is consistent with Chapter 395 of the Texas Local Government Code.

This report establishes the maximum allowable roadway impact fee that could be assessed by the City of Sanger, as shown in the previously referenced **Table 10**. This document serves as a guide to the assessment of roadway impact fees pertaining to future development, and the City's need for transportation improvements to accommodate that growth. Following the public hearing process, the City Council may establish an impact fee amount to be collected, up to the calculated maximum and establish the Roadway Impact Fee Ordinance accordingly.

In conclusion, it is our opinion that the data and methodology used in this analysis are appropriate and consistent with Chapter 395 of the Texas Local Government Code. Furthermore, the Land Use Assumptions and the proposed Capital Improvements Plan are appropriately incorporated into the development of the maximum assessable roadway impact fee.

**Table 12** below lists the 2024 Roadway Impact Fee Study's Maximum Assessable Impact Fee Per Service Unit (Vehicle-Mile):

**Table 12. Maximum Assessable Roadway Impact Fee Per Service Unit (Vehicle-Mile)**

| Service Area | Maximum Fee Per Service Unit<br>(per Vehicle-Mile) |
|--------------|----------------------------------------------------|
| Sanger       | \$2,305                                            |



## **APPENDIX A – CONCEPTUAL LEVEL PROJECT COST PROJECTIONS**



**City of Sanger - 2024 Roadway Impact Fee Study**  
Capital Improvements Plan

| #            | Length<br>(ft) | Impact Fee<br>Class  | Project                       | Limits                    |                                           | Existing Cross<br>Section | Ultimate Cross<br>Section | Status       | Percent in<br>Service Area | Total Cost in<br>Service Area |
|--------------|----------------|----------------------|-------------------------------|---------------------------|-------------------------------------------|---------------------------|---------------------------|--------------|----------------------------|-------------------------------|
|              |                |                      |                               | From                      | To                                        |                           |                           |              |                            |                               |
| 1            | 3,030          | Collector            | North Metz to I-35 Connector  | 3,030' W of I-35 SBFR     | I-35 SBFR                                 | None                      | 2U                        | New          | 100%                       | \$ 6,251,000                  |
| 2            | 4,375          | Collector            | Chisam Rd                     | I-35 NBFR                 | 4,375' E of I-35 NBFR                     | 2U                        | 2U                        | Widening     | 100%                       | \$ 10,309,000                 |
| 3            | 3,645          | Minor Arterial       | Lois Rd W                     | 3,645' W of I-35 SBFR     | I-35 SBFR                                 | 2U                        | 4U                        | Widening     | 100%                       | \$ 11,535,000                 |
| 4            | 525            | Minor Arterial       | Lois Rd E (1)                 | I-35 NBFR                 | 525' E of I-35 NBFR                       | 2U                        | 4U                        | Widening     | 100%                       | \$ 1,549,000                  |
| 5            | 250            | Minor Arterial       | Lois Rd E (2)                 | 525' E of I-35 NBFR       | 775' E of I-35 NBFR                       | None                      | 4U                        | New          | 100%                       | \$ 745,000                    |
| 6            | 1,480          | Minor Arterial       | Lois Rd E (3)                 | 775' E of I-35 NBFR       | 2,255' E of I-35 NBFR                     | 2U                        | 4U                        | Widening     | 100%                       | \$ 6,333,000                  |
| 7            | 4,935          | Collector            | South Metz to I-35 Connector  | 4,935' W of I-35 SBFR     | I-35 SBFR                                 | None                      | 2U                        | New          | 100%                       | \$ 9,509,000                  |
| 8            | 1,920          | Collector            | Utility Rd                    | I-35 NBFR                 | 1,920' E of I-35 NBFR                     | 2U                        | 2U                        | Widening     | 100%                       | \$ 4,448,000                  |
| 9            | 4,820          | Minor Arterial       | Belz Rd                       | Metz Rd                   | I-35 SBFR                                 | 2U                        | 4U                        | Widening     | 100%                       | \$ 15,788,000                 |
| 10           | 5,630          | Minor Arterial       | Indian Ln (1)                 | I-35 SBFR                 | FM 455                                    | None                      | 4U                        | New          | 100%                       | \$ 19,659,000                 |
| 11           | 1,290          | Minor Arterial (1/3) | Indian Ln (2)                 | 1,290' N of McReynolds Rd | McReynolds Rd                             | 2U                        | 3U                        | Widening 1/3 | 100%                       | \$ 725,000                    |
| 12           | 3,365          | Collector            | Indian Ln (3)                 | McReynolds Rd             | 3,365' S of McReynolds Rd                 | None                      | 2U                        | New          | 100%                       | \$ 6,484,000                  |
| 13           | 28,860         | Principal Arterial   | FM 455 (1)                    | FM 2450                   | 830' E of Marion Rd                       | 2U                        | 4D                        | Construction | 100%                       | \$ 7,850,949                  |
| 14           | 15,015         | Principal Arterial   | FM 455 (2)                    | 830' E of Marion Rd       | 2,110' S of FM 2164                       | 2U                        | 4D                        | Widening     | 100%                       | \$ 11,020,000                 |
| 15           | 5,015          | Minor Arterial       | Willow St                     | Cowling Rd                | Indian Ln                                 | 2U                        | 4U                        | Widening     | 100%                       | \$ 18,725,000                 |
| 16           | 5,715          | Minor Arterial       | McReynolds Rd                 | Indian Ln                 | 600' E of PR 6630                         | 2U                        | 4U                        | Widening     | 100%                       | \$ 21,576,000                 |
| 17           | 900            | Minor Arterial       | 5th St                        | Keaton Rd                 | I-35 SBFR                                 | 2U                        | 4U                        | Widening     | 100%                       | \$ 489,000                    |
| 18           | 2,740          | Minor Arterial       | Cowling to Railroad Connector | Cowling Rd                | Railroad Ave                              | None                      | 4U                        | New          | 100%                       | \$ 8,167,000                  |
| 19           | 2,730          | Collector            | Rector Rd                     | 2,730' W of Railroad Ave  | Railroad Ave                              | None                      | 2U                        | New          | 100%                       | \$ 8,141,000                  |
| 20           | 1,320          | Collector            | N Tejas Dr                    | 1,245' S of FM 455        | 1,490' N of Duck Creek Rd                 | None                      | 2U                        | New          | 100%                       | \$ 2,545,000                  |
| 21           | 8,105          | Collector            | Jennifer Cir (1)              | Lois Rd W                 | Belz Rd                                   | None                      | 2U                        | New          | 100%                       | \$ 16,029,000                 |
| 22           | 1,555          | Collector            | Jennifer Cir (2)              | Belz Rd                   | 1,555' S of Belz Rd                       | 2U                        | 2U                        | Widening     | 100%                       | \$ 2,965,000                  |
| 23           | 705            | Collector            | Jennifer Cir (3)              | 1,555' S of Belz Rd       | Keith Dr                                  | None                      | 2U                        | New          | 100%                       | \$ 1,359,000                  |
| 24           | 1,405          | Collector            | Keith Dr                      | Jennifer Cir              | FM 455                                    | 2U-G                      | 2U                        | Widening     | 100%                       | \$ 2,679,000                  |
| 25           | 5,615          | Minor Arterial       | Cowling Rd                    | 5th St                    | 3,335' S of Cowling to Railroad Connector | 2U                        | 4U                        | Widening     | 100%                       | \$ 19,706,000                 |
| 26           | 3,630          | Collector            | 2nd St                        | Indian Ln                 | FM 455                                    | None                      | 2U                        | New          | 100%                       | \$ 9,052,000                  |
| 27           | 3,185          | Minor Arterial       | Marion Rd                     | 270' N of Avion Dr        | FM 455                                    | 2U                        | 4U                        | Widening     | 100%                       | \$ 10,573,000                 |
| 28           | 5,490          | Minor Arterial       | Union Hill Rd                 | FM 455                    | McReynolds Rd                             | None                      | 4U                        | New          | 100%                       | \$ 16,773,000                 |
| <b>TOTAL</b> |                |                      |                               |                           |                                           |                           |                           |              |                            | <b>\$ 250,984,949</b>         |

**NOTE:** These planning level cost projections listed in this Appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger. These planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                                    | Description:                                                                     | Project No. | 1 |
|----------------------|------------------------------------|----------------------------------------------------------------------------------|-------------|---|
| Name:                | North Metz to I-35 Connector       | This project consists of the construction of a new two-lane undivided collector. |             |   |
| Limits:              | 3,030' W of I-35 SBFR to I-35 SBFR |                                                                                  |             |   |
| Impact Fee Class:    | Collector                          |                                                                                  |             |   |
| Length (lf):         | 3,030                              |                                                                                  |             |   |
| Service Area(s):     | Sanger                             |                                                                                  |             |   |

| Roadway Construction Cost Projection                         |                                  |                              |                     |                                |                |
|--------------------------------------------------------------|----------------------------------|------------------------------|---------------------|--------------------------------|----------------|
| No.                                                          | Item Description                 | Quantity                     | Unit                | Unit Price                     | Item Cost      |
| 103                                                          | Unclassified Roadway Excavation  | 6,060                        | cy                  | \$ 40.00                       | \$ 242,400     |
| 203                                                          | 8" Lime Stabilized Subgrade      | 11,783                       | sy                  | \$ 35.00                       | \$ 412,417     |
| 303                                                          | 8" 4,000 psi Reinforced Concrete | 9,763                        | sy                  | \$ 120.00                      | \$ 1,171,600   |
| 403                                                          | 4" Concrete Sidewalk             | 30,300                       | sf                  | \$ 10.00                       | \$ 303,000     |
| 503                                                          | Curb & Gutter                    | 6,060                        | lf                  | \$ 30.00                       | \$ 181,800     |
| 603                                                          | Topsoil                          | 5,723                        | sy                  | \$ 15.00                       | \$ 85,850      |
| Paving Construction Cost Subtotal:                           |                                  |                              |                     |                                | \$ 2,397,067   |
| Major Construction Component Allowances**:                   |                                  |                              |                     |                                |                |
| Item Description                                             |                                  | Notes                        | Allowance           | Item Cost                      |                |
| ✓                                                            | Traffic Control                  | None Anticipated             | 0%                  | \$                             | -              |
| ✓                                                            | Pavement Markings/Markers        |                              | 3%                  | \$                             | 71,912         |
| ✓                                                            | Roadway Drainage                 | Standard Internal System     | 25%                 | \$                             | 599,267        |
| ✓                                                            | Special Drainage Structures      | Minor Stream Crossing        | -                   | \$                             | 250,000        |
| ✓                                                            | Water                            | Minor Adjustments            | 5%                  | \$                             | 119,853        |
| ✓                                                            | Sewer                            | Minor Adjustments            | 5%                  | \$                             | 119,853        |
| ✓                                                            | Landscaping and Irrigation       |                              | 4%                  | \$                             | 95,883         |
| ✓                                                            | Illumination                     | Standard Illumination System | 6%                  | \$                             | 143,824        |
|                                                              | Other:                           |                              | \$0                 | \$                             | -              |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              | Allowance Subtotal: | \$                             | 1,400,592      |
|                                                              |                                  |                              |                     | Paving and Allowance Subtotal: | \$ 3,797,659   |
|                                                              |                                  |                              |                     | Construction Contingency:      | 15% \$ 569,649 |
|                                                              |                                  |                              |                     | Mobilization                   | 5% \$ 189,883  |
|                                                              |                                  |                              |                     | Prep ROW                       | 1% \$ 37,977   |
|                                                              |                                  |                              |                     | Construction Cost TOTAL:       | \$ 4,596,000   |

| Impact Fee Project Cost Summary |                       |           |              |
|---------------------------------|-----------------------|-----------|--------------|
| Item Description                | Notes:                | Allowance | Item Cost    |
| Construction:                   |                       | -         | \$ 4,596,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 735,360   |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 919,200   |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 6,251,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                                    | Description:                                                                               | Project No. | 2 |
|----------------------|------------------------------------|--------------------------------------------------------------------------------------------|-------------|---|
| Name:                | Chisam Rd                          | This project consists of widening the existing facility to a two-lane undivided collector. |             |   |
| Limits:              | I-35 NBFR to 4,375' E of I-35 NBFR |                                                                                            |             |   |
| Impact Fee Class:    | Collector                          |                                                                                            |             |   |
| Length (lf):         | 4,375                              |                                                                                            |             |   |
| Service Area(s):     | Sanger                             |                                                                                            |             |   |

| Roadway Construction Cost Projection                         |                                  |                                    |                     |                                |                |
|--------------------------------------------------------------|----------------------------------|------------------------------------|---------------------|--------------------------------|----------------|
| No.                                                          | Item Description                 | Quantity                           | Unit                | Unit Price                     | Item Cost      |
| 103                                                          | Unclassified Roadway Excavation  | 8,750                              | cy                  | \$ 40.00                       | \$ 350,000     |
| 203                                                          | 8" Lime Stabilized Subgrade      | 17,014                             | sy                  | \$ 35.00                       | \$ 595,486     |
| 303                                                          | 8" 4,000 psi Reinforced Concrete | 14,097                             | sy                  | \$ 120.00                      | \$ 1,691,667   |
| 403                                                          | 4" Concrete Sidewalk             | 43,750                             | sf                  | \$ 10.00                       | \$ 437,500     |
| 503                                                          | Curb & Gutter                    | 8,750                              | lf                  | \$ 30.00                       | \$ 262,500     |
| 603                                                          | Topsoil                          | 8,264                              | sy                  | \$ 15.00                       | \$ 123,958     |
| Paving Construction Cost Subtotal:                           |                                  |                                    |                     |                                | \$ 3,461,111   |
| Major Construction Component Allowances**:                   |                                  |                                    |                     |                                |                |
| Item Description                                             |                                  | Notes                              | Allowance           | Item Cost                      |                |
| ✓                                                            | Traffic Control                  | Construction Phase Traffic Control | 5%                  | \$                             | 173,056        |
| ✓                                                            | Pavement Markings/Markers        |                                    | 3%                  | \$                             | 103,833        |
| ✓                                                            | Roadway Drainage                 | Standard Internal System           | 25%                 | \$                             | 865,278        |
| ✓                                                            | Special Drainage Structures      | Minor Stream Crossing (2)          | -                   | \$                             | 500,000        |
| ✓                                                            | Water                            | Minor Adjustments                  | 5%                  | \$                             | 173,056        |
| ✓                                                            | Sewer                            | Minor Adjustments                  | 5%                  | \$                             | 173,056        |
| ✓                                                            | Landscaping and Irrigation       |                                    | 4%                  | \$                             | 138,444        |
| ✓                                                            | Illumination                     | Standard Illumination System       | 6%                  | \$                             | 207,667        |
| ✓                                                            | Other:                           | Railroad Crossing                  | \$750,000           | \$                             | 750,000        |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                                    | Allowance Subtotal: | \$                             | 3,084,389      |
|                                                              |                                  |                                    |                     | Paving and Allowance Subtotal: | \$ 6,545,500   |
|                                                              |                                  |                                    |                     | Construction Contingency:      | 15% \$ 981,825 |
|                                                              |                                  |                                    |                     | Mobilization                   | 5% \$ 327,275  |
|                                                              |                                  |                                    |                     | Prep ROW                       | 5% \$ 327,275  |
|                                                              |                                  |                                    |                     | Construction Cost TOTAL:       | \$ 8,182,000   |

| Impact Fee Project Cost Summary |                    |           |               |
|---------------------------------|--------------------|-----------|---------------|
| Item Description                | Notes:             | Allowance | Item Cost     |
| Construction:                   |                    | -         | \$ 8,182,000  |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 1,309,120  |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 818,200    |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 10,309,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                                    | Description:                                                                               | Project No. | 3 |
|----------------------|------------------------------------|--------------------------------------------------------------------------------------------|-------------|---|
| Name:                | Lois Rd W                          | This project consists of widening the existing facility to a four-lane undivided arterial. |             |   |
| Limits:              | 3,645' W of I-35 SBFR to I-35 SBFR |                                                                                            |             |   |
| Impact Fee Class:    | Minor Arterial                     |                                                                                            |             |   |
| Length (lf):         | 3,645                              |                                                                                            |             |   |
| Service Area(s):     | Sanger                             |                                                                                            |             |   |

| Roadway Construction Cost Projection                         |                                  |                                    |      |                     |                  |
|--------------------------------------------------------------|----------------------------------|------------------------------------|------|---------------------|------------------|
| No.                                                          | Item Description                 | Quantity                           | Unit | Unit Price          | Item Cost        |
| 102                                                          | Unclassified Roadway Excavation  | 10,834                             | cy   | \$ 40.00            | \$ 433,350       |
| 202                                                          | 10" Lime Stabilized Subgrade     | 21,263                             | sy   | \$ 40.00            | \$ 850,500       |
| 302                                                          | 9" 4,000 psi Reinforced Concrete | 19,035                             | sy   | \$ 130.00           | \$ 2,474,550     |
| 402                                                          | 4" Concrete Sidewalk             | 36,450                             | sf   | \$ 10.00            | \$ 364,500       |
| 502                                                          | Curb & Gutter                    | 7,290                              | lf   | \$ 30.00            | \$ 218,700       |
| 602                                                          | Topsoil                          | 7,898                              | sy   | \$ 15.00            | \$ 118,463       |
| Paving Construction Cost Subtotal:                           |                                  |                                    |      |                     | \$ 4,460,063     |
| Major Construction Component Allowances**:                   |                                  |                                    |      |                     |                  |
| Item Description                                             |                                  | Notes                              |      | Allowance           | Item Cost        |
| √                                                            | Traffic Control                  | Construction Phase Traffic Control |      | 5%                  | \$ 223,003       |
| √                                                            | Pavement Markings/Markers        |                                    |      | 3%                  | \$ 133,802       |
| √                                                            | Roadway Drainage                 | Standard Internal System           |      | 25%                 | \$ 1,115,016     |
| √                                                            | Special Drainage Structures      | Minor Stream Crossing (2)          |      | -                   | \$ 500,000       |
| √                                                            | Water                            | Minor Adjustments                  |      | 5%                  | \$ 223,003       |
| √                                                            | Sewer                            | Minor Adjustments                  |      | 5%                  | \$ 223,003       |
| √                                                            | Landscaping and Irrigation       |                                    |      | 4%                  | \$ 178,403       |
| √                                                            | Illumination                     | Standard Illumination System       |      | 6%                  | \$ 267,604       |
|                                                              | Other:                           |                                    |      | \$0                 | \$ -             |
|                                                              |                                  |                                    |      | Allowance Subtotal: | \$ 2,863,833     |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                                    |      |                     |                  |
| Paving and Allowance Subtotal:                               |                                  |                                    |      |                     | \$ 7,323,896     |
| Construction Contingency:                                    |                                  |                                    |      |                     | 15% \$ 1,098,584 |
| Mobilization                                                 |                                  |                                    |      |                     | 5% \$ 366,195    |
| Prep ROW                                                     |                                  |                                    |      |                     | 5% \$ 366,195    |
| Construction Cost TOTAL:                                     |                                  |                                    |      |                     | \$ 9,155,000     |

| Impact Fee Project Cost Summary |                    |           |               |
|---------------------------------|--------------------|-----------|---------------|
| Item Description                | Notes:             | Allowance | Item Cost     |
| Construction:                   |                    | -         | \$ 9,155,000  |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 1,464,800  |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 915,500    |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 11,535,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.



**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.

updated: 7/10/2024

| Project Information: |                                  | Description:                                                                                      | Project No. | 4 |
|----------------------|----------------------------------|---------------------------------------------------------------------------------------------------|-------------|---|
| Name:                | Lois Rd E (1)                    | <b>This project consists of widening the existing facility to a four-lane undivided arterial.</b> |             |   |
| Limits:              | I-35 NBFR to 525' E of I-35 NBFR |                                                                                                   |             |   |
| Impact Fee Class:    | Minor Arterial                   |                                                                                                   |             |   |
| Length (lf):         | 525                              |                                                                                                   |             |   |
| Service Area(s):     | Sanger                           |                                                                                                   |             |   |

| Roadway Construction Cost Projection                         |                                  |                                    |      |                                |                |
|--------------------------------------------------------------|----------------------------------|------------------------------------|------|--------------------------------|----------------|
| No.                                                          | Item Description                 | Quantity                           | Unit | Unit Price                     | Item Cost      |
| 102                                                          | Unclassified Roadway Excavation  | 1,560                              | cy   | \$ 40.00                       | \$ 62,417      |
| 202                                                          | 10" Lime Stabilized Subgrade     | 3,063                              | sy   | \$ 40.00                       | \$ 122,500     |
| 302                                                          | 9" 4,000 psi Reinforced Concrete | 2,742                              | sy   | \$ 130.00                      | \$ 356,417     |
| 402                                                          | 4" Concrete Sidewalk             | 5,250                              | sf   | \$ 10.00                       | \$ 52,500      |
| 502                                                          | Curb & Gutter                    | 1,050                              | lf   | \$ 30.00                       | \$ 31,500      |
| 602                                                          | Topsoil                          | 1,138                              | sy   | \$ 15.00                       | \$ 17,063      |
| Paving Construction Cost Subtotal:                           |                                  |                                    |      |                                | \$ 642,396     |
| Major Construction Component Allowances**:                   |                                  |                                    |      |                                |                |
| Item Description                                             |                                  | Notes                              |      | Allowance                      | Item Cost      |
| ✓                                                            | Traffic Control                  | Construction Phase Traffic Control |      | 5%                             | \$ 32,120      |
| ✓                                                            | Pavement Markings/Markers        |                                    |      | 3%                             | \$ 19,272      |
| ✓                                                            | Roadway Drainage                 | Standard Internal System           |      | 25%                            | \$ 160,599     |
|                                                              | Special Drainage Structures      | None Anticipated                   |      | -                              | \$ -           |
| ✓                                                            | Water                            | Minor Adjustments                  |      | 5%                             | \$ 32,120      |
| ✓                                                            | Sewer                            | Minor Adjustments                  |      | 5%                             | \$ 32,120      |
| ✓                                                            | Landscaping and Irrigation       |                                    |      | 4%                             | \$ 25,696      |
| ✓                                                            | Illumination                     | Standard Illumination System       |      | 6%                             | \$ 38,544      |
|                                                              | Other:                           |                                    |      | \$0                            | \$ -           |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                                    |      | Allowance Subtotal:            | \$ 340,470     |
|                                                              |                                  |                                    |      | Paving and Allowance Subtotal: | \$ 982,866     |
|                                                              |                                  |                                    |      | Construction Contingency:      | 15% \$ 147,430 |
|                                                              |                                  |                                    |      | Mobilization                   | 5% \$ 49,143   |
|                                                              |                                  |                                    |      | Prep ROW                       | 5% \$ 49,143   |
|                                                              |                                  |                                    |      | Construction Cost TOTAL:       | \$ 1,229,000   |

| Impact Fee Project Cost Summary |                    |           |              |
|---------------------------------|--------------------|-----------|--------------|
| Item Description                | Notes:             | Allowance | Item Cost    |
| Construction:                   |                    | -         | \$ 1,229,000 |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 196,640   |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 122,900   |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 1,549,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                                            | Description:                                                                     | Project No. | 5 |
|----------------------|--------------------------------------------|----------------------------------------------------------------------------------|-------------|---|
| Name:                | Lois Rd E (2)                              | This project consists of the construction of a new four-lane undivided arterial. |             |   |
| Limits:              | 525' E of I-35 NBFR to 775' E of I-35 NBFR |                                                                                  |             |   |
| Impact Fee Class:    | Minor Arterial                             |                                                                                  |             |   |
| Length (lf):         | 250                                        |                                                                                  |             |   |
| Service Area(s):     | Sanger                                     |                                                                                  |             |   |

| Roadway Construction Cost Projection                         |                                  |                              |                     |                                |               |
|--------------------------------------------------------------|----------------------------------|------------------------------|---------------------|--------------------------------|---------------|
| No.                                                          | Item Description                 | Quantity                     | Unit                | Unit Price                     | Item Cost     |
| 102                                                          | Unclassified Roadway Excavation  | 743                          | cy                  | \$ 40.00                       | \$ 29,722     |
| 202                                                          | 10" Lime Stabilized Subgrade     | 1,458                        | sy                  | \$ 40.00                       | \$ 58,333     |
| 302                                                          | 9" 4,000 psi Reinforced Concrete | 1,306                        | sy                  | \$ 130.00                      | \$ 169,722    |
| 402                                                          | 4" Concrete Sidewalk             | 2,500                        | sf                  | \$ 10.00                       | \$ 25,000     |
| 502                                                          | Curb & Gutter                    | 500                          | lf                  | \$ 30.00                       | \$ 15,000     |
| 602                                                          | Topsoil                          | 542                          | sy                  | \$ 15.00                       | \$ 8,125      |
| Paving Construction Cost Subtotal:                           |                                  |                              |                     |                                | \$ 305,903    |
| Major Construction Component Allowances**:                   |                                  |                              |                     |                                |               |
| Item Description                                             |                                  | Notes                        | Allowance           | Item Cost                      |               |
| ✓                                                            | Traffic Control                  | None Anticipated             | 0%                  | \$                             | -             |
| ✓                                                            | Pavement Markings/Markers        |                              | 3%                  | \$                             | 9,177         |
| ✓                                                            | Roadway Drainage                 | Standard Internal System     | 25%                 | \$                             | 76,476        |
|                                                              | Special Drainage Structures      | None Anticipated             | -                   | \$                             | -             |
| ✓                                                            | Water                            | Minor Adjustments            | 5%                  | \$                             | 15,295        |
| ✓                                                            | Sewer                            | Minor Adjustments            | 5%                  | \$                             | 15,295        |
| ✓                                                            | Landscaping and Irrigation       |                              | 4%                  | \$                             | 12,236        |
| ✓                                                            | Illumination                     | Standard Illumination System | 6%                  | \$                             | 18,354        |
|                                                              | Other:                           |                              | \$0                 | \$                             | -             |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              | Allowance Subtotal: | \$                             | 146,833       |
|                                                              |                                  |                              |                     | Paving and Allowance Subtotal: | \$ 452,736    |
|                                                              |                                  |                              |                     | Construction Contingency:      | 15% \$ 67,910 |
|                                                              |                                  |                              |                     | Mobilization                   | 5% \$ 22,637  |
|                                                              |                                  |                              |                     | Prep ROW                       | 1% \$ 4,527   |
|                                                              |                                  |                              |                     | Construction Cost TOTAL:       | \$ 548,000    |

| Impact Fee Project Cost Summary |                       |           |            |
|---------------------------------|-----------------------|-----------|------------|
| Item Description                | Notes:                | Allowance | Item Cost  |
| Construction:                   |                       | -         | \$ 548,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 87,680  |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 109,600 |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 745,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                                              | Description:                                                                                      | Project No. | 6 |
|----------------------|----------------------------------------------|---------------------------------------------------------------------------------------------------|-------------|---|
| Name:                | Lois Rd E (3)                                | <b>This project consists of widening the existing facility to a four-lane undivided arterial.</b> |             |   |
| Limits:              | 775' E of I-35 NBFR to 2,255' E of I-35 NBFR |                                                                                                   |             |   |
| Impact Fee Class:    | Minor Arterial                               |                                                                                                   |             |   |
| Length (lf):         | 1,480                                        |                                                                                                   |             |   |
| Service Area(s):     | Sanger                                       |                                                                                                   |             |   |

| Roadway Construction Cost Projection |                                  |          |      |            |              |
|--------------------------------------|----------------------------------|----------|------|------------|--------------|
| No.                                  | Item Description                 | Quantity | Unit | Unit Price | Item Cost    |
| 102                                  | Unclassified Roadway Excavation  | 4,399    | cy   | \$ 40.00   | \$ 175,956   |
| 202                                  | 10" Lime Stabilized Subgrade     | 8,633    | sy   | \$ 40.00   | \$ 345,333   |
| 302                                  | 9" 4,000 psi Reinforced Concrete | 7,729    | sy   | \$ 130.00  | \$ 1,004,756 |
| 402                                  | 4" Concrete Sidewalk             | 14,800   | sf   | \$ 10.00   | \$ 148,000   |
| 502                                  | Curb & Gutter                    | 2,960    | lf   | \$ 30.00   | \$ 88,800    |
| 602                                  | Topsoil                          | 3,207    | sy   | \$ 15.00   | \$ 48,100    |
| Paving Construction Cost Subtotal:   |                                  |          |      |            | \$ 1,810,944 |

| Major Construction Component Allowances**:                   |                                    |                                |                |
|--------------------------------------------------------------|------------------------------------|--------------------------------|----------------|
| Item Description                                             | Notes                              | Allowance                      | Item Cost      |
| ✓ Traffic Control                                            | Construction Phase Traffic Control | 5%                             | \$ 90,547      |
| ✓ Pavement Markings/Markers                                  |                                    | 3%                             | \$ 54,328      |
| ✓ Roadway Drainage                                           | Standard Internal System           | 25%                            | \$ 452,736     |
| ✓ Special Drainage Structures                                | Major Stream Crossing              | -                              | \$ 500,000     |
| ✓ Water                                                      | Minor Adjustments                  | 5%                             | \$ 90,547      |
| ✓ Sewer                                                      | Minor Adjustments                  | 5%                             | \$ 90,547      |
| ✓ Landscaping and Irrigation                                 |                                    | 4%                             | \$ 72,438      |
| ✓ Illumination                                               | Standard Illumination System       | 6%                             | \$ 108,657     |
| ✓ Other:                                                     | Railroad Crossing                  | \$750,000                      | \$ 750,000     |
| **Allowances based on % of Paving Construction Cost Subtotal |                                    | Allowance Subtotal:            | \$ 2,209,801   |
|                                                              |                                    | Paving and Allowance Subtotal: | \$ 4,020,745   |
|                                                              |                                    | Construction Contingency:      | 15% \$ 603,112 |
|                                                              |                                    | Mobilization                   | 5% \$ 201,037  |
|                                                              |                                    | Prep ROW                       | 5% \$ 201,037  |
|                                                              |                                    | Construction Cost TOTAL:       | \$ 5,026,000   |

| Impact Fee Project Cost Summary |                    |                                |              |
|---------------------------------|--------------------|--------------------------------|--------------|
| Item Description                | Notes:             | Allowance                      | Item Cost    |
| Construction:                   |                    | -                              | \$ 5,026,000 |
| Engineering/Survey/Testing:     |                    | 16%                            | \$ 804,160   |
| ROW/Easement Acquisition:       | Existing Alignment | 10%                            | \$ 502,600   |
|                                 |                    | Impact Fee Project Cost TOTAL: | \$ 6,333,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                                    | Description:                                                                     | Project No. | 7 |
|----------------------|------------------------------------|----------------------------------------------------------------------------------|-------------|---|
| Name:                | South Metz to I-35 Connector       | This project consists of the construction of a new two-lane undivided collector. |             |   |
| Limits:              | 4,935' W of I-35 SBFR to I-35 SBFR |                                                                                  |             |   |
| Impact Fee Class:    | Collector                          |                                                                                  |             |   |
| Length (lf):         | 4,935                              |                                                                                  |             |   |
| Service Area(s):     | Sanger                             |                                                                                  |             |   |

| Roadway Construction Cost Projection                         |                                  |                              |                     |                |
|--------------------------------------------------------------|----------------------------------|------------------------------|---------------------|----------------|
| No.                                                          | Item Description                 | Quantity                     | Unit                | Item Cost      |
| 103                                                          | Unclassified Roadway Excavation  | 9,870                        | cy                  | \$ 394,800     |
| 203                                                          | 8" Lime Stabilized Subgrade      | 19,192                       | sy                  | \$ 671,708     |
| 303                                                          | 8" 4,000 psi Reinforced Concrete | 15,902                       | sy                  | \$ 1,908,200   |
| 403                                                          | 4" Concrete Sidewalk             | 49,350                       | sf                  | \$ 493,500     |
| 503                                                          | Curb & Gutter                    | 9,870                        | lf                  | \$ 296,100     |
| 603                                                          | Topsoil                          | 9,322                        | sy                  | \$ 139,825     |
| Paving Construction Cost Subtotal:                           |                                  |                              |                     | \$ 3,904,133   |
| Major Construction Component Allowances**:                   |                                  |                              |                     |                |
| Item Description                                             |                                  | Notes                        | Allowance           | Item Cost      |
| ✓                                                            | Traffic Control                  | None Anticipated             | 0%                  | \$ -           |
| ✓                                                            | Pavement Markings/Markers        |                              | 3%                  | \$ 117,124     |
| ✓                                                            | Roadway Drainage                 | Standard Internal System     | 25%                 | \$ 976,033     |
|                                                              | Special Drainage Structures      | None Anticipated             | -                   | \$ -           |
| ✓                                                            | Water                            | Minor Adjustments            | 5%                  | \$ 195,207     |
| ✓                                                            | Sewer                            | Minor Adjustments            | 5%                  | \$ 195,207     |
| ✓                                                            | Landscaping and Irrigation       |                              | 4%                  | \$ 156,165     |
| ✓                                                            | Illumination                     | Standard Illumination System | 6%                  | \$ 234,248     |
|                                                              | Other:                           |                              | \$0                 | \$ -           |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              | Allowance Subtotal: | \$ 1,873,984   |
| Paving and Allowance Subtotal:                               |                                  |                              |                     | \$ 5,778,117   |
| Construction Contingency:                                    |                                  |                              |                     | 15% \$ 866,718 |
| Mobilization                                                 |                                  |                              |                     | 5% \$ 288,906  |
| Prep ROW                                                     |                                  |                              |                     | 1% \$ 57,781   |
| Construction Cost TOTAL:                                     |                                  |                              |                     | \$ 6,992,000   |

| Impact Fee Project Cost Summary |                       |           |              |
|---------------------------------|-----------------------|-----------|--------------|
| Item Description                | Notes:                | Allowance | Item Cost    |
| Construction:                   |                       | -         | \$ 6,992,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 1,118,720 |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 1,398,400 |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 9,509,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.



**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                                    | Description:                                                                                      | Project No. | 8 |
|----------------------|------------------------------------|---------------------------------------------------------------------------------------------------|-------------|---|
| Name:                | Utility Rd                         | <b>This project consists of widening the existing facility to a two-lane undivided collector.</b> |             |   |
| Limits:              | I-35 NBFR to 1,920' E of I-35 NBFR |                                                                                                   |             |   |
| Impact Fee Class:    | Collector                          |                                                                                                   |             |   |
| Length (lf):         | 1,920                              |                                                                                                   |             |   |
| Service Area(s):     | Sanger                             |                                                                                                   |             |   |

| Roadway Construction Cost Projection |                                  |          |      |            |              |
|--------------------------------------|----------------------------------|----------|------|------------|--------------|
| No.                                  | Item Description                 | Quantity | Unit | Unit Price | Item Cost    |
| 103                                  | Unclassified Roadway Excavation  | 3,840    | cy   | \$ 40.00   | \$ 153,600   |
| 203                                  | 8" Lime Stabilized Subgrade      | 7,467    | sy   | \$ 35.00   | \$ 261,333   |
| 303                                  | 8" 4,000 psi Reinforced Concrete | 6,187    | sy   | \$ 120.00  | \$ 742,400   |
| 403                                  | 4" Concrete Sidewalk             | 19,200   | sf   | \$ 10.00   | \$ 192,000   |
| 503                                  | Curb & Gutter                    | 3,840    | lf   | \$ 30.00   | \$ 115,200   |
| 603                                  | Topsoil                          | 3,627    | sy   | \$ 15.00   | \$ 54,400    |
| Paving Construction Cost Subtotal:   |                                  |          |      |            | \$ 1,518,933 |

| Major Construction Component Allowances**: |                                    |           |            |
|--------------------------------------------|------------------------------------|-----------|------------|
| Item Description                           | Notes                              | Allowance | Item Cost  |
| ✓ Traffic Control                          | Construction Phase Traffic Control | 5%        | \$ 75,947  |
| ✓ Pavement Markings/Markers                |                                    | 3%        | \$ 45,568  |
| ✓ Roadway Drainage                         | Standard Internal System           | 25%       | \$ 379,733 |
| ✓ Special Drainage Structures              | Major Stream Crossing              | -         | \$ 500,000 |
| ✓ Water                                    | Minor Adjustments                  | 5%        | \$ 75,947  |
| ✓ Sewer                                    | Minor Adjustments                  | 5%        | \$ 75,947  |
| ✓ Landscaping and Irrigation               |                                    | 4%        | \$ 60,757  |
| ✓ Illumination                             | Standard Illumination System       | 6%        | \$ 91,136  |
| Other:                                     |                                    | \$0       | \$ -       |

\*\*Allowances based on % of Paving Construction Cost Subtotal

|                                |     |    |           |
|--------------------------------|-----|----|-----------|
| Paving and Allowance Subtotal: |     | \$ | 2,823,968 |
| Construction Contingency:      | 15% | \$ | 423,595   |
| Mobilization                   | 5%  | \$ | 141,198   |
| Prep ROW                       | 5%  | \$ | 141,198   |
| Construction Cost TOTAL:       |     | \$ | 3,530,000 |

| Impact Fee Project Cost Summary |                    |           |              |
|---------------------------------|--------------------|-----------|--------------|
| Item Description                | Notes:             | Allowance | Item Cost    |
| Construction:                   |                    | -         | \$ 3,530,000 |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 564,800   |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 353,000   |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 4,448,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                      | Description:                                                                                      | Project No. | 9 |
|----------------------|----------------------|---------------------------------------------------------------------------------------------------|-------------|---|
| Name:                | Belz Rd              | <b>This project consists of widening the existing facility to a four-lane undivided arterial.</b> |             |   |
| Limits:              | Metz Rd to I-35 SBFR |                                                                                                   |             |   |
| Impact Fee Class:    | Minor Arterial       |                                                                                                   |             |   |
| Length (lf):         | 4,820                |                                                                                                   |             |   |
| Service Area(s):     | Sanger               |                                                                                                   |             |   |

| Roadway Construction Cost Projection |                                  |          |      |            |              |
|--------------------------------------|----------------------------------|----------|------|------------|--------------|
| No.                                  | Item Description                 | Quantity | Unit | Unit Price | Item Cost    |
| 102                                  | Unclassified Roadway Excavation  | 14,326   | cy   | \$ 40.00   | \$ 573,044   |
| 202                                  | 10" Lime Stabilized Subgrade     | 28,117   | sy   | \$ 40.00   | \$ 1,124,667 |
| 302                                  | 9" 4,000 psi Reinforced Concrete | 25,171   | sy   | \$ 130.00  | \$ 3,272,244 |
| 402                                  | 4" Concrete Sidewalk             | 48,200   | sf   | \$ 10.00   | \$ 482,000   |
| 502                                  | Curb & Gutter                    | 9,640    | lf   | \$ 30.00   | \$ 289,200   |
| 602                                  | Topsoil                          | 10,443   | sy   | \$ 15.00   | \$ 156,650   |
| Paving Construction Cost Subtotal:   |                                  |          |      |            | \$ 5,897,806 |

| Major Construction Component Allowances**:                   |                                                  |                     |              |
|--------------------------------------------------------------|--------------------------------------------------|---------------------|--------------|
| Item Description                                             | Notes                                            | Allowance           | Item Cost    |
| √ Traffic Control                                            | Construction Phase Traffic Control               | 5%                  | \$ 294,890   |
| √ Pavement Markings/Markers                                  |                                                  | 3%                  | \$ 176,934   |
| √ Roadway Drainage                                           | Standard Internal System                         | 25%                 | \$ 1,474,451 |
| √ Special Drainage Structures                                | Minor Stream Crossing (2), Major Stream Crossing | -                   | \$ 1,000,000 |
| √ Water                                                      | Minor Adjustments                                | 5%                  | \$ 294,890   |
| √ Sewer                                                      | Minor Adjustments                                | 5%                  | \$ 294,890   |
| √ Landscaping and Irrigation                                 |                                                  | 4%                  | \$ 235,912   |
| √ Illumination                                               | Standard Illumination System                     | 6%                  | \$ 353,868   |
| Other:                                                       |                                                  | \$0                 | \$ -         |
| **Allowances based on % of Paving Construction Cost Subtotal |                                                  | Allowance Subtotal: | \$ 4,125,837 |

|                                |                  |
|--------------------------------|------------------|
| Paving and Allowance Subtotal: | \$ 10,023,643    |
| Construction Contingency:      | 15% \$ 1,503,546 |
| Mobilization                   | 5% \$ 501,182    |
| Prep ROW                       | 5% \$ 501,182    |
| Construction Cost TOTAL:       | \$ 12,530,000    |

| Impact Fee Project Cost Summary |                    |           |               |
|---------------------------------|--------------------|-----------|---------------|
| Item Description                | Notes:             | Allowance | Item Cost     |
| Construction:                   |                    | -         | \$ 12,530,000 |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 2,004,800  |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 1,253,000  |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 15,788,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                     | Description:                                                                     | Project No. | 10 |
|----------------------|---------------------|----------------------------------------------------------------------------------|-------------|----|
| Name:                | Indian Ln (1)       | This project consists of the construction of a new four-lane undivided arterial. |             |    |
| Limits:              | I-35 SBFR to FM 455 |                                                                                  |             |    |
| Impact Fee Class:    | Minor Arterial      |                                                                                  |             |    |
| Length (lf):         | 5,630               |                                                                                  |             |    |
| Service Area(s):     | Sanger              |                                                                                  |             |    |

| Roadway Construction Cost Projection                         |                                  |                              |                     |                                |                  |
|--------------------------------------------------------------|----------------------------------|------------------------------|---------------------|--------------------------------|------------------|
| No.                                                          | Item Description                 | Quantity                     | Unit                | Unit Price                     | Item Cost        |
| 102                                                          | Unclassified Roadway Excavation  | 16,734                       | cy                  | \$ 40.00                       | \$ 669,344       |
| 202                                                          | 10" Lime Stabilized Subgrade     | 32,842                       | sy                  | \$ 40.00                       | \$ 1,313,667     |
| 302                                                          | 9" 4,000 psi Reinforced Concrete | 29,401                       | sy                  | \$ 130.00                      | \$ 3,822,144     |
| 402                                                          | 4" Concrete Sidewalk             | 56,300                       | sf                  | \$ 10.00                       | \$ 563,000       |
| 502                                                          | Curb & Gutter                    | 11,260                       | lf                  | \$ 30.00                       | \$ 337,800       |
| 602                                                          | Topsoil                          | 12,198                       | sy                  | \$ 15.00                       | \$ 182,975       |
| Paving Construction Cost Subtotal:                           |                                  |                              |                     |                                | \$ 6,888,931     |
| Major Construction Component Allowances**:                   |                                  |                              |                     |                                |                  |
| Item Description                                             |                                  | Notes                        | Allowance           | Item Cost                      |                  |
| ✓                                                            | Traffic Control                  | None Anticipated             | 0%                  | \$                             | -                |
| ✓                                                            | Pavement Markings/Markers        |                              | 3%                  | \$                             | 206,668          |
| ✓                                                            | Roadway Drainage                 | Standard Internal System     | 25%                 | \$                             | 1,722,233        |
| ✓                                                            | Special Drainage Structures      | Major Stream Crossing (2)    | -                   | \$                             | 1,000,000        |
| ✓                                                            | Water                            | Minor Adjustments            | 5%                  | \$                             | 344,447          |
| ✓                                                            | Sewer                            | Minor Adjustments            | 5%                  | \$                             | 344,447          |
| ✓                                                            | Landscaping and Irrigation       |                              | 4%                  | \$                             | 275,557          |
| ✓                                                            | Illumination                     | Standard Illumination System | 6%                  | \$                             | 413,336          |
| ✓                                                            | Other:                           | Railroad Crossing            | \$750,000           | \$                             | 750,000          |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              | Allowance Subtotal: | \$                             | 5,056,687        |
|                                                              |                                  |                              |                     | Paving and Allowance Subtotal: | \$ 11,945,617    |
|                                                              |                                  |                              |                     | Construction Contingency:      | 15% \$ 1,791,843 |
|                                                              |                                  |                              |                     | Mobilization                   | 5% \$ 597,281    |
|                                                              |                                  |                              |                     | Prep ROW                       | 1% \$ 119,456    |
|                                                              |                                  |                              |                     | Construction Cost TOTAL:       | \$ 14,455,000    |

| Impact Fee Project Cost Summary |                       |           |               |
|---------------------------------|-----------------------|-----------|---------------|
| Item Description                | Notes:                | Allowance | Item Cost     |
| Construction:                   |                       | -         | \$ 14,455,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 2,312,800  |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 2,891,000  |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 19,659,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                                            | Description: | Project No.                                                                                                                                             | 11 |
|----------------------|--------------------------------------------|--------------|---------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| Name:                | Indian Ln (2)                              |              | This project consists of the construction of the additional one lane of a three-lane undivided arterial in continuity with the adjacent cross-sections. |    |
| Limits:              | 1,290' N of McReynolds Rd to McReynolds Rd |              |                                                                                                                                                         |    |
| Impact Fee Class:    | Minor Arterial (1/3)                       |              |                                                                                                                                                         |    |
| Length (lf):         | 1,290                                      |              |                                                                                                                                                         |    |
| Service Area(s):     | Sanger                                     |              |                                                                                                                                                         |    |

| Roadway Construction Cost Projection                         |                                  |                                    |      |                     |            |
|--------------------------------------------------------------|----------------------------------|------------------------------------|------|---------------------|------------|
| No.                                                          | Item Description                 | Quantity                           | Unit | Unit Price          | Item Cost  |
| 104                                                          | Unclassified Roadway Excavation  | 1,003                              | cy   | \$ 40.00            | \$ 40,133  |
| 204                                                          | 10" Lime Stabilized Subgrade     | 1,935                              | sy   | \$ 40.00            | \$ 77,400  |
| 304                                                          | 9" 4,000 psi Reinforced Concrete | 1,577                              | sy   | \$ 130.00           | \$ 204,967 |
| 404                                                          | 4" Concrete Sidewalk             | 6,450                              | sf   | \$ 10.00            | \$ 64,500  |
| 504                                                          | Curb & Gutter                    | 1,290                              | lf   | \$ 30.00            | \$ 38,700  |
| 604                                                          | Topsoil                          | 1,362                              | sy   | \$ 15.00            | \$ 20,425  |
| Paving Construction Cost Subtotal:                           |                                  |                                    |      |                     | \$ 446,125 |
| Major Construction Component Allowances**:                   |                                  |                                    |      |                     |            |
|                                                              | Item Description                 | Notes                              |      | Allowance           | Item Cost  |
| √                                                            | Traffic Control                  | Construction Phase Traffic Control |      | 5%                  | \$ 22,306  |
| √                                                            | Pavement Markings/Markers        |                                    |      | 3%                  | \$ 13,384  |
|                                                              | Roadway Drainage                 | None Anticipated                   |      | 0%                  | \$ -       |
|                                                              | Special Drainage Structures      | Existing Major Stream Crossing     |      | -                   | \$ -       |
|                                                              | Water                            | None Anticipated                   |      | 0%                  | \$ -       |
|                                                              | Sewer                            | None Anticipated                   |      | 0%                  | \$ -       |
| √                                                            | Landscaping and Irrigation       |                                    |      | 4%                  | \$ 17,845  |
|                                                              | Illumination                     | None Anticipated                   |      | 0%                  | \$ -       |
|                                                              | Other:                           |                                    |      | \$0                 | \$ -       |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                                    |      |                     |            |
|                                                              |                                  |                                    |      | Allowance Subtotal: | \$ 53,535  |
| Paving and Allowance Subtotal:                               |                                  |                                    |      |                     | \$ 499,660 |
| Construction Contingency:                                    |                                  |                                    |      | 15%                 | \$ 74,949  |
| Mobilization                                                 |                                  |                                    |      | 5%                  | \$ 24,983  |
| Prep ROW                                                     |                                  |                                    |      | 5%                  | \$ 24,983  |
| Construction Cost TOTAL:                                     |                                  |                                    |      |                     | \$ 625,000 |

| Impact Fee Project Cost Summary |                                   |           |            |
|---------------------------------|-----------------------------------|-----------|------------|
| Item Description                | Notes:                            | Allowance | Item Cost  |
| Construction:                   |                                   | -         | \$ 625,000 |
| Engineering/Survey/Testing:     |                                   | 16%       | \$ 100,000 |
| ROW/Easement Acquisition:       | No ROW Acquisition Costs included | 0%        | \$ -       |
| Impact Fee Project Cost TOTAL:  |                                   |           | \$ 725,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.



City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                                            | Description:                                                                     | Project No. | 12 |
|----------------------|--------------------------------------------|----------------------------------------------------------------------------------|-------------|----|
| Name:                | Indian Ln (3)                              | This project consists of the construction of a new two-lane undivided collector. |             |    |
| Limits:              | McReynolds Rd to 3,365' S of McReynolds Rd |                                                                                  |             |    |
| Impact Fee Class:    | Collector                                  |                                                                                  |             |    |
| Length (lf):         | 3,365                                      |                                                                                  |             |    |
| Service Area(s):     | Sanger                                     |                                                                                  |             |    |

| Roadway Construction Cost Projection                         |                                  |                              |                     |                                |                |
|--------------------------------------------------------------|----------------------------------|------------------------------|---------------------|--------------------------------|----------------|
| No.                                                          | Item Description                 | Quantity                     | Unit                | Unit Price                     | Item Cost      |
| 103                                                          | Unclassified Roadway Excavation  | 6,730                        | cy                  | \$ 40.00                       | \$ 269,200     |
| 203                                                          | 8" Lime Stabilized Subgrade      | 13,086                       | sy                  | \$ 35.00                       | \$ 458,014     |
| 303                                                          | 8" 4,000 psi Reinforced Concrete | 10,843                       | sy                  | \$ 120.00                      | \$ 1,301,133   |
| 403                                                          | 4" Concrete Sidewalk             | 33,650                       | sf                  | \$ 10.00                       | \$ 336,500     |
| 503                                                          | Curb & Gutter                    | 6,730                        | lf                  | \$ 30.00                       | \$ 201,900     |
| 603                                                          | Topsoil                          | 6,356                        | sy                  | \$ 15.00                       | \$ 95,342      |
| Paving Construction Cost Subtotal:                           |                                  |                              |                     |                                | \$ 2,662,089   |
| Major Construction Component Allowances**:                   |                                  |                              |                     |                                |                |
| Item Description                                             |                                  | Notes                        | Allowance           | Item Cost                      |                |
| ✓                                                            | Traffic Control                  | None Anticipated             | 0%                  | \$                             | -              |
| ✓                                                            | Pavement Markings/Markers        |                              | 3%                  | \$                             | 79,863         |
| ✓                                                            | Roadway Drainage                 | Standard Internal System     | 25%                 | \$                             | 665,522        |
|                                                              | Special Drainage Structures      | None Anticipated             | -                   | \$                             | -              |
| ✓                                                            | Water                            | Minor Adjustments            | 5%                  | \$                             | 133,104        |
| ✓                                                            | Sewer                            | Minor Adjustments            | 5%                  | \$                             | 133,104        |
| ✓                                                            | Landscaping and Irrigation       |                              | 4%                  | \$                             | 106,484        |
| ✓                                                            | Illumination                     | Standard Illumination System | 6%                  | \$                             | 159,725        |
|                                                              | Other:                           |                              | \$0                 | \$                             | -              |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              | Allowance Subtotal: | \$                             | 1,277,803      |
|                                                              |                                  |                              |                     | Paving and Allowance Subtotal: | \$ 3,939,892   |
|                                                              |                                  |                              |                     | Construction Contingency:      | 15% \$ 590,984 |
|                                                              |                                  |                              |                     | Mobilization                   | 5% \$ 196,995  |
|                                                              |                                  |                              |                     | Prep ROW                       | 1% \$ 39,399   |
|                                                              |                                  |                              |                     | Construction Cost TOTAL:       | \$ 4,768,000   |

| Impact Fee Project Cost Summary |                       |           |              |
|---------------------------------|-----------------------|-----------|--------------|
| Item Description                | Notes:                | Allowance | Item Cost    |
| Construction:                   |                       | -         | \$ 4,768,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 762,880   |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 953,600   |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 6,484,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                                | Description:                                                                                                                                     | Project No. | 13 |
|----------------------|--------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------|-------------|----|
| Name:                | FM 455 (1)                     | <b>This project consisted of the City's contribution of the widening to the ultimate section. The overall City contribution was \$7,850,949.</b> |             |    |
| Limits:              | FM 2450 to 830' E of Marion Rd |                                                                                                                                                  |             |    |
| Impact Fee Class:    | Principal Arterial             |                                                                                                                                                  |             |    |
| Length (lf):         | 28,860                         |                                                                                                                                                  |             |    |
| Service Area(s):     | Sanger                         |                                                                                                                                                  |             |    |

| Impact Fee Project Cost Summary |        |           |              |
|---------------------------------|--------|-----------|--------------|
| Item Description                | Notes: | Allowance | Item Cost    |
| Construction:                   |        |           |              |
| Engineering/Survey/Testing:     |        |           | \$ 7,850,949 |
| ROW/Easement Acquisition:       |        |           |              |
| Impact Fee Project Cost TOTAL:  |        |           | \$ 7,850,949 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                                            | Description:                                                                                          | Project No. | 14 |
|----------------------|--------------------------------------------|-------------------------------------------------------------------------------------------------------|-------------|----|
| Name:                | FM 455 (2)                                 | <b>This project consists of widening the existing facility to a four-lane divided TxDOT arterial.</b> |             |    |
| Limits:              | 830' E of Marion Rd to 2,110' S of FM 2164 |                                                                                                       |             |    |
| Impact Fee Class:    | Principal Arterial                         |                                                                                                       |             |    |
| Length (lf):         | 15,015                                     |                                                                                                       |             |    |
| Service Area(s):     | Sanger                                     |                                                                                                       |             |    |

| Roadway Construction Cost Projection |                                  |          |      |            |               |
|--------------------------------------|----------------------------------|----------|------|------------|---------------|
| No.                                  | Item Description                 | Quantity | Unit | Unit Price | Item Cost     |
| 101                                  | Unclassified Roadway Excavation  | 49,216   | cy   | \$ 40.00   | \$ 1,968,633  |
| 201                                  | 10" Lime Stabilized Subgrade     | 95,095   | sy   | \$ 40.00   | \$ 3,803,800  |
| 301                                  | 9" 4,000 psi Reinforced Concrete | 85,085   | sy   | \$ 130.00  | \$ 11,061,050 |
| 401                                  | 4" Concrete Sidewalk             | 150,150  | sf   | \$ 10.00   | \$ 1,501,500  |
| 501                                  | Curb & Gutter                    | 60,060   | lf   | \$ 30.00   | \$ 1,801,800  |
| 601                                  | Topsoil                          | 61,728   | sy   | \$ 15.00   | \$ 925,925    |
| 701                                  | Turn Lanes and Median Openings   | 12,588   | sy   | \$ 170.00  | \$ 2,140,017  |
| Paving Construction Cost Subtotal:   |                                  |          |      |            | \$ 23,202,725 |

| Major Construction Component Allowances**: |                                                      |           |               |
|--------------------------------------------|------------------------------------------------------|-----------|---------------|
| Item Description                           | Notes                                                | Allowance | Item Cost     |
| ✓ Traffic Control                          | Construction Phase Traffic Control                   | 5%        | \$ 1,160,136  |
| ✓ Pavement Markings/Markers                |                                                      | 3%        | \$ 696,082    |
| ✓ Roadway Drainage                         | Standard Internal System                             | 25%       | \$ 5,800,681  |
| ✓ Special Drainage Structures              | Minor Stream Crossing (2), Major Stream Crossing (4) | -         | \$ 2,500,000  |
| ✓ Water                                    | Minor Adjustments                                    | 5%        | \$ 1,160,136  |
| ✓ Sewer                                    | Minor Adjustments                                    | 5%        | \$ 1,160,136  |
| ✓ Landscaping and Irrigation               |                                                      | 4%        | \$ 928,109    |
| ✓ Illumination                             | Standard Illumination System                         | 6%        | \$ 1,392,164  |
| Other:                                     |                                                      | \$0       | \$ -          |
| Allowance Subtotal:                        |                                                      |           | \$ 14,797,444 |

\*\*Allowances based on % of Paving Construction Cost Subtotal

|                                |                  |
|--------------------------------|------------------|
| Paving and Allowance Subtotal: | \$ 38,000,169    |
| Construction Contingency:      | 15% \$ 5,700,025 |
| Mobilization                   | 5% \$ 1,900,008  |
| Prep ROW                       | 5% \$ 1,900,008  |
| Construction Cost TOTAL:       | \$ 47,501,000    |

| Impact Fee Project Cost Summary                        |               |           |               |
|--------------------------------------------------------|---------------|-----------|---------------|
| Item Description                                       | Notes:        | Allowance | Item Cost     |
| Construction:                                          |               | -         | \$ 47,501,000 |
| Engineering/Survey/Testing:                            |               | 16%       | \$ 7,600,160  |
| ROW/Easement Acquisition:                              | TxDOT Roadway | 0%        | \$ -          |
| Impact Fee Project Cost TOTAL (20% City Contribution): |               |           | \$ 11,020,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                         | Description:                                                                               | Project No. | 15 |
|----------------------|-------------------------|--------------------------------------------------------------------------------------------|-------------|----|
| Name:                | Willow St               | This project consists of widening the existing facility to a four-lane undivided arterial. |             |    |
| Limits:              | Cowling Rd to Indian Ln |                                                                                            |             |    |
| Impact Fee Class:    | Minor Arterial          |                                                                                            |             |    |
| Length (lf):         | 5,015                   |                                                                                            |             |    |
| Service Area(s):     | Sanger                  |                                                                                            |             |    |

| Roadway Construction Cost Projection                         |                                  |                                                               |                     |                                |                  |
|--------------------------------------------------------------|----------------------------------|---------------------------------------------------------------|---------------------|--------------------------------|------------------|
| No.                                                          | Item Description                 | Quantity                                                      | Unit                | Unit Price                     | Item Cost        |
| 102                                                          | Unclassified Roadway Excavation  | 14,906                                                        | cy                  | \$ 40.00                       | \$ 596,228       |
| 202                                                          | 10" Lime Stabilized Subgrade     | 29,254                                                        | sy                  | \$ 40.00                       | \$ 1,170,167     |
| 302                                                          | 9" 4,000 psi Reinforced Concrete | 26,189                                                        | sy                  | \$ 130.00                      | \$ 3,404,628     |
| 402                                                          | 4" Concrete Sidewalk             | 50,150                                                        | sf                  | \$ 10.00                       | \$ 501,500       |
| 502                                                          | Curb & Gutter                    | 10,030                                                        | lf                  | \$ 30.00                       | \$ 300,900       |
| 602                                                          | Topsoil                          | 10,866                                                        | sy                  | \$ 15.00                       | \$ 162,988       |
| Paving Construction Cost Subtotal:                           |                                  |                                                               |                     |                                | \$ 6,136,410     |
| Major Construction Component Allowances**:                   |                                  |                                                               |                     |                                |                  |
| Item Description                                             |                                  | Notes                                                         | Allowance           | Item Cost                      |                  |
| √                                                            | Traffic Control                  | Construction Phase Traffic Control                            | 5%                  | \$                             | 306,820          |
| √                                                            | Pavement Markings/Markers        |                                                               | 3%                  | \$                             | 184,092          |
| √                                                            | Roadway Drainage                 | Standard Internal System                                      | 25%                 | \$                             | 1,534,102        |
| √                                                            | Special Drainage Structures      | Minor Stream Crossing, Major Stream Crossing, Bridge Crossing | -                   | \$                             | 1,750,000        |
| √                                                            | Water                            | Minor Adjustments                                             | 5%                  | \$                             | 306,820          |
| √                                                            | Sewer                            | Minor Adjustments                                             | 5%                  | \$                             | 306,820          |
| √                                                            | Landscaping and Irrigation       |                                                               | 4%                  | \$                             | 245,456          |
| √                                                            | Illumination                     | Standard Illumination System                                  | 6%                  | \$                             | 368,185          |
| √                                                            | Other:                           | Railroad Crossing                                             | \$750,000           | \$                             | 750,000          |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                                                               | Allowance Subtotal: | \$                             | 5,752,297        |
|                                                              |                                  |                                                               |                     | Paving and Allowance Subtotal: | \$ 11,888,707    |
|                                                              |                                  |                                                               |                     | Construction Contingency:      | 15% \$ 1,783,306 |
|                                                              |                                  |                                                               |                     | Mobilization                   | 5% \$ 594,435    |
|                                                              |                                  |                                                               |                     | Prep ROW                       | 5% \$ 594,435    |
|                                                              |                                  |                                                               |                     | Construction Cost TOTAL:       | \$ 14,861,000    |

| Impact Fee Project Cost Summary |                    |           |               |
|---------------------------------|--------------------|-----------|---------------|
| Item Description                | Notes:             | Allowance | Item Cost     |
| Construction:                   |                    | -         | \$ 14,861,000 |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 2,377,760  |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 1,486,100  |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 18,725,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.



**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                                | Description:                                                                                      | Project No. | 16 |
|----------------------|--------------------------------|---------------------------------------------------------------------------------------------------|-------------|----|
| Name:                | McReynolds Rd                  | <b>This project consists of widening the existing facility to a four-lane undivided arterial.</b> |             |    |
| Limits:              | Indian Ln to 600' E of PR 6630 |                                                                                                   |             |    |
| Impact Fee Class:    | Minor Arterial                 |                                                                                                   |             |    |
| Length (lf):         | 5,715                          |                                                                                                   |             |    |
| Service Area(s):     | Sanger                         |                                                                                                   |             |    |

| Roadway Construction Cost Projection |                                  |          |      |            |              |
|--------------------------------------|----------------------------------|----------|------|------------|--------------|
| No.                                  | Item Description                 | Quantity | Unit | Unit Price | Item Cost    |
| 102                                  | Unclassified Roadway Excavation  | 16,986   | cy   | \$ 40.00   | \$ 679,450   |
| 202                                  | 10" Lime Stabilized Subgrade     | 33,338   | sy   | \$ 40.00   | \$ 1,333,500 |
| 302                                  | 9" 4,000 psi Reinforced Concrete | 29,845   | sy   | \$ 130.00  | \$ 3,879,850 |
| 402                                  | 4" Concrete Sidewalk             | 57,150   | sf   | \$ 10.00   | \$ 571,500   |
| 502                                  | Curb & Gutter                    | 11,430   | lf   | \$ 30.00   | \$ 342,900   |
| 602                                  | Topsoil                          | 12,383   | sy   | \$ 15.00   | \$ 185,738   |
| Paving Construction Cost Subtotal:   |                                  |          |      |            | \$ 6,992,938 |

| Major Construction Component Allowances**: |                                                |           |              |
|--------------------------------------------|------------------------------------------------|-----------|--------------|
| Item Description                           | Notes                                          | Allowance | Item Cost    |
| ✓ Traffic Control                          | Construction Phase Traffic Control             | 5%        | \$ 349,647   |
| ✓ Pavement Markings/Markers                |                                                | 3%        | \$ 209,788   |
| ✓ Roadway Drainage                         | Standard Internal System                       | 25%       | \$ 1,748,234 |
| ✓ Special Drainage Structures              | Major Stream Crossing (2), Bridge Crossing (2) | -         | \$ 3,000,000 |
| ✓ Water                                    | Minor Adjustments                              | 5%        | \$ 349,647   |
| ✓ Sewer                                    | Minor Adjustments                              | 5%        | \$ 349,647   |
| ✓ Landscaping and Irrigation               |                                                | 4%        | \$ 279,718   |
| ✓ Illumination                             | Standard Illumination System                   | 6%        | \$ 419,576   |
| Other:                                     |                                                | \$0       | \$ -         |

\*\*Allowances based on % of Paving Construction Cost Subtotal

|                                |     |    |            |
|--------------------------------|-----|----|------------|
| Paving and Allowance Subtotal: |     | \$ | 13,699,194 |
| Construction Contingency:      | 15% | \$ | 2,054,879  |
| Mobilization                   | 5%  | \$ | 684,960    |
| Prep ROW                       | 5%  | \$ | 684,960    |
| Construction Cost TOTAL:       |     | \$ | 17,124,000 |

| Impact Fee Project Cost Summary |                    |           |               |
|---------------------------------|--------------------|-----------|---------------|
| Item Description                | Notes:             | Allowance | Item Cost     |
| Construction:                   |                    | -         | \$ 17,124,000 |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 2,739,840  |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 1,712,400  |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 21,576,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                        | Description:                                                                                            | Project No. | 17 |
|----------------------|------------------------|---------------------------------------------------------------------------------------------------------|-------------|----|
| Name:                | 5th St                 | <b>This project consists of widening the existing facility to a four-lane undivided TxDOT arterial.</b> |             |    |
| Limits:              | Keaton Rd to I-35 SBFR |                                                                                                         |             |    |
| Impact Fee Class:    | Minor Arterial         |                                                                                                         |             |    |
| Length (lf):         | 900                    |                                                                                                         |             |    |
| Service Area(s):     | Sanger                 |                                                                                                         |             |    |

| Roadway Construction Cost Projection                         |                                  |                                    |                     |                                |                |
|--------------------------------------------------------------|----------------------------------|------------------------------------|---------------------|--------------------------------|----------------|
| No.                                                          | Item Description                 | Quantity                           | Unit                | Unit Price                     | Item Cost      |
| 102                                                          | Unclassified Roadway Excavation  | 2,675                              | cy                  | \$ 40.00                       | \$ 107,000     |
| 202                                                          | 10" Lime Stabilized Subgrade     | 5,250                              | sy                  | \$ 40.00                       | \$ 210,000     |
| 302                                                          | 9" 4,000 psi Reinforced Concrete | 4,700                              | sy                  | \$ 130.00                      | \$ 611,000     |
| 402                                                          | 4" Concrete Sidewalk             | 9,000                              | sf                  | \$ 10.00                       | \$ 90,000      |
| 502                                                          | Curb & Gutter                    | 1,800                              | lf                  | \$ 30.00                       | \$ 54,000      |
| 602                                                          | Topsoil                          | 1,950                              | sy                  | \$ 15.00                       | \$ 29,250      |
| Paving Construction Cost Subtotal:                           |                                  |                                    |                     |                                | \$ 1,101,250   |
| Major Construction Component Allowances**:                   |                                  |                                    |                     |                                |                |
| Item Description                                             |                                  | Notes                              | Allowance           | Item Cost                      |                |
| ✓                                                            | Traffic Control                  | Construction Phase Traffic Control | 5%                  | \$                             | 55,063         |
| ✓                                                            | Pavement Markings/Markers        |                                    | 3%                  | \$                             | 33,038         |
| ✓                                                            | Roadway Drainage                 | Standard Internal System           | 25%                 | \$                             | 275,313        |
|                                                              | Special Drainage Structures      | None Anticipated                   | -                   | \$                             | -              |
| ✓                                                            | Water                            | Minor Adjustments                  | 5%                  | \$                             | 55,063         |
| ✓                                                            | Sewer                            | Minor Adjustments                  | 5%                  | \$                             | 55,063         |
| ✓                                                            | Landscaping and Irrigation       |                                    | 4%                  | \$                             | 44,050         |
| ✓                                                            | Illumination                     | Standard Illumination System       | 6%                  | \$                             | 66,075         |
|                                                              | Other:                           |                                    | \$0                 | \$                             | -              |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                                    | Allowance Subtotal: | \$                             | 583,663        |
|                                                              |                                  |                                    |                     | Paving and Allowance Subtotal: | \$ 1,684,913   |
|                                                              |                                  |                                    |                     | Construction Contingency:      | 15% \$ 252,737 |
|                                                              |                                  |                                    |                     | Mobilization                   | 5% \$ 84,246   |
|                                                              |                                  |                                    |                     | Prep ROW                       | 5% \$ 84,246   |
|                                                              |                                  |                                    |                     | Construction Cost TOTAL:       | \$ 2,107,000   |

| Impact Fee Project Cost Summary                       |               |           |              |
|-------------------------------------------------------|---------------|-----------|--------------|
| Item Description                                      | Notes:        | Allowance | Item Cost    |
| Construction:                                         |               | -         | \$ 2,107,000 |
| Engineering/Survey/Testing:                           |               | 16%       | \$ 337,120   |
| ROW/Easement Acquisition:                             | TxDOT Roadway | 0%        | \$ -         |
| Impact Fee Project Cost TOTAL (20% City Contribution) |               |           | \$ 489,000   |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                               | Description:                                                                     | Project No. | 18 |
|----------------------|-------------------------------|----------------------------------------------------------------------------------|-------------|----|
| Name:                | Cowling to Railroad Connector | This project consists of the construction of a new four-lane undivided arterial. |             |    |
| Limits:              | Cowling Rd to Railroad Ave    |                                                                                  |             |    |
| Impact Fee Class:    | Minor Arterial                |                                                                                  |             |    |
| Length (lf):         | 2,740                         |                                                                                  |             |    |
| Service Area(s):     | Sanger                        |                                                                                  |             |    |

| Roadway Construction Cost Projection                         |                                  |                              |                     |                                |                |
|--------------------------------------------------------------|----------------------------------|------------------------------|---------------------|--------------------------------|----------------|
| No.                                                          | Item Description                 | Quantity                     | Unit                | Unit Price                     | Item Cost      |
| 102                                                          | Unclassified Roadway Excavation  | 8,144                        | cy                  | \$ 40.00                       | \$ 325,756     |
| 202                                                          | 10" Lime Stabilized Subgrade     | 15,983                       | sy                  | \$ 40.00                       | \$ 639,333     |
| 302                                                          | 9" 4,000 psi Reinforced Concrete | 14,309                       | sy                  | \$ 130.00                      | \$ 1,860,156   |
| 402                                                          | 4" Concrete Sidewalk             | 27,400                       | sf                  | \$ 10.00                       | \$ 274,000     |
| 502                                                          | Curb & Gutter                    | 5,480                        | lf                  | \$ 30.00                       | \$ 164,400     |
| 602                                                          | Topsoil                          | 5,937                        | sy                  | \$ 15.00                       | \$ 89,050      |
| Paving Construction Cost Subtotal:                           |                                  |                              |                     |                                | \$ 3,352,694   |
| Major Construction Component Allowances**:                   |                                  |                              |                     |                                |                |
| Item Description                                             |                                  | Notes                        | Allowance           | Item Cost                      |                |
| ✓                                                            | Traffic Control                  | None Anticipated             | 0%                  | \$                             | -              |
| ✓                                                            | Pavement Markings/Markers        |                              | 3%                  | \$                             | 100,581        |
| ✓                                                            | Roadway Drainage                 | Standard Internal System     | 25%                 | \$                             | 838,174        |
|                                                              | Special Drainage Structures      | None Anticipated             | -                   | \$                             | -              |
| ✓                                                            | Water                            | Minor Adjustments            | 5%                  | \$                             | 167,635        |
| ✓                                                            | Sewer                            | Minor Adjustments            | 5%                  | \$                             | 167,635        |
| ✓                                                            | Landscaping and Irrigation       |                              | 4%                  | \$                             | 134,108        |
| ✓                                                            | Illumination                     | Standard Illumination System | 6%                  | \$                             | 201,162        |
|                                                              | Other:                           |                              | \$0                 | \$                             | -              |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              | Allowance Subtotal: | \$                             | 1,609,293      |
|                                                              |                                  |                              |                     | Paving and Allowance Subtotal: | \$ 4,961,988   |
|                                                              |                                  |                              |                     | Construction Contingency:      | 15% \$ 744,298 |
|                                                              |                                  |                              |                     | Mobilization                   | 5% \$ 248,099  |
|                                                              |                                  |                              |                     | Prep ROW                       | 1% \$ 49,620   |
|                                                              |                                  |                              |                     | Construction Cost TOTAL:       | \$ 6,005,000   |

| Impact Fee Project Cost Summary |                       |           |              |
|---------------------------------|-----------------------|-----------|--------------|
| Item Description                | Notes:                | Allowance | Item Cost    |
| Construction:                   |                       | -         | \$ 6,005,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 960,800   |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 1,201,000 |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 8,167,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.

updated: 7/10/2024

| Project Information: |                                          | Description:                                                                            | Project No. | 19 |
|----------------------|------------------------------------------|-----------------------------------------------------------------------------------------|-------------|----|
| Name:                | Rector Rd                                | <b>This project consists of the construction of a new two-lane undivided collector.</b> |             |    |
| Limits:              | 2,730' W of Railroad Ave to Railroad Ave |                                                                                         |             |    |
| Impact Fee Class:    | Collector                                |                                                                                         |             |    |
| Length (lf):         | 2,730                                    |                                                                                         |             |    |
| Service Area(s):     | Sanger                                   |                                                                                         |             |    |

| Roadway Construction Cost Projection |                                  |          |      |            |              |
|--------------------------------------|----------------------------------|----------|------|------------|--------------|
| No.                                  | Item Description                 | Quantity | Unit | Unit Price | Item Cost    |
| 103                                  | Unclassified Roadway Excavation  | 5,460    | cy   | \$ 40.00   | \$ 218,400   |
| 203                                  | 8" Lime Stabilized Subgrade      | 10,617   | sy   | \$ 35.00   | \$ 371,583   |
| 303                                  | 8" 4,000 psi Reinforced Concrete | 8,797    | sy   | \$ 120.00  | \$ 1,055,600 |
| 403                                  | 4" Concrete Sidewalk             | 27,300   | sf   | \$ 10.00   | \$ 273,000   |
| 503                                  | Curb & Gutter                    | 5,460    | lf   | \$ 30.00   | \$ 163,800   |
| 603                                  | Topsoil                          | 5,157    | sy   | \$ 15.00   | \$ 77,350    |
| Paving Construction Cost Subtotal:   |                                  |          |      |            | \$ 2,159,733 |

| Major Construction Component Allowances**: |                              |           |              |
|--------------------------------------------|------------------------------|-----------|--------------|
| Item Description                           | Notes                        | Allowance | Item Cost    |
| ✓ Traffic Control                          | None Anticipated             | 0%        | \$ -         |
| ✓ Pavement Markings/Markers                |                              | 3%        | \$ 64,792    |
| ✓ Roadway Drainage                         | Standard Internal System     | 25%       | \$ 539,933   |
| ✓ Special Drainage Structures              | Bridge Crossing              | -         | \$ 1,000,000 |
| ✓ Water                                    | Minor Adjustments            | 5%        | \$ 107,987   |
| ✓ Sewer                                    | Minor Adjustments            | 5%        | \$ 107,987   |
| ✓ Landscaping and Irrigation               |                              | 4%        | \$ 86,389    |
| ✓ Illumination                             | Standard Illumination System | 6%        | \$ 129,584   |
| ✓ Other:                                   | Railroad Crossing            | \$750,000 | \$ 750,000   |

\*\*Allowances based on % of Paving Construction Cost Subtotal

|                                |     |    |           |
|--------------------------------|-----|----|-----------|
| Paving and Allowance Subtotal: |     | \$ | 4,946,405 |
| Construction Contingency:      | 15% | \$ | 741,961   |
| Mobilization                   | 5%  | \$ | 247,320   |
| Prep ROW                       | 1%  | \$ | 49,464    |
| Construction Cost TOTAL:       |     | \$ | 5,986,000 |

| Impact Fee Project Cost Summary |                       |           |              |
|---------------------------------|-----------------------|-----------|--------------|
| Item Description                | Notes:                | Allowance | Item Cost    |
| Construction:                   |                       | -         | \$ 5,986,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 957,760   |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 1,197,200 |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 8,141,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.



**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                                                 | Description:                                                                     | Project No. | 20 |
|----------------------|-------------------------------------------------|----------------------------------------------------------------------------------|-------------|----|
| Name:                | N Tejas Dr                                      | This project consists of the construction of a new two-lane undivided collector. |             |    |
| Limits:              | 1,245' S of FM 455 to 1,490' N of Duck Creek Rd |                                                                                  |             |    |
| Impact Fee Class:    | Collector                                       |                                                                                  |             |    |
| Length (lf):         | 1,320                                           |                                                                                  |             |    |
| Service Area(s):     | Sanger                                          |                                                                                  |             |    |

| Roadway Construction Cost Projection                         |                                  |                              |      |                                |                |
|--------------------------------------------------------------|----------------------------------|------------------------------|------|--------------------------------|----------------|
| No.                                                          | Item Description                 | Quantity                     | Unit | Unit Price                     | Item Cost      |
| 103                                                          | Unclassified Roadway Excavation  | 2,640                        | cy   | \$ 40.00                       | \$ 105,600     |
| 203                                                          | 8" Lime Stabilized Subgrade      | 5,133                        | sy   | \$ 35.00                       | \$ 179,667     |
| 303                                                          | 8" 4,000 psi Reinforced Concrete | 4,253                        | sy   | \$ 120.00                      | \$ 510,400     |
| 403                                                          | 4" Concrete Sidewalk             | 13,200                       | sf   | \$ 10.00                       | \$ 132,000     |
| 503                                                          | Curb & Gutter                    | 2,640                        | lf   | \$ 30.00                       | \$ 79,200      |
| 603                                                          | Topsoil                          | 2,493                        | sy   | \$ 15.00                       | \$ 37,400      |
| Paving Construction Cost Subtotal:                           |                                  |                              |      |                                | \$ 1,044,267   |
| Major Construction Component Allowances**:                   |                                  |                              |      |                                |                |
| Item Description                                             |                                  | Notes                        |      | Allowance                      | Item Cost      |
|                                                              | Traffic Control                  | None Anticipated             |      | 0%                             | \$ -           |
| √                                                            | Pavement Markings/Markers        |                              |      | 3%                             | \$ 31,328      |
| √                                                            | Roadway Drainage                 | Standard Internal System     |      | 25%                            | \$ 261,067     |
|                                                              | Special Drainage Structures      | None Anticipated             |      | -                              | \$ -           |
| √                                                            | Water                            | Minor Adjustments            |      | 5%                             | \$ 52,213      |
| √                                                            | Sewer                            | Minor Adjustments            |      | 5%                             | \$ 52,213      |
| √                                                            | Landscaping and Irrigation       |                              |      | 4%                             | \$ 41,771      |
| √                                                            | Illumination                     | Standard Illumination System |      | 6%                             | \$ 62,656      |
|                                                              | Other:                           |                              |      | \$0                            | \$ -           |
|                                                              |                                  |                              |      | Allowance Subtotal:            | \$ 501,248     |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              |      |                                |                |
|                                                              |                                  |                              |      | Paving and Allowance Subtotal: | \$ 1,545,515   |
|                                                              |                                  |                              |      | Construction Contingency:      | 15% \$ 231,827 |
|                                                              |                                  |                              |      | Mobilization                   | 5% \$ 77,276   |
|                                                              |                                  |                              |      | Prep ROW                       | 1% \$ 15,455   |
|                                                              |                                  |                              |      | Construction Cost TOTAL:       | \$ 1,871,000   |

| Impact Fee Project Cost Summary |                       |           |              |
|---------------------------------|-----------------------|-----------|--------------|
| Item Description                | Notes:                | Allowance | Item Cost    |
| Construction:                   |                       | -         | \$ 1,871,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 299,360   |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 374,200   |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 2,545,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                      | Description:                                                                     | Project No. | 21 |
|----------------------|----------------------|----------------------------------------------------------------------------------|-------------|----|
| Name:                | Jennifer Cir (1)     | This project consists of the construction of a new two-lane undivided collector. |             |    |
| Limits:              | Lois Rd W to Belz Rd |                                                                                  |             |    |
| Impact Fee Class:    | Collector            |                                                                                  |             |    |
| Length (lf):         | 8,105                |                                                                                  |             |    |
| Service Area(s):     | Sanger               |                                                                                  |             |    |

| Roadway Construction Cost Projection                         |                                  |                              |                     |                                |                  |
|--------------------------------------------------------------|----------------------------------|------------------------------|---------------------|--------------------------------|------------------|
| No.                                                          | Item Description                 | Quantity                     | Unit                | Unit Price                     | Item Cost        |
| 103                                                          | Unclassified Roadway Excavation  | 16,210                       | cy                  | \$ 40.00                       | \$ 648,400       |
| 203                                                          | 8" Lime Stabilized Subgrade      | 31,519                       | sy                  | \$ 35.00                       | \$ 1,103,181     |
| 303                                                          | 8" 4,000 psi Reinforced Concrete | 26,116                       | sy                  | \$ 120.00                      | \$ 3,133,933     |
| 403                                                          | 4" Concrete Sidewalk             | 81,050                       | sf                  | \$ 10.00                       | \$ 810,500       |
| 503                                                          | Curb & Gutter                    | 16,210                       | lf                  | \$ 30.00                       | \$ 486,300       |
| 603                                                          | Topsoil                          | 15,309                       | sy                  | \$ 15.00                       | \$ 229,642       |
| Paving Construction Cost Subtotal:                           |                                  |                              |                     |                                | \$ 6,411,956     |
| Major Construction Component Allowances**:                   |                                  |                              |                     |                                |                  |
| Item Description                                             |                                  | Notes                        | Allowance           | Item Cost                      |                  |
| ✓                                                            | Traffic Control                  | None Anticipated             | 0%                  | \$                             | -                |
| ✓                                                            | Pavement Markings/Markers        |                              | 3%                  | \$                             | 192,359          |
| ✓                                                            | Roadway Drainage                 | Standard Internal System     | 25%                 | \$                             | 1,602,989        |
| ✓                                                            | Special Drainage Structures      | Minor Stream Crossing        | -                   | \$                             | 250,000          |
| ✓                                                            | Water                            | Minor Adjustments            | 5%                  | \$                             | 320,598          |
| ✓                                                            | Sewer                            | Minor Adjustments            | 5%                  | \$                             | 320,598          |
| ✓                                                            | Landscaping and Irrigation       |                              | 4%                  | \$                             | 256,478          |
| ✓                                                            | Illumination                     | Standard Illumination System | 6%                  | \$                             | 384,717          |
|                                                              | Other:                           |                              | \$0                 | \$                             | -                |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              | Allowance Subtotal: | \$                             | 3,327,739        |
|                                                              |                                  |                              |                     | Paving and Allowance Subtotal: | \$ 9,739,694     |
|                                                              |                                  |                              |                     | Construction Contingency:      | 15% \$ 1,460,954 |
|                                                              |                                  |                              |                     | Mobilization                   | 5% \$ 486,985    |
|                                                              |                                  |                              |                     | Prep ROW                       | 1% \$ 97,397     |
|                                                              |                                  |                              |                     | Construction Cost TOTAL:       | \$ 11,786,000    |

| Impact Fee Project Cost Summary |                       |           |               |
|---------------------------------|-----------------------|-----------|---------------|
| Item Description                | Notes:                | Allowance | Item Cost     |
| Construction:                   |                       | -         | \$ 11,786,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 1,885,760  |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 2,357,200  |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 16,029,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                                | Description:                                                                                      | Project No. | 22 |
|----------------------|--------------------------------|---------------------------------------------------------------------------------------------------|-------------|----|
| Name:                | Jennifer Cir (2)               | <b>This project consists of widening the existing facility to a two-lane undivided collector.</b> |             |    |
| Limits:              | Belz Rd to 1,555' S of Belz Rd |                                                                                                   |             |    |
| Impact Fee Class:    | Collector                      |                                                                                                   |             |    |
| Length (lf):         | 1,555                          |                                                                                                   |             |    |
| Service Area(s):     | Sanger                         |                                                                                                   |             |    |

| Roadway Construction Cost Projection |                                  |          |      |            |              |
|--------------------------------------|----------------------------------|----------|------|------------|--------------|
| No.                                  | Item Description                 | Quantity | Unit | Unit Price | Item Cost    |
| 103                                  | Unclassified Roadway Excavation  | 3,110    | cy   | \$ 40.00   | \$ 124,400   |
| 203                                  | 8" Lime Stabilized Subgrade      | 6,047    | sy   | \$ 35.00   | \$ 211,653   |
| 303                                  | 8" 4,000 psi Reinforced Concrete | 5,011    | sy   | \$ 120.00  | \$ 601,267   |
| 403                                  | 4" Concrete Sidewalk             | 15,550   | sf   | \$ 10.00   | \$ 155,500   |
| 503                                  | Curb & Gutter                    | 3,110    | lf   | \$ 30.00   | \$ 93,300    |
| 603                                  | Topsoil                          | 2,937    | sy   | \$ 15.00   | \$ 44,058    |
| Paving Construction Cost Subtotal:   |                                  |          |      |            | \$ 1,230,178 |

| Major Construction Component Allowances**:                   |                                    |                     |            |
|--------------------------------------------------------------|------------------------------------|---------------------|------------|
| Item Description                                             | Notes                              | Allowance           | Item Cost  |
| ✓ Traffic Control                                            | Construction Phase Traffic Control | 5%                  | \$ 61,509  |
| ✓ Pavement Markings/Markers                                  |                                    | 3%                  | \$ 36,905  |
| ✓ Roadway Drainage                                           | Standard Internal System           | 25%                 | \$ 307,544 |
| Special Drainage Structures                                  | None Anticipated                   | -                   | \$ -       |
| ✓ Water                                                      | Minor Adjustments                  | 5%                  | \$ 61,509  |
| ✓ Sewer                                                      | Minor Adjustments                  | 5%                  | \$ 61,509  |
| ✓ Landscaping and Irrigation                                 |                                    | 4%                  | \$ 49,207  |
| ✓ Illumination                                               | Standard Illumination System       | 6%                  | \$ 73,811  |
| Other:                                                       |                                    | \$0                 | \$ -       |
| **Allowances based on % of Paving Construction Cost Subtotal |                                    | Allowance Subtotal: | \$ 651,994 |

|                                |     |    |           |
|--------------------------------|-----|----|-----------|
| Paving and Allowance Subtotal: |     | \$ | 1,882,172 |
| Construction Contingency:      | 15% | \$ | 282,326   |
| Mobilization                   | 5%  | \$ | 94,109    |
| Prep ROW                       | 5%  | \$ | 94,109    |
| Construction Cost TOTAL:       |     | \$ | 2,353,000 |

| Impact Fee Project Cost Summary |                    |           |              |
|---------------------------------|--------------------|-----------|--------------|
| Item Description                | Notes:             | Allowance | Item Cost    |
| Construction:                   |                    | -         | \$ 2,353,000 |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 376,480   |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 235,300   |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 2,965,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.

updated: 7/10/2024

| Project Information: |                                 | Description:                                                                            | Project No. | 23 |
|----------------------|---------------------------------|-----------------------------------------------------------------------------------------|-------------|----|
| Name:                | Jennifer Cir (3)                | <b>This project consists of the construction of a new two-lane undivided collector.</b> |             |    |
| Limits:              | 1,555' S of Belz Rd to Keith Dr |                                                                                         |             |    |
| Impact Fee Class:    | Collector                       |                                                                                         |             |    |
| Length (lf):         | 705                             |                                                                                         |             |    |
| Service Area(s):     | Sanger                          |                                                                                         |             |    |

| Roadway Construction Cost Projection                         |                                  |                              |      |                                |                |
|--------------------------------------------------------------|----------------------------------|------------------------------|------|--------------------------------|----------------|
| No.                                                          | Item Description                 | Quantity                     | Unit | Unit Price                     | Item Cost      |
| 103                                                          | Unclassified Roadway Excavation  | 1,410                        | cy   | \$ 40.00                       | \$ 56,400      |
| 203                                                          | 8" Lime Stabilized Subgrade      | 2,742                        | sy   | \$ 35.00                       | \$ 95,958      |
| 303                                                          | 8" 4,000 psi Reinforced Concrete | 2,272                        | sy   | \$ 120.00                      | \$ 272,600     |
| 403                                                          | 4" Concrete Sidewalk             | 7,050                        | sf   | \$ 10.00                       | \$ 70,500      |
| 503                                                          | Curb & Gutter                    | 1,410                        | lf   | \$ 30.00                       | \$ 42,300      |
| 603                                                          | Topsoil                          | 1,332                        | sy   | \$ 15.00                       | \$ 19,975      |
| Paving Construction Cost Subtotal:                           |                                  |                              |      |                                | \$ 557,733     |
| Major Construction Component Allowances**:                   |                                  |                              |      |                                |                |
| Item Description                                             |                                  | Notes                        |      | Allowance                      | Item Cost      |
|                                                              | Traffic Control                  | None Anticipated             |      | 0%                             | \$ -           |
| ✓                                                            | Pavement Markings/Markers        |                              |      | 3%                             | \$ 16,732      |
| ✓                                                            | Roadway Drainage                 | Standard Internal System     |      | 25%                            | \$ 139,433     |
|                                                              | Special Drainage Structures      | None Anticipated             |      | -                              | \$ -           |
| ✓                                                            | Water                            | Minor Adjustments            |      | 5%                             | \$ 27,887      |
| ✓                                                            | Sewer                            | Minor Adjustments            |      | 5%                             | \$ 27,887      |
| ✓                                                            | Landscaping and Irrigation       |                              |      | 4%                             | \$ 22,309      |
| ✓                                                            | Illumination                     | Standard Illumination System |      | 6%                             | \$ 33,464      |
|                                                              | Other:                           |                              |      | \$0                            | \$ -           |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              |      | Allowance Subtotal:            | \$ 267,712     |
|                                                              |                                  |                              |      | Paving and Allowance Subtotal: | \$ 825,445     |
|                                                              |                                  |                              |      | Construction Contingency:      | 15% \$ 123,817 |
|                                                              |                                  |                              |      | Mobilization                   | 5% \$ 41,272   |
|                                                              |                                  |                              |      | Prep ROW                       | 1% \$ 8,254    |
|                                                              |                                  |                              |      | Construction Cost TOTAL:       | \$ 999,000     |

| Impact Fee Project Cost Summary |                       |           |              |
|---------------------------------|-----------------------|-----------|--------------|
| Item Description                | Notes:                | Allowance | Item Cost    |
| Construction:                   |                       | -         | \$ 999,000   |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 159,840   |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 199,800   |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 1,359,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.



**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                        | Description:                                                                                      | Project No. | 24 |
|----------------------|------------------------|---------------------------------------------------------------------------------------------------|-------------|----|
| Name:                | Keith Dr               | <b>This project consists of widening the existing facility to a two-lane undivided collector.</b> |             |    |
| Limits:              | Jennifer Cir to FM 455 |                                                                                                   |             |    |
| Impact Fee Class:    | Collector              |                                                                                                   |             |    |
| Length (lf):         | 1,405                  |                                                                                                   |             |    |
| Service Area(s):     | Sanger                 |                                                                                                   |             |    |

| Roadway Construction Cost Projection |                                  |          |      |            |              |
|--------------------------------------|----------------------------------|----------|------|------------|--------------|
| No.                                  | Item Description                 | Quantity | Unit | Unit Price | Item Cost    |
| 103                                  | Unclassified Roadway Excavation  | 2,810    | cy   | \$ 40.00   | \$ 112,400   |
| 203                                  | 8" Lime Stabilized Subgrade      | 5,464    | sy   | \$ 35.00   | \$ 191,236   |
| 303                                  | 8" 4,000 psi Reinforced Concrete | 4,527    | sy   | \$ 120.00  | \$ 543,267   |
| 403                                  | 4" Concrete Sidewalk             | 14,050   | sf   | \$ 10.00   | \$ 140,500   |
| 503                                  | Curb & Gutter                    | 2,810    | lf   | \$ 30.00   | \$ 84,300    |
| 603                                  | Topsoil                          | 2,654    | sy   | \$ 15.00   | \$ 39,808    |
| Paving Construction Cost Subtotal:   |                                  |          |      |            | \$ 1,111,511 |

| Major Construction Component Allowances**:                   |                                    |                     |            |
|--------------------------------------------------------------|------------------------------------|---------------------|------------|
| Item Description                                             | Notes                              | Allowance           | Item Cost  |
| ✓ Traffic Control                                            | Construction Phase Traffic Control | 5%                  | \$ 55,576  |
| ✓ Pavement Markings/Markers                                  |                                    | 3%                  | \$ 33,345  |
| ✓ Roadway Drainage                                           | Standard Internal System           | 25%                 | \$ 277,878 |
| Special Drainage Structures                                  | None Anticipated                   | -                   | \$ -       |
| ✓ Water                                                      | Minor Adjustments                  | 5%                  | \$ 55,576  |
| ✓ Sewer                                                      | Minor Adjustments                  | 5%                  | \$ 55,576  |
| ✓ Landscaping and Irrigation                                 |                                    | 4%                  | \$ 44,460  |
| ✓ Illumination                                               | Standard Illumination System       | 6%                  | \$ 66,691  |
| Other:                                                       |                                    | \$0                 | \$ -       |
| **Allowances based on % of Paving Construction Cost Subtotal |                                    | Allowance Subtotal: | \$ 589,101 |

|                                 |                     |
|---------------------------------|---------------------|
| Paving and Allowance Subtotal:  | \$ 1,700,612        |
| Construction Contingency:       | 15% \$ 255,092      |
| Mobilization                    | 5% \$ 85,031        |
| Prep ROW                        | 5% \$ 85,031        |
| <b>Construction Cost TOTAL:</b> | <b>\$ 2,126,000</b> |

| Impact Fee Project Cost Summary       |                    |           |                     |
|---------------------------------------|--------------------|-----------|---------------------|
| Item Description                      | Notes:             | Allowance | Item Cost           |
| Construction:                         |                    | -         | \$ 2,126,000        |
| Engineering/Survey/Testing:           |                    | 16%       | \$ 340,160          |
| ROW/Easement Acquisition:             | Existing Alignment | 10%       | \$ 212,600          |
| <b>Impact Fee Project Cost TOTAL:</b> |                    |           | <b>\$ 2,679,000</b> |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

**City of Sanger**  
**2024 Roadway Impact Fee Study**  
**Conceptual Level Project Cost Projection**

Kimley-Horn and Associates, Inc.  
 updated: 7/10/2024

| Project Information: |                                                     | Description:                                                                                      | Project No. | 25 |
|----------------------|-----------------------------------------------------|---------------------------------------------------------------------------------------------------|-------------|----|
| Name:                | Cowling Rd                                          | <b>This project consists of widening the existing facility to a four-lane undivided arterial.</b> |             |    |
| Limits:              | 5th St to 3,335' S of Cowling to Railroad Connector |                                                                                                   |             |    |
| Impact Fee Class:    | Minor Arterial                                      |                                                                                                   |             |    |
| Length (lf):         | 5,615                                               |                                                                                                   |             |    |
| Service Area(s):     | Sanger                                              |                                                                                                   |             |    |

| Roadway Construction Cost Projection |                                  |          |      |            |              |
|--------------------------------------|----------------------------------|----------|------|------------|--------------|
| No.                                  | Item Description                 | Quantity | Unit | Unit Price | Item Cost    |
| 102                                  | Unclassified Roadway Excavation  | 16,689   | cy   | \$ 40.00   | \$ 667,561   |
| 202                                  | 10" Lime Stabilized Subgrade     | 32,754   | sy   | \$ 40.00   | \$ 1,310,167 |
| 302                                  | 9" 4,000 psi Reinforced Concrete | 29,323   | sy   | \$ 130.00  | \$ 3,811,961 |
| 402                                  | 4" Concrete Sidewalk             | 56,150   | sf   | \$ 10.00   | \$ 561,500   |
| 502                                  | Curb & Gutter                    | 11,230   | lf   | \$ 30.00   | \$ 336,900   |
| 602                                  | Topsoil                          | 12,166   | sy   | \$ 15.00   | \$ 182,488   |
| Paving Construction Cost Subtotal:   |                                  |          |      |            | \$ 6,870,576 |

| Major Construction Component Allowances**: |                                    |           |              |
|--------------------------------------------|------------------------------------|-----------|--------------|
| Item Description                           | Notes                              | Allowance | Item Cost    |
| ✓ Traffic Control                          | Construction Phase Traffic Control | 5%        | \$ 343,529   |
| ✓ Pavement Markings/Markers                |                                    | 3%        | \$ 206,117   |
| ✓ Roadway Drainage                         | Standard Internal System           | 25%       | \$ 1,717,644 |
| ✓ Special Drainage Structures              | Bridge Crossing (2)                | -         | \$ 2,000,000 |
| ✓ Water                                    | Minor Adjustments                  | 5%        | \$ 343,529   |
| ✓ Sewer                                    | Minor Adjustments                  | 5%        | \$ 343,529   |
| ✓ Landscaping and Irrigation               |                                    | 4%        | \$ 274,823   |
| ✓ Illumination                             | Standard Illumination System       | 6%        | \$ 412,235   |
| Other:                                     |                                    | \$0       | \$ -         |

\*\*Allowances based on % of Paving Construction Cost Subtotal

|                                |     |    |            |
|--------------------------------|-----|----|------------|
| Paving and Allowance Subtotal: |     | \$ | 12,511,982 |
| Construction Contingency:      | 15% | \$ | 1,876,797  |
| Mobilization                   | 5%  | \$ | 625,599    |
| Prep ROW                       | 5%  | \$ | 625,599    |
| Construction Cost TOTAL:       |     | \$ | 15,640,000 |

| Impact Fee Project Cost Summary |                    |           |               |
|---------------------------------|--------------------|-----------|---------------|
| Item Description                | Notes:             | Allowance | Item Cost     |
| Construction:                   |                    | -         | \$ 15,640,000 |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 2,502,400  |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 1,564,000  |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 19,706,000 |

**NOTE:** The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                     | Description:                                                                     | Project No. | 26 |
|----------------------|---------------------|----------------------------------------------------------------------------------|-------------|----|
| Name:                | 2nd St              | This project consists of the construction of a new two-lane undivided collector. |             |    |
| Limits:              | Indian Ln to FM 455 |                                                                                  |             |    |
| Impact Fee Class:    | Collector           |                                                                                  |             |    |
| Length (lf):         | 3,630               |                                                                                  |             |    |
| Service Area(s):     | Sanger              |                                                                                  |             |    |

| Roadway Construction Cost Projection                         |                                  |                                        |                     |            |              |
|--------------------------------------------------------------|----------------------------------|----------------------------------------|---------------------|------------|--------------|
| No.                                                          | Item Description                 | Quantity                               | Unit                | Unit Price | Item Cost    |
| 103                                                          | Unclassified Roadway Excavation  | 7,260                                  | cy                  | \$ 40.00   | \$ 290,400   |
| 203                                                          | 8" Lime Stabilized Subgrade      | 14,117                                 | sy                  | \$ 35.00   | \$ 494,083   |
| 303                                                          | 8" 4,000 psi Reinforced Concrete | 11,697                                 | sy                  | \$ 120.00  | \$ 1,403,600 |
| 403                                                          | 4" Concrete Sidewalk             | 36,300                                 | sf                  | \$ 10.00   | \$ 363,000   |
| 503                                                          | Curb & Gutter                    | 7,260                                  | lf                  | \$ 30.00   | \$ 217,800   |
| 603                                                          | Topsoil                          | 6,857                                  | sy                  | \$ 15.00   | \$ 102,850   |
| Paving Construction Cost Subtotal:                           |                                  |                                        |                     |            | \$ 2,871,733 |
| Major Construction Component Allowances**:                   |                                  |                                        |                     |            |              |
| Item Description                                             |                                  | Notes                                  | Allowance           | Item Cost  |              |
| ✓                                                            | Traffic Control                  | None Anticipated                       | 0%                  | \$         | -            |
| ✓                                                            | Pavement Markings/Markers        |                                        | 3%                  | \$         | 86,152       |
| ✓                                                            | Roadway Drainage                 | Standard Internal System               | 25%                 | \$         | 717,933      |
| ✓                                                            | Special Drainage Structures      | Minor Stream Crossing, Bridge Crossing | -                   | \$         | 1,250,000    |
| ✓                                                            | Water                            | Minor Adjustments                      | 5%                  | \$         | 143,587      |
| ✓                                                            | Sewer                            | Minor Adjustments                      | 5%                  | \$         | 143,587      |
| ✓                                                            | Landscaping and Irrigation       |                                        | 4%                  | \$         | 114,869      |
| ✓                                                            | Illumination                     | Standard Illumination System           | 6%                  | \$         | 172,304      |
|                                                              | Other:                           |                                        | \$0                 | \$         | -            |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                                        | Allowance Subtotal: | \$         | 2,628,432    |
| Paving and Allowance Subtotal:                               |                                  |                                        |                     | \$         | 5,500,165    |
| Construction Contingency:                                    |                                  |                                        |                     | 15%        | \$ 825,025   |
| Mobilization                                                 |                                  |                                        |                     | 5%         | \$ 275,008   |
| Prep ROW                                                     |                                  |                                        |                     | 1%         | \$ 55,002    |
| Construction Cost TOTAL:                                     |                                  |                                        |                     | \$         | 6,656,000    |

| Impact Fee Project Cost Summary |                       |           |              |
|---------------------------------|-----------------------|-----------|--------------|
| Item Description                | Notes:                | Allowance | Item Cost    |
| Construction:                   |                       | -         | \$ 6,656,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 1,064,960 |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 1,331,200 |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 9,052,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.

City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                              | Description:                                                                               | Project No. | 27 |
|----------------------|------------------------------|--------------------------------------------------------------------------------------------|-------------|----|
| Name:                | Marion Rd                    | This project consists of widening the existing facility to a four-lane undivided arterial. |             |    |
| Limits:              | 270' N of Avion Dr to FM 455 |                                                                                            |             |    |
| Impact Fee Class:    | Minor Arterial               |                                                                                            |             |    |
| Length (lf):         | 3,185                        |                                                                                            |             |    |
| Service Area(s):     | Sanger                       |                                                                                            |             |    |

| Roadway Construction Cost Projection                         |                                  |                                              |      |                     |              |
|--------------------------------------------------------------|----------------------------------|----------------------------------------------|------|---------------------|--------------|
| No.                                                          | Item Description                 | Quantity                                     | Unit | Unit Price          | Item Cost    |
| 102                                                          | Unclassified Roadway Excavation  | 9,467                                        | cy   | \$ 40.00            | \$ 378,661   |
| 202                                                          | 10" Lime Stabilized Subgrade     | 18,579                                       | sy   | \$ 40.00            | \$ 743,167   |
| 302                                                          | 9" 4,000 psi Reinforced Concrete | 16,633                                       | sy   | \$ 130.00           | \$ 2,162,261 |
| 402                                                          | 4" Concrete Sidewalk             | 31,850                                       | sf   | \$ 10.00            | \$ 318,500   |
| 502                                                          | Curb & Gutter                    | 6,370                                        | lf   | \$ 30.00            | \$ 191,100   |
| 602                                                          | Topsoil                          | 6,901                                        | sy   | \$ 15.00            | \$ 103,513   |
| Paving Construction Cost Subtotal:                           |                                  |                                              |      |                     | \$ 3,897,201 |
| Major Construction Component Allowances**:                   |                                  |                                              |      |                     |              |
| Item Description                                             |                                  | Notes                                        |      | Allowance           | Item Cost    |
| √                                                            | Traffic Control                  | Construction Phase Traffic Control           |      | 5%                  | \$ 194,860   |
| √                                                            | Pavement Markings/Markers        |                                              |      | 3%                  | \$ 116,916   |
| √                                                            | Roadway Drainage                 | Standard Internal System                     |      | 25%                 | \$ 974,300   |
| √                                                            | Special Drainage Structures      | Minor Stream Crossing, Major Stream Crossing |      | -                   | \$ 750,000   |
| √                                                            | Water                            | Minor Adjustments                            |      | 5%                  | \$ 194,860   |
| √                                                            | Sewer                            | Minor Adjustments                            |      | 5%                  | \$ 194,860   |
| √                                                            | Landscaping and Irrigation       |                                              |      | 4%                  | \$ 155,888   |
| √                                                            | Illumination                     | Standard Illumination System                 |      | 6%                  | \$ 233,832   |
|                                                              | Other:                           |                                              |      | \$0                 | \$ -         |
|                                                              |                                  |                                              |      | Allowance Subtotal: | \$ 2,815,517 |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                                              |      |                     |              |
| Paving and Allowance Subtotal:                               |                                  |                                              |      | \$                  | 6,712,718    |
| Construction Contingency:                                    |                                  |                                              |      | 15%                 | \$ 1,006,908 |
| Mobilization                                                 |                                  |                                              |      | 5%                  | \$ 335,636   |
| Prep ROW                                                     |                                  |                                              |      | 5%                  | \$ 335,636   |
| Construction Cost TOTAL:                                     |                                  |                                              |      | \$                  | 8,391,000    |

| Impact Fee Project Cost Summary |                    |           |               |
|---------------------------------|--------------------|-----------|---------------|
| Item Description                | Notes:             | Allowance | Item Cost     |
| Construction:                   |                    | -         | \$ 8,391,000  |
| Engineering/Survey/Testing:     |                    | 16%       | \$ 1,342,560  |
| ROW/Easement Acquisition:       | Existing Alignment | 10%       | \$ 839,100    |
| Impact Fee Project Cost TOTAL:  |                    |           | \$ 10,573,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.



City of Sanger  
2024 Roadway Impact Fee Study  
Conceptual Level Project Cost Projection

Kimley-Horn and Associates, Inc.  
updated: 7/10/2024

| Project Information: |                         | Description:                                                                     | Project No. | 28 |
|----------------------|-------------------------|----------------------------------------------------------------------------------|-------------|----|
| Name:                | Union Hill Rd           | This project consists of the construction of a new four-lane undivided arterial. |             |    |
| Limits:              | FM 455 to McReynolds Rd |                                                                                  |             |    |
| Impact Fee Class:    | Minor Arterial          |                                                                                  |             |    |
| Length (lf):         | 5,490                   |                                                                                  |             |    |
| Service Area(s):     | Sanger                  |                                                                                  |             |    |

| Roadway Construction Cost Projection                         |                                  |                              |                     |            |              |
|--------------------------------------------------------------|----------------------------------|------------------------------|---------------------|------------|--------------|
| No.                                                          | Item Description                 | Quantity                     | Unit                | Unit Price | Item Cost    |
| 102                                                          | Unclassified Roadway Excavation  | 16,318                       | cy                  | \$ 40.00   | \$ 652,700   |
| 202                                                          | 10" Lime Stabilized Subgrade     | 32,025                       | sy                  | \$ 40.00   | \$ 1,281,000 |
| 302                                                          | 9" 4,000 psi Reinforced Concrete | 28,670                       | sy                  | \$ 130.00  | \$ 3,727,100 |
| 402                                                          | 4" Concrete Sidewalk             | 54,900                       | sf                  | \$ 10.00   | \$ 549,000   |
| 502                                                          | Curb & Gutter                    | 10,980                       | lf                  | \$ 30.00   | \$ 329,400   |
| 602                                                          | Topsoil                          | 11,895                       | sy                  | \$ 15.00   | \$ 178,425   |
| Paving Construction Cost Subtotal:                           |                                  |                              |                     |            | \$ 6,717,625 |
| Major Construction Component Allowances**:                   |                                  |                              |                     |            |              |
| Item Description                                             |                                  | Notes                        | Allowance           | Item Cost  |              |
| ✓                                                            | Traffic Control                  | None Anticipated             | 0%                  | \$         | -            |
| ✓                                                            | Pavement Markings/Markers        |                              | 3%                  | \$         | 201,529      |
| ✓                                                            | Roadway Drainage                 | Standard Internal System     | 25%                 | \$         | 1,679,406    |
| ✓                                                            | Special Drainage Structures      | Minor Stream Crossing        | -                   | \$         | 250,000      |
| ✓                                                            | Water                            | Minor Adjustments            | 5%                  | \$         | 335,881      |
| ✓                                                            | Sewer                            | Minor Adjustments            | 5%                  | \$         | 335,881      |
| ✓                                                            | Landscaping and Irrigation       |                              | 4%                  | \$         | 268,705      |
| ✓                                                            | Illumination                     | Standard Illumination System | 6%                  | \$         | 403,058      |
|                                                              | Other:                           |                              | \$0                 | \$         | -            |
| **Allowances based on % of Paving Construction Cost Subtotal |                                  |                              | Allowance Subtotal: | \$         | 3,474,460    |
| Paving and Allowance Subtotal:                               |                                  |                              |                     | \$         | 10,192,085   |
| Construction Contingency:                                    |                                  |                              |                     | 15%        | \$ 1,528,813 |
| Mobilization                                                 |                                  |                              |                     | 5%         | \$ 509,604   |
| Prep ROW                                                     |                                  |                              |                     | 1%         | \$ 101,921   |
| Construction Cost TOTAL:                                     |                                  |                              |                     | \$         | 12,333,000   |

| Impact Fee Project Cost Summary |                       |           |               |
|---------------------------------|-----------------------|-----------|---------------|
| Item Description                | Notes:                | Allowance | Item Cost     |
| Construction:                   |                       | -         | \$ 12,333,000 |
| Engineering/Survey/Testing:     |                       | 16%       | \$ 1,973,280  |
| ROW/Easement Acquisition:       | New Roadway Alignment | 20%       | \$ 2,466,600  |
| Impact Fee Project Cost TOTAL:  |                       |           | \$ 16,773,000 |

NOTE: The planning level cost projections listed in this appendix have been developed for Impact Fee calculations only and should not be used for any future Capital Improvement Planning within the City of Sanger.

The planning level cost projections shall not supersede the City's design standards or the determination of the City Engineer for a specific project.



## **APPENDIX B— CAPITAL IMPROVEMENTS PLAN SERVICE UNITS OF SUPPLY**

## City of Sanger - 2024 Roadway Impact Fee Study

### Capital Improvements Plan Units of Supply

7/11/2024

| PROJECT ID # | ROADWAY                       | LIMITS                                              | LENGTH (MI) | LANES | IMPACT FEE CLASSIFICATION | PEAK HOUR VOLUME | % IN SERVICE AREA | VEH-MI CAPACITY PK-HR PER LN | VEH-MI SUPPLY PK-HR TOTAL | VEH-MI TOTAL DEMAND PK-HR | EXCESS CAPACITY PK-HR VEH-MI | TOTAL COST IN SERVICE AREA |
|--------------|-------------------------------|-----------------------------------------------------|-------------|-------|---------------------------|------------------|-------------------|------------------------------|---------------------------|---------------------------|------------------------------|----------------------------|
| 1            | North Metz to I-35 Connector  | 3,030' W of I-35 SBFR to I-35 SBFR                  | 0.57        | 2     | Collector                 | New              | 100%              | 425                          | 485                       | 0                         | 485                          | \$ 6,251,000               |
| 2            | Chisam Rd                     | I-35 NBFR to 4,375' E of I-35 NBFR                  | 0.83        | 2     | Collector                 | 16               | 100%              | 425                          | 706                       | 13                        | 692                          | \$ 10,309,000              |
| 3            | Lois Rd W                     | 3,645' W of I-35 SBFR to I-35 SBFR                  | 0.69        | 4     | Minor Arterial            | 42               | 100%              | 525                          | 1,449                     | 29                        | 1,420                        | \$ 11,535,000              |
| 4            | Lois Rd E (1)                 | I-35 NBFR to 525' E of I-35 NBFR                    | 0.10        | 4     | Minor Arterial            | 288              | 100%              | 525                          | 210                       | 29                        | 181                          | \$ 1,549,000               |
| 5            | Lois Rd E (2)                 | 525' E of I-35 NBFR to 775' E of I-35 NBFR          | 0.05        | 4     | Minor Arterial            | New              | 100%              | 525                          | 105                       | 0                         | 105                          | \$ 745,000                 |
| 6            | Lois Rd E (3)                 | 775' E of I-35 NBFR to 2,255' E of I-35 NBFR        | 0.28        | 4     | Minor Arterial            | 148              | 100%              | 525                          | 588                       | 41                        | 547                          | \$ 6,333,000               |
| 7            | South Metz to I-35 Connector  | 4,935' W of I-35 SBFR to I-35 SBFR                  | 0.93        | 2     | Collector                 | New              | 100%              | 425                          | 791                       | 0                         | 791                          | \$ 9,509,000               |
| 8            | Utility Rd*                   | I-35 NBFR to 1,920' E of I-35 NBFR                  | 0.36        | 2     | Collector                 | 100              | 100%              | 425                          | 306                       | 36                        | 270                          | \$ 4,448,000               |
| 9            | Belz Rd*                      | Metz Rd to I-35 SBFR                                | 0.91        | 4     | Minor Arterial            | 200              | 100%              | 525                          | 1,911                     | 182                       | 1,729                        | \$ 15,788,000              |
| 10           | Indian Ln (1)                 | I-35 SBFR to FM 455                                 | 1.07        | 4     | Minor Arterial            | New              | 100%              | 525                          | 2,247                     | 0                         | 2,247                        | \$ 19,659,000              |
| 11           | Indian Ln (2)                 | 1,290' N of McReynolds Rd to McReynolds Rd          | 0.24        | 1     | Minor Arterial (1/3)      | N/A              | 100%              | 525                          | 126                       | 0                         | 126                          | \$ 725,000                 |
| 12           | Indian Ln (3)                 | McReynolds Rd to 3,365' S of McReynolds Rd          | 0.64        | 2     | Collector                 | New              | 100%              | 425                          | 544                       | 0                         | 544                          | \$ 6,484,000               |
| 13           | FM 455 (1)                    | FM 2450 to 830' E of Marion Rd                      | 5.47        | 4     | Principal Arterial        | 580              | 100%              | 650                          | 14,222                    | 3,173                     | 11,049                       | \$ 7,850,949               |
| 14           | FM 455 (2)                    | 830' E of Marion Rd to 2,110' S of FM 2164          | 2.84        | 4     | Principal Arterial        | 434              | 100%              | 650                          | 7,384                     | 1,233                     | 6,151                        | \$ 11,020,000              |
| 15           | Willow St                     | Cowling Rd to Indian Ln                             | 0.95        | 4     | Minor Arterial            | 226              | 100%              | 525                          | 1,995                     | 215                       | 1,780                        | \$ 18,725,000              |
| 16           | McReynolds Rd                 | Indian Ln to 600' E of PR 6630                      | 1.08        | 4     | Minor Arterial            | 124              | 100%              | 525                          | 2,268                     | 134                       | 2,134                        | \$ 21,576,000              |
| 17           | 5th St                        | Keaton Rd to I-35 SBFR                              | 0.17        | 4     | Minor Arterial            | 286              | 100%              | 525                          | 357                       | 49                        | 308                          | \$ 489,000                 |
| 18           | Cowling to Railroad Connector | Cowling Rd to Railroad Ave                          | 0.52        | 4     | Minor Arterial            | New              | 100%              | 525                          | 1,092                     | 0                         | 1,092                        | \$ 8,167,000               |
| 19           | Rector Rd                     | 2,730' W of Railroad Ave to Railroad Ave            | 0.52        | 2     | Collector                 | New              | 100%              | 425                          | 442                       | 0                         | 442                          | \$ 8,141,000               |
| 20           | N Tejas Dr                    | 1,245' S of FM 455 to 1,490' N of Duck Creek Rd     | 0.25        | 2     | Collector                 | New              | 100%              | 425                          | 213                       | 0                         | 213                          | \$ 2,545,000               |
| 21           | Jennifer Cir (1)              | Lois Rd W to Belz Rd                                | 1.54        | 2     | Collector                 | New              | 100%              | 425                          | 1,309                     | 0                         | 1,309                        | \$ 16,029,000              |
| 22           | Jennifer Cir (2)*             | Belz Rd to 1,555' S of Belz Rd                      | 0.29        | 2     | Collector                 | 100              | 100%              | 425                          | 247                       | 29                        | 218                          | \$ 2,965,000               |
| 23           | Jennifer Cir (3)              | 1,555' S of Belz Rd to Keith Dr                     | 0.13        | 2     | Collector                 | New              | 100%              | 425                          | 111                       | 0                         | 111                          | \$ 1,359,000               |
| 24           | Keith Dr*                     | Jennifer Cir to FM 455                              | 0.27        | 2     | Collector                 | 100              | 100%              | 425                          | 230                       | 27                        | 203                          | \$ 2,679,000               |
| 25           | Cowling Rd                    | 5th St to 3,335' S of Cowling to Railroad Connector | 1.06        | 4     | Minor Arterial            | 140              | 100%              | 525                          | 2,226                     | 148                       | 2,078                        | \$ 19,706,000              |
| 26           | 2nd St                        | Indian Ln to FM 455                                 | 0.69        | 2     | Collector                 | New              | 100%              | 425                          | 587                       | 0                         | 587                          | \$ 9,052,000               |
| 27           | Marion Rd                     | 270' N of Avion Dr to FM 455                        | 0.60        | 4     | Minor Arterial            | 196              | 100%              | 525                          | 1,260                     | 118                       | 1,142                        | \$ 10,573,000              |
| 28           | Union Hill Rd                 | FM 455 to McReynolds Rd                             | 1.04        | 4     | Minor Arterial            | New              | 100%              | 525                          | 2,184                     | 0                         | 2,184                        | \$ 16,773,000              |
|              |                               |                                                     |             |       |                           |                  |                   | <b>SUBTOTAL</b>              | <b>45,591</b>             | <b>5,455</b>              | <b>40,136</b>                | <b>\$ 250,984,949</b>      |

\*Existing peak hour volumes assumed based on road context and development access

**Roadway Impact Fee Study Cost \$ 50,000**

**TOTAL COST \$ 251,034,949**



## **APPENDIX C – EXISTING ROADWAY FACILITIES INVENTORY**



**City of Sanger - 2024 Roadway Impact Fee Study**  
**Existing Roadway Facilities Inventory**

7/11/2024

| ROADWAY         | FROM                          | TO                                        | LENGTH<br>(ft) | LENGTH<br>(mi) | EXISTING<br>LANES |       | EXISTING<br>SECTION | PM<br>PEAK<br>HOUR<br>VOL |       | % IN<br>SERVICE<br>AREA | VEH-MI<br>CAPACITY<br>PK-HR<br>PER LN |       | VEH-MI<br>SUPPLY<br>PK-HR<br>TOTAL |              | VEH-MI<br>DEMAND<br>PK-HR<br>TOTAL |              | EXCESS<br>CAPACITY<br>PK-HR<br>VEH-MI |              | EXISTING<br>DEFICIENCIES<br>PK-HR<br>VEH-MI |           |
|-----------------|-------------------------------|-------------------------------------------|----------------|----------------|-------------------|-------|---------------------|---------------------------|-------|-------------------------|---------------------------------------|-------|------------------------------------|--------------|------------------------------------|--------------|---------------------------------------|--------------|---------------------------------------------|-----------|
|                 |                               |                                           |                |                | NB/EB             | SB/WB |                     | NB/EB                     | SB/WB |                         | NB/EB                                 | SB/WB | NB/EB                              | SB/WB        | NB/EB                              | SB/WB        | NB/EB                                 | SB/WB        | NB/EB                                       | SB/WB     |
| 5th St          | I-35 NBFR                     | FM 455                                    | 1,755          | 0.33           | 1                 | 1     | 2U                  | 107                       | 107   | 100%                    | 425                                   | 425   | 141                                | 141          | 36                                 | 36           | 105                                   | 105          |                                             |           |
| 5th St          | FM 455                        | Willow St                                 | 2,610          | 0.49           | 1                 | 1     | 2U                  | 188                       | 188   | 100%                    | 425                                   | 425   | 210                                | 210          | 93                                 | 93           | 117                                   | 117          |                                             |           |
| 5th St          | Willow St                     | Cowling Rd                                | 3,335          | 0.63           | 1                 | 1     | 2U                  | 47                        | 47    | 100%                    | 425                                   | 425   | 268                                | 268          | 30                                 | 30           | 238                                   | 238          |                                             |           |
| 5th St          | Cowling Rd                    | I-35 SBFR                                 | 1,835          | 0.35           | 1                 | 1     | 2U                  | 439                       | 439   | 100%                    | 425                                   | 425   | 148                                | 148          | 153                                | 153          | -5                                    | -5           | 5                                           | 5         |
| 5th St          | Keaton Rd                     | I-35 SBFR                                 | 900            | 0.17           | 1                 | 1     | 2U                  | 143                       | 143   | 100%                    | 425                                   | 425   | 72                                 | 72           | 24                                 | 24           | 48                                    | 48           |                                             |           |
| Avion Dr*       | Utility Rd                    | Marion Rd                                 | 2,970          | 0.56           | 1                 | 1     | 2U                  | 50                        | 50    | 100%                    | 425                                   | 425   | 239                                | 239          | 28                                 | 28           | 211                                   | 211          |                                             |           |
| Belz Rd*        | Metz Rd                       | Jennifer Cir                              | 1,660          | 0.31           | 1                 | 1     | 2U                  | 100                       | 100   | 100%                    | 425                                   | 425   | 134                                | 134          | 31                                 | 31           | 103                                   | 103          |                                             |           |
| Belz Rd*        | Jennifer Cir                  | I-35 SBFR                                 | 3,160          | 0.60           | 1                 | 1     | 2U                  | 100                       | 100   | 100%                    | 425                                   | 425   | 254                                | 254          | 60                                 | 60           | 194                                   | 194          |                                             |           |
| Chisam Rd       | I-35 NBFR                     | 4,375' E of I-35 NBFR                     | 4,375          | 0.83           | 1                 | 1     | 2U                  | 8                         | 8     | 100%                    | 425                                   | 425   | 352                                | 352          | 7                                  | 7            | 345                                   | 345          |                                             |           |
| Cowling Rd      | 5th St                        | Cowling to Railroad Connector             | 2,275          | 0.43           | 1                 | 1     | 2U                  | 70                        | 70    | 100%                    | 425                                   | 425   | 183                                | 183          | 30                                 | 30           | 153                                   | 153          |                                             |           |
| Cowling Rd      | Cowling to Railroad Connector | 3,335' S of Cowling to Railroad Connector | 3,335          | 0.63           | 1                 | 1     | 2U                  | 70                        | 70    | 100%                    | 425                                   | 425   | 268                                | 268          | 44                                 | 44           | 224                                   | 224          |                                             |           |
| Duck Creek Rd   | Keaton Rd (W)                 | Keaton Rd (E)                             | 810            | 0.15           | 1                 | 1     | 2U                  | 214                       | 214   | 100%                    | 425                                   | 425   | 65                                 | 65           | 33                                 | 33           | 32                                    | 32           |                                             |           |
| Duck Creek Rd   | Keaton Rd (E)                 | I-35 SBFR                                 | 675            | 0.13           | 1                 | 1     | 2U                  | 152                       | 152   | 100%                    | 425                                   | 425   | 54                                 | 54           | 19                                 | 19           | 35                                    | 35           |                                             |           |
| FM 455          | FM 2450                       | Metz Rd                                   | 15,885         | 3.01           | 1                 | 1     | 2U                  | 227                       | 227   | 100%                    | 425                                   | 425   | 1,279                              | 1,279        | 683                                | 683          | 596                                   | 596          |                                             |           |
| FM 455          | Metz Rd                       | N Tejas Dr                                | 965            | 0.18           | 1                 | 1     | 2U                  | 216                       | 216   | 100%                    | 425                                   | 425   | 78                                 | 78           | 39                                 | 39           | 39                                    | 39           |                                             |           |
| FM 455          | N Tejas Dr                    | Keith Dr                                  | 1,525          | 0.29           | 1                 | 1     | 2U                  | 216                       | 216   | 100%                    | 425                                   | 425   | 123                                | 123          | 62                                 | 62           | 61                                    | 61           |                                             |           |
| FM 455          | Keith Dr                      | I-35                                      | 2,400          | 0.45           | 1                 | 1     | 2U                  | 457                       | 457   | 100%                    | 425                                   | 425   | 193                                | 193          | 208                                | 208          | -15                                   | -15          | 15                                          | 15        |
| FM 455          | I-35                          | 5th St                                    | 1,535          | 0.29           | 1                 | 1     | 2U                  | 455                       | 455   | 100%                    | 425                                   | 425   | 124                                | 124          | 132                                | 132          | -8                                    | -8           | 8                                           | 8         |
| FM 455          | 5th St                        | 2nd St                                    | 755            | 0.14           | 1                 | 1     | 2U                  | 385                       | 385   | 100%                    | 425                                   | 425   | 61                                 | 61           | 55                                 | 55           | 6                                     | 6            |                                             |           |
| FM 455          | 2nd St                        | Indian Ln                                 | 3,180          | 0.60           | 1                 | 1     | 2U                  | 385                       | 385   | 100%                    | 425                                   | 425   | 256                                | 256          | 232                                | 232          | 24                                    | 24           |                                             |           |
| FM 455          | Indian Ln                     | Marion Rd                                 | 1,790          | 0.34           | 1                 | 1     | 2U                  | 391                       | 391   | 100%                    | 425                                   | 425   | 144                                | 144          | 133                                | 133          | 11                                    | 11           |                                             |           |
| FM 455          | Marion Rd                     | 830' E of Marion Rd                       | 830            | 0.16           | 1                 | 1     | 2U                  | 231                       | 231   | 100%                    | 425                                   | 425   | 67                                 | 67           | 36                                 | 36           | 31                                    | 31           |                                             |           |
| FM 455          | 830' E of Marion Rd           | FM 2164                                   | 12,905         | 2.44           | 1                 | 1     | 2U                  | 231                       | 231   | 100%                    | 425                                   | 425   | 1,039                              | 1,039        | 565                                | 565          | 474                                   | 474          |                                             |           |
| FM 455          | FM 2164                       | 2,110' S of FM 2164                       | 2,110          | 0.40           | 1                 | 1     | 2U                  | 127                       | 127   | 100%                    | 425                                   | 425   | 170                                | 170          | 51                                 | 51           | 119                                   | 119          |                                             |           |
| Indian Ln       | FM 455                        | 1,290' N of McReynolds Rd                 | 3,375          | 0.64           | 1                 | 1     | 3U                  | 47                        | 47    | 100%                    | 525                                   | 525   | 336                                | 336          | 30                                 | 30           | 306                                   | 306          |                                             |           |
| Indian Ln       | 1,290' N of McReynolds Rd     | McReynolds Rd                             | 1,290          | 0.24           | 1                 | 1     | 2U                  | 47                        | 47    | 100%                    | 425                                   | 425   | 104                                | 104          | 11                                 | 11           | 93                                    | 93           |                                             |           |
| Jennifer Cir*   | Belz Rd                       | 1,555' S of Belz Rd                       | 1,555          | 0.29           | 1                 | 1     | 2U                  | 50                        | 50    | 100%                    | 425                                   | 425   | 125                                | 125          | 15                                 | 15           | 110                                   | 110          |                                             |           |
| Keaton Rd       | FM 455                        | Duck Creek Rd                             | 3,755          | 0.71           | 1                 | 1     | 2U                  | 114                       | 114   | 100%                    | 425                                   | 425   | 302                                | 302          | 81                                 | 81           | 221                                   | 221          |                                             |           |
| Keaton Rd       | Duck Creed Rd                 | 5th St                                    | 2,280          | 0.43           | 1                 | 1     | 2U                  | 135                       | 135   | 100%                    | 425                                   | 425   | 184                                | 184          | 58                                 | 58           | 126                                   | 126          |                                             |           |
| Keith Dr*       | Jennifer Cir                  | FM 455                                    | 1,405          | 0.27           | 1                 | 1     | 2U-G                | 50                        | 50    | 100%                    | 150                                   | 150   | 40                                 | 40           | 13                                 | 13           | 27                                    | 27           |                                             |           |
| Lois Rd W       | 3,645' W of I-35 SBFR         | I-35 SBFR                                 | 3,645          | 0.69           | 1                 | 1     | 2U                  | 21                        | 21    | 100%                    | 425                                   | 425   | 293                                | 293          | 14                                 | 14           | 279                                   | 279          |                                             |           |
| Lois Rd E       | I-35 NBFR                     | 525' E of I-35 NBFR                       | 525            | 0.10           | 1                 | 1     | 2U                  | 144                       | 144   | 100%                    | 425                                   | 425   | 42                                 | 42           | 14                                 | 14           | 28                                    | 28           |                                             |           |
| Lois Rd E       | 775' E of I-35 NBFR           | 2,255' E of I-35 NBFR                     | 1,480          | 0.28           | 1                 | 1     | 2U                  | 74                        | 74    | 100%                    | 425                                   | 425   | 119                                | 119          | 21                                 | 21           | 98                                    | 98           |                                             |           |
| Marion Rd       | 270' N of Avion Dr            | Avion Dr                                  | 270            | 0.05           | 1                 | 1     | 2U                  | 68                        | 68    | 100%                    | 425                                   | 425   | 22                                 | 22           | 3                                  | 3            | 19                                    | 19           |                                             |           |
| Marion Rd*      | Avion Dr                      | FM 455                                    | 2,915          | 0.55           | 1                 | 1     | 2U                  | 100                       | 100   | 100%                    | 425                                   | 425   | 235                                | 235          | 55                                 | 55           | 180                                   | 180          |                                             |           |
| McReynolds Rd   | Indian Ln                     | PR 6630                                   | 5,115          | 0.97           | 1                 | 1     | 2U                  | 61                        | 61    | 100%                    | 425                                   | 425   | 412                                | 412          | 59                                 | 59           | 353                                   | 353          |                                             |           |
| McReynolds Rd   | PR 6630                       | 600' E of PR 6630                         | 600            | 0.11           | 1                 | 1     | 2U                  | 69                        | 69    | 100%                    | 425                                   | 425   | 48                                 | 48           | 8                                  | 8            | 40                                    | 40           |                                             |           |
| Metz Rd         | 545' N of FM 455              | FM 455                                    | 545            | 0.10           | 1                 | 1     | 2U                  | 27                        | 27    | 100%                    | 425                                   | 425   | 44                                 | 44           | 3                                  | 3            | 41                                    | 41           |                                             |           |
| N Tejas Dr*     | FM 455                        | 1,245' S of FM 455                        | 1,245          | 0.24           | 1                 | 1     | 2U                  | 50                        | 50    | 100%                    | 425                                   | 425   | 100                                | 100          | 12                                 | 12           | 88                                    | 88           |                                             |           |
| S Keaton Rd*    | 5th St                        | 1,150' S of 5th St                        | 1,150          | 0.22           | 1                 | 1     | 2U                  | 50                        | 50    | 100%                    | 425                                   | 425   | 93                                 | 93           | 11                                 | 11           | 82                                    | 82           |                                             |           |
| Tejas Dr*       | 1,490' N of Duck Creek Rd     | Duck Creek Rd                             | 1,490          | 0.28           | 1                 | 1     | 2U                  | 50                        | 50    | 100%                    | 425                                   | 425   | 120                                | 120          | 14                                 | 14           | 106                                   | 106          |                                             |           |
| Utility Rd*     | I-35 NBFR                     | 1,920' E of I-35 NBFR                     | 1,920          | 0.36           | 1                 | 1     | 2U                  | 50                        | 50    | 100%                    | 425                                   | 425   | 155                                | 155          | 18                                 | 18           | 137                                   | 137          |                                             |           |
| Willow St       | Cowling Rd                    | Indian Ln                                 | 5,015          | 0.95           | 1                 | 1     | 2U                  | 113                       | 113   | 100%                    | 425                                   | 425   | 404                                | 404          | 107                                | 107          | 297                                   | 297          |                                             |           |
| <b>SUBTOTAL</b> |                               |                                           | <b>113,150</b> | <b>21.43</b>   |                   |       |                     |                           |       |                         |                                       |       | <b>9,100</b>                       | <b>9,100</b> | <b>3,331</b>                       | <b>3,331</b> | <b>5,769</b>                          | <b>5,769</b> | <b>28</b>                                   | <b>28</b> |
| <b>TOTAL</b>    |                               |                                           |                |                |                   |       |                     |                           |       |                         |                                       |       | <b>18,200</b>                      |              | <b>6,662</b>                       |              | <b>11,538</b>                         |              | <b>56</b>                                   |           |

\*Existing peak hour volumes assumed based on road context and development access

## EXHIBIT B

### Roadway Impact Fee Collection Rate

|                                     |          |
|-------------------------------------|----------|
| Residential Fee Per Service Unit    | \$922 00 |
| Nonresidential Fee Per Service Unit | \$806 75 |