

CITY OF SANGER, TEXAS

ORDINANCE 05-09-24

AN ORDINANCE OF THE CITY COUNCIL OF THE CITY OF SANGER, DENTON COUNTY, TEXAS, AMENDING THE ZONING MAP BY AMENDING (PD 04-11-22) THE PLANNED DEVELOPMENT DISTRICT CREATED BY ORDINANCE 04-11-22 TO EXTEND THE BOUNDARIES THEREOF TO INCLUDE APPROXIMATELY 21.17 ACRES OF TRACT DESCRIBED AS A0029A R BEEBE, 65B; AND REZONE SAID TRACT FROM (A) AGRICULTURAL TO (PD) PLANNED DEVELOPMENT AND TO FURTHER AMEND CERTAIN DEVELOPMENT REQUIREMENTS WITH THE PLANNED DEVELOPMENT; PROVIDING FOR THE REPEAL OF ALL ORDINANCES IN CONFLICT; PROVIDING A CUMULATIVE CLAUSE; PROVIDING FOR A SEVERABILITY CLAUSE; PROVIDING FOR A PENALTY OF FINE IN ACCORDANCE WITH SECTION 1.109 OF THE CODE OF ORDINANCE FOR VIOLATIONS; AND PROVIDING A SAVINGS CLAUSE; AUTHORIZING PUBLICATION; AND ESTABLISHING AN EFFECTIVE DATE.

WHEREAS, the City of Sanger (the “City”) is a home rule municipality regulated by state law and Charter; and

WHEREAS, the City Council finds it necessary for the public health, safety, and welfare that development occur in a controlled and orderly manner; and

WHEREAS, the Planning and Zoning Commission on January 8, 2024, duly covered and conducted a public hearing for the purpose of assessing a request for amendment to the Zoning Map, recommending approval for the hereinafter described property; and

WHEREAS, all requests for amendment to the Zoning Map were duly filed with the City of Sanger, Texas, concerning the hereinafter described property; and

WHEREAS, the following provision of proper legal notice requirements, including written notice to owners within 200 feet of the subject property, were made in the time and manner prescribed by law; and

WHEREAS, the City Council finds that the passage of this Ordinance is in the best interest of the citizens of Sanger.

NOW, THEREFORE, BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF SANGER, TEXAS:

SECTION 1. That the Planned Development (PD 04-11-22) created by Ordinance 04-11-22 is hereby amended as follows;

1. The boundaries of PD 04-11-22 are extended to include approximately 21.17 acres of land described A0029A R BEEBE, 65B and further described by metes and bounds in Exhibit A.
2. That said tract described in Section 1.1 and further described in Exhibit A is rezoned from (A) Agricultural to PD (04-11-22).
3. That certain development provisions are hereby amended as described in Exhibit B.

SECTION 2. Except as specifically amended hereby, all provisions of PD 04-11-22 shall remain in full force and effect.

SECTION 3. That all matters stated in the preamble are found to be true and correct and are incorporated herein as if copied in their entirety.

SECTION 4. It is hereby declared to be the intention of the City Council that the sections, paragraphs, sentences, clauses, phrases and words of this Ordinance are severable and, if any word, phrase, clause, sentence, paragraph, or section of this Ordinance shall be declared unconstitutional by the valid judgment or decree of any court of competent jurisdiction, such unconstitutionality shall not affect any of the remaining portions of this Ordinance, since the same would have been enacted by the City Council without the incorporation in this Ordinance of any such unconstitutional word, phrase, clause, sentence, paragraph, or section.

SECTION 5. Any person, firm or corporation who shall violate any of the provisions of this article shall be guilty of a misdemeanor and upon conviction shall be fined in accordance with the general penalty provision found in The Code of Ordinances, Section 1.109 General Penalty for Violations of Code.

SECTION 6. This ordinance will take effect immediately from and after its passage and the publication of the caption, as the law and Charter in such cases provide.

PASSED AND APPROVED by the City Council of the City of Sanger, Texas, on this 6th day of February 5, 2024.

APPROVED:

ATTEST:

Thomas E. Muir, Mayor

Kelly Edwards, City Secretary

APPROVED TO FORM:

Hugh Coleman, City Attorney

EXHIBIT A

LEGAL DESCRIPTION

All that certain lot, tract, or parcel of land, being part of the Rueben Bebee Survey, Abstract No. 29, Denton County, Texas, and being all of that tract of land described in a deed to Hien & Duyet Nguyen recorded in Document No. 2016-27020 Real Property Records of Denton, County, Texas (RPRDCT) and all of that tract of land described in a deed to Dualbond Holdings, LLC recorded in Document No. 2016-27021 (RPRDCT) and all of that tract of land described in a deed to Sanger Town Center LLC recorded in Document No. 2017-48301 (RPRDCT) and a part of that tract of land described in a deed to Marion Hills Apartments, LLC recorded in Document No. 2017-48293 (RPRDCT), being more completely described as follows, to-wit:

BEGINNING at 1/2" iron rod set for the southeast corner of the Hien & Duyet Nguyen tract and the north right-of-way line of McReynolds Road;

THENCE with the north right-of-way line of McReynolds Road North 87°54'58" West a distance of 1,789.63 feet to a 1/2" iron rod set for the southwest corner of the Hien & Duyet Nguyen tract and the southeast corner of a tract of land described in a deed to Winston Grove Apartments, LLC recorded in Document No. 2018-13037 (RPRDCT);

THENCE North 2°23'22" East a distance of 2,526.23 feet to 1/2" iron rod set for the northeast corner of a tract of land described in a deed to Marion Hills Apartments, LLC recorded in Document No. 2017-92008 (RPRDCT);

THENCE North 88°13'32" West a distance of 1,325.35 feet to a 2" iron rod found for the northwest corner of the Marion Hills Apartments, LLC;

THENCE South 2°25'03" West a distance of 2,504.45 feet to a 1/2" iron rod set for the southwest corner of Lake Ridge Estates, Phase 1 an addition to the City of Sanger recorded in Cabinet V, Page 752 of the Plat Records of Denton County, Texas (PRDCT) and the north right-of-way line of McReynolds Road;

THENCE with the north right-of-way line of McReynolds Road North 87°25'44" West a distance of 612.45 feet to a 1/2" iron rod set for the southwest corner of the Sanger Town Center LLC tract and the east right-of-way line of Indian Lane right-of-way recorded in Document No. 2004-145888 (RPRDCT);

THENCE with the east right-of-way line of Indian Lane as follows:

North 2°15'10" East a distance of 1,935.36 feet to a 1/2" iron rod set for corner;

North 5°39'58" East a distance of 200.32 feet to a 1/2" iron rod set for corner;

North 2°02'56" East a distance of 24.96 feet to the beginning of a curve to the left, having a radius of 550.39 feet, a chord of North 16° 40' 37" West – 354.48 feet, a distance of 360.91 feet to a 1/2" iron rod set for corner in the east line of a tract of land described in a deed to Sanger ISD (herein called Tract 1) recorded in Volume 1841, Page 662 (RPRDCT);

THENCE South 88°03'30" East a distance of 21.92 feet to a 1/2" iron rod set for the southwest corner of a tract of land described in a deed to Sanger ISD recorded in Document No. 2022-160016 (RPRDCT);

THENCE with the south and east line of the Sanger ISD tract

North 56°02'48" East a distance of 62.25 feet to a 1/2" iron rod set for corner;

North 02°36'29" East a distance of 643.72 feet to a 1/2" iron rod set for corner;

North 45°05'54" East a distance of 148.05 feet to a 1/2" iron rod set for corner;

North 02°36'29" East a distance of 1013.28 feet to a 1/2" iron rod set for the northeast corner of a tract of land described in a deed to Sanger ISD recorded in Document No. 2022-160017 (RPRDCT);

THENCE with the north line of the Sanger ISD tract North $87^{\circ}23'31''$ West a distance of 150.00 feet to a 1/2" iron rod set for corner in the east line of a tract of land described in a deed to Sanger ISD Tract 1;

THENCE with the east line of the Sanger ISD Tract 1 North $2^{\circ}36'29''$ East a distance of 616.01 feet to a 1/2" iron rod set for the northeast corner of the Sanger ISD Tract 1 and the northwest corner of the Sanger Town Center LLC and the south right-of-way line of West Chapman Road;

THENCE with the south right-of-way line of West Chapman Road and the north line of the Sanger Town Center LLC as follows:

South $87^{\circ}53'26''$ East a distance of 1,269.90 feet to a 1/2" iron rod set for corner;

South $88^{\circ}02'57''$ East a distance of 500.69 feet to a 1/2" iron rod set for corner;

South $87^{\circ}47'23''$ East a distance of 2,068.95 feet to a 1/2" iron rod set for the northeast corner of the Dualbond Holdings, LLC Tract and the northwest corner of a tract of land described in a deed to Miller Family Trust recorded in Document No. 94-0089391 (RPRDCT);

THENCE with the west line of the Miller Family Trust tract South $2^{\circ}58'32''$ West a distance of 1,272.08 feet to a 1/2" iron rod set for corner;

THENCE South $2^{\circ}42'07''$ West a distance of 3,659.25 feet to the place of beginning, containing 347.329 acres, or 15,129,632 square feet of land.

347.329 ACRE LANE RANCH PD SUMMARY

Purpose Statement - To amend PD 04-11-22 and establish a quality master planned multi-phase and multiple product residential and commercial community for the property described by metes and bounds on Exhibit "A" (the "Property") of this PD Ordinance. Development and use of the Property shall comply with the Sanger Zoning Ordinance as it existed on the date of its adoption on August 3, 1987 and subsequent amended (the "The Zoning Ordinance") and this PD ordinance. In the event of a conflict between the Zoning Ordinance and this PD Ordinance, this PD ordinance shall control.

PROPOSED USES

Single Family (210.499 Acres)

Approximately 190.299 acres are proposed as single-family detached uses and 20.20 acres as single family attached (townhome).

Business District (50.14 Acres)

Approximately 50.14 acres are proposed as local business and retail. Within this area we also anticipate approximately 8 acres of assisted living along with 15 acres of multi-family.

Open Space/Floodplain (86.69 Acres)

Approximately 86.69 acres of proposed open space, park area and floodplain.

COMMUNITY FEATURES

The hardscape within the community shall include entry monuments, screening walls and community signage constructed primarily of brick and stone. Wood and metal elements can be used to add interest. Signs shall not be within the sight visibility triangles.

A mandatory homeowners association shall be established to own and maintain the private open spaces, common areas and greenbelts; all private landscape improvements; dog parks and dog waste stations, perimeter masonry and tubular steel fencing; entry monuments and signage. The homeowner's association shall maintain on street parking spaces within a street right-of-way

and any parking spaces located within a common area lot. Private trails and sidewalks shall be constructed within a pedestrian access easement and owned and maintained by the HOA.

The 100-year floodplain shall be designated as a public drainage easement within the Public Parkland dedication. Maintenance responsibility shall be identified on the plat using the City of Sanger Standard drainage easement inscription.

RESIDENTIAL LAND USES

I. Lot Sizes, Setbacks, etc. for Single Family Detached. Except as otherwise provided below, detached single family residences shall comply with Section 53, “R-1” RESIDENTIAL DISTRICT -1 of the Zoning Ordinance, subject to the following changes:

A. Minimum Lot Width, Depth, and Size.

The Estate Lots:

The minimum lot width shall be 60 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 7,200 square feet.

The Manor Lots:

The minimum lot width shall be 50 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 6,000 square feet.

The Garden Lots:

The minimum lot width shall be 40 feet. The minimum lot depth shall be 120 feet. The minimum lot size shall be 4,800 square feet.

B. Lot Depths for Cul-de-Sac and Eyebrow Lots.

The minimum lot depth for all lots within any proposed residential use along a cul-de-sac or eyebrow may have a reduced lot depth of 95 feet. The lot minimum square footage still applies.

C. Minimum House Size.

The Estate Lots:

The minimum air-conditioned area within each residence shall be 2,250 square feet.

The Manor Lots:

The minimum air-conditioned area within each residence shall be 1,650 square feet. The Manor Lots shall place a limit of 20% of the total lot count to be below 2,000 square feet. No more than 10% shall be between 1,650 square feet to 1,800 square feet.

The Garden Lots:

The minimum air-conditioned area within each residence shall be 1,500 square feet. Garden Lots shall place a limit of 20% of the total lot count to be below 1,650 square feet.

D. Maximum Height.

The maximum building height shall be 2 stories or 35 feet.

E. Front Yard Setback.

The minimum front yard building setback for all lots shall be 25 feet. Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet.

F. Side Yard Setback.

The minimum side yard building setback shall be five feet (5') on each side. A side yard adjacent to a street on a corner lot shall always have a minimum ten-foot (10') side yard building setback.

G. Rear Yard Setback.

The minimum rear yard building setback for all lots shall be 20 feet from the rear facade of the residence (excluding porches and projecting architectural features) to the rear lot line. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet (5').

H. Maximum Lot Coverage.

The maximum lot coverage will be 65% for any residential lot.

I. Garages.

An enclosed parking area of at least four hundred square feet shall be provided for a garage (this does not count towards the minimum house size). The face of a garage door must be located at least 20 feet from the street right-of-way line that the garage door faces. The garage door does not have to be behind the street facing façade of the house. Split garage doors with a separate door for each vehicle bay are not required.

J. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019, except as noted below:

- 1.3 Garages shall be a minimum of 400 square feet. Any garage facing a public street may not extend more than 15 feet beyond the house front or front porch, whichever is closer. On non-typical lots where site constraints are present, a variance to the maximum 15 feet garage extension beyond house front may be approved by the Director of Development Services or through an alternative façade permit application by the City Council.

- 1.4 All walls, except gabled roof areas, which are on the front façade and face a street other than an alley must contain at least 25% of the wall space in windows and doors. The garage door shall count as a “door” towards the 25% requirement.

In lieu of side yard walls on corner lots requiring windows and doors comprising of 25% of the wall space, a corner lot shall comply with the following:

1. A side yard wall on a corner lot facing a street shall consist of at least 2 windows or doors totaling 25 square feet in aggregate area.
2. On corner lots, side yard fencing facing residential streets and the adjacent gate return, shall be a stained 6-foot-tall cedar board-on-board fence with a decorative top cap and metal posts. Posts and hardware shall be on the internal side of the fence and not viewed from the public ROW.
3. On corner lots, fencing facing a collector or arterial street shall be a 6-foot masonry wall with columns.
4. On corner lots, front fencing or gates that face a primary street shall be set back from the front façade a minimum of 10 feet but no more than 15 feet.
5. If a window of any size is not installed on the side of a house on a corner lot between the front build line and side yard fence return, shrubs of a minimum of 3 gallons in size shall be planted between front build line and fence return at a spacing of 4 feet on center. In addition, one 3-inch caliper eastern red cedar (*Juniperus virginiana*), or other evergreen tree species approved by the Director of Development Services, shall be planted at the longitudinal midpoint between the front build line and fence return.

II. Lot Sizes, Setbacks, etc. for Single Family Attached. Except as otherwise provided below, attached single family residences shall comply with Section 57, “TH” TOWNHOME RESIDENTIAL DISTRICT of the Zoning Ordinance, subject to the following changes:

A. Minimum Lot Width, Depth, and Size.

The minimum lot width shall be 22 feet. The minimum lot depth shall be 90 feet. The minimum lot size shall be 1,980 square feet.

B. Minimum House Size.

The minimum air-conditioned area within each residence shall be 1,300 square feet.

C. Maximum Height.

The maximum building height shall be 2 stories or 40 feet.

D. Driveway/Garage Locations.

All residential dwellings shall be either front entry from a public street, or rear entry from an alleyway.

E. Front Yard Setback.

The minimum front yard building setback for all lots shall be 20 feet. Front porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the front yard a maximum of five feet.

F. Side Yard Setback.

The minimum side yard building setback shall be seven and one-half feet (7.5') on each side. A side yard adjacent to a street on a corner lot shall always have a minimum ten-foot (10') side yard building setback. For end dwelling units that abut a common area lot rather than an alley or street right of way, the minimum side yard setback adjacent to the common area lot shall be 5 feet.

G. Rear Yard Setback.

The minimum rear yard building setback for all front entry lots shall be 10 feet from the rear facade of the residence (excluding porches and projecting architectural features) to the rear lot line. All rear entry lots shall have a 20-foot setback from the garage to the alley right-of-way. Porches and architectural features such as stoops, overhangs, courtyard walls, masonry chimneys and bay windows may extend into the rear yard a maximum of five feet (5').

H. Maximum Lot Coverage.

The maximum lot coverage shall not apply to any townhomes.

I. Parking.

Two off-street parking spaces shall be provided per unit within the required garage. All residential dwellings shall have a minimum 20-foot driveway for additional parking beyond the garage.

Guest parking will be provided within the site at a ratio of 1 space per 4 units.

J. Design Elements

All residential dwellings will meet the City of Sanger Exterior Façade Design Criteria Manual as adopted on October 7, 2019, except as noted below:

- 1.3 Have attached garages with a minimum of 400 square feet. Any garage facing a public street may not extend more than 15 feet beyond the house front. On non-typical lots where site constraints are present, a variance to the maximum 15 feet garage extension beyond house front may be approved by the Director of Development Services or through an alternative façade permit application by the City Council.

- 1.4 All walls, except gabled roof areas, which are on the front façade and face a street other than an alley must contain at least 25% of the wall space in windows and doors. The garage door will count as a “door” towards the 25% requirement.

III. Lot Sizes, Setbacks, etc. for Multi-Family. Except as otherwise provided below, Multi-Family residences shall comply with Section 19, “MF-2” MULTI-FAMILY RESIDENTIAL DISTRICT – 2 of the Zoning Ordinance., subject to the following changes:

A. Maximum Height.

The maximum building height shall be 3 stories or 45 feet.

IV. General Conditions.

- A. For the purposes of determining compliance with the lot width requirements, lot widths shall be measured at the rear of the required front yard setback as shown on the Final Plats.
- B. Sidewalks may be located outside of the public right-of-way if located within an adjacent open space lot with a pedestrian access easement to provide for meandering sidewalks and trails that may be located within adjacent common area lots or to preserve existing trees along perimeter roads.

V. Residential Single Family Detached Landscape Requirements. Except as otherwise provided below, landscape requirements shall comply with Section 48, Landscape Regulations of the Zoning Ordinance, subject to the following changes:

The following requirements apply to single family residential development:

- A. Each single-family residence shall have an irrigation system in the front yard and street corner side yard with a freeze sensor regulator shut off.
- B. Each Home lot shall have a minimum of two shade trees that are at least three inches in caliper planted. The trees shall be planted in the front and rear yard. If the lot fronts or sides onto a common area lot, the front yard requirement may be satisfied with the trees located in the adjacent greenspace. No other front yard or side yard tree planting requirement shall apply.
- C. All required trees shall be selected from a tree list approved during the Home Permitting stage.
- D. Each Home lot shall have a minimum of twelve (12) shrubs placed in the front yard. Individual shrubs shall be a minimum of three (3) gallons in size when planted.

VI. Multifamily, Townhome and Non-residential Uses Landscape Requirements.

All landscape requirements shall comply with Sections 48.4 and 48.5, Landscape Regulations of the Zoning Ordinance.

VII. Parkland/Open Space (86.69 Acres)

- A. The developer, and its assigns, agree to dedicate approximately 38.50 acres of the total 86.69 acres of open space/floodplain as Public Park property (the “Parkland”) to the City of Sanger. Common areas shall include floodplain, ponds, detention areas, and small open spaces as shown on the Preliminary Park Concept Plan. Small Open Spaces shall be connected with sidewalks to be a comprehensive pedestrian system. Common areas will abut a public street right-of-way in at least one location with a sidewalk connection. The Parkland shall be credited toward the Park Land Dedication requirement.
- B. A pedestrian circulation system shall be provided that affords connectivity to the entire community and the perimeter of the Property. The pedestrian circulation system shall include concrete trails that are a minimum of six feet in width. Trails in greenbelts will be constructed of concrete and shall connect with the project sidewalks. The pedestrian circulation system may be located on private property with a pedestrian access easement or within the right-of-way. The pedestrian circulation system shall include such items as benches, landscaping, signage, lighting, bike racks, water fountains, trash cans, and doggie waste stations. These items are represented on the Preliminary Park Concept Plan.
- C. All interior residential street rights-of-way shall be improved with sidewalks that are a minimum of four feet in width and (1) constructed by the homebuilders at the time of adjacent house construction; or (2) constructed by the developer for all non-buildable lots. All sidewalks along Collector and Arterial Road frontages are to be five feet in width. The pedestrian circulation system will replace the required public sidewalk along Lane Ranch Drive as shown on the Preliminary Park Concept Plan.
- D. The developer, and its assigns, agree to also install additional amenities such as an off-street parking lot, dog park, covered picnic area, playground equipment and fishing docks as shown on the Preliminary Park Concept Plan. The exact number and location of these amenities may change during the final design process. They are generally represented on the Preliminary Park Concept Plan.
- E. The phasing of the park improvements will coincide with the residential phasing plan and is noted on the overall Preliminary Park Concept Plan.

VIII. Fencing Requirements

- A. The developer shall install a perimeter brick or stone screening wall along Major Collector Streets as shown on the Concept Plan. Floodplain, parks, open spaces, right-of-way shall be exempt from the screening requirements in this Section; however, tubular steel fencing may be installed in these areas at the developer's option.
- B. Homebuilder side yard and back yard fencing on residential lots shall be a maximum of six feet in height and shall be setback a minimum of five feet from the front building line shown on the Detail Plan.
- C. Fencing on all residential lots abutting an open space lot or greenbelt shall be restricted to tubular steel painted black. No solid fencing other than a brick and/or stone masonry courtyard wall under 42 inches shall be permitted abutting an open space lot or greenbelt; however, landscape borders, including trimmed hedges, are permitted.

IX. Street Typology

- A. Standard curbs will be required adjacent to streets abutting all residential lot types unless otherwise approved by the City's engineering department.
- B. Streets fronting open space lots must have standard curbs adjacent to the common area lot. Streets adjacent to common area lots may provide for on-street parking. In addition, the street faces adjacent to open spaces near the flood plain will have a maintenance access location.
- C. Developer shall work with City to determine the location and number of stop signs within the subdivision and speed limits to facilitate traffic calming and maximize the benefit from the pedestrian system.

X. Utilities and Equipment

- A. Electrical and gas utility meters and AC condensers should be unobtrusively located beyond the front or side street facade zone and screened from view from adjacent streets or common open spaces with landscaping or appropriate fencing.
- B. Transformers on individual lots should be screened to minimize visual impact.
- C. Satellite dishes and solar panels should be located in less conspicuous locations and out of view from adjacent streets or common open spaces when possible.
- D. Antennas should be located inside the building when possible.
- E. Solar panels, when visible from the front, should be flush with the roof.
- F. All public utility easements (PUE) shall be a minimum of 15 feet in width. All franchise utility easements (FUE) shall be a minimum of 10 feet in width.

XI. Refuse Locations

- A. Refuse containers should be stored within an enclosed storage area, fenced, or walled to be screened from view from adjacent streets or common open spaces. Landscaping could also be added as a screening measure.


XII. Home Variety

- A. Detached home designs with the same or similar facade, materials, or colors should be separated by a minimum of three lots on the same side of the street and should not be located directly across or diagonally across the street from each other.
- B. If a detached home plan is repeated on an adjacent lot, it should be elevated with a different architectural style or two of the following three elevation changes - brick color, roof color, or flipped plan.

BUSINESS DISTRICT USES

Except as otherwise provided below, commercial uses shall comply with Section 23, “B-2” Business District - 2 of the Zoning Ordinance, subject to the following changes:

- 1. A 15-acre multi-family site will be allowed. The base zoning for this tract will be “MF-2” Multi-Family Residential District - 2 at 20 units per gross acre. See Section III for other changes to the MF-2 base zoning category.
- 2. Self-Storage facilities may be allowed by SUP approval.
- 3. Boat storage facilities may be allowed by SUP approval.
- 4. The building height for a pitched roof building shall be a maximum of 45 feet.
- 5. The front, rear, and side building setbacks adjacent to any internal street shall be a minimum of 15 feet.
- 6. Any mechanical equipment including roof top equipment shall be screened from residential districts either by fencing, landscaping, or rooftop screening as applicable.



LEGEND


- GENERAL BUSINESS AREAS
- 60' ESTATE LOTS
- 50' MANOR LOTS
- 40' GARDEN LOTS
- TOWN HOME LOTS
- GRASS/OPEN SPACE
- LAKES
- LAKERIDGE PD

APPROX. RESIDENTIAL LOT COUNT BY TYPE

54	LOTS (ESTATE LOTS)
603	LOTS (MANOR LOTS)
299	LOTS (GARDEN LOTS)
130	LOTS (TOWN HOMES)
TOTAL	1086 LOTS

RESIDENTIAL AREA	210.499 AC.
• SINGLE FAMILY	190.299 AC.
• TOWN HOMES	20.20 AC.
GENERAL BUSINESS AREA	50.14 AC.
OPEN SPACE/FLOODPLAIN	86.69 AC.

PRELIMINARY - FOR REVIEW ONLY
These documents are for design review
and are not intended for construction or
permit purposes. They were prepared by
F. E. MIDDLETON, JR., P.E. 67449



No.	DATE	REVISION	APPROV.
			9-18-23

M

&

A

PROJECT ENGINEER:

Middleton & Associates, LLC.

CONSULTING CIVIL ENGINEERS & LAND PLANNERS

TBPE #F-10900 © Copyright 2023

2785 ROCKBROOK DRIVE, SUITE 105

LEWISVILLE, TEXAS 75067 (972) 393-9800


CONCEPT PLAN

LANE RANCH

347.329 ACRES - CITY OF SANGER

DENTON COUNTY TEXAS

Drawing File: 0001032CONCEPT6.DWG	DATE: 9-18-23	SCALE: 1"=250'	SHEET NO: 1
Project No. 0001032			1





LEGEND

- PARK BENCH/DOG WASTE STATION/TRASH CANS
- 6' HIKE & BIKE TRAIL
- PARK AREA/OPEN SPACE
- LAKES
- COVERED PICNIC AREA
- ⊙ PLAYGROUND
- ⊥ FISHING PIER
- ① PARK PHASE NUMBER
- PARK PHASE LINE
- PARKING AREA FOR PARKS

TOTAL OPEN SPACE - 86.69 AC.


PARKLAND DEDICATION REQUIREMENT

- SINGLE FAMILY (1 AC./50 D.U.) 21.70 AC.
- MULTI-FAMILY (1 AC./21 BEDROOMS) 16.80 AC.
- TOTAL 38.50 AC.

PARKLAND DEDICATION WILL BE ACCOMPLISHED BY DEDICATING OPEN SPACE AND USABLE FLOODPLAIN WITHIN THE 90.69 ACRES.

TOTAL LENGTH OF TRAIL SYSTEM=15,976 L.F. (3.02 MILES)

PRELIMINARY - FOR REVIEW ONLY
These documents are for design review
and not intended for construction or
permit purposes. The user is responsible for
F. E. MIDDLETON, JR. P.E. 67449



No.	DATE	REVISION	APPROV.

**Middleton PROJECT ENGINEER:
& Associates, LLC.**

CONSULTING CIVIL ENGINEERS & LAND PLANNERS
TBPE #10900
2785 ROCKBROOK DRIVE, SUITE 105
LEWISVILLE, TEXAS 75067 (972) 393-9800

PRELIMINARY PARK CONCEPT PLAN

LANE RANCH
347.329 ACRES - CITY OF SANGER
DENTON COUNTY TEXAS

Drawing File: 0001032CONCEPT6-PARK	DATE: 9-18-23	SCALE: 1"=250'	SHEET NO: 1
Project No. 0001032			1

