

Santaquin ULS Connection



VanCon Inc.

2335 South State Street

Provo, UT 84606

Contact: Chad Hunsaker

Phone: 801-491-8898

Quote To: Santaquin City
Attn: John Lundell

Job Name:

Date:

Phone:

Revision Date:

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1	Mobilization	1.00	LS	7,650.00	7,650.00
2	16" WSP w/ 24" x 16 WSP Reducer	1.00	LS	44,189.00	44,189.00
3	16" BFV 300 # Double Off-Set Valve	1.00	EA	24,117.00	24,117.00
GRAND TOTAL					\$75,956.00

NOTES:

VanCon is pleased to provide the following quote for your review and approval.

VanCon proposes the following. Providing a single spool that is a 24" x 16" WSP Flange x Flange Spool with 300 # flanges on each end that will be roughly 20' to 22' in length that is Standard wall thickness with Cement Mortar lining (CML) x Cement Mortar Coating (CMC).

Spool will be attached to existing CUWCD pipeline with a 24 inch insulating kit.

At the end of the WSP spool a 16 Inch Avtec Double Off-Set BFV will be installed, there is currently (1) in stock in Utah.

Pipe will be bedded and backfill with CLSM (Flowfill)

Pipe will be pressure tested.

VanCon has all the required WSP available. Fabrication time will be 2-3 weeks after flange delivery which is 2-3 weeks. BFV is available at the current date subject to sale. Flange Bolts, Gaskets, and Insulating Kits are typically 2-3 week lead time from approval.

Work can be completed in 5-7 weeks from approval or sooner potentially based on supply availability.

Please reach out with any questions.

Chad Hunsaker
VanCon Inc.