


Amsource Santaquin

Main Street & Highland Drive Santaquin, Utah, 84655



Vicinity Map
Not to Scale

Civil Sheet Index

C0.0	Cover Sheet
C0.1	Subdivision Plat
C1.0	Demolition Plan
C1.1	Overall Site Plan
C1.2	Site Plan
C2.1	Phasing Plan
C2.2	Grading Plan
C3.1	Grading Details
C3.2	Utility Plan
C3.3	Waterline Plan & Profile
C3.4	Waterline Plan & Profile
C3.5	Waterline Plan & Profile
C4.1	Sewer Plan & Profile
C4.2	Details
C4.3	Details
C5.1	Erosion Control Plan - Pre-Construction
C5.2	Erosion Control Plan - During Construction
C5.3	Erosion Control Details

Abbreviations

BCR	Begin Curb Return	PP	Power Pole
BOL	Bollard	PT	Point of Tangency
BRW	Finish Grade - Bottom of Retaining Wall	PVC	Polyvinyl Chloride
CATV	Cable Television Box	PVI	Point of Vertical Intersection
CB	Catch Basin	RCP	Reinforced Concrete Pipe
CMP	Corrugated Metal Pipe	RD	Roof Drain
COB	Cleanout Box	SB	Signal Box
COTG	Cleanout to Grade	SD	Storm Drain
EA	Edge of Asphalt	SDMH	Storm Drain Manhole
EB	Electrical Box	SMH	Sewer Manhole
EC	End of Curve	SP	Signal Pole
ECR	End Curb Return	SS	Sanitary Sewer
FF	Finished Floor	SVZ	Sight Visibility Zone
g	Ground	SW	Secondary Water
GB	Grade Break	TA	Top of Asphalt
GM	Gas Meter	TB	Telephone Box
HB	Hose Bib	TBC	Top Back of Curb
HP	High Point	TG	Top of Grate
I	Irrigation Line	TMH	Telephone Manhole
ICB	Irrigation Control Box	TP	Top of Concrete
Lip	Lip of Gutter	TRW	Finish Grade - Top of Retaining Wall
LP	Light Pole	TW	Top of Walk
MH	Manhole	VC	Vertical Curve
Mon	Monument	VPC	Vertical Point of Curve
PC	Point of Curvature	VPT	Vertical Point of Tangency
PCC	Point of Compound Curvature	WL	Waterline
PI	Point of Intersection	WP	Working Point
PM	Power Meter	WV	Water Valve

Legend

Proposed Curb & Gutter	Existing Improvements	Existing Asphalt
Proposed Open Face C & G	Existing Asphalt	Existing Concrete
Proposed Asphalt	Existing Inlet Box	Existing Catch Basin
Proposed Concrete	Existing Manhole	Existing Fire Hydrant
Proposed Truncated Domes	Existing Fire Hydrant	Existing Water Valve
Proposed Inlet Box	Existing Water Valve	Existing Overhead Power Line
Proposed Catch Basin	Existing Overhead Power Line	Existing Water
Proposed Manhole	Existing Water	Existing Secondary Water
Proposed Transformer	Existing Sewer	Existing Storm Drain
Proposed Meter Box	Existing Storm Drain	Existing Gas
Proposed Water Meter	Existing Gas	Existing Power
Proposed Combo Box	Existing Power	Existing Telephone
Proposed Fire Hydrant	Existing Telephone	Existing Fiber Optic
Proposed Water Valve	Existing Fiber Optic	Existing Fence
Proposed Water Line	Existing Fence	Flowline
Proposed Sanitary Sewer	Flowline	Centerline
Proposed Storm Drain	Centerline	Existing Contour
Proposed Conduit Line	Existing Contour	Existing Spot
Proposed Power Line	Existing Spot	Existing Light Pole
Proposed Gas Line	Existing Light Pole	Existing Street Light
Proposed Fire Line	Existing Street Light	Existing Building
Proposed Fiber Optic	Existing Building	Existing Telephone Box
Proposed Secondary Water Line	Existing Telephone Box	Existing Power Meter
Proposed Roof Drain	Existing Power Meter	Existing Electrical Box
Proposed Fence	Existing Electrical Box	Existing Electrical Cabinet
Ridge line	Existing Electrical Cabinet	Existing Gas Meter
Grade Break	Existing Gas Meter	Existing Water Meter
Proposed Contour	Existing Water Meter	Existing Irrig. Control Box
Direction of Drainage	Existing Irrig. Control Box	Existing Bollard
Proposed Spot	Existing Bollard	Existing Hose Bib
ADA Accessible Route	Existing Hose Bib	Working Point
Property Line	Working Point	Existing Deciduous Tree
Sawcut Line	Existing Deciduous Tree	Existing Coniferous Tree
Proposed Light Pole	Existing Coniferous Tree	Detail Number
Proposed Street Light	Detail Number	Sheet Number
Proposed Building	Sheet Number	
Existing Power Pole		
Existing Power Pole w/ Guy		
Existing Utility Marker		
Existing Post		

Developer:

Corner Partners, LLC
Address: 3307 West 200 South, Suite
3003 Salt Lake City, Utah 84101
Phone: (801) 111-1234

Civil Engineer:

AWA
Address: 2010 North Redwood Road
Salt Lake City, Utah 84116
Phone: (801) 111-1234

Geotechnical Engineer:

GSH
Address: 473 West 4800 South
Salt Lake City, Utah 84123
Phone: (801) 685-9190

Overall Site Data Table

Zoning Designation: C-1 General Commercial

Total Number of Lots: 5

Total Site Area = 235,801 s.f. (5.413 ac.)

- Lot 1 = 48,993 s.f. (1.125 ac.)
- Lot 2 = 53,575 s.f. (1.230 ac.)
- Lot 3 = 22,994 s.f. (0.528 ac.)
- Lot 4 = 34,961 s.f. (0.803 ac.)
- Lot 5 = 106,340 s.f. (2.441 ac.)

Impervious Area Provided = 20,676 s.f.

Santaquin City Notes

It is important for the developer and the general contractor to understand that it is his/her responsibility to ensure that all improvements installed within this development are constructed in full compliance with all state and Santaquin City codes, ordinances and standards. This fact does not relieve the developer or general contractor from full compliance with all minimum state and Santaquin City standards.

Santaquin City Note to Developers & General Contractors

All recommendations made in the provided geotechnical report/study shall be followed explicitly during construction of building and site improvements.

Flood Zone

This property lies entirely within Flood Zone X as designated on FEMA Flood Insurance Rate Map for Utah County, Utah and Incorporated Areas Community Map No. 49049C0975F dated June 19, 2020. Flood Zone X is defined as "Areas determined to be outside the 0.2% annual floodplain." (No Shading)

Basis of Bearings

A line between monuments found for the South Quarter and the Southeast Quarter of Section 1 was assigned the Utah County bearing of North 88°57'44" East as the Basis of Bearings to place the Survey on the NAD83 Utah Central Zone State Plane Datum.

Benchmark

Brass Cap Monument for the East Quarter of Section 1, T10S, R1E, SLB&M Elevation = 5024.32 feet (Ortho Height, Geoid 18)



Legal Description

File No. 2251028:

Lot 1, Plat "A" PARKER VIEW SUBDIVISION, also Amending Parcel 5, Maverik Subdivision, Santaquin, Utah, according to the Official Plat thereof on file in the Office of the Recorder, Utah County, Utah.

File No. 2266491:

Lot 76, Plat "A", SANTAQUIN ESTATES, a residential Subdivision, according to the Official Plat thereof recorded April 12, 2023, as Entry No. 22969:2023, as Map Filing No. 18709, in the Office of the Utah County Recorder.





7 Apr, 2025

SHEET NO.

C0.0



Amsource Santaquin Subdivision

Amending all of Lot 1 of Parker View Subdivision Plat 'A' and all of Lot 76 of Santaquin Estates Plat 'A' being A part of the Southeast Quarter of Section 1, Township 10 South, Range 1 East, Salt Lake Base and Meridian, U.S. Survey, City of Santaquin, Utah County, Utah 2025



Scale: 1" = 50'

50' 0 50' 100'



Vicinity Map
Not to Scale

Narrative

This Subdivision was requested by Amsource Development in order to amend the existing Lots 1 and 76 and create 6 Lots.

This Survey retraces and honors the underlying plats and a 2024 ALTA survey by AWA Engineering.

A line between monuments found for the South Quarter and the Southeast Quarter of Section 1 was assigned the Utah County bearing of North 88°57'44" East as the Basis of Bearings to place the Survey on the NAD83 Utah Central Zone State Plane Datum.

Acknowledgment

State of _____
County of _____

ss

On this _____ day of _____, 20____, personally appeared before me, Peter Evans the signer of the foregoing Instrument, who duly acknowledged to me that he is an Authorized Manager of BCP Development Inc., and is authorized to execute the foregoing Dedication in its behalf and that he executed it in such capacity.

Notary Public Full Name: _____

Commission Number: _____

My Commission Expires: _____

A Notary Public Commissioned in Utah

A Notary Public

Rocky Mountain Power

1. Pursuant to Utah Code Ann. 54-3-27 this plat conveys to the Owner(s) or operators of utility facilities a public utility easement along with all the rights and duties described therein.
2. Pursuant to Utah Code Ann. 17-27A-603(4)(c)(ii) Rocky Mountain Power accepts delivery of the PUE as described in this plat and approves this plat solely for the purpose of confirming that the plat contains Public Utility Easements and approximates the location of the Public Utility Easements, but does not warrant their precise location. Rocky Mountain Power may require other easements in order to serve this development. This approval does not effect any right that Rocky Mountain Power has under:

- A recorded easement or Right-of-Way
- The law applicable to prescriptive rights
- Title 54, Chapter 8a, damage to underground utility facilities or
- Any other provision of law

Approved this _____ day of _____, 20____,

Rocky Mountain Power Company

By—

Title—

Enbridge Gas Utah

Questar Gas Company, dba Enbridge Gas Utah, hereby approves this plat solely for the purposes of confirming that the plat contains public utility easements. Enbridge Gas Utah may require additional easements in order to serve this development. This approval does not constitute abrogation or waiver of any other existing rights, obligations or liabilities including prescriptive rights and other rights, obligations or liabilities provided by law or equity. This approval does not constitute acceptance, approval or acknowledgement of any terms contained in the plat, including those set forth in the Owner Dedication or in the Notes, and does not constitute a guarantee of particular terms or conditions of natural gas service. For further information please contact Enbridge Gas Utah's Right-of-Way Department at 800-366-8532.

QUESTAR GAS COMPANY
dba ENBRIDGE GAS UTAH

APPROVED THIS _____ DAY OF _____, 20____.

BY—

TITLE—

Lumen/Centurylink

Approved by Lumen this _____ Day of _____, A.D. 20____.

Lumen/Centurylink

Comcast

Approved by Comcast this _____ Day of _____, A.D. 20____.

Lumen/Centurylink

Acknowledgment

On this _____ day of _____, 20____, personally appeared before me, John Gaskill the signer of the foregoing Instrument, who duly acknowledged to me that he is an Authorized Owner of Amsource SQ1, LLC, and is authorized to execute the foregoing Dedication in its behalf and that he executed it in such capacity.

Notary Public Full Name: _____

Commission Number: _____

My Commission Expires: _____

A Notary Public Commissioned in Utah

A Notary Public

Surveyor's Certificate

I, David M. Hamilton, do hereby certify that I am a Licensed Professional Land Surveyor in the State of Utah and that I hold License No. 12966234 in accordance with Title 58, Chapter 22, of the Professional Engineers and Land Surveyors Licensing Act; I further certify for, and on behalf of AWA that by authority of the Owners I have completed Utah County Record of Survey No. _____, being a survey of the property described on this Subdivision Plat in accordance with Section 17-23-17 and have verified all measurements; that the reference monuments shown on this plat are located as indicated and are sufficient to retrace or reestablish this plat; and that the information shown herein is sufficient to accurately establish the lateral boundaries of the herein described tract of real property; hereafter known as

Amsource Santaquin Subdivision

Description

Amending all of Lot 1 of Parker View Subdivision Plat 'A' recorded as Entry No. 15585:2021 and as Map No. 17506 in the Official Records of Utah County and all of Lot 76 of Santaquin Estates Plat 'A' recorded as Entry No. 22969:2023 in the Official Records of Utah County, located within the Southeast Quarter of Section 1, Township 10 South, Range 1 East, Salt Lake Base and Meridian, U.S. Survey, in the City of Santaquin, Utah County, Utah:

Beginning at a point of curvature and the Northeast corner of said Lot 76 on the Southerly line of Main Street as it exists at 35.00 foot half-width, located 29.49 feet North 89°18'00" West to the Northwest Corner of Open Space Parcel A of said Santaquin Estates Subdivision; 103.60 feet South 0°25'42" East to the Southeast Corner of Main Street per the Final Plat of Maverik Subdivision recorded as Entry No. 88178:2009 and as Map No. 13078 in the Official Records of Utah County; and 114.77 feet North 89°30'30" West along said Southerly line of Main Street per said Maverik Subdivision from a Brass Cap Monument found marking the East Quarter Corner of said Section 1; and running thence Southeasterly along the arc of a 15.00 foot radius curve to the right a distance of 23.32 feet (Central Angle equals 89°04'48" and Long Chord bears South 44°58'06" East 21.04 feet) to a point of tangency on the Westerly line of 900 East Street as it exists at 50.00 foot half-width; thence South 0°25'42" East 191.43 feet along said Westerly line to a point of curvature; thence Southwesterly along the arc of a 250.00 foot radius curve to the right a distance of 394.57 feet (Central Angle equals 90°25'42" and Long Chord bears South 44°47'09" West 354.87 feet) to a point of tangency on the Northerly line of Highland Drive as it exists at 50.00 foot half-width; thence West 277.62 feet along said Northerly line to a point on the Easterly line of said Parker View Subdivision Plat 'A'; thence North 0°26'12" West 311.92 feet along said Easterly line to the Northeast corner of Lot 2 of said Parker View Subdivision Plat 'A'; thence North 75°34'42" West 206.75 feet along the Northerly line of said Lot 2 to the Northwest corner thereof on the Easterly line of State Route 195; thence North 10°16'26" East 126.15 feet along said Easterly line; thence North 50°16'36" East 25.68 feet to said Southerly line of Main Street; thence along said Southerly line the following five courses: South 89°43'34" East 178.49 feet to a point of curvature; Southeasterly along the arc of a 315.00 foot radius curve to the right a distance of 91.79 feet (Central Angle equals 16°41'43" and Long Chord bears South 81°22'42" East 91.46 feet) to a point of tangency; South 73°01'51" East 42.07 feet to a point of curvature; Southeasterly along the arc of a 385.00 foot radius curve to the left a distance of 110.72 feet (Central Angle equals 16°28'39" and Long Chord bears South 81°16'10" East 110.34 feet) to a point of tangency; and South 89°30'30" East 253.47 feet to the point of beginning.

Contains 266,863 sq. ft.
Or 6.126 acres
5 Lots

Date: _____

David M. Hamilton
Utah PLS No. 12966234

Owner's Dedication and Consent to Record

Know all men by these presents that I, the undersigned Owner of the hereon described tract of land, hereby set apart and subdivide the same into Lots as shown on this plat and name said plat

Amsource Santaquin Subdivision

and do hereby, grant and convey to the City of Santaquin all those parts or portions of said tract of land designated as public utility easements as shown herein to be used for the installation, maintenance and operation of Public Utility service lines.

In witness whereof I have hereunto set my hand This _____ Day of _____ AD, 20____.

BCP Development Inc.

by: Peter Evans
its: Manager

Planning Commission Approval

Approved this _____ Day of _____, AD 20____, by the Santaquin City Planning Commission.

Chairperson, Planning Commission

Date


Director — Secretary

Date

Amsource Santaquin Subdivision



Amending all of Lot 1 of Parker View Subdivision Plat 'A' and all of Lot 76 of Santaquin Estates Plat 'A' being A part of the Southeast Quarter of Section 1, Township 10 South, Range 1 East, Salt Lake Base and Meridian, U.S. Survey, City of Santaquin, Utah County, Utah

Surveyors Seal



City Engineer Seal

Clerk-Recorder Seal



Scale: 1" = 30'



General Demolition Notes:

1. Demolition and site clearing for this contract are to include all areas shown within demolition limits or by note.
2. Refer to site improvement plans for more details on limits of removal.
3. All curbs, gutters, walks, slabs, walls, fences, flatwork, asphalt, waterlines and manholes, gas lines, sewer lines, light poles, buried cables, storm drain piping and structures within the demolition limits to be cleared from site unless otherwise shown.
4. All utilities, sewer, water, gas, telephone and electrical services to be disconnected and capped according to city, county and utility company requirements, unless otherwise shown.
5. Excavated areas to be backfilled with clean granular material compacted to 95% of maximum lab density as determined by ASTM D 1557. (Test results to be given to owner) Excavated areas should be backfilled per the geotechnical report prepared for the project.
6. Clear and grub trees, shrubs, and vegetation within demolition limits, disposal to be off-site except where noted otherwise.
7. DO NOT interrupt any services or disrupt the operation of any businesses shown outside the demolition limits.
8. Remove debris, rubbish, and other materials resulting from the demolition and site clearing operations from the site and dispose of in a legal manner.
9. The location and/or elevation of existing utilities as shown on these plans is based on records of the various utility companies and, where possible, measurements taken in the field. This information is not to be relied upon as being exact or complete. Contractor shall contact authorities having jurisdiction for field locations. Contractor shall be responsible for protection of in place and relocated utilities during construction.
10. Stockpiles shall be graded to maintain slopes not greater than 3 horizontal to 1 vertical. Provide erosion control as necessary to prevent sediment transport to adjacent drainage ways.
11. Contractor shall be responsible for disposal of all waste material. Disposal shall be at an approved site for such material. Burning onsite is not permitted.
12. Contractor shall verify with city any street removal, curb cuts, and any restoration required for utility line removal.
13. Install traffic warning devices as needed in accordance with local standards.
14. Contractor shall obtain all permits necessary for demolition from City, County, State or Federal Agencies as required.
15. Demolish existing buildings and clear from site. (Including removal of all footings and foundations.)
16. If Contractor observes evidence of hazardous materials or contaminated soils he shall immediately contact the project engineer to provide notification and obtain direction before proceeding with disturbance of said materials or contaminated soil.
17. Limits of demolition/disturbed areas shown on the plans may not be an exact depiction. It is the contractor's responsibility to arrange the means and methods of how the work will be completed. The contractor shall determine the area of construction impact. The contractor is responsible to restore the area to original condition. All restoration shall be part of the contract bid.
18. Contractor shall store and protect neighboring properties per CDMA site during excavating activities and any necessary excavation shall remain on and within the bounds of the subject property. Unless specifically noted on the plans and approval from adjoining neighbor has been obtained prior to any excavation beyond the subject property limits.

CAUTION :


The location and/or elevation of existing utilities as shown on these plans is based on records of the various utility companies and, where possible, measurements taken in the field. The information is not to be relied on as being exact or complete.



Demolition Plan

Amsource Santaquin


lain Street & Highalnd Drive
Santaquin, Utah



7 Apr, 2025

SHEET NO.

CO.1








1. *All dimensions are to back of curb unless otherwise noted.*
2. *Fire lane markings and signs to be installed as directed by the Fire Marshal.*
3. *Aisle markings, directional arrows and stop bars will be painted at each driveway as shown on the plans.*
4. *Const. curb transition at all points where curb abuts sidewalk, see detail.*
5. *Contractor shall place asphalt paving in the direction of vehicle travel where possible.*
6. *Limits of demolition/disturbed areas shown on the plans may not be an exact depiction. It is the contractor's responsibility to determine the means and methods of how the work will be completed. The contractor shall determine the area of construction impact. The contractor is responsible to restore all disturbed areas and oil restoration shall be part of the contract bid.*


The Construction Survey Layout for this project will be provided by Anderson Wahlen & Associates. The Layout Proposal and Professional Services Agreement will be provided to the General Contractor(s) for inclusion in base bids. The Survey Layout proposal has been broken out into Building Costs and Site Costs for use in the Site Work Bid Form.



The Contractor agrees that he shall assume sole and complete responsibility for job site conditions during the course of construction of this project, including safety of all persons and property; that this requirement shall apply continuously and not be limited to normal working hours; and that the contractor shall defend, indemnify, and hold the owner and the engineer harmless from any and all liability, real or alleged, in connection with the performance of work on this project, excepting for liability arising from the sole negligence of the owner or the engineer.

The contractor or surveyor shall be responsible for following the National Society of Professional Surveyors (NSPS) model standards for any surveying or construction layout to be performed. The contractor or surveyor shall follow the standards of Anderson Wahlen and Associates construction improvement plans. Prior to proceeding with construction staking, the contractor or surveyor shall compare the construction layout from the survey monuments and for verifying any additional control points shown on an ALTA survey, improvement plan, or other electronic data provided by Anderson Wahlen and Associates. The surveyor shall also use the benchmarks as shown on the plan, and verify them against no less than three additional benchmarks. The contractor or surveyor shall use or electronic data provided by Anderson Wahlen and Associates. If any discrepancies are encountered, the surveyor shall stop construction and report the discrepancies to the owner. Discrepancies before proceeding with any construction staking.

	<i>Standard Asphalt Paving</i>
	<i>Existing Asphalt Paving</i>
	<i>Standard Concrete Paving</i>
	<i>Existing Concrete Paving</i>
	<i>Building Interior</i>

- | | | |
|---|--|----------|
| 1 | Const. 24" Curb & Gutter | 1
C&I |
| 2 | Const. Asphalt Paving | 2
C&I |
| 3 | Const. 4" White Paint Stripe (Typ.) Contractor shall provide 15 mils min. dry thickness (Two Coats) | |
| 4 | Sawcut; Provide Smooth Clean Edge | |
| 5 | Const. Directional Arrows per MUTCD | |
| 6 | Const. 24" White Stop Bar | |
| 7 | Const. Curb Transition | 6
C&I |
| 8 | Conn. and Match Existing Improvements | |
| 9 | Const. Asphalt Paving per UDOT Design Specs.
PG 64-64/PG 64-64 Better HMA over 6" Unreated Base Course over 12" Granular Borrow | |

- | | |
|--|--|
| <p>10 Const. 10.0' Asphalt Trail per Santaquin City Standard Drawing No. ST4</p> <p>11 Const. UDOT Conc. Driveway and Sidewalk per UDOT Std. Dwg. No. GW 3A</p> <p>12 Existing Asphalt Trail to Remain</p> <p>13 Const. Asphalt Paving per Santaquin City Standards</p> <p>14 Const. Stop Sign per MUTCD R1-1</p> <p>15 Const. Driveway Approach with Park Strip per Santaquin City Standard Drawing No. CG3</p> <p>16 Const. Curb and Gutter per Santaquin City Standard Drawing No. CG4</p> <p>17 Const. 4" Solid Double Yellow Paint Stripe per UDOT Dwg. No DM 9.2</p> |  <p>18 Const. 12" White Stop Bar</p> <p>19 Const. Breakaway Gate per Santaquin City Standards</p> |
|--|--|



Phase 1 - Site Data Table

Zoning Designation:	C-1 General Commercial
Total Number of Lots:	5
Total Site Area =	129,461 s.f. (2.972 ac.)
- Lot 1 =	48,993 s.f. (1.125 ac.)
- Lot 2 =	53,575 s.f. (1.230 ac.)
- Lot 3 =	22,994 s.f. (0.528 ac.)
- Lot 4 =	34,961 s.f. (0.803 ac.)
Impervious Area Provided =	20,676 s.f.

Phase 2 - Site Data Table

Zoning Designation:	C-1 General Commercial
Total Number of Lots:	1
Total Site Area =	106,340 s.f. (2.441 ac.)
- Lot 5 =	106,340 s.f. (2.441 ac.)
Impervious Area Provided =	0 s.f.

DESIGNED BY: JW	DATE: 4/7/25	DESCRIPTION: PHASING PLAN
DRAFTED BY: JW	REV: 0	
CLIENT NAME: Amsource		
PROJECT NO: 24-043 SP		

2010 North Redwood Road, Salt Lake City, Utah 84116
(801) 521-8629 - AWEngineering.net


Phasing Plan

Amsource Santaquin

Main Street & Highland Drive
Santaquin, Utah

7 Apr, 2025

SHEET NO. **C1.2**



General Grading Notes:

- All grading shall be in accordance with the project geotechnical study.
- Cut slopes shall be no steeper than 3 horizontal to 1 vertical.
- Fill slopes shall be no steeper than 3 horizontal to 1 vertical.
- Fills shall be compacted per the recommendations of the geotechnical report prepared for the project and shall be certified by a Geotechnical Engineer.
- Areas to receive fill shall be properly prepared and approved by a Geotechnical Engineer prior to placing fill.
- Fills shall be benched into competent material as per specifications and geotechnical report.
- All trench backfill shall be tested and certified by a Geotechnical Engineer.
- A geotechnical engineer shall perform periodic inspections and submit a complete report and map upon completion of the rough grading.
- The final compaction report and certification from a Geotechnical Engineer shall contain the type of field testing performed. Each test shall be identified with the method of obtaining the *n*-place density, whether sand cone or drive ring and shall be so noted for each test. Sufficient maximum density determinations shall be performed to verify the accuracy of the maximum density curves used by the field technician.
- Dust shall be controlled by watering.
- The location and protection of all utilities is the responsibility of the permittee.
- Approved protective measures and temporary drainage provisions must be used to protect adjoining properties during the grading process.
- All public roadways must be cleared daily of all dirt, mud and debris deposited on them as a result of the grading operation. Cleaning is to be done to the satisfaction of the City Engineer.
- The site shall be cleared and grubbed of all vegetation and deleterious matter prior to grading.

- The contractor shall provide shoring in accordance with OSHA requirements for trench walls.
- Aggregate base shall be compacted per the geotechnical report prepared for the project.
- The recommendations in the following Geotechnical Engineering Report by GeoStrata are included in the requirements of grading and site Preparation. The Report is titled "Geotechnical Investigation Santaquin Commercial Property".
Project No.: 1960-001
Dated: January 24, 2025
- As part of the construction documents, owner has provided contractor with a topographic survey performed by manual or aerial means. Such survey was prepared for project design purposes and is provided to the contractor as a courtesy. It is expressly understood that such survey may not accurately reflect existing topographic conditions.
- If Contractor observes evidence of hazardous materials or contaminated soils he shall immediately contact the project engineer to provide notification and obtain direction before proceeding with disturbance of said materials or contaminated soil.

Curb and Gutter Construction Notes:

- Open face gutter shall be constructed where drainage is directed away from curb.
- Open face gutter locations are indicated by shading and notes on the grading plan.
- It is the responsibility of the surveyor to adjust top of asphalt grades to top of curb grades at the time of construction staking.
- Refer to the typical details for standard and open face curb and gutter dimensions.
- Transitions from open face to standard curb and gutter are to be smooth. Hand form these areas if necessary.
- Spot elevations are shown on this plan with text masking. Coordinate and verify site information with project drawings.

Sidewalk Construction Notes:


- Concrete sidewalk shall be constructed with a cross slope of 1.5% unless shown otherwise on plan.
- Running slope of sidewalks shall be built per grades shown on the plan. where grades are not provided, sidewalks shall be constructed with a maximum running slope of 4.5%.
- Refer to the Site Plan for sidewalk dimensions.

Designed by: JW
Drafted by: JW
Client Name: Amsource
24-043 GR - Phase 1


2010 North Redwood Road, Salt Lake City, Utah 84116
(801) 521-8529 - AmsourceEngineering.net

Grading Plan
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah


7 Apr, 2025
SHEET NO.
C2.1




5 Temporary Drainage Swale
Not to Scale




4 Temporary Drainage Swale
Not to Scale



3 Temporary Drainage Swale
Not to Scale



2 Enlarged Grading Detail
Scale: 1" = 5'




Note:
2.0% - 3.0% Cross Slope from
Edge of Asphalt at Sawcut to New Lip
of Gutter. Field Verify Cross Slope
Prior to Forming or Pouring Concrete.

1 Enlarged Grading Detail
Scale: 1" = 5'

Designed by: JW
Drafted by: JW
Client Name:
Amsource
24-043 GR - Phase 1




Grading Details
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah



7 Apr, 2025

SHEET NO.

C2.2



General Utility Notes:

- All sewer and water facilities shall be constructed per local jurisdiction standards and specifications. Contractor is responsible to obtain standards and specifications.
- Coordinate all utility connections to building with plumbing plans and building contractor.
- Verify depth and location of all existing utilities prior to constructing any new utility lines. Notify Civil Engineer of any discrepancies or conflicts prior to any connections being made.
- All catch basin and inlet box grates are to be bicycle proof.
- Refer to the site electrical plan for details and locations of electrical lines, transformers and light poles.
- Gas lines, telephone lines, and cable TV lines are not a part of these plans.
- Water meters are to be installed per city standards and specifications. It will be the contractor's responsibility to install all items required.
- Water lines, valves, fire hydrants, fittings etc. are to be constructed as shown. Contractor is responsible, at no cost to the owner, to construct any vertical adjustments necessary to clear sewer, storm drain, or other utilities as necessary including valve boxes and hydrant spools to proper grade.
- Contractor shall install a 12" concrete collar around all manholes, valves, catch basins, cleanouts & any other structures located within the asphalt.

Utility Piping Materials:

All piping materials shall be per local agency standards or the specifications below at a minimum. All utility piping shall be installed per manufacturers recommendations. Refer to project specifications for more detailed information regarding materials, installation, etc.

Culinary Service Laterals

- Polyethylene (PE) Water Pipe (Up to 3 inches diameter), AWWA C901, PE 340B, SDR 9 (200 psi)
- Copper Pipe (Up to 3 inches diameter): Type "K."

Water Main Lines and Fire Lines

- Polyvinyl Chloride (PVC) (4 inches to 12 inches diameter): AWWA C900, Class 235

Sanitary Sewer Lines

- All sewer piping to be Polyvinyl Chloride (PVC) sewer pipe, ASTM D3034, Type PSM, SDR 35

Storm Drain Lines

- 12" pipes or smaller — Polyvinyl Chloride (PVC) sewer pipe, ASTM D3034, Type PSM, SDR 35
- 15" pipes or larger — Reinforced Concrete Pipe, ASTM C76, Class III

Onsite Utility Connection Notes:

- Contractor shall field verify all utility connection elevations prior to any utility construction has begun.
- Contractor shall construct utility lines into site prior to any onsite utility construction. Gravelly lines are to be constructed starting at the lowest point and be installed prior to any waterline installation
- Construction of any onsite utilities prior to the offsite connection will be done at the contractors risk.

Storm Drain & Sanitary Sewer Note:

All Storm Drainage & Sanitary Sewer Pipe Lengths and Slopes are from Center of Structure to Center of Structure

CAUTION :


The locations and/or elevations of existing utilities as shown on these plans are based on records of the various utility companies and, where possible, measurements taken in the field. The information is not to be relied on as being exact or complete.



PVC Pipe Protection During Construction:
PVC Pipe must have 24" cover for heavy construction loading during construction. The Contractor is responsible to temporarily protect any pipes with less than 24" cover by berming over the pipes.

Utility Plan

Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah




7 Apr, 2025

SHEET NO.

C3.1


ANNA
2010 North Redwood Road, Salt Lake City, Utah 84116
(801) 521-8629 - ANNAengineering.net

Designed by: JW
Drafted by: JW
Client Name:
Amsource
24-043 UT



Scale: 1" = 20'







Horizontal Scale: 1" = 20'
Vertical Scale: 1" = 2'



Key Map
Not to Scale



Plan View



Profile View

PVC Pipe Protection During Construction:
PVC Pipe must have 24" cover for heavy construction loading during construction. The Contractor is responsible to temporarily protect any pipes with less than 24" cover by berming over the pipes.

Onsite Utility Connection Notes:

- Contractor shall field verify all utility connection elevations prior to any utility construction has begun.
- Contractor shall construct utility lines into site prior to any onsite utility construction. Gravity lines are to be constructed starting at the lowest point and be installed prior to any waterline installation.
- Construction of any onsite utilities prior to the offsite connection will be done at the contractors risk.

Storm Drain & Sanitary Sewer Note:

All Storm Drainage & Sanitary Sewer Pipe
Lengths and Slopes are from
Center of Structure to Center of Structure

CAUTION :
The locations and/or elevations of existing utilities as shown on these plans are based on records of the various utility companies and, where possible, measurements taken in the field. The information is not to be relied on as being exact or complete.




Waterline Plan & Profile
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah



7 Apr, 2025



SHEET NO.

C3.2




Key Map
Not to Scale

Horizontal Scale: 1" = 20'
Vertical Scale: 1" = 2'



Plan View



Profile View

PVC Pipe Protection During Construction:
PVC Pipe must have 24" cover for heavy construction loading during construction. The Contractor is responsible to temporarily protect any pipes with less than 24" cover by berming over the pipes.

Onsite Utility Connection Notes:

- Contractor shall field verify all utility connection elevations prior to any utility construction has begun.
- Contractor shall construct utility lines into site prior to any onsite utility construction. Gravity lines are to be constructed starting at the lowest point and be installed prior to any waterline installation.
- Construction of any onsite utilities prior to the offsite connection will be done at the contractors risk.

Storm Drain & Sanitary Sewer Note:


All Storm Drainage & Sanitary Sewer Pipe
Lengths and Slopes are from
Center of Structure to Center of Structure

CAUTION :

The locations and/or elevations of existing utilities as shown on these plans are based on records of the various utility companies and, where possible, measurements taken in the field. The information is not to be relied on as being exact or complete.




Waterline Plan & Profile
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah



7 Apr, 2025


SHEET NO.

C3.3




Horizontal Scale: 1" = 20'
Vertical Scale: 1" = 2'

Key Map
Not to Scale



Plan View



Profile View

PVC Pipe Protection During Construction:
PVC Pipe must have 24\"/>

Onsite Utility Connection Notes:

- Contractor shall field verify all utility connection elevations prior to any utility construction has begun.
- Contractor shall construct utility lines into site prior to any onsite utility construction. Gravity lines are to be constructed starting at the lowest point and be installed prior to any waterline installation
- Construction of any onsite utilities prior to the offsite connection will be done at the contractors risk.


Storm Drain & Sanitary Sewer Note:

All Storm Drainage & Sanitary Sewer Pipe
Lengths and Slopes are from
Center of Structure to Center of Structure

CAUTION :
The locations and/or elevations of existing utilities as shown on these plans are based on records of the various utility companies and, where possible, measurements taken in the field. The information is not to be relied on as being exact or complete.



Waterline Plan & Profile
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah




7 Apr, 2025


SHEET NO.

C3.4


Key Map
Not to Scale



Horizontal Scale: 1" = 20'
Vertical Scale: 1" = 5'



Plan View



Profile View

PVC Pipe Protection During Construction:
PVC Pipe must have 24" cover for heavy construction loading during construction. The Contractor is responsible to temporarily protect any pipes with less than 24" cover by berming over the pipes.

Onsite Utility Connection Notes:

- Contractor shall field verify all utility connection elevations prior to any utility construction has begun.
- Contractor shall construct utility lines into site prior to any onsite utility construction. Gravity lines are to be constructed starting at the lowest point and be installed prior to any waterline installation.
- Construction of any onsite utilities prior to the onsite connection will be done at the contractors risk.

Storm Drain & Sanitary Sewer Note:

All Storm Drainage & Sanitary Sewer Pipe Lengths and Slopes are from Center of Structure to Center of Structure

CAUTION :


The locations and/or elevations of existing utilities as shown on these plans are based on records of the various utility companies and, where possible, measurements taken in the field. The information is not to be relied on as being exact or complete.



Sewer Plan & Profile

Amsource Santaquin


Main Street & Highland Drive
Santaquin, Utah



7 Apr, 2025

SHEET NO.


C3.5



**Santaquin City -
Curb Inlet Box Assembly**

8


Not to Scale



**Santaquin City -
Typical Trench Section**

7


Not to Scale



Curb Transition

6

Not to Scale




Stop Sign

5

Not to Scale


1. See Geotechnical Report for Project for Future Details
2. See Concrete Joint Detail



Concrete Paving Section

4

Not to Scale




Typical Cleanout Detail

3

Not to Scale

1. See Geotechnical Report for Project




Standard Asphalt Section

2


Not to Scale

1. Contraction Joints
A. Spacing = 10' o.c., see joint detail
B. 1/8" wide by 2" deep from top of curb at 15'-0" intervals
2. Expansion Joints
A. Make expansion joints full depth, see joint detail
B. Place expansion joint at all cold joints
C. Expansion joints are required at ends of all radii 0.08.
D. Required 5'-0" on each side of drainage structures
E. Required at 90'-0" maximum intervals in straight curb and gutter
F. Provide #6 x 18" long smooth steel dowel bars with 1" dia. grease cap through expansion joints (3/4" thick bituminous filler material)
3. 2'-6" Long tie bar on 2'-6" centers shall be provided when curb is adjacent to P.C.C. pavement
4. Provide (2) #6 x 2'-6" long tie bars to connect existing and new curb and gutter
5. Remove forms as early as possible. Brush top and face of curbs to remove all imperfections. Typical of all form work.
6. All radii shall be true arcs
7. Medium to light broom finish on all exterior concrete



Standard

Note: All Curb and Gutter to be Standard Unless Otherwise Noted



Open Face

1. See Concrete Joint Detail

24" Curb And Gutter


1

Not to Scale



2010 North Redwood Road, Salt Lake City, Utah 84116
(801) 521-8629 - AWAEngineering.net

Details
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah



7 Apr, 2025

SHEET NO.

C4.1

Santaquin City -
Not Used

16

Not to Scale

Santaquin City -
Typical Trench Section

14

Not to Scale

Santaquin City -
Typical Sewer Manhole

12

Not to Scale


Santaquin City -
Driveway Approach with Park Strip

10


Not to Scale

- NOTES:
1. PROVIDE A TOOLED JOINT EVERY 10' IN CURB & GUTTER, & EVERY 5' IN SIDEWALK.
 2. PROVIDE AN EXPANSION JOINT EVERY 30' IN SIDEWALK.

TYPICAL HIGH BACK CURB AND GUTTER



MODIFIED CURB AND GUTTER



CROSS GUTTER

CURB & GUTTER
AND CROSS GUTTER DETAILS
SANTAQUIN CITY
275 WEST MAIN STREET

CG4

Santaquin City -
Curb & Gutter and Cross Gutter Details

15

Not to Scale

Santaquin City -
Typical Sewer Lateral

13

Not to Scale

Santaquin City -
Culinary Water Service Connection

11


Not to Scale

Santaquin City -
Highland Drive Cross Section

9

Not to Scale

Details
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah



7 Apr, 2025
SHEET NO.
C4.2



User Inputs


Chamber Model: MC-3500
Outlet Control Structure: No
Project Name: Amsource Santaquin
Engineer: Jordan Webb
Project Location: Utah
Measurement Type: Imperial
Required Storage Volume: 826 cubic ft.
Stone Porosity: 40%
Stone Foundation Depth: 9 in.
Stone Above Chambers: 12 in.
Design Constraint Dimensions: (20 ft. x 80 ft.)

Results

System Volume and Bed Size
Installed Storage Volume: 918.92 cubic ft.
Storage Volume Per Chamber: 109.90 cubic ft.
Number Of Chambers Required: 4
Number Of End Caps Required: 2
Chamber Rows: 1
Maximum Length: 34.42 ft.
Maximum Width: 8.42 ft.
Approx. Bed Size Required: 289.67 square ft.
Average Cover Over Chambers: N/A.

System Components


Amount Of Stone Required: 42 cubic yards
Volume Of Excavation (Not Including Fill): 60 cubic yards
Total Non-woven Geotextile Required: 141 square yards
Woven Geotextile Required (excluding Isolator Row): 0 square yards
Woven Geotextile Required (Isolator Row): 38 square yards
Total Woven Geotextile Required: 38 square yards
Impervious Liner Required: 0 square yards




ADS Stormtech MC-3500
System Specifications

18

Not to Scale




FLARED DRIVEWAY WITH ADJACENT SIDEWALK




SECTION A-A

DRIVEWAY FLARE AREA CHART	
FLARED DRIVEWAY	
DISTANCE FROM BACK OF CURB TO SIDEWALK	FLARE AREA
3 FT	19 ft ²
4 FT	24 ft ²
6 FT	36 ft ²
8 FT	48 ft ²
10 FT	60 ft ²
ADD (DL/DW) FOR TOTAL QUANTITY	
QUANTITY CALCULATED USING A 6 INCH CURB	



EXPANSION-CONTRACTION JOINT DETAIL



FLARED DRIVEWAY WITH PARKSTRIP

NOTES:

- SIDEWALK CROSS SLOPE DIMENSIONS SHOWN ARE NOT SUBJECT TO CONVENTIONAL INDUSTRY TOLERANCES. CONSTRUCT SIDEWALKS AND RAMPS SUCH THAT THE MAXIMUM OR MINIMUM VALUES ARE NOT EXCEEDED. WORK THAT EXCEEDS THOSE VALUES WILL NOT BE ACCEPTED.
- MAXIMUM DISTANCE BETWEEN CONTROL JOINTS 10 FT. LATERNALLY AND LONGITUDINALLY SPACED EQUALLY.
- PROVIDE EXPANSION-CONTRACTION JOINTS IN CONCRETE SIDEWALK AT 30 FT INTERVALS AND WHERE CONCRETE SIDEWALK ADJUTS THE DRIVEWAY.
- FLARED CONCRETE DRIVEWAY
A. RESIDENTIAL - 6 INCH THICK, COMMERCIAL - 7 INCH THICK.
USE THESE THICKNESSES FOR APRON, SIDEWALK WITHIN DRIVEWAY AREA, APPROACH AND FLARE.
B. DEPRESS THE LONGITUDINAL SLOPE OF THE SIDEWALK AT A MAXIMUM RATE OF 5 PERCENT TO MEET THE APRON. APPROACH ELEVATION IF THE GRADES SHOWN ON THE SLOPE DETAIL CANNOT BE MET, THE TOP BACK OF SIDEWALK IS TO BE A MINIMUM 6 INCHES ABOVE THE FLOWLINE OF CURB AND GUTTER AT ALL TIMES.
- USE UNTREATED BASE COURSE UNDER ALL SIDEWALKS AND DRIVEWAYS.
- REMOVE EXISTING SIDEWALK AND REPLACE BACK TO NEAREST EXPANSION-CONTRACTION JOINT.

REVISIONS	
NO.	DESCRIPTION
1	ISSUED FOR PERMIT
2	ISSUED FOR CONSTRUCTION
3	ISSUED FOR CONSTRUCTION
4	ISSUED FOR CONSTRUCTION
5	ISSUED FOR CONSTRUCTION
6	ISSUED FOR CONSTRUCTION
7	ISSUED FOR CONSTRUCTION
8	ISSUED FOR CONSTRUCTION
9	ISSUED FOR CONSTRUCTION
10	ISSUED FOR CONSTRUCTION

UTAH DEPARTMENT OF TRANSPORTATION
STANDARD DRAWINGS FOR ROAD AND BRIDGE CONSTRUCTION
SALT LAKE CITY, UTAH
8" STANDARD DRAWINGS EDITION
2025 Standard Drawing

CONCRETE DRIVEWAYS AND SIDEWALKS

STD. DRAW. NO.
GW 3A

UDOT - Concrete Driveways and Sidewalks

17

Not to Scale




Details
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah



7 Apr, 2025

SHEET NO.

C4.3



Scale: 1" = 30'

Legend

- Place Inlet Protection at all Inlet Locations to prevent boxes from silting.
- Silt Fence
- Limit of Disturbance
- Construction Entrance / Truck Wash (50'x24' Min.)
- Concrete Washout Area
- Portable Toilet
- Gravel Sock
- Existing Contour
- Existing Spot
- Proposed Contour


Erosion Control Notes

- Storm water will be discharged into an existing drainage system. Existing Lines shall be inspected prior to Certificate of Occupancy and cleaned if necessary.
- The Storm Water Prevention Plan shall conform to all State Division of Environmental Protection Regulations.
- All Construction equipment will enter thru Designated Construction Entrances.
- Coordinate Entrance locations with the local jurisdiction.
- Inlet Protection Devices and Barriers shall be Repaired or Replaced if they Show Signs of Undermining or Deterioration.
- Silt Fences shall be Repaired to their Original Conditions if Damaged. Sediment shall be Removed from Silt Fences when it Reaches one-half the Height of the Silt Fence.
- The Construction Entrances shall be Maintained in a Condition which will Prevent Tracking or Flow of Mud onto Public Right-of-Way. This may Require Periodic Top Dressing of the Construction Entrances as Conditions Demand.
- All Materials Spilled, Dropped, Washed or Tracked from Vehicles onto Roadways or into Storm Drains must be Removed Immediately.
- Due to the Grade Changes During the Development of the Project, the Contractor shall be Responsible for Adjusting the Erosion Control Measures (Silt Fences, Inlet Protection, Etc...) to Prevent Erosion.
- Contractor shall use Vehicle Tracking Control at all Locations where Vehicles will Enter or Exit the Site. Control Facilities will be Maintained while Construction is in Progress, Moved when Necessary and Removed when the Site is Paved.
- Inlet Protection Devices shall be Installed Immediately upon Individual Inlets becoming Functional.
- This Document is Fluid Allowing for Changes, Modifications, Updates and Alternatives. It is the Responsibility of the Contractor to Keep Record of all Alterations made to the Erosion Control Measures Implemented for the Project on this Plan and in the Storm Water Pollution Prevention Plan.
- Cover Exposed stockpiles of soils, construction and landscaping materials with heavy plastic sheeting.
- Re-vegetate areas where landscaping has died or not taken hold.
- Divert storm water runoff around disturbed soils with berms or dirt swales.
- Contractor to provide permanent stabilization to any areas disturbed by construction by hydroseding native vegetation (if not otherwise stabilized).
- Contractor is responsible for obtaining a fugitive dust control permit through the Division of Air Quality. All responsibilities relating to the production of the dust control plan shall be the responsibility of the Contractor.


Designed by: JW
Drafted by: JW
Client Name: Amsource
24-043 EC1



Erosion Control Plan - Pre-Construction
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah



7 Apr, 2025
SHEET NO.
C5.1



Place Inlet Protection at all Inlet
Locations to prevent boxes from silting.
Silt Fence
Limit of Disturbance
Construction Entrance /
Truck Wash (50'x24' Min.)
Concrete Washout Area
Portable Toilet
Gravel Sock
Existing Contour
Existing Spot
Proposed Contour

1. Storm water will be discharged into an existing drainage system. Existing Lines shall be inspected prior to Certificate of Occupancy and cleaned if necessary.
2. The Storm Water Prevention Plan shall conform to all State Division of Environmental Protection Regulations.
3. All Construction equipment will enter thru Designated Construction Entrances.
4. Coordinate Entrance locations with the local jurisdiction.
5. Inlet Protection Devices and Barriers shall be Repaired or Replaced if they Show Signs of Undermining or Deterioration.
6. Silt Fences shall be Repaired to their Original Conditions if Damaged, Sediment shall be Removed for all Fences when it Reaches one-half the Height of the Silt Fence.
7. The Construction Entrances shall be Maintained in a Condition which will Prevent Tracking or Flow of Mud onto Public Right-of-Way. This may Require Periodic Top Dressing of the Construction Entrances as Conditions Demand.
8. All Materials Spilled, Dropped, Washed or Tracked from Vehicles onto Roadways or into Storm Drains must be Removed Immediately.
9. Due to the Grade Changes During the Development of a Condition, the Contractor shall be Responsible for Adjusting the Erosion Control Measures (Silt Fences, Inlet Protection, Etc...) to Prevent Erosion.
10. Contractor shall use Vehicle Tracking Control at all Locations where Vehicles will Enter or Exit the Site. Control Facilities will be Maintained while Construction is in Progress, Moved when Necessary and Removed when the Site is Paved.
11. Inlet Protection Devices shall be Installed Immediately upon individual Inlets becoming Functional.
12. This Document is Fluid Allowing for Changes, Modifications, Updates and Alternatives. It is the Responsibility of the Contractor to keep Record of all Alterations made to the Erosion Control Measures Implemented for the Project on this Plan and in the Storm Water Pollution Prevention Plan.
13. Cover Exposed stockpiles of soils, construction and landscaping materials with heavy plastic sheeting.
14. Re-vegetate areas where landscaping has died or not taken hold.
15. Divert storm water runoff around disturbed soils with berms or dirt swales.
16. Contractor to provide permanent stabilization to any areas disturbed by construction by hydroseeding native vegetation (if not otherwise stabilized).
17. Contractor is responsible for obtaining a fugitive dust control permit through the Division of Air Quality. All responsibilities relating to the production of the dust control plan shall be the responsibility of the Contractor.

Main Street & Highalnd Drive
Santaquin, Utah



6


Not Used

Not to Scale

3

Silt Fence Section


Not to Scale



5

Gravel Sock Sediment Barrier


Not to Scale



2

Dandy Sack Inlet Protection


Not to Scale



4

Concrete Washout

Not to Scale




1

Stabilized Construction Entrance

Not to Scale



Erosion Control Details
Amsource Santaquin
Main Street & Highland Drive
Santaquin, Utah



7 Apr, 2025
SHEET NO.
C5.3

