

vaughn concrete products, inc.

12650 Tucson Street Henderson, Colorado 80640-9443 (303) 659-3747 Fax (303) 659-1333
2671 S. Greeley Hwy Cheyenne, Wyoming 82007-3681 (307) 634-0695 Fax (307) 634-0694
10021 Amarillo Blvd E. Amarillo, Texas 79108-7542 (806) 374-3747 Fax (806) 335-3717
Toll Free Phone (877) 827-8255 Toll Free Fax (877) 827-7363
www.vaughnconcreteproducts.com

Town of Saratoga, WY
Attn: Emery Penner
307-447-2882
emerypenner@saratogawyo.org

Project: **September 18, 2023-REVISED**
Myrtle Lift Station
Saratoga, WY

MATERIALS QUOTE NO. PQ 10356R

We are pleased to quote the following on the above-mentioned project. Our quote is in accordance with our interpretation of the plans and specifications, or the information we were provided with, quantities are believed correct, but they are not guaranteed. If actual quantities differ, unit prices must be used. Contractor to determine if materials quoted are suitable. VCP to supply materials to approved submittals.

ALTERNATE (If Suitable)

Our Standard Precast Concrete 60" ID Manhole For Lift Station (1 Required)

Manufactured In Sections With 6" Thick Walls Per ASTM C-478 To Satisfy AASHTO HS-20-44 Loadings

Price Includes: Precast Concrete Base 84" Diameter x 8" Thick, 8VF OF 60" ID Precast Concrete Manhole Barrel, w/ Up To (4) Piping Blockouts w/Press-In Gaskets, 72" Diameter Traffic Lid (Flat Top) w/ 30" x 48" Access Opening, w/ **Alternate** APS300 30" x 48" Aluminum Hatch Cast In (Rated for Pedestrian Loading), Joints Primed For Sealant, 2 Rows Joint Sealant/Joint Of Manhole

\$5,600.00 Each**

Price Provides Manhole with Top Of Lid To Top Of Base Elevation Of 9'-0"

- Contractor To Supply Enclosure, Pumps & Any Other Items Not Specifically Listed Above
- No Coating Are Included In Any of This Pricing
- Additional 60" ID Manhole @ **\$180.00/Ft** (As Required)
Price Includes: 2 Rows of Joint Sealant/Joint Of Manhole

Pricing Is FOB Jobsite, Contractor Unloads, 1 Hour Unloading Time/Truck With Sufficient Truck Access, Full Truckloads Required. Additional Truck Time @ **\$150.00/Hour/Truck** (If Required).

**** ADD \$ 200.00** For VCP To Deliver and Offload Into Ready Excavation or On Top OF Ground w/ Sufficient Boom Truck/Trailer Access, 1 Hour Unloading Time/Truck, VCP Furnishes Boom Truck/Trailer Operator Only, Contractor to Furnish Qualified Personnel to Assist in Unloading, Maximum of 12' From the Back of Our Boom Truck/Trailer on Stable Ground to Center of Excavation, Full Truckloads Required, Additional Truck/Trailer Time @ **\$180.00/Hour/Truck** (If Required)

Any Structure That Must Be Water Tight, Must Be Water Or Vacuum Tested Prior to Backfilling

Pricing Is Based On Current Steel, Cement & Fuel Prices & Is Subject To Change Should Any Of These Prices Increase More Than 10% & A Fuel Surcharge May Be Required At Time Of Delivery

**Production Lead-Time May Vary Dependent On Availability of Reinforcing Steel & Cement From Our Suppliers
Items left at VCP over 30 Days are Subject to Storage Fees on a per Structure Basis**

TERMS

NET 30 DAYS (OAC)

REQUIRES PAYMENT WITHIN 30 DAYS FOLLOWING THE INVOICE/STATEMENT DATE OR AN ADDITIONAL 10% WILL APPLY - NO APPLICABLE TAXES INCLUDED - SUBJECT TO YOUR MATERIAL REQUIREMENTS MEETING OUR PRODUCTION SCHEDULE - PRICE SUBJECT TO CHANGE IF FUEL COSTS CHANGE SIGNIFICANTLY - THIS QUOTE MAY BE WITHDRAWN BY US IF NOT ACCEPTED WITHIN 30 DAYS THESE PRICES ARE VALID ONLY UNDER THE TERMS AND CONDITIONS OF THIS QUOTE.

VAUGHN CONCRETE PRODUCTS, Inc.

ACCEPTED BY: _____

DATE _____