



Wynn O. Jones & Associates
 754 Alderson Street
 Schofield, WI 54476-0318
 (715) 359-5196 PH (715) 355-4197 FX

October 28, 2024

Estimate #E40159SG

Sheboygan WWTP
 3333 Lakeshore Drive
 Sheboygan, WI 53081
 Attn: Jordan Skiff – Wastewater Superintendent

Ref: *Quote for Laboratory Casework, Chemical Fume Hood & Related Counters & Accessories*

Dear Jordan: PO REQUESTED 630361-631200 ~~PH~~ 1/21/25
2025 FUNDS

Please find the attached quotation for the Mott Manufacturing laboratory casework and fume hood products that we have been working on together. The pricing summary, in accordance with **UW-Madison Contract #23-5846**, is as follows:

➤ Base Price:

We propose to deliver and install the steel lab casework, chemical fume hood assembly, counters, sinks and related fixtures and accessories.

Delivered Product	\$ 71,249.68
Non-Mechanical Installation	<u>\$ 10,560.00</u>
GRAND TOTAL	\$81,809.68

Above prices do not include sales tax charges. Shipping and non-mechanical installation is included. Delivery of the above items can be made after receipt of your purchase order, approved shop drawings, verified field dimensions, finish selections, and a copy of this quotation. I have priced your project to deliver in the March 2025 timeframe. This quote is valid for 15 days. Payment terms are net 30 days.

Clarifications:

1. Mott's inset steel casework series has been quoted.
2. Worksurfaces to be supplied will be 1" thick, black, phenolic resin (Fundermax) with butt curbs at the locations shown.
3. Epoxy resin sinks and plumbing service fixtures are included. Traps are not included and should be provided by the plumbing contractor.
4. The freestanding safety shower/eye-wash station and the associated in-line tempering valve should be provided by the plumbing contractor if required.
5. Epoxy resin drying racks are included with stainless steel drip troughs.
6. One (1) 96" wide *Pro Restricted Bypass Series* bench top fume hood has been priced. Dished epoxy resin counter, ceiling enclosure and airflow alarm are included. Factory pre-piped and pre-wired services are included.
7. Lab chairs/stools are not included.
8. Keyboard trays and mechanisms are not included.
9. Magnetic LED task lighting is included.

10. Blocking/backing required in building walls is not included and should be provided by the general contractor.
11. Base molding is not included since this is usually provided by the flooring contractor.
12. Demolition and disposal of existing furniture, casework & equipment is not included.
13. Final HVAC, electrical and plumbing connections are not included and should be provided by the appropriate contractor.
14. Electrical raceway, wiring, and electrical/data devices are not included. Island counter pedestal boxes are included.
15. Fume hood exhaust blower, ductwork, duct collar transitions and building wall exhaust grilles are not included and should be provided by the HVAC contractor.
16. Non-mechanical installation is included and will be performed by a factory certified installation crew in one phase.
17. We assume a working elevator will be made available to us for use during the installation phase of this project. We have not included the cost of supplying temporary hoisting or lifting.
18. Mott's standard finish colors and cabinet hardware options are included. Wire pulls and 5-knuckle door hinges to be stainless steel. All drawer slides to be full extension and have the soft close feature. Casework components and fume hood base & accent color to be: Steel Gray #693185; as confirmed at our 10/24/24 meeting.



Jordan, I would like to thank you for your interest in Mott Manufacturing's laboratory casework and fume hoods. [www.mott.ca] [www.wynnjones.com] Your business is very important to Wynn O. Jones & Associates. If you should have any questions or need further clarification, please do not hesitate to call me at 715-877-2544.

Sincerely,

Steve Gillett
Wynn O. Jones & Associates

