

PARCEL NO.: \_\_\_\_\_  
MAP NO.: \_\_\_\_\_  
ZONING CLASSIFICATION: \_\_\_\_\_

Office Use Only

DATE SUBMITTED: \_\_\_\_\_  
REVIEW DATE: \_\_\_\_\_

## CITY OF SHEBOYGAN ARCHITECTURAL REVIEW APPLICATION

Revised November 2019

**FEE \$100.00**

Completed application must be filed with the Department of City Development, 828 Center Avenue, Suite 208. To be placed on the agenda of the Architectural Review Board, application **must be filed two weeks prior** to date of meeting. Applications that are not complete or that are not legible will not be accepted.

### 1. APPLICANT INFORMATION

APPLICANT: Sheboygan EFree Church

ADDRESS: 1710 N 15<sup>th</sup> Street, Sheboygan, WI 53081

CONTACTS/E-MAIL: Jon MacDonald [jon.m@e-free-family.com](mailto:jon.m@e-free-family.com)  
Heather Tempas [heather.t@e-free-family.com](mailto:heather.t@e-free-family.com)

PHONE: 920-452-6520

FAX NO. None

### 2. DESCRIPTION OF THE SUBJECT SITE/PROPOSED PROJECT

NAME OF PROPOSED/EXISTING BUSINESS: Sheboygan E Free Church

ADDRESS OF PROPERTY AFFECTED: 1710 N 15<sup>th</sup> Street, Sheboygan, WI 53081

NEW BUILDING: \_\_\_\_\_ ADDITION: X REMODELING: X

DESCRIPTION OF PROPOSED PROJECT:

See attached Narrative for Conditional Use Permit & Architectural Review Applications

DESCRIPTION OF **EXISTING** EXTERIOR DESIGN AND MATERIALS:

See attached Narrative for Conditional Use Permit & Architectural Review Applications

DESCRIPTION OF THE **PROPOSED** EXTERIOR DESIGN AND MATERIALS:

See attached Narrative for Conditional Use Permit & Architectural Review Applications

### NAMES AND ADDRESSES

OWNER OF SITE: Sheboygan EFree Church

ADDRESS: 1710 N 15<sup>th</sup> Street, Sheboygan, WI 53081

EMAIL: [jon.m@e-free-family.com](mailto:jon.m@e-free-family.com) [heather.t@e-free-family.com](mailto:heather.t@e-free-family.com)

PHONE: 920-452-6520 FAX NO.: None

**ARCHITECT:** Station 19 Architects, Inc.

ADDRESS: 2001 University Ave., Minneapolis, MN 55414

EMAIL ADDRESS: akuntz@station19.com

PHONE: (612) 623-1800 FAX NO.: None

**CONTRACTOR:** Catalyst Construction

ADDRESS: 833 E Michigan Street, Milwaukee, WI 53202

EMAIL: ewilliams@catalystbuilds.com

PHONE: 414.587.5062 FAX NO.: None

### 3. APPLICATION SUBMITTAL REQUIREMENTS


- A. A scale drawing of all exterior elevations showing the design and appearance of the proposed building or structure.
- B. Three 11 X 17 colored renderings of the proposed building elevations and material samples.
- C. A .pdf file of all drawings either by email or CD**
- D. A scale drawing of the site plan showing the relationship of the building to the site and adjacent properties.
- E. A written description of the proposed general design, arrangement, texture, material and color of the building or structure. Describe the relationship of such factors to similar features of buildings located within the same block or located along the frontage or any block across the street from the proposed building or structure for which architectural approval is sought.

### 4. CERTIFICATE

I hereby certify that all the above statements and attachments submitted hereto are true and correct to the best of my knowledge and belief.

  
APPLICANT'S SIGNATURE

4-14-22  
DATE

  
PRINT ABOVE NAME

OFFICE USE ONLY

### ACTION BY ARCHITECTURAL REVIEW BOARD

DATE OF MEETING: \_\_\_\_\_

APPROVED: \_\_\_\_\_

CONDITIONALLY APPROVED: \_\_\_\_\_

## **Narrative for Conditional Use Permit and Architectural Review Applications – 4/19/22**

### **Project Name and Address**

Sheboygan E Free Church  
1710 North 15<sup>th</sup> Street  
Sheboygan, WI 53081

### **Parcel Information and Legal Description**

- Lots 1-7 in Block 2 of Cole's Subdivision No. 2 including vacated alley being part of Lots "D" and "A" being the E1/2 of the SW1/4 of the SE1/4 Sec. 15, T15N, R23E and
- Lots 1-10 in Block 3 of O.C. Neumeister's Re-Subdivision of Blocks 5.9.8-14, Block 2 Coles Subdivision No. 2, all in the City of Sheboygan together with
- The East West alley lying between said Block 2, Cole's Subdivision No. 2 and said Block 3 of O.C. Neumeister's Re-Subdivision
- All located in the SW1/4 of the SE1/4 Sec. 15, T15N, R23E City of Sheboygan, Sheboygan County, Wisconsin; containing 92,203 S.F. (2.117 Acres) of land.

### **Project Description**

The proposed project is the 2<sup>nd</sup> Phase of a 3-Phase masterplan.

- Phase 1 was a new parking lot on the block west of the building site off 16<sup>th</sup> Street - completed in 2019.
- The proposed Phase 2 project proposed in this submittal will add a **1,400 square foot** entrance addition and **12,740 square foot** of site work including improved drop-off curb and walk, landscaping, and new relocated drive entrance off Saemann Avenue.
- Design intent for the proposed addition and remodel is to provide:
  - Increased visibility and updated identity and presence for the Church entrance from Calumet Drive
  - Central, welcoming, and expanded hospitality Lobby
  - Secure and welcoming Children's classrooms
  - Refreshed Worship finishes and seating
- The final Phase 3 phase will culminate in a new Worship Center replacing a portion of the current Worship structure, adding approximately **4,000 square feet** of addition along Cambridge Avenue with expansion and redesign of the east parking lot. The church anticipates 5-10 years before Phase 3 will be completed.

### **Architecture**

#### **Existing Building**

- The existing building is a combination of materials built in 3 phases.
- The original building and first addition are located at the south end of the site and house the Worship Center, Meeting and Education rooms.
  - It is built of concrete block walls with exterior brick cladding. The east elevation has a combination of brick, wood timbering and aggregate coatings.
  - The roof is primarily flat/slightly sloped membrane roof with a perimeter of metal capped parapet on the south and west sides and metal mansard roof on the east side with fragments of mansard roof on the south and west sides.

- The 1988 addition was built to the north of the original building. It houses a Multi-purpose/Gym, Administration Offices, Storage and Nursery rooms.
  - The 1988 addition is built of metal stud and block walls with exterior split-face block cladding and brick accent bands.
  - The roof is flat/slightly sloped membrane roof with a perimeter of metal capped parapet with a sloped asphalt shingle roof over the Multi-Purpose/Gym.

### **East Façade**

- The primary exterior work for the Phase 2 project will be on the east façade.
- The exterior east façade for the new entrance addition will be approximately 20 feet in height, corresponding to the roof edge height of the existing Multi-Purpose/Gym.
- The exterior materials of the addition will be a combination of glass, new metal entrance canopy and a 2-color variation of high-quality vertical cement board panels (Nichiha) relating to the Church branding colors, and providing a contemporary central entrance point for the facility which reflects the Church identity to the community.
- The existing east façade south of the addition will be painted to visually blend with the existing block and brick facade north of the new entrance. Both north and south facades are intended to act a backdrop for the colorful central entrance.
- Note that the south portion of the east façade will be removed in 5-10 years at the time of the Phase 3 addition construction.

### **South Façade**

- The south façade will remain as existing except for the east end at the mansard roof and wall area below it.
- New paint to blend with the north end of the east façade will continue around the corner onto the south façade covering the mansard roof and wall surfaces below it.

### **West Façade**

- The exterior entrance at on the west side of the building will be modified to remove a small mansard roof fragment remaining from the original addition.
- New high-quality vertical cement board panels (Nichiha) will be installed over the patched area to match the materials at the new east entrance.
- The new panels will provide a visual emphasis for the west entrance improving wayfinding for guests arriving from the west parking lot.
- New windows will be added along the south end of the west façade for the children's classrooms presenting a more hospitable appearance to the community.

### **Signage**

- Signage for the east façade will consist of metal lettering or internally lit lettering placed at the edge of the new canopy. This will replace of the current lettering located on the wall at the north end of the east façade.
- Signage for the west façade will be metal lettering or internally lit lettering mounted to the wall panels.
- Exact signage will be submitted separately at a later date.

### **Mechanical**

- Mechanical units will remain as existing with replacements in place as determined for new uses.

### **Interior Work**

- The proposed Phase 2 project will include approximately **24,594 square feet** of interior remodel for an expanded hospitality Lobby, accessible elevator access to the Lower-Level classrooms and meeting rooms, remodel of Main Level small children's education wing and refresh of the current Worship Center finishes and seating for approximately .

## **Description of Current Facility Use**

Primary use of Facility is currently and will continue to be: As a church, to teach people of all ages about God. The two major days are:

- Sundays - AM worship services
- Wednesdays –AM Bible studies, evening Awana (children) and Bible studies, Evening Youth group

Secondary use of Facility: as a social, meeting and parking site for individuals within the church and groups/organizations within the community

- Weddings and funerals
- Parties (birthday, anniversary, wedding and baby showers)
- Special church events (weekends)
- Community meetings and conferences
- City polling site (three wards)
- Community blood drive – 2x/year
- Weekday parking for employees of three companies (about 50 stalls total between east and west lots), various neighborhood residents (as needed), and Jefferson School (as needed)
- Available as Jefferson School's evacuation site

## **Days/Hours of Operation, Participants (typical per week, unless indicated)**

Sundays - 7am-12:30pm

- Worship services/choir and praise team rehearsals
  - 2 Sunday morning services with **510 total worshippers plus up to 5 Tech**
    - 8 am – 235 adults
    - **9:30am – 275 adults (LARGEST HOUR)**
  - Meetings (11 rooms) - 70 kids plus teachers – 9:30am
  - Children's programming – 110 (kids and teachers) – 9:30am
  - Students (grades 7-12) – 20 – 9:30am

Monday-Friday – 9am-5pm

- office hours – 12 staff onsite
- Tues – GriefShare -12; MOPS (biweekly) – 27 adults, kids (5 rooms)
- Wed - various AM Bible studies – 63 (4 rooms)
- Thur (biweekly) – Homeschool - 130 kids and adults (9 rooms)

Mondays: 6-9pm – 1-2 meetings, 6-12 people each

Tuesdays: 6-8:30pm – 3 meetings, 6-15 people each

Wednesdays: 6-9pm – Awana – 137 kids + 35 adults ((27 breakout rooms plus gym and sanctuary), quiz practice - 12, choir practice – 21  
5-9pm Youth group – 80 (students and adults), 2 large rooms, gym, kitchen, 16 small breakout rooms)

Thursdays: 6-8:30pm – GriefShare -10, 2 praise team rehearsals – 16 (2 rooms)

There are various activities that occur periodically on Fridays (set-up/decorate for special Sat events) and Saturdays (parties, showers, Sunday worship set-up, etc)

There are various events that occur annually:

- 1 weekend in March – Mission Conference
- 1 Friday in April – Show Hope conference
- 1 weekend in summer – Serve Sheboygan (help neighborhood)
- 1 week in September – Jefferson School evac drills

## **Zoning Classification**

Zoned: Neighborhood Residential-6 (NR-6) – Church Use as a Conditional Use

	<u>Required Setbacks</u>	<u>Variance Requested*</u>
Front Yard (N 15 <sup>th</sup> Street)	25 feet	none
Rear Yard (N 16 <sup>th</sup> Street)	25 feet	0 setback - existing building
Side Yard (Saemann Avenue)	25 feet	0 setback - existing building
Side Yard (Cambridge Avenue)	25 feet	0 setback - existing building

\*See Variance Description.

## **Site Considerations: Land Use / Lot Coverage**

- The current building is a 1-story building with a partial basement.
- The building and parking lot drain to the City storm sewer system.
- No change to the current surface drainage system is proposed due no change to drainage patterns or increase to impervious surface area.

<u>Lot Coverage</u>	<u>Existing</u>	<u>Proposed</u>	<u>Impact to Site</u>
Parcel area	92,203 sq. ft.		9,550 sq. ft. (10.4% of site)
Building coverage	35,385 sq. ft.	36,734 sq. ft.	1,400 sq. ft. / 4% increase
Impervious Surface coverage	86,936 sq. ft.	85,628 sq. ft.	
Pervious Surface coverage	5,267 sq. ft.	6,575 sq. ft.	1,308/ 1.4% increase

<u>Parking / Seating</u>	<u>Existing</u>	<u>Proposed</u>
Parking Stalls	208 stalls (126 stalls (east lot) +82 stall (west lot))	204 stalls (122 stalls (east lot) +82 stall (west lot))

<u>Seating</u>	<u>Allowable</u>	<u>Proposed</u>
Allowable seating (*based on largest service)	1,020 seats* 204 available stalls x 5 seats per stall	674 Worship Occupants

## **Landscape**

- Landscape plantings will be provided at the new east entrance addition and drop-off area. Grass and grass and mulch will be provided at the disturbed areas along new walks and stoops.
- 18 Landscape points are proposed, exceeding the 10 required Landscape points. See Landscape Plans for proposed shrubs, grasses, perennials and mulch areas.

## **Traffic**

- The site is currently accessed with entrance drives off N 15<sup>th</sup> Street (2 total), Saemann Avenue (1 total) and Cambridge Avenue (2 total).
- The proposed Phase 2 addition will maintain all 4 entrance points on N 15<sup>th</sup> Street and Cambridge Avenue.
- The entrance driveway on Saemann is proposed to be relocated approximately 14' east of the current drive to allow for increased drop-off curb, walk and landscaping next to the building. We anticipate no impact to site access.

## **Lighting**

- Existing parking lot lights will remain with no change to impact on neighboring sites.
- New lighting below the new canopy will be down lights well within the interior of the site with little to no impact to neighboring sites.
- The New Cross will be lit from the front from lights located on the new canopy shining up at the cross.
- The metal lettering on the east canopy and the West wall will be either metal lettering or internally lit lettering – to be determined per separate signage submittal at a later date.
- Due to the center-site location of the front lit cross and signage lettering there will be minimal impact to neighboring sites from the east side. The west signage lighting will also have minimal impact, primarily to the west parking lot owned by the Church.

### **Trash Enclosure**

- The trash for the current building is located on the southeast lot line corner and enclosed on the east and south sides with a wood fence.
- The trash location and enclosure will be modified with the Phase 3 Addition and Remodel to the building and parking lot.
- No change is proposed at this time.

### **Proposed Conditional Use**

The current Church began as a remodel and conversion of an existing grocery store in the 1960's with a small classroom addition built along 16<sup>th</sup> Street in approximately 1970. The building was later expanded in 1988 to its' current footprint with the addition of a gymnasium, classrooms, and office suite.

The Church (as described in the Description of Facility Use above) provides support for the community to meet, worship, socialize, vote, give blood, park etc. Church use meets the intent of the "small community uses" recommended for the Neighborhood Residential (NR-6) zoning district in the City of Sheboygan Comprehensive Plan.

### **Variance Description**

The existing building setbacks are non-compliant with the current zoning code.


The proposed Phase 2 addition is proposed to be within the required setbacks.

3 total variances are requested as follows in bold text:


	<u>Required Setbacks</u>	<u>Variance Requested</u>
Front Yard (N 15 <sup>th</sup> Street)	25 feet	none
<b>Rear Yard (N 16<sup>th</sup> Street)</b>	<b>25 feet</b>	<b>0 setback - existing building</b>
<b>Side Yard (Saemann Avenue)</b>	<b>25 feet</b>	<b>0 setback - existing building</b>
<b>Side Yard (Cambridge Avenue)</b>	<b>25 feet</b>	<b>0 setback - existing building</b>

The requested variance is to allow zero setback along N 16<sup>th</sup> Street, Saemann Avenue and Cambridge Avenue to accommodate the existing construction presumed to have been built prior to the current regulations.

## EXISTING SITE



## PROPOSED SITE




## PARKING TABLE

PARKING TABLE		
	EXISTING PARKING	PROPOSED PARKING
MAIN CHURCH SITE	126 (13 HC)	122 (7 HC)
WEST PARKING LOT	82	82
TOTAL	208 (13 HC)	204 (7 HC)
TOTAL REQUIRED*	135	135
HC REQUIRED**	7	7

\* 1 PARKING STALL PER 5 SEATS (674SEATS PROVIDED)  
\*\* 7 HC STALLS REQUIRED FOR 200-300 STALL PARKING FACILITIES


## LANDSCAPE RATIO (LSR) TABLE (MAIN CHURCH SITE)

	EXISTING	PROPOSED
IMPERVIOUS AREA	86,936 FT <sup>2</sup>	85,628 FT <sup>2</sup>
LANDSCAPED AREA	5,267 FT <sup>2</sup>	6,575 FT <sup>2</sup>
TOTAL LOT AREA	92,203 FT <sup>2</sup>	92,203 FT <sup>2</sup>
LSR	0.057	0.071



### EXISTING VS. PROPOSED FIGURE





PHASE II IMPROVEMENTS  
SHEBOYGAN eFREE CHURCH  
1710 N<sup>TH</sup> 17<sup>TH</sup> ST.  
SHEBOYGAN, WI 53081

SCALE	
HOR.	1"=20'
VER.	N/A
DATE	4/11/2022
JOB	20410-E
BY	BRW
CK	RGM
SHEET	

**MILLER**  
**ENGINEERS**  
**SCIENTISTS**

5308 S. 12th Street  
Sheboygan, WI 53081-8099  
Phone: (920) 458-6164  
Fax: (920) 458-0369  
[www.startwithmiller.com](http://www.startwithmiller.com)

Working in Harmony with the Environment

[illegible]

PHASE II IMPROVE/  
SHEBOYGAN eFREE CHIL  
1710 N<sup>TH</sup> 17<sup>TH</sup> ST.  
SHEBOYGAN, WI 53081

SCALE	
HOR.	1"=20'
VER.	N/A
DATE	
4/11/2022	

BY	BRW
----	-----

RGM

SHEET

C2

**MILLER**  
**ENGINEERS**  
**SCIENTISTS**

5308 S. 12th Street  
Sheboygan, WI 53081-8099  
Phone: (920) 458-6164  
Fax: (920) 458-0369  
[www.startwithmiller.com](http://www.startwithmiller.com)

Working in Harmony with the Environment

[illegible]

PHASE II IMPROVEMENTS  
SHEBOYGAN eFREE CHURCH  
1710 N<sup>TH</sup> 17<sup>TH</sup> ST.  
SHEBOYGAN, WI 53081

SCALE	
HOR.	1"=20'
VER.	N/A
DATE	
4/11/2022	

BY	BRW
----	-----

RGM

SHEET

C2



A. ALTERATIONS TO BE DONE IN A MANNER THAT MAINTAINS THE LEVEL OF FIRE PROTECTION PROTECTION PROVIDED.

B. AREAS SHOWN GREY ARE EXISTING TO REMAIN.

C. EXTEND AND MODIFY EXISTING FIRE SPRINKLER AND FIRE ALARM SYSTEMS FOR NEW WORK.

1 STORY ABOVE GRADE WITH BASEMENT (A-3 OCC.)  
EXISTING SPRINKLER IN PARTIAL BASEMENT AT 1988 ADDITION - EXTEND NEW SPRINKLER THROUGHOUT REMAINING  
FIRE ALARM SYSTEM - EXTEND AND UPGRADED FOR COMPLIANCE

**MAIN LEVEL (1 STORY): "A-3" OCCUPANCY FOR WORSHIP WITH RELIGIOUS EDUCATION  
"E" CLASSROOMS (304.1.1) AND "B" OFFICES AS NON-SEPARATED ACCESSORY USE TO A  
OCCUPANCY (508.2.4)**

**LOWER LEVEL (BASEMENT): "A-3" OCCUPANCY FOR WORSHIP WITH RELIGIOUS EDUCATION**  
**"E" CLASSROOMS (304.1.1) AS NON-SEPARATED ACCESSORY USE TO A3 OCCUPANCY**

TYPE 3B  
POSSIBLY NEED TO PROVIDE 2 HOUR PROTECTION OF EXISTING COLUMNS IN EXTERIOR WALL ALONG GRID 2

FIRE RESISTIVE REQUIREMENTS	TYPE 3B	
	REQUIRED	PROVIDED
STRUCTURAL FRAME (COLUMNS, BEAMS, JOISTS)	0 HR.	0 HR.
BEARING WALLS - EXTERIOR (CURRENTLY 1 HR AND 2 HR (GYMNASIUM) AT 1988 ADDITION)	0 HR.	1 HR AND 2 HR.
BEARING WALLS - INTERIOR	0 HR.	0 HR.
NON-BEARING WALLS AND PARTITIONS - EXTERIOR	0 HR.	0 HR.
NON-BEARING WALLS AND PARTITIONS - INTERIOR	0 HR.	0 HR.
FLOOR CONSTRUCTION (INCLUDING SUPPORTING BEAMS AND JOISTS)	0 HR.	0 HR.
ROOF CONSTRUCTION (INCLUDING SUPPORTING BEAMS AND JOISTS)	0 HR.	0 HR.

FIRE SEPARATION DISTANCE	HOURS
=> 30'-0"	0 HR.

## 75 FT (OR 60 FT) APPROX. 31 FT

At = TABULAR AREA PER STORY IN ACCORDANCE WITH T.506.2 FOR SPRINKLERED BLDG  
NS = TABULAR AREA PER STORY FOR NON-SPRINKLERED BLDG IN T.506.2 =

IF = AREA INCREASE FACTOR DUE TO FRONTAGE PER SECTION 506.3 =

F = BUILDING PERIMETER WHICH FRONTS ON A PUBLIC WAY OR OPEN SPACE (20' MIN)  
P = PERIMETER OF ENTIRE BUILDING

W = WIDTH OF A PUBLIC WAY OR OPEN SPACE (30' MAX)

**ALLOWABLE AREA PER FLOOR (Aa)**  $Aa = At + [NS * If] = 38,000 + [9,500 * 0.15] = 54,250$  sq ft

PROPOSED AREA

	EXISTING	35,425 SQ.FT.
	PROPOSED NEW	1,400 SQ.FT.
	<b>TOTAL PROPOSED NEW + EXISTING</b>	<b>36,825 SQ.FT. &lt; 45,625 SQ. FT ALLOWED</b>
	<u>ALLOWABLE FUTURE ADDITION</u>	8,300 SQ.FT. (VS. 3,882 ADDITIONAL SQ.FT. PROPOSED IN MASTER PLAN)
	<b>REMODEL AREA</b>	
	ML	23,889 SQ.FT. (67.44% OF ML)
	LL	705 SQ.FT. (3.05% OF LL)

## CHAPTER 29 PLUMBING SYSTEMS

**MINIMUM NUMBER OF PLUMBING SYSTEMS**  
TOTAL OCCUPANCY: 595 occ. (MPR/GYM) + 674 occ. (WORSHIP) = 1,269 occupants  
634 MEN AND 635 WOMEN

	<u>REQUIRED</u>	<u>PROPOSED</u>
MEN'S WATER CLOSETS (634/150)	4	10 PROVIDED: 5 (ML) + 5 (LL)
MEN'S LAVATORIES (634/200)	3	7 PROVIDED: 3 (ML) + 4 (LL)
WOMEN'S WATER CLOSETS (635/75)	8	10 PROVIDED: 5 (ML) + 5 (LL)
WOMEN'S LAVATORIES (635/200)	3	7 PROVIDED: 3 (ML) + 4 (LL)
UNISEX RESTROOMS		1 public + 6 dedicated
DRINKING FOUNTAINS (1:1000)	2	5 PROVIDED: 3 (ML), 2 (LL)

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Architect under the laws of the state of WISCONSIN.

**SIGNATURE:** NICOLE THOMPSON

**REGISTRATION #:** \*\*\*\*\*

DATE: 04/15/2022

1710 N 15TH STREET, SHEBOYGAN WISCONSIN  
53081

PROJECT NO: 4514

DRAWN BY: AK. KM

COPYRIGHT: 2022

Errors may occur in the transmission of electronic files. Station Nineteen Architects, Inc. is not responsible for any claims, damages or expenses arising out of the unauthorized use of the information contained in electronic files. It is the responsibility of the user to verify all layouts, dimensions and other related information. This document may not be used or copied without prior consent.

[illegible]

CITY SUBMISSION

## MAIN LEVEL CODE PLAN



I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Architect under the laws of the state of WISCONSIN.

1710 N 15TH STREET, SHEBOYGAN WISCONSIN  
53081


Errors may occur in the transmission of electronic files. Station Nineteen Architects, Inc. is not responsible for any claims, damages or expenses arising out of the unauthorized use of the information contained in electronic files. It is the responsibility of the user to verify all layouts, dimensions and other related information. This document may not be used or copied without prior consent.



A. GRADE SITE TO PROVIDE POSITIVE DRAINAGE AWAY FROM BUILDING.  
B. PROVIDE LIGHTING FOR CROSS FROM CANOPY ROOF.

1. NICHHA FIBER CEMENT PANELS OVER NEW WALL.
2. NICHHA FIBER CEMENT PANELS OVER EXISTING WALL.
3. ALUMINUM STOREFRONT WINDOWS AND DOORS
4. PREFINISHED METAL PARAPET CAP
5. SUSPENSION CABLE AND STEEL TUBE SUPPORTED CANOPY WITH PREFINISHED METAL PARAPET/FASCIA, SIDE GUTTERS AND DOWNSPOUTS AT SIDES.
6. EXISTING PREFINISHED METAL PARAPET CAP
7. EXISTING BLOCK WITH BRICK BAND (AS OCCURS).
8. INTERNALLY BACK-LIT SIGNAGE ATTACHED TO CANOPY EDGE.
9. PAINT OVER EXISTING METAL MANSARD, BRICK, WOOD TRIM & AGGREGATE COATINGS, DOOR & WINDOW TRIM
10. NEW MASONRY OPENING AND ALUMINUM WINDOWS. PATCH MASONRY TO MATCH EXISTING.
11. EXISTING DOOR
12. PAINTED GALVANIZED STEEL CROSS
13. EXISTING ROOF
14. NEW PARAPETS BEYOND
15. EXISTING BRICK
16. INTERNALLY BACK-LIT SIGNAGE ATTACHED TO FIBER CEMENT PANELS.
17. EXISTING DOWNSPOUT
18. PATCH WALL AT REMOVED CANOPY AND PIER WITH STUCCO COATING.

STATION19.COM | 612.623.1800



I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Architect under the laws of the state of WISCONSIN.

DATE: 04/15/2022



1710 N 15TH STREET, SHEBOYGAN WISCONSIN  
53081

COPYRIGHT: 2022

Errors may occur in the transmission of electronic files. Station Nineteen Architects, Inc. is not responsible for any claims, damages or expenses arising out of the unauthorized use of the information contained in electronic files. It is the responsibility of the user to verify all layouts, dimensions and other related information. This document may not be used or copied without prior consent.

CITY SUBMISSION

## A60







Sheboygan EFree  
**EXTERIOR VIEW | East**









# Sheboygan EFree

## **EXTERIOR** | West View









Sheboygan, Wisconsin



Street View - Jul 2019





















