

## Stormwater

Stormwater projects included provision of stormwater mains where drainage or flooding issues have been observed, or where growth or future projects indicated a need.

*Table 3: Storm Water Projects with Priority Ranking Score*

Storm Water Project	Project Year	Funding Sources	Priority (1-5)	Project Costs
Meadows Subdivision Phase 1	2025		1	\$375,165.00
5 <sup>th</sup> St SW	2025		3	\$894,391.00
Meadows Subdivision Phase 2	2026		2	\$535,444.00
Wagon Wheel Phase 1	2027		1	\$950,806.00
Wagon Wheel Phase 2	2028		2	\$1,507,911.00
Railroad ROW Phase 1	Future		1	\$932,973.00
Railroad ROW Phase 2	Future		2	\$69,289.00
11 <sup>th</sup> St SW to 9 <sup>th</sup> Ave SW	Future		1	\$806,350.00

### Meadows Subdivision Phase 1 – \$375,1265.00

Improvement to the North Meadow Village retention pond. New head gate, clean out, and possibly deepen the pond.

### 5<sup>th</sup> St SW – \$894,391.00

Installation of a storm pipe along Lincoln Ave. from 5th ST SW to 7th St W.

### Meadows Subdivision Phase 2 – \$535,444.00

Project will install a new 60" stormwater collector starting on Sunflower Lane and head south with inlets and connecting into the ditch.

### Wagon Wheel Phase 1 – \$950,806.00

Construction of a retention pond on C/S 27-732 to serve Phase 1 of Wagon Wheel Subdivision.

### Wagon Wheel Phase 2 – \$1,507,911.00

Construction of curb and gutter along the streets in Wagon Wheel Subdivision Phase 2.

### Railroad ROW Phase 1 – \$932,973.00

Relocation of a storm drainpipe in Nielson Halverson Subdivision on 9th Ave. that currently runs underneath an existing structure.

### Railroad ROW Phase 2 – \$69,289.00

Improvements to approximately 1,500 lf of drainage ditch in the Railroad Right of Way that extends from 10th St. SE to 2nd St. SE.

### 11<sup>th</sup> St SW to 9<sup>th</sup> Ave SW – \$806,350.00

Installation of drainage piping within Petersons Second Addition along 11th St. SW and up to 9th Ave. SW