Attachment D
Beauty Barn Salon
Building Elevations

1 NORTH ELEVATION - SALON
1/4" = 1'-0"

4 EAST ELEVATION - SALON
1/4" = 1'-0"

EXTERIOR FINISH SCHEDULE	
A	BRICK VENEER
B	PRE-CAST CONCRETE PANELS, 4" THICK
C	CAST-IN-PLACE CONCRETE
D	1" LOW-E INSULATED DOUBLE GLASS PANE IN THERMALLY BROKEN FRAME & TEMPERED WHERE REQUIRED - TINTED FLOAT GLASS VE30 SR COT
E	BLACK ANODIZED ALUMINUM FRAME - KAWNEER 451T
F	BLACK ALUMINUM CANOPY
G	STEEL BOARD AND BATTEN SIDING, NAIL STRIP PANELS WITH 2" BATTENS & 12" COVERAGE - WESTERN STATES METAL ROOFING - CHARCOAL GRAY

PROJECT NUMBER
24-02

REVISIONS
NO. | DATE

SHEET TITLE
ELEVATIONS

PROJECT OWNER
PPA SOUTH JORDAN CENTER
2723 W 11000 S
South Jordan, UT 84095

ARCHITECT
NICHOLS • NAYLOR
ARCHITECTS
10469 SOUTH 1300 WEST
SOUTH JORDAN, UTAH 84095 • (801) 487-3330

DATE
6/3/2025

SHEET NUMBER
A2.0

N:\2422_PPA PICKELBALL CENTER SOUTH JORDAN\ARCHITECTURAL\WORKING\250904_PPA South Jordan Center_Salon_07082026.rvt
7/15/2026 1:39:28 PM