

ESTIMATE

Fields Contracting LLC
45134 John Ave
Harris, MN 55032-3474

josh@fieldscontracting.net
+1 (612) 801-9774



Bill to
City of St Francis, MN

Ship to
City of St Francis, MN

Estimate details

Estimate no.: 1024
Estimate date: 03/31/2025

#	Date	Product or service	Description	Qty	Rate	Amount
1.		Sitework	Supply equipment and Labor to remove and replace both failing culverts on 238th Ave, St Francis Dig out and shape inlet and outlets of pipes to improve flows Rough grade roadway with salvaged gravel	1	\$11,000.00	\$11,000.00
2.		Parts	2- 30" x 60' galvanized steel spiral culverts with aprons *** These culverts are 10' wider than existing to improve slope on inlet side***	1	\$10,000.00	\$10,000.00
3.		Erosion Control and Seeding	Seed with ditch mix and install fiber blanket and staples	1	\$750.00	\$750.00

Total

\$21,750.00

Note to customer

City will supply rock as needed for pipe bedding and finish grade roadway after culvert replacement

Existing materials are considered suitable for reuse. If unsuitable soils are encountered, Additional work may be required resulting in a change order. Discussion with city will be had before further actions are taken

Accepted date

Accepted by