A & S Paving, Inc.

P.O. Box 633 2747 S. Stone Mtn./Lithonia Rd. Lithonia, GA 30058 Tel #: 770-482-1597

Fax #: 770-482-4422 Email: info@aspaving.com

JOB ESTIMATE

Date: April 9, 2025

Page 1 of 2

Bid To: City of Stone Mountain 684 Main Street Stone Mountain, GA 30083

A & S Paving is a FBE and WBE Certified Corporation.

We are pleased to submit the following job estimate:

UNIT	DESCRIPTION	PRICE	TOTAL
	Dig out dirt, install 6" GAB and 3.5" asphalt, 450' curb,	Lump Sum	\$350,00
	striping and wheel stops, ADA ramp, concrete apron,		
	silt fence, safety fence, 4" pipe in pond, tie into		
	manhole, plants, mulch for pond, construction exit,		
	15" HDPE pipe, and compaction test on dirt and rock.		
	*Note: Quote is based on removing 9.5" - 10" of dirt in	-	
	parking lot, installing 6" GAB & 3.5" asphalt. A proof		
	roll wil be done once the dirt has been cut out, any		
	unsuitable soil areas will be dug out and removed &		
	any extra rock needed will be an additional cost.		
	Con't on Page 2		

A & S Paving, Inc.

P.O. Box 633
2747 S. Stone Mtn./Lithonia Rd.
Lithonia, GA 30058
Tel #: 770-482-1597
Fax #: 770-482-4422

Fax #: 770-482-4422 Email: info@aspaving.com

JOB ESTIMATE

Date: ____ April 9, 2025

Page 2 of 2

Bid To: City of Stone Mountain 684 Main Street Stone Mountain, GA 30083

A & S Paving is a FBE and WBE Certified Corporation.

We are pleased to submit the following job estimate:

	UNIT	DESCRIPTION	PRICE	TOTAL
			PRICE	TOTAL
		(Entrance off of S. Main Street)	Lump Sum	\$31,250
		Excavate dirt, install concrete apron, curbing, rock,		40.1,200
		asphalt, traffic control, and striping stop bar and		
		double yellow line		
		(Pond)		
-		Install fence around Bio pond and around police	Lump Sum	\$21,700
		parking with sliding gate.		
		*Note: This estimate is for 5' galvanized chain link		
		fence and galvanized sliding gate, does not include		
		barbed wire or remote opening.		
		and the or remote opening.		
			TOTAL:	\$402,950