

City of Sweeny  
Natural Gas Distribution Project

The City of Sweeny Texas is proposing to replace part of the existing Natural Gas Distribution system located in the South Western part of the City limits. The project will consist of installing a combination of 4" and 2" PE 2708 Poly Gas mains with 1" service risers. Testing of pipe prior to placing in service at a minimum of 90#PSI with air or inert gas will be required. This project can be accomplished by either Open cut trenching or Directional boring. Any and all road and driveway open cuts must be repaired to current condition or better.

The project will consist of approximate footages by road:

Pecan St.	1700' 4" pipe	2-4" valves	22-Services
Sycamore St	1300' 2" pipe		24- Services
M L King north	1050' 2" pipe		14 - Services
Cedar St.	750' 2" pipe		6 - Services
Magnolia St.	400' 2" pipe		3 - Services
Peach St.	1500' 2" pipe		25 - Services
Second St.	600' 2" pipe	1-2" valve	6- Services
Fourth St.	1500' 2" pipe	6-2" valves	16- Services
Sixth St.	1800' 4" pipe	6-2" valves	10 Services
Willow St.	650' 2" pipe	2-2" valves	7 Services
M L King South	920' 2" pipe	2-2" valves	8 Services
Travis St.	900' 2" pipe	1-2" valve	8 Services
	450' 4" Pipe	1-4" valve	
Harlem St.	1500' 4" pipe	2=4" valves	11 Services

**NOTE: WE ARE CURRENTLY WORKING WITH CONTRACTORS FOR PRICING**