



Proposal

To: Michelle Medina
CC: Sweeny EDC
From: Wayman Hutchings
Date: September 9, 2026
Re: Street Lights Project
Proposal Number: C070-26-001

Below please find the scope of work for the Street Lights Project at the City of Sweeny Main Street. This proposal is based on communications with Site Team members. Adeptability Corporation activities are as follows.

A.M. "Chick" Anderson Park: Street Lights

Adeptability Corporation will remove two existing Light Poles (one has the base broken and needs to be removed). Install 4 new 9.5 Ft 5 Arm Victorian Light Poles – Square Base. Install new anchors and wire the lights to existing electrical. Each light pole cost \$2500 plus shipping.

Labot:	\$ 2,000
Material:	\$10,000
Total:	\$12,000

Street Light Pole #6: Replace Street Light Electrical

Adeptability Corporation will remove existing Light Pole #6. Jack Hammer 120 feet of concrete between Pole #4 and Pole #6, replace existing PVC Conduit, install new 12/3 Electrical Wire, mix and pour concrete and re-install Street Light Pole. Install receptacle, outdoor wall plate, light socket and light.

Labot:	\$ 4,000
Material:	\$ 2,200
Total:	\$ 6,200

Street Light Poles #6 & #32: Replace Street Light Globe

Adeptability Corporation will remove existing broken Light Globe at Pole #32 and install a new one. Need new Globe for Pole #6 as well.

Labot:	\$ 200
Material:	\$ 400
Total:	\$ 600



Street Light Bulbs: Replace Street Light Bulbs

Adeptability Corporation will remove existing light bulbs and install 24 new one.

Labot:	\$	400
Material:	\$	360
Total:	\$	760

This Proposal is valid for 30 days.

Here is the Adeptability Corporation Lump Sum price:

Total Cost: **\$ 19,560.00**