

City of Sweeny
Interlocal Agreement Project Request Summary FY-26

DO NOT ALTER THIS FORM OR ADD ADDITIONAL LINES

STREET/LOCATION	LIMITS (TO - FROM)	LENGTH (FT)	WIDTH (FT)	WORK DESCRIPTION (Major Street Projects and/or Ditch Digging ONLY)	FOR OFFICE USE ONLY
1 SIXTH STREET	MAIN TO MAGNOLIA	1820'	19'	GRIND, RESET, PAVE	
2 MAGNOLIA	SIXTH TO FIFTH	400'	18'	GRIND, RESET, PAVE	
3 FIFTH STREET	MAGNOLIA TO ELM	2500'	18'	GRIND, RESET, PAVE	
4 OAK STREET	SECOND TO AVENUE A	700'	18'	GRIND, RESET, PAVE	

Note: Must have Mayoral approval

Return to: County Engineer's Office
Engineer-interlocals@brazoriacountytx.gov


Approved By: Mayor
11-14-2025
Date

City of Sweeny
Interlocal Agreement Project Request Summary FY-26

DO NOT ALTER THIS FORM OR ADD ADDITIONAL LINES

STREET/LOCATION	LIMITS (TO - FROM)	LENGTH (FT)	WIDTH (FT)	WORK DESCRIPTION (Major Street Projects and/or Ditch Digging ONLY)	FOR OFFICE USE ONLY
1 ROSS					
2 ALICE	SECOND TO ALICE	800'	22'	GRIND, RESET, PAVE	
3 HACKBERRY	ROSS TO MCKINNEY	560'	22'	GRIND, RESET, PAVE	
4 ELM	SIXTH TO FIFTH	1500'	30'	GRIND, RESET, PAVE	
	SIXTH TO FRISKY	1500'	30'	GRIND, RESET, PAVE	

Note: Must have Mayoral approval

Return to: County Engineer's Office
Engineer-interlocals@brazoriacountytx.gov

Done for Hospital

[Signature]

Approved By: Mayor

11-14-2025

Date

Materials Cost Estimate for Project: FY26 - Sixth St.

<i>Limits</i>	<i>Len</i>	<i>Pct</i>	<i>Ctr</i>	<i>Area</i>	<i>Priority</i>	<i>Type</i>	<i>FY</i>
Main to Magnolia	0.34	4	Bra	Wes	1	IS	2026

Item Description	Len_Mi	Wid_Ft	Thk_In	Rate	Rate Unit	Qty	Unit	Price	ItemCost
ABS-65	0.34	21		0.2	Gal/SqYd	849	Gal	2.96	2,514
ABS-65	0.34	21		1.4	Gal/SqYd	5,945	Gal	2.96	17,598
Asphalt - HMAC Type D	0.34	19	2			421	Ton	82.00	34,499

Project Cost:	54,612
----------------------	---------------

Materials Cost Estimate for Project: FY26 - Magnolia

<i>Limits</i>	<i>Len</i>	<i>Pct</i>	<i>Ctr</i>	<i>Area</i>	<i>Priority</i>	<i>Type</i>	<i>FY</i>
<i>Sixth to Fifth</i>	<i>0.08</i>	<i>4</i>	<i>Bra</i>	<i>Wes</i>	<i>2</i>	<i>IS</i>	<i>2026</i>

Item Description	Len_Mi	Wid_Ft	Thk_In	Rate	Rate Unit	Qty	Unit	Price	ItemCost
ABS-65	0.08	20		0.2	Gal/SqYd	178	Gal	2.96	526
ABS-65	0.08	20		1.4	Gal/SqYd	1,244	Gal	2.96	3,684
Asphalt - HMAC Type D	0.08	18	2			88	Ton	82.00	7,183

Project Cost:	11,393
----------------------	---------------

Materials Cost Estimate for Project: FY26 - Fifth St.

<i>Limits</i>	<i>Len</i>	<i>Pct</i>	<i>Ctr</i>	<i>Area</i>	<i>Priority</i>	<i>Type</i>	<i>FY</i>
<i>Magnolia to Elm</i>	<i>0.47</i>	<i>4</i>	<i>Bra</i>	<i>Wes</i>	<i>3</i>	<i>IS</i>	<i>2026</i>

Item Description	Len_Mi	Wid_Ft	Thk_In	Rate	Rate Unit	Qty	Unit	Price	ItemCost
ABS-65	0.47	20		0.2	Gal/SqYd	1,111	Gal	2.96	3,289
ABS-65	0.47	20		1.4	Gal/SqYd	7,778	Gal	2.96	23,022
Asphalt - HMAC Type D	0.47	18	2			547	Ton	82.00	44,895

Project Cost:	71,206
----------------------	---------------

Materials Cost Estimate for Project: FY26 - Oak St.

<i>Limits</i>	<i>Len</i>	<i>Pct</i>	<i>Ctr</i>	<i>Area</i>	<i>Priority</i>	<i>Type</i>	<i>FY</i>
<i>Second to Avenue A</i>	<i>0.13</i>	<i>4</i>	<i>Bra</i>	<i>Wes</i>	<i>4</i>	<i>IS</i>	<i>2026</i>

Item Description	Len_Mi	Wid_Ft	Thk_In	Rate	Rate Unit	Qty	Unit	Price	ItemCost
ABS-65	0.13	20		0.2	Gal/SqYd	311	Gal	2.96	921
ABS-65	0.13	20		1.4	Gal/SqYd	2,178	Gal	2.96	6,446
Asphalt - HMAC Type D	0.13	18	2			153	Ton	82.00	12,571

Project Cost:	19,938
----------------------	---------------

Materials Cost Estimate for Project: FY26 - Ross St.

<i>Limits</i>	<i>Len</i>	<i>Pct</i>	<i>Ctr</i>	<i>Area</i>	<i>Priority</i>	<i>Type</i>	<i>FY</i>
<i>Second to Alice</i>	<i>0.15</i>	<i>4</i>	<i>Bra</i>	<i>Wes</i>	<i>5</i>	<i>IS</i>	<i>2026</i>

Item Description	Len_Mi	Wid_Ft	Thk_In	Rate	Rate Unit	Qty	Unit	Price	ItemCost
ABS-65	0.15	24		0.2	Gal/SqYd	427	Gal	2.96	1,263
ABS-65	0.15	24		1.4	Gal/SqYd	2,987	Gal	2.96	8,841
Asphalt - HMAC Type D	0.15	22	2			214	Ton	82.00	17,559

Project Cost:	27,662
----------------------	---------------

Materials Cost Estimate for Project: FY26 - Alice St.

<i>Limits</i>	<i>Len</i>	<i>Pct</i>	<i>Ctr</i>	<i>Area</i>	<i>Priority</i>	<i>Type</i>	<i>FY</i>
<i>Ross to McKinney</i>	<i>0.11</i>	<i>4</i>	<i>Bra</i>	<i>Wes</i>	<i>6</i>	<i>IS</i>	<i>2026</i>

Item Description	Len_Mi	Wid_Ft	Thk_In	Rate	Rate Unit	Qty	Unit	Price	ItemCost
ABS-65	0.11	24		0.2	Gal/SqYd	299	Gal	2.96	884
ABS-65	0.11	24		1.4	Gal/SqYd	2,091	Gal	2.96	6,188
Asphalt - HMAC Type D	0.11	22	2			150	Ton	82.00	12,291

Project Cost:	19,364
----------------------	---------------

Materials Cost Estimate for Project: FY26 - Hackberry

<i>Limits</i>	<i>Len</i>	<i>Pct</i>	<i>Ctr</i>	<i>Area</i>	<i>Priority</i>	<i>Type</i>	<i>FY</i>
<i>Sixth to Foy</i>	<i>0.28</i>	<i>4</i>	<i>Bra</i>	<i>Wes</i>	<i>7</i>	<i>IS</i>	<i>2026</i>

Item Description	Len_Mi	Wid_Ft	Thk_In	Rate	Rate Unit	Qty	Unit	Price	ItemCost
ABS-65	0.28	22		0.2	Gal/SqYd	733	Gal	2.96	2,171
ABS-65	0.28	22		1.4	Gal/SqYd	5,133	Gal	2.96	15,195
Asphalt - HMAC Type D	0.28	20	2			365	Ton	82.00	29,930

Project Cost:	47,295
----------------------	---------------

Materials Cost Estimate for Project: FY26 - Elm

<i>Limits</i>	<i>Len</i>	<i>Pct</i>	<i>Ctr</i>	<i>Area</i>	<i>Priority</i>	<i>Type</i>	<i>FY</i>
<i>Sixth to Frisky</i>	<i>0.28</i>	<i>4</i>	<i>Bra</i>	<i>Wes</i>	<i>8</i>	<i>IS</i>	<i>2026</i>

Item Description	Len_Mi	Wid_Ft	Thk_In	Rate	Rate Unit	Qty	Unit	Price	ItemCost
ABS-65	0.28	32		0.2	Gal/SqYd	1,067	Gal	2.96	3,157
ABS-65	0.28	32		1.4	Gal/SqYd	7,467	Gal	2.96	22,101
Asphalt - HMAC Type D	0.28	30	2			547	Ton	82.00	44,895

Project Cost:	70,154
----------------------	---------------