

WEISINGER INCORPORATED

PO Box 909 • Willis, TX 77378
936-756-7721 • 281-353-8484 • 936-756-7723 fax
www.weisingerinc.com

October 25, 2024

City of Tomball
401 West Market Street, Suite C
Tomball, TX 77375

Attn: Will Goff, CWP

Ref: City of Tomball Well 5 Rehabilitation

Mr. Goff –

As you requested, we are pleased to provide the following quotation which is in accordance with our understanding of your requirements.

Scope of Services

Pull, Inspection, and Survey

\$36,225.00

- Mobilize service rig and crew to pull existing pumping equipment
- Remove the pumping equipment from the well under normal removal procedures
- Haul original pumping equipment to our facility, perform disassembly, inspection, and present a report of our findings
- Perform a TV survey and present a report of findings

Well Rehabilitation

\$56,015.00

- Haul work pipe, air compressor, and ancillary equipment necessary for wire brushing and jetting
- Service rig and crew to perform wire-brush operations
- Service rig and crew to jet fill and debris from the bottom of the well
- Perform a TV Survey of the well and present a report of findings

Pumping Equipment

- Furnish 720 ft. of 8" x 3" x 1-15/16" column assembly with suction pipe and stainless steel strainer \$112,255.00
- Furnish a new 700 GPM at 723' TDH enclosed lineshaft bowl assembly \$29,575.00
- Furnish a new 3-gallon epoxy coated oil reservoir complete with immersion heater and lubrication kit \$4,320.00
- Furnish 730 feet of new 1/4" stainless steel airline and new water level detection kit \$3,165.00
- Sand blast, prime, paint, and re-use the existing fabricated steel discharge head \$2,410.00
- Refurbish and re-wind the existing 200 horsepower electric well pump motor. \$17,060.00
- Furnish a new 1-15/16" motor drive shaft complete with head shaft nut and gib key \$1,230.00
- Furnish a new 1-15/16" x 3" tube tension bearing with O-rings \$1,490.00
- Miscellaneous items necessary to make the pumping equipment operational \$2,700.00

Installation

\$41,045.00

- Shop labor to assemble and prepare new equipment for shipment
- Haul pumping equipment to the well site
- Service rig and crew to install pumping equipment in the well
- Service Technician to start-up, test the well, and collect (3) bacteriological samples

Total for the Scope of Services and Materials Outlined Above.....\$307,490.00

WEISINGER INCORPORATED

October 25, 2024
Attn: Will Goff, CWP
Ref: City of Tomball Water Well No. 5 Rehabilitation
Page -2-

Additive Items

- | | | |
|--------|---|-------------|
| 1 L.S. | - Perform acid treatment of well screens with 1,500 gallon of hydrochloric acid with inhibitor, mixed with 25 gallons of NW-310 acid enhancer | \$62,230.00 |
| 1 L.S. | - Perform 400 ppm downhole sodium hypochlorite disinfection treatment in the screened sections of the well | \$17,440.00 |

Thank you for the opportunity to offer you our services as we await your response.

Sincerely,



Cristian Rivera
Weisinger Incorporated



BuyBoard Contract # 672-22