

Bid No. 2022-08 - S. Persimmon Asphalt Overlay		Bidder No. 1	Bidder No. 2	Bidder No. 3
Base Price Table		Hayden Paving Total	AAA Asphalt Paving Inc Total	B & Constructors, LP Total
Item	Description			
1	Demo Concrete: Remove existing 4' x 4' concrete and lower 17 existing 36" manholes on S. Persimmon. Place and compact 6" of Black Base.	\$25,500.00	\$31,000.00	\$65,675.00
2	Profile Mill: Mill 0.5" to 1.5" prior to paving of S. Persimmon Street, beginning at the tie-in south of Lizzie Lane and extending south to Agg Road to the intersection tie-in. Work to include all cleaning, sweeping, and hauling off any spoils.	\$12,500.00	\$28,810.00	\$89,208.00
3	Overlay: Apply SS-1 tack coat at 0.05 to 0.15 gal/sq., place and compact 2" of type 'D' HMAC on existing asphalt pavement. Work to include all cleaning, sweeping, application of tack coat per specifications, and compaction of asphalt to approximate 95% Standard Proctor Density.	\$129,940.00	\$133,246.25	\$201,957.00
4	Traffic Control: A traffic control plan will be required for S. Persimmon as this is a highly utilized road	\$3,500.00	\$14,405.00	\$22,300.00
	Total Bid with proposed Additional Work	\$171,440.00	\$207,461.25	\$379,140.00