

November 8, 2024

Drew Huffman
 Director of Public Works
 City of Tomball
 501 James Street, Tomball, TX, 77375

Reference: City of Tomball – Baker Drive Water Plant: Recommendation of Award Letter

Dear Mr. Huffman,

On Monday, October 28, 2023, the City of Tomball received five offers for the Baker Drive Water Plant Project. Upon review of the offered Alternatives the City elected to incorporate Alternate 1 “Decorative Metal Fence in lieu of Chain-Link Fence” (Bid Item 39) and Bid Alternate 4 “0.5 MG Glass-Fused-to-Steel Ground Storage Tank” (Bid Item 42) into the Contract. With the elected Alternative the total bid pricing has been calculated in the table below adding the additions and deductions from the selected alternates and the base bid price. A copy of the tabulation is attached for your reference and use.

Table 1: Summary of Total Bid Price

No.	Offeror	Base Bid	Alternative Bid	Total Bid Price
1	IECONI	\$9,269,531.80	-\$420,934.75	\$8,848,597.05
2	Industrial TX Corp.	\$9,184,000.00	-\$120,000.00	\$9,064,000.00
3	Wharton-Smith, Inc.	\$10,349,500.00	-\$154,000.00	\$10,195,500.00
4	BCI Water Resources Group, Inc.	\$10,568,000.00	-\$98,000.00	\$10,470,000.00
5	W.W. Payton Corporation	\$11,500,000.00	+\$40,000.00	\$11,540,000.00

With the selected Alternatives, IECONI was selected as the top ranked offeror, as they offered the lowest total price for the Baker Drive Water Plant. Based on the evaluation of the provided bids and selection of Alternates by the City of Tomball, we recommend awarding the construction contract for the Baker Drive Water Plant to IECONI in the amount of \$8,848,597.05.

Sincerely,



Carlos Quintero, P.E.



11/08/2024

Attachment A: Formal Tabulation of Offers

Project:	Tomball Baker Drive Water Plant
Owner:	City of Tomball
Project No.:	2024-11R/TMB23728

Item	Description	Unit	Quantity	Engineer's Estimate (5/29/24)		Industrial TX Corp.		Wharton-Smith, Inc.		BCI Water Resources Group, Inc.		IECONI		W.W. Payton Corporation	
				Unit Price	Total	Unit Price	Total	Unit Price	Total	Unit Price	Total	Unit Price	Total	Unit Price	Total
I: Base Bid Items															
1	MOBILIZATION	LS	1.00	\$365,000.00	\$365,000.00	\$275,000.00	\$275,000.00	\$450,000.00	\$450,000.00	\$500,000.00	\$500,000.00	\$301,267.00	\$301,267.00	\$600,000.00	\$600,000.00
2	SITE WORK INCLUDING DETENTION, STORM PIPING, AND RE-GRADING	LS	1.00	\$269,121.00	\$269,121.00	\$350,000.00	\$350,000.00	\$300,000.00	\$300,000.00	\$165,000.00	\$165,000.00	\$155,084.00	\$155,084.00	\$150,000.00	\$150,000.00
3	REMOVE AND REPLACE CHAIN-FENCE	LF	795.00	\$88.00	\$69,960.00	\$100.00	\$79,500.00	\$75.00	\$59,625.00	\$90.00	\$71,550.00	\$53.25	\$42,333.75	\$100.00	\$79,500.00
4	DEMOLITION	LS	1.00	\$65,400.00	\$65,400.00	\$350,000.00	\$350,000.00	\$150,000.00	\$150,000.00	\$150,000.00	\$150,000.00	\$287,329.00	\$287,329.00	\$200,000.00	\$200,000.00
5	CONCRETE PAVEMENT	SY	460.00	\$153.00	\$70,380.00	\$125.00	\$57,500.00	\$275.00	\$126,500.00	\$150.00	\$69,000.00	\$240.56	\$110,657.60	\$150.00	\$69,000.00
6	WELL DISCHARGE PIPING AND EXTERIOR WATER TREATMENT SYSTEM, INCLUDING, AERATOR, FILTERS, FOUNDATIONS, APPURTENANCES, AND	LS	1.00	\$2,579,485.00	\$2,579,485.00	\$2,300,000.00	\$2,300,000.00	\$2,428,375.00	\$2,428,375.00	\$2,753,175.00	\$2,753,175.00	\$2,765,302.00	\$2,765,302.00	\$2,800,000.00	\$2,800,000.00
7	0.5 MG WELDED STEEL GROUND STORAGE TANK, INCLUDING FOUNDATION, PIPING, AND APPURTENANCES	EA	1.00	\$1,287,681.00	\$1,287,681.00	\$966,400.00	\$966,400.00	\$1,400,000.00	\$1,400,000.00	\$960,000.00	\$960,000.00	\$1,333,224.00	\$1,333,224.00	\$1,800,000.00	\$1,800,000.00
8	YARD PIPING, INCLUDING VALVES, APPURTENANCES, AND FITTINGS	LS	1.00	\$65,400.00	\$65,400.00	\$475,000.00	\$475,000.00	\$375,000.00	\$375,000.00	\$330,000.00	\$330,000.00	\$466,583.00	\$466,583.00	\$800,000.00	\$800,000.00
9	TRENCH SAFETY	LF	450.00	\$11.00	\$4,950.00	\$5.00	\$2,250.00	\$1.00	\$450.00	\$1.50	\$675.00	\$20.00	\$9,000.00	\$1.00	\$450.00
10	BOOSTER PUMP STATION, INCLUDING (3) 500 GPM HORIZONTAL SPLIT CASE PUMPS, PIPING, FOUNDATION, APPURTENANCES, FITTINGS, AND VALVES	LS	1.00	\$366,240.00	\$366,240.00	\$350,000.00	\$350,000.00	\$400,000.00	\$400,000.00	\$450,000.00	\$450,000.00	\$237,016.00	\$237,016.00	\$800,000.00	\$800,000.00
11	PRE-ENGINEERED METAL BUILDING, INCLUDING HVAC, LOUVER, HEATER, AND SUPPLY FAN FOR CHLORINE ROOM	LS	1.00	\$402,600.00	\$402,600.00	\$444,000.00	\$444,000.00	\$525,000.00	\$525,000.00	\$475,000.00	\$475,000.00	\$302,232.00	\$302,232.00	\$600,000.00	\$600,000.00
12	ELECTRICAL AND CONTROL COMPONENTS	LS	1.00	\$1,107,842.00	\$1,107,842.00	\$1,780,000.00	\$1,780,000.00	\$2,400,000.00	\$2,400,000.00	\$2,875,000.00	\$2,875,000.00	\$1,490,969.00	\$1,490,969.00	\$2,072,965.00	\$2,072,965.00
13	GENERATOR, INCLUDING CONCRETE PAD	LS	1.00	\$1,155,291.00	\$1,155,291.00	\$650,000.00	\$650,000.00	\$725,000.00	\$725,000.00	\$688,000.00	\$688,000.00	\$789,925.00	\$789,925.00	\$700,000.00	\$700,000.00
14	TREATMENT EQUIPMENT INCLUDING CHLORINATION AND CORROSION	LS	1.00	\$512,300.00	\$512,300.00	\$425,000.00	\$425,000.00	\$350,000.00	\$350,000.00	\$450,000.00	\$450,000.00	\$317,265.00	\$317,265.00	\$150,000.00	\$150,000.00
15	WELL VIDEO SURVEY INSPECTION AND WRITTEN REPORT	EA	4.00	-	-	\$500.00	\$2,000.00	\$2,000.00	\$8,000.00	\$2,000.00	\$8,000.00	\$2,093.00	\$8,372.00	\$2,000.00	\$8,000.00
16	FURNISH, INSTALL AND REMOVE STEEL TANK AND TEMPORARY PIPING FOR WELL CONTRACTOR OPERATIONS AND DISCHARGES	LS	1.00	-	-	\$9,000.00	\$9,000.00	\$25,000.00	\$25,000.00	\$6,300.00	\$6,300.00	\$6,696.00	\$6,696.00	\$10,000.00	\$10,000.00
17	PERFORM MECHANICAL CLEANING OF THE WELL SCREENS	HR	20.00	-	-	\$750.00	\$15,000.00	\$500.00	\$10,000.00	\$475.00	\$9,500.00	\$502.00	\$10,040.00	\$420.00	\$8,400.00
18	PERFORM WELL CHEMICAL ACID TREATMENT OF THE WELL SCREENS WITH 70% HYDROXYACETIC ACID (550 GALLONS), CHEMICAL ENHANCER AND CORROSION INHIBITOR	LS	1.00	-	-	\$34,000.00	\$34,000.00	\$50,000.00	\$50,000.00	\$50,000.00	\$50,000.00	\$52,427.00	\$52,427.00	\$60,000.00	\$60,000.00
19	PERFORM AIRLIFT PUMPING AND AGITATION WITH DOUBLE DISK SURGE BLOCK AGITATOR, AND NEUTRALIZATION OF CHEMICALS FOLLOWING WELL CHEMICAL TREATMENT	HR	20.00	-	-	\$825.00	\$16,500.00	\$500.00	\$10,000.00	\$510.00	\$10,200.00	\$538.00	\$10,760.00	\$450.00	\$9,000.00
20	CUT AND REMOVE 50 FEET OF THE UPPER BLANK LINER (LAP) LINER	LS	1.00	-	-	\$115,000.00	\$115,000.00	\$110,000.00	\$110,000.00	\$103,700.00	\$103,700.00	\$109,434.00	\$109,434.00	\$120,000.00	\$120,000.00
21	JET / AIRLIFT PUMP AND REMOVE SEDIMENT FILL FROM THE WELL	HR	30.00	-	-	\$780.00	\$23,400.00	\$550.00	\$16,500.00	\$515.00	\$15,450.00	\$544.00	\$16,320.00	\$455.00	\$13,650.00
22	PERFORM CHLORINE DISINFECTION OF THE WELL AND WELL SCREENS	LS	1.00	-	-	\$16,000.00	\$16,000.00	\$7,000.00	\$7,000.00	\$7,100.00	\$7,100.00	\$7,533.00	\$7,533.00	\$7,000.00	\$7,000.00
23	FURNISH AND INSTALL NEW FABRICATED STEEL WELL DISCHARGE HEAD WITH MACHINED HOLES FOR PVC PIPE, AIRLINE AND ANY OTHER ACCESSORY, PLUS 4 LIFTING LUGS WITH CORRECTLY SIZED WELL DISCHARGE AND FLANGE TO CONNECT TO SEPARATE WELL DISCHARGE	LS	1.00	-	-	\$15,000.00	\$15,000.00	\$25,000.00	\$25,000.00	\$26,000.00	\$26,000.00	\$27,430.00	\$27,430.00	\$30,000.00	\$30,000.00
24	FURNISH AND INSTALL VERTICAL TURBINE, LINE SHAFT PUMP BOWL WITH DESIGN CONDITIONS OF 800 GPM AT 585 FEET TDH WITH COUPLING, STAINLESS STEEL COLLETS AND WEAR RINGS, SUCTION PIPE AND STAINLESS STEEL CONE STRAINER INCLUDING NON-WITNESS PUMP BOWL	LS	1.00	-	-	\$72,000.00	\$72,000.00	\$55,000.00	\$55,000.00	\$52,000.00	\$52,000.00	\$54,980.00	\$54,980.00	\$60,000.00	\$60,000.00
25	FURNISH AND INSTALL 20-FOOT SECTION OF NEW 8-INCH (0.322" WALL THICKNESS) COLUMN PIPE, 3-INCH OIL TUBING AND 1-15/16-INCH LINE SHAFT, BEARINGS, COUPLINGS AND RUBBER TUBE STABILIZER	EA	27.00	-	-	\$3,800.00	\$102,600.00	\$4,500.00	\$121,500.00	\$4,350.00	\$117,450.00	\$4,604.00	\$124,308.00	\$3,850.00	\$103,950.00
26	FURNISH AND INSTALL 10-FOOT SECTION OF NEW 8-INCH (0.322" WALL THICKNESS) COLUMN PIPE, 3-INCH OIL TUBING AND 1-15/16-INCH LINE SHAFT, BEARINGS, COUPLINGS AND RUBBER TUBE STABILIZER	EA	1.00	-	-	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$2,200.00	\$2,200.00	\$2,302.00	\$2,302.00	\$2,000.00	\$2,000.00
27	FURNISH AND INSTALL 10-FOOT SECTION OF NEW 8-INCH (0.322" WALL THICKNESS) TOP SPECIAL THREADED COLUMN PIPE, 3-INCH OIL TUBING AND 1-15/16-INCH LINE SHAFT, BEARINGS AND COUPLINGS	EA	1.00	-	-	\$3,300.00	\$3,300.00	\$3,000.00	\$3,000.00	\$3,000.00	\$3,000.00	\$3,187.00	\$3,187.00	\$3,000.00	\$3,000.00
28	FURNISH AND INSTALL NEW 1-15/16-INCH X 3-INCH TENSION BEARING, NUT AND PLATE ASSEMBLY	EA	1.00	-	-	\$2,400.00	\$2,400.00	\$3,000.00	\$3,000.00	\$3,200.00	\$3,200.00	\$3,348.00	\$3,348.00	\$3,000.00	\$3,000.00
29	FURNISH 1-1/4-INCH PVC PIPE (SCH. 80) AND INSTALL SECURELY TO THE PUMP COLUMN PIPE FROM THE WELL PUMP TO ABOVE LAND SURFACE WITH THREADED CAP	FT	565.00	-	-	\$4.50	\$2,542.50	\$4.00	\$2,260.00	\$4.00	\$2,260.00	\$3.95	\$2,231.75	\$3.40	\$1,921.00
30	FURNISH 1/4-INCH STAINLESS STEEL AIRLINE WITH PVC WRAP WITH ALL FITTING(S) AND AN OIL-FILLED PRESSURE GAUGE AND INSTALL SECURELY TO THE PUMP COLUMN PIPE FROM THE WELL PUMP TO ABOVE LAND	FT	565.00	-	-	\$5.50	\$3,107.50	\$6.00	\$3,390.00	\$6.00	\$3,390.00	\$6.58	\$3,717.70	\$5.60	\$3,164.00
31	FURNISH AND INSTALL A NEW OIL LUBRICATOR WITH 3-GALLON CAPACITY RESERVOIR, IMMERSION HEATER AND THERMOSTAT, SOLENOID AND FLOW REGULATING VALVE	LS	1.00	-	-	\$5,500.00	\$5,500.00	\$5,000.00	\$5,000.00	\$5,300.00	\$5,300.00	\$5,620.00	\$5,620.00	\$6,000.00	\$6,000.00
32	FURNISH AND INSTALL NEW 250 HP, TEFC, 1,780 RPM, 460 VOLT, 3-PHASE, PREMIUM EFFICIENT ELECTRIC WELL MOTOR WITH COMBINATION MOTOR DRIVE SHAFT AND NEW HEAD SHAFT NUT AND GIB KEYS WITH ALL NECESSARY ELECTRICAL CONNECTIONS	LS	1.00	-	-	\$110,000.00	\$110,000.00	\$100,000.00	\$100,000.00	\$103,000.00	\$103,000.00	\$108,520.00	\$108,520.00	\$120,000.00	\$120,000.00

33	DEMOLISH AND REPLACE EXISTING WELL CONCRETE SEALING BLOCK AND WELL PUMP SUPPORT	LS	1.00	-	-	\$30,000.00	\$30,000.00	\$10,000.00	\$10,000.00	\$9,500.00	\$9,500.00	\$10,045.00	\$10,045.00	\$10,000.00	\$10,000.00
34	CHLORINATE AND DISINFECT THE WELL PUMP EQUIPMENT AND WELL AND PERFORM WATER SAMPLING AND BACTERIOLOGICAL ANALYSES (REQUIRE 3 NEGATIVE BACTERIOLOGICAL SAMPLES)	LS	1.00	-	-	\$2,000.00	\$2,000.00	\$3,000.00	\$3,000.00	\$2,800.00	\$2,800.00	\$2,990.00	\$2,990.00	\$3,000.00	\$3,000.00
35	PERFORM WELL, PUMP AND MOTOR EQUIPMENT PERFORMANCE TESTING WITH VIBRATION ANALYSES AND PROVIDE WRITTEN REPORT	LS	1.00	-	-	\$1,000.00	\$1,000.00	\$900.00	\$900.00	\$850.00	\$850.00	\$897.00	\$897.00	\$1,000.00	\$1,000.00
36	PERFORM 36-HOUR PUMPING TEST WITH THE PERMANENT WELL PUMPING EQUIPMENT INSTALLED AND PROVIDE WRITTEN REPORT	LS	1.00	-	-	\$16,000.00	\$16,000.00	\$8,000.00	\$8,000.00	\$8,500.00	\$8,500.00	\$8,968.00	\$8,968.00	\$10,000.00	\$10,000.00
37	COLLECT WATER SAMPLES AND HAVE LABORATORY PERFORM ANALYSES FOR COMPLETE TCEQ PUBLIC WATER SUPPLY ANALYSES AND OTHER CONSTITUENTS AND PROVIDE COMPLETE LAB ANALYSES	LS	1.00	-	-	\$6,000.00	\$6,000.00	\$6,000.00	\$6,000.00	\$5,900.00	\$5,900.00	\$6,218.00	\$6,218.00	\$10,000.00	\$10,000.00
Sub Totals						\$8,321,650.00	\$9,109,000.00	\$10,274,500.00	\$10,493,000.00	\$9,194,531.80	\$11,425,000.00				
II: Allowances															
38	GAS AND ELECTRIC UTILITY COORDINATION AND INSTALLATION	LS	1.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00
Sub Totals						\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00	\$75,000.00
III: Alternates: Additions or Deductions															
39	DECORATIVE METAL FENCE IN LIEU OF CHAIN LINK FENCE	LF	1.00	\$143,100.00	\$143,100.00	\$30,000.00	\$30,000.00	\$46,000.00	\$46,000.00	\$52,000.00	\$52,000.00	\$98,230.25	\$98,230.25	\$140,000.00	\$140,000.00
40	AUTOMATIC SLIDE GATE IN LIEU OF MANUAL SLIDE GATE	LS	1.00	\$12,000.00	\$12,000.00	\$18,000.00	\$18,000.00	\$6,800.00	\$6,800.00	\$7,600.00	\$7,600.00	\$8,871.00	\$8,871.00	\$15,000.00	\$15,000.00
41	0.5 MG PRESTRESSED TYPE III CONCRETE GROUND STORAGE TANK	LS	1.00	(\$64,308.00)	(\$64,308.00)	\$615,000.00	\$615,000.00	\$455,000.00	\$455,000.00	\$570,000.00	\$570,000.00	\$520,702.00	\$520,702.00	\$500,000.00	\$500,000.00
42	0.5 MG GLASS-FUSED-TO-STEEL GROUND STORAGE TANK	LS	1.00	(\$186,270.10)	(\$186,270.10)	(\$150,000.00)	(\$150,000.00)	(\$200,000.00)	(\$200,000.00)	(\$150,000.00)	(\$150,000.00)	(\$519,165.00)	(\$519,165.00)	(\$100,000.00)	(\$100,000.00)
43	0.4 MG GALLON PRESTRESSED TYPE III CONCRETE GROUND STORAGE TANK	LS	1.00	(\$294,308.00)	(\$294,308.00)	\$528,000.00	\$528,000.00	\$380,000.00	\$380,000.00	\$485,000.00	\$485,000.00	\$392,474.00	\$392,474.00	\$400,000.00	\$400,000.00
44	0.4 MG GALLON WELDED STEEL GROUND STORAGE TANK	LS	1.00	(\$301,366.24)	(\$301,366.24)	(\$30,000.00)	(\$30,000.00)	(\$30,000.00)	(\$30,000.00)	(\$25,000.00)	(\$25,000.00)	(\$573,675.00)	(\$573,675.00)	(\$30,000.00)	(\$30,000.00)
45	0.4 MG GLASS-FUSED-TO-STEEL GROUND STORAGE TANK	LS	1.00	(\$346,476.92)	(\$346,476.92)	(\$230,000.00)	(\$230,000.00)	(\$260,000.00)	(\$260,000.00)	(\$200,000.00)	(\$200,000.00)	(\$609,649.00)	(\$609,649.00)	(\$180,000.00)	(\$180,000.00)
46	CMU CONCRETE BUILDING WITH BRICK VENEER, INCLUDING HVAC, LOUVER, HEATER, AND SUPPLY FAN FOR CHLORINE ROOM	LS	1.00	-	-	\$225,000.00	\$225,000.00	\$169,000.00	\$169,000.00	\$160,000.00	\$160,000.00	\$83,568.00	\$83,568.00	\$300,000.00	\$300,000.00
47	CMU CONCRETE BUILDING WITH BRICK VENEER ONLY AROUND THE ELECTRICAL ROOM, INCLUDING HVAC, LOUVER, HEATER, AND SUPPLY FAN FOR CHLORINE ROOM	LS	1.00	-	-	\$85,000.00	\$85,000.00	\$139,000.00	\$139,000.00	\$140,000.00	\$140,000.00	\$39,538.00	\$39,538.00	\$260,000.00	\$260,000.00
48	PERFORM WELL CHEMICAL ACID TREATMENT OF THE WELL SCREENS WITH 15% HYDROCHLORIC ACID (550 GALLONS), CHEMICAL ENHANCER AND CORROSION INHIBITOR	LS	1.00	-	-	\$13,500.00	\$13,500.00	\$26,000.00	\$26,000.00	\$25,500.00	\$25,500.00	\$30,979.00	\$30,979.00	\$30,000.00	\$30,000.00
49	15% HYDROCHLORIC ACID, CHEMICAL ENHANCER AND CORROSION INHIBITOR FOR ACID VOLUME THAT IS MORE OR LESS THAN SPECIFIED IN	GAL	50.00	-	-	\$11.00	\$550.00	\$100.00	\$5,000.00	\$101.00	\$5,050.00	\$2.46	\$123.00	\$90.00	\$4,500.00
50	70% HYDROXYACETIC ACID, CHEMICAL ENHANCER AND CORROSION INHIBITOR FOR ACID VOLUME THAT IS MORE OR LESS THAN SPECIFIED IN	GAL	50.00	-	-	\$6.00	\$300.00	\$140.00	\$7,000.00	\$146.00	\$7,300.00	\$3.55	\$177.50	\$130.00	\$6,500.00
51	REFINISH THE TOP OR BASE OF THE EXISTING WELL PUMP FOUNDATION FOR INSTALLATION AND SEALING OF THE NEW WELL DISCHARGE HEAD	LS	1.00	-	-	(\$15,000.00)	(\$15,000.00)	\$9,500.00	\$9,500.00	\$9,500.00	\$9,500.00	\$11,464.00	\$11,464.00	\$10,000.00	\$10,000.00
52	FURNISH AND INSTALL VERTICAL TURBINE, LINE SHAFT PUMP BOWL WITH DESIGN CONDITIONS OF 700 GPM AT 585 FEET TDH WITH COUPLING, STAINLESS STEEL COLLETS AND WEAR RINGS, SUCTION PIPE AND STAINLESS STEEL CONE STRAINER THAT DOES NOT INCLUDE NON-WITNESS PUMP BOWL TESTING AND WRITTEN REPORT	LS	1.00	-	-	\$68,000.00	\$68,000.00	\$48,000.00	\$48,000.00	\$47,000.00	\$47,000.00	\$57,509.00	\$57,509.00	\$55,000.00	\$55,000.00
53	FURNISH AND INSTALL NEW 200 HP, TEFC, 1,780 RPM, 460 VOLT, 3-PHASE, PREMIUM EFFICIENT ELECTRIC WELL MOTOR WITH COMBINATION MOTOR DRIVE SHAFT AND NEW HEAD SHAFT NUT AND GIB KEYS WITH ALL NECESSARY ELECTRICAL CONNECTIONS	LS	1.00	-	-	\$97,000.00	\$97,000.00	\$100,000.00	\$100,000.00	\$97,000.00	\$97,000.00	\$126,649.00	\$126,649.00	\$110,000.00	\$110,000.00
54	FURNISH, INSTALL AND REMOVE A CONTRACTOR PROVIDED PORTABLE GENERATOR AND ALL EQUIPMENT TO POWER THE NEW WELL PUMP AND WELL MOTOR FOR FIELD TESTING AND/OR OWNER OPERATION	LS	1.00	-	-	\$5,000.00	\$5,000.00	\$13,500.00	\$13,500.00	\$13,500.00	\$13,500.00	\$25,637.00	\$25,637.00	\$15,000.00	\$15,000.00
55	RENTAL OF A CONTRACTOR PROVIDED PORTABLE GENERATOR AND ALL EQUIPMENT TO POWER THE NEW WELL PUMP AND WELL MOTOR FOR FIELD TESTING AND/OR OWNER OPERATION	WK	8.00	-	-	\$20,000.00	\$160,000.00	\$9,000.00	\$72,000.00	\$9,000.00	\$72,000.00	\$1,343.38	\$10,747.04	\$10,000.00	\$80,000.00
56	FURNISH, INSTALL AND REMOVE A CONTRACTOR PROVIDED PORTABLE ENGINE, RIGHT-ANGLE GEAR DRIVE, 200 HP OR 250 HP ELECTRIC MOTOR AND ALL EQUIPMENT TO POWER THE NEW WELL PUMP FOR FIELD TESTING AND/OR OWNER OPERATION	LS	1.00	-	-	\$6,000.00	\$6,000.00	\$75,000.00	\$75,000.00	\$72,200.00	\$72,200.00	\$96,421.00	\$96,421.00	\$75,000.00	\$75,000.00
57	RENTAL OF A CONTRACTOR PROVIDED PORTABLE ENGINE, RIGHT-ANGLE GEAR DRIVE, 200 HP OR 250 HP ELECTRIC MOTOR AND ALL EQUIPMENT TO POWER THE NEW WELL PUMP FOR FIELD TESTING AND/OR OWNER OPERATION	WK	8.00	-	-	\$3,200.00	\$25,600.00	\$7,200.00	\$57,600.00	\$7,000.00	\$56,000.00	\$1,969.00	\$15,752.00	\$10,000.00	\$80,000.00
58	EVOUQUA/WALLACE AND TIERNAN CHLORINE FEED EQUIPMENT PER SPECIFICATION 46 31 11 CHLORINE GAS FEED EQUIPMENT AND 46 33 49 SOLENOID METERING PUMPS	LS	1.00	-	-	\$100,000.00	\$100,000.00	\$390,610.00	\$390,610.00	\$218,000.00	\$218,000.00	\$602,149.00	\$602,149.00	\$500,000.00	\$500,000.00
Sub Totals (Alternate 1 & 4 (Bid Item 39 & 42))						(\$43,170.10)	(\$120,000.00)	(\$154,000.00)	(\$98,000.00)	(\$420,934.75)	\$40,000.00				
Base Bid Total						\$8,396,650.00	\$9,184,000.00	\$10,349,500.00	\$10,568,000.00	\$9,269,531.80	\$11,500,000.00				
Grand Total with Alternate 1 & 4 (Bid Item 39 & 42)						\$8,353,479.90	\$9,064,000.00	\$10,195,500.00	\$10,470,000.00	\$8,848,597.05	\$11,540,000.00				