


FINAL

**CITY OF TOMBALL
DRAINAGE MASTER PLAN
CITY OF TOMBALL, HARRIS COUNTY, TX**




CITY OF TOMBALL CONTRACT# 2023-10008

PREPARED BY:



**CIVIL SYSTEMS ENGINEERING, INC.
TBPE# F-5246**




Kurt E. Killian, P.E., CFM
TX PE #95742
Civil Systems Engineering, Inc.
F-5246
March 18, 2025

MARCH 2025

TABLE OF CONTENTS

1.0	EXECUTIVE SUMMARY	6
1.1	PROJECT STUDY AREA	6
1.2	SUGGESTED IMPROVEMENTS	7
1.3	DRAINAGE CRITERIA AND STANDARDS.....	8
1.4	PROJECT FUNDING	8
2.0	INTRODUCTION.....	10
2.1	SCOPE	10
2.2	DESIGN CRITERIA.....	10
2.3	PROJECT STUDY AREA	10
2.4	PROJECT DESCRIPTION	11
2.5	DESIGN CRITERIA AND REFERENCES.....	11
2.6	PROJECT DATUM.....	12
2.7	CITY INFRASTRUCTURE MASTER PLAN	12
2.8	DEFINITION	13
2.9	FEMA EFFECTIVE FLOODPLAIN.....	14
2.10	AGENCY COORDINATION AND PUBLIC OUTREACH.....	14
3.0	GIS APPLICATION	16
3.1	DATUM AND COORDINATE SYSTEM.....	16
3.2	GIS FEATURE LAYERS.....	16
3.3	LIDAR DEM	17
3.4	AERIAL PHOTOGRAPHS	18
4.0	HYDROLOGY	19
4.1	SUBWATERSHED BASINS	19
4.2	MAJOR DRAINAGE BASINS	19
4.3	DRAINAGE AREA DELINEATIONS	20
4.4	HYDROLOGIC METHODS	20
5.0	HYDRAULICS	24
5.1	MAJOR DRAINAGE SYSTEMS	24
5.2	HYDRAULIC METHODOLOGIES	24
5.3	OVERALL 2D HEC-RAS MODEL	24
6.0	FLOOD RISK AREAS	27
6.1	HISTORIC FLOODING EVENTS	27
6.2	REPORTED FLOODED STREETS	30
7.0	MITIGATION / IMPROVEMENTS STRATEGIES.....	32
7.1	IMPROVEMENT COMPONENTS.....	32
7.2	PROPOSED ALTERNATIVES AND CIP	33
7.3	CHALLENGES WITH IMPLEMENTING CIP PROJECTS	33
8.0	M116 BASIN.....	35
8.1	BASIN DESCRIPTION	35

8.2	BASIN HISTORY	36
8.3	OUTSIDE AGENCY PROJECTS & COORDINATION	37
8.4	DRAINAGE ISSUES & PROBLEMATIC AREAS	37
8.5	PROPOSED ALTERNATIVES	39
9.0	M118 BASIN.....	41
9.1	BASIN DESCRIPTION	41
9.2	BASIN HISTORY	42
9.3	OUTSIDE AGENCY PROJECTS & AGENCY COORDINATION	46
9.4	DRAINAGE ISSUES & PROBLEMATIC AREA.....	46
9.5	PROPOSED ALTERNATIVES	47
10.0	M121 BASIN.....	51
10.1	BASIN DESCRIPTION	51
10.2	BASIN HISTORY	52
10.3	OUTSIDE AGENCY PROJECTS & AGENCY COORDINATION	54
10.4	DRAINAGE ISSUES & PROBLEMATIC AREA.....	54
10.5	PROPOSED ALTERNATIVES	56
11.0	M124 BASIN.....	63
11.1	BASIN DESCRIPTION	63
11.2	BASIN HISTORY	64
11.3	OUTSIDE AGENCY PROJECTS & AGENCY COORDINATION	65
11.4	DRAINAGE ISSUES & PROBLEMATIC AREA.....	67
11.5	PROPOSED ALTERNATIVES	68
12.0	M125 BASIN.....	70
12.1	BASIN DESCRIPTION	70
12.2	BASIN HISTORY	71
12.3	OUTSIDE AGENCY PROJECTS & AGENCY COORDINATION	72
12.4	DRAINAGE ISSUES & PROBLEMATIC AREAS	72
12.5	PROPOSED ALTERNATIVES	72
13.0	J131 BASIN	74
13.1	BASIN DESCRIPTION	74
13.2	BASIN HISTORY	74
13.3	OUTSIDE AGENCY PROJECTS & AGENCY COORDINATION	76
13.4	DRAINAGE ISSUES & PROBLEMATIC AREAS	76
13.5	PROPOSED ALTERNATIVES	79
14.0	J132 BASIN	86
14.1	BASIN DESCRIPTION	86
14.2	BASIN HISTORY	86
14.3	OUTSIDE AGENCY PROJECTS & AGENCY COORDINATION	87
14.4	DRAINAGE ISSUES & PROBLEMATIC AREA.....	87
14.5	PROPOSED ALTERNATIVES	87
15.0	J133 BASIN	88

15.1	BASIN DESCRIPTION	88
15.2	BASIN HISTORY	88
15.3	OUTSIDE AGENCY PROJECTS & AGENCY COORDINATION	89
15.4	DRAINAGE ISSUES & PROBLEMATIC AREA.....	89
15.5	PROPOSED ALTERNATIVES	90
16.0	DRAINAGE CRITERIA AND STANDARDS	92
16.1	DISCLAIMER	92
16.2	NO ADVERSE IMPACT	92
16.3	DRAINAGE FACILITY MAINTENANCE	93
16.4	DESIGN CRITERIA MANUAL UPDATES	93
16.5	TECHNICAL SPECIFICATIONS	94
17.0	CAPITAL IMPROVEMENT PLAN	95
17.1	PROPOSED PROJECT COST ESTIMATES	95
17.2	PRIORITIZATION	95
17.3	FINANCING / FUNDING ALTERNATIVES	96
18.0	BASIN IMPACT FEE	98
18.1	COLLECTION OF BASIN IMPACT FEES	98

TABLES

Table 1-1.	Tomball Major Drainage Basins Summary	6
Table 1-2.	City of Tomball Current Basin Impact Fees	9
Table 4-1.	Rainfall Depths: 24-Hour Totals – Harris County, Region 1	20
Table 4-2.	Watershed Soil Data	21
Table 4-3.	Watershed Parameter Description	21
Table 4-4.	Land Use Imperviousness & Runoff Coefficients	22
Table 4-5.	Rational Method e, b, d Coefficients: Harris County, Region 1	23
Table 5-1.	Major Drainage Systems	24
Table 6-1.	Reported Street Flooding Locations: Harvey 2017	30
Table 6-2.	Reported Street Flooding Locations: May 2, 2024.....	31
Table 8-1.	M116 Drainage Crossing Inventory.....	36
Table 9-1.	M118 Drainage Crossing Inventory.....	42
Table 10-1.	M121 Drainage Crossing Inventory.....	52
Table 11-1.	M124 Drainage Crossing Inventory.....	64
Table 12-1.	M125 Drainage Crossing Inventory.....	70
Table 13-1.	J131 Drainage Crossing Inventory	75
Table 14-1.	J132 Drainage Crossing Inventory	87
Table 15-1.	J133 Drainage Crossing Inventory	89
Table 18-1.	DMP CIP Cost Summary Per Basin	96
Table 18-1.	City of Tomball Current Basin Development Fees.....	98
Table 18-2.	City of Tomball Current Basin Development Fees.....	98

EXHIBITS

EXHIBIT 1 - Overall Basin Map
EXHIBIT 2 – M116 Basin Drainage Area Map
EXHIBIT 3 – M118 Basin Drainage Area Map
EXHIBIT 4 – M121 Basin Drainage Area Map
EXHIBIT 5 – M124 Basin Drainage Area Map
EXHIBIT 6 – M125 Basin Drainage Area Map
EXHIBIT 7 – J131 Basin Drainage Area Map
EXHIBIT 8 – J100-J132-J133 Basin Drainage Area Map

APPENDICES

Appendix A – Drainage Design Criteria Manual
Appendix B – Design Specifications
Appendix C – CIP Packets
Appendix D – CIP Cost Summary
Appendix E – Impact Fee Listing Maps

ELECTRONIC DELIVERABLES

GIS Deliverables
Electronic Copy of Models

1.0 EXECUTIVE SUMMARY

Civil Systems Engineering, Inc was contracted by the City of Tomball, which was executed on May 15th, 2023, to perform engineering studies relative to drainage infrastructure. The objective of these studies is to update/develop a comprehensive Drainage Master Plan (DMP) to better identify drainage problem areas, potential solutions, serve as a guidance document for drainage infrastructure needs and approach for both private and public improvements, and assembly of a drainage capital improvement projects plan. Additionally, the studies included review of the City's current Drainage Criteria Manual, Drainage Standards, Drainage Impact Fees, and alternative funding strategies used for drainage infrastructure improvements. This effort, as applicable, was performed in conformance with Local Government Code, Title 12, Planning and Development, Chapter 395, Financing Capital Improvements Required by New Development in Municipalities, Counties, and Certain Other Local Governments.

1.1 Project Study Area

The project study area covers the City of Tomball corporate boundaries (City limits) and extraterritorial jurisdiction (ETJ), as shown in **Figure 2-1**. The City of Tomball covers a total area of 36.67 square miles. The City is located within the Spring Creek and Willow Creek watersheds. The topography of the study area is typical of areas located in the Gulf Coastal Plan. It is generally flat, sloping gently towards receiving drainage ditches and streams.

TABLE 1-1. TOMBALL MAJOR DRAINAGE BASINS SUMMARY

DITCH UNIT NO	DITCH/ STREAM NAME	BASIN AREA (ACRE/ SQ. MILES)	DITCH OWNER	FEMA MAPPING DETAILS
M100-00-00	Willow Creek	54 SQ.MI.	HCFC	DETAIL STUDY, ZONE AE/FWY
M112-00-00	Roan Gully / Tributary 6.52 to Willow Creek	2,455 AC	HCFC	DETAIL STUDY, ZONE AE/FWY
M116-00-00	Tributary 8.16 to Willow Creek	1,169 AC	HCFC	DETAIL STUDY, ZONE AE/FWY
M118-00-00	N/A	1,013 AC	COT	N/A
M121-00-00	N/A	1,848 AC	HCFC	
M121-01-00	M121 WEST	958 AC	COT	N/A
M121-02-00	M121 EAST	647 AC	COT	N/A
M124-00-00	Tributary 13.50 to Willow Creek	2,660 AC	COT/ HCFC	DETAIL STUDY, ZONE AE/FWY
M125-00-00	N/A	787 AC	COT	N/A
J100-00-00	Spring Creek	284 SQ.MI.	HCFC	DETAIL STUDY, ZONE AE/FWY
J131-00-00	Boggs Gully	2,543 AC	HCFC	DETAIL STUDY, ZONE AE/FWY

DITCH UNIT NO	DITCH/ STREAM NAME	BASIN AREA (ACRE/ SQ. MILES)	DITCH OWNER	FEMA MAPPING DETAILS
J131-01-00	Tributary 1.25 to Boggs Gully	367 AC	HCFC	DETAIL STUDY, ZONE AE/FWY
J131-03-00	N/A	367 AC	HCFC	N/A *
J132-00-00	N/A	50 AC	HCFC	N/A *
J133-00-00	N/A	248 AC	HCFC	N/A *

N/A – Unstudied stream.

N/A * – Unstudied stream with reach of Zone AE/A due to receiving stream backwater.

1.2 Suggested Improvements

Existing conditions were evaluated for each of the City’s drainage subbasins to identify problematic areas and apply multiple storm frequencies including 2, 5, 10, 25, 50, and 100-year storm events. Problematic areas were identified as those with the potential for structural flooding and/or impassable roadways. Additional modeling incorporated future development based on the future land uses, the City’s major thoroughfare plan, and other applicable planning documents to evaluate potential impacts to the City’s existing drainage systems. Suggested improvements were developed to mitigate both existing and future drainage issues within the study area and are further described in their respective subbasin sections of this report. Through coordination with City staff, a Capital Improvement Plan for 5-year, 10-year and long-range planning horizons is developed considering implementation strategy, identified repetitive loss locations, cost, and other factors.

CIP PROGRAM YEAR	SUGGESTED IMPROVEMENT BASIN	OPINION OF PROBABLE COSTS TO IMPLEMENT (2024)
5-Year	J131, M118, M121	\$31,164,288
10-Year	M116, M118, M121, M124, M125, J131, J133	\$39,116,390
>10-Year	M112, M116, M118, M121, M124, J131	\$168,155,637
Total		\$238,436,316

Notes:

1. Cost assumes no change from existing conditions from time of cost preparation.
2. Assumes design and construction occur in a single fiscal year.
3. Annual rate of 8% was used for inflation and escalation for each year past original year of cost preparation to implementation.
4. All estimates assume City of Tomball is sole implementor with overlapping jurisdiction of the drainage basins potential for partnering with other agencies.
5. Some projects may require implementation by private developers upon approval by City.
6. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.
7. Pricing excludes cost for well abandonment or the cost of pipeline relocations.

Improvements evaluated as part of this DMP are preliminary and are intended to be used for the purposes of planning purposes based on the best available information at the time of the study. Further detailed analysis and engineering shall be performed as part of the implementation of these preferred alternatives.

1.3 Drainage Criteria and Standards

As part of this DMP, the current City of Tomball Drainage Criteria Manual (DCM) was reviewed and updates were proposed. The DCM was originally published and adopted in 2011 and updated in June 2021. The DCM establishes rules and regulations that must be consistently followed and enforced throughout the City for drainage design and implementation.

DCM suggested updates/ modifications include:

- Adopt principle of “No Adverse Impact”
 - No peak flow increases to receiving conveyance
 - No impact to receiving conveyance water surface elevation and/or ponding
- Increase minimum detention rate from 0.55 ac-ft/ac to 0.75 ac-ft/ac with analysis of No Adverse Impact
- Roadway Drainage Criteria Hierarchy for primary conveyance/storm sewer
 - Limiting Ponding Width based on roadway classification to establish minimum required passable lanes during any particle rainfall event
 - 25-Year (2-Year Current) minimum design frequency for minor roadway
- Add provisions to allow other pipe materials for storm sewer construction such as High-Density Polyethylene (HDPE) and Polypropylene (PP)

1.4 Project Funding

In addition to traditional City infrastructure project funding mechanisms, options are available to build project funding reserves and to reduce or eliminate City “out of pocket” cost of implementation. These include:

Grants – FEMA, Texas Water Development Board (TWDB), FHWA RAISE, Texas General Land Office (GLO), US Housing and Urban Development (HUD), and etc. A CIP plan Having adopted plans such as these, aid in the success in most grant awards along with other factors such as Benefit Cost Analysis (BCA).

Joint Agency Partnership - A number of the drainage facilities in Tomball overlap jurisdictions providing mutual benefit for entities such as TxDOT, Harris County, Harris County Flood Control District. This could provide opportunities for joint project implementation and cost sharing.

Drainage Impact Fee – Drainage impact fees are permissible under the guidelines and procedures defined in Local Government Code, Title 12, Planning and Development, Chapter 395, Financing Capital Improvements Required by New Development in Municipalities, Counties, and Certain Other Local Governments. Currently, as of 2024, the City of Tomball has established Drainage Impact Fees for four (4) basins, which were adopted on June 10, 2009. Currently, the City has indicated a desire to change, modify or eliminate the current basin impact fee schedule.

These current fees are listed in **Table 1-2**.

TABLE 1-2. CITY OF TOMBALL CURRENT BASIN IMPACT FEES

Basin	Impact Fee (\$ / acre)
M118	\$6,023.00
M121East	\$6,828.71
M121West	\$4,985.14
M125	\$574.40

2.0 INTRODUCTION

2.1 Scope

The City of Tomball (City) is a fast-growing municipality in northwest Harris County, about 40 miles north of Houston, accessible via State Highway 249 and FM 2920. The City is comprised of approximately 12 square miles of land within the city limits with additional developable land in its extra-territorial jurisdiction.

Tomball has a population of about 13,500 people and daily visitor traffic of about 30,000. Recent developments include new residential and commercial centers and the expansion of major roadways. The City is expected to continue to grow, both in population and economic vitality, resulting in the need for additional drainage infrastructure improvements. The previous City of Tomball drainage master plan was published in 2014 and does not reflect current conditions. The combination of the age of the previous master drainage study, anticipated City growth, latest methodologies and technologies, and drainage improvements since the previous master plan requires that a new drainage master plan be developed.

The objective of this study is to develop a comprehensive Drainage Master Plan (DMP) and make recommendations of needed capital projects to address existing and future drainage issues, drainage infrastructure needs, and flood relief. In addition, this study will investigate and update the current drainage impact fee structure. The resulting drainage master plan and the recommended drainage impact fee and stormwater utility fee structure will provide sufficient information for the City to plan, fund, and implement future drainage / flood control. This effort shall be in conformance with Local Government Code, Title 12, Planning and Development, Chapter 395, Financing Capital Improvements Required by New Development in Municipalities, Counties, and Certain Other Local Governments.

2.2 Design Criteria

The Tomball DMP analyses were developed utilizing standard accepted engineering methodologies and practices for hydrology and hydraulics. The larger basin hydrology was performed in accordance with Harris County Flood Control District (HCFCD) hydrologic methods. Localized analyses were performed utilizing the updated City criteria presented within this study. Hydraulics analyses were performed using accepted engineering methodologies, calculations, and public domain hydraulic software.

2.3 Project Study Area

The project study area covers the City of Tomball corporate boundaries (City limits) and extraterritorial jurisdiction (ETJ), as shown in **Figure 2-1**. The City of Tomball covers a total area of 36.67 square miles. The City is located within the Spring Creek and Willow Creek watersheds. The topography of the study area is typical of areas located in the Gulf Coastal

Plan. It is generally flat, sloping gently towards receiving drainage ditches and streams. The flat topography imposes problems on the design of practical drainage systems because the hydraulic grades for drainage ditches are limited. Further, the southern portions of the City are located within the natural “Willow Flats” area of Willow Creek Watershed, which includes flat overland flow paths without any naturally defined drainage ditches or conveyance systems. Over the past few decades, the City as a solo agency and in cooperation with Harris County Flood Control District (HCFCD) has added some drainage infrastructure to aid in providing conveyance systems to this area.

The watershed boundary within the City is generally located along FM 2920 (Main St.). North of FM 2920, the general overland slopes from south to north. South of FM 2920, the overland generally slopes from north to south.

The urbanized portion of the City is primarily served by roadside ditches with some of the newer roadways utilizing storm sewer systems. Open drainage ditches serve as the primary outfall channels for the City and its internal drainage systems. These ditches outfall either directly into, or into a lateral of, Willow Creek or Spring Creek.

2.4 Project Description

This Drainage Master Plan is presented based an evaluation of the existing drainage infrastructure within the City and its ETJ, relief of existing flooding and drainage problems, and future infrastructure needs to accommodate the roadway improvement and City’s growth demands. Several factors were considered in evaluating the existing drainage infrastructure, identifying flooding problem areas, inadequate drainage systems, and determining optimal drainage improvements. These include:

- Historical documented flooding areas obtained from the City, County, and public.
- Public infrastructure areas that are considered high flood risk, as identified by the City and Harris County.
- Current and future roadway / drainage infrastructure projects by the City of Tomball and Harris County.
- Previously constructed, on-going, and future drainage CIP projects by City of Tomball and Harris County Flood Control District.

2.5 Design Criteria and References

The hydrologic and hydraulic analyses were performed in accordance with the methodology and procedures established in the following documents:

- *City of Tomball Community Development Department Minimum Standards for Stormwater Drainage Design* adopted September 6, 2011.

- *City of Tomball Infrastructure Master Plan & Capital Recovery Fee Determination 2012 to 2022* dated April 2014 by CLR, Inc., Gunda Corporation, and Rydan & Associates LLC.
- *Hydraulic Design Manual*, Texas Department of Transportation, Revised September 2019.
- *Harris County Initial Countywide FIS Study*, effective date September 28, 1990.
- Flood Insurance Study Harris County, Texas and Incorporated Areas, FEMA, Effective August 18, 2007, (updated various dates thru 10th Revision dated 11/15/2019).
- Flood Insurance Study Montgomery County, Texas and Incorporated Areas, FEMA, Effective August 18, 2014.
- Google Earth imagery for Harris & Montgomery Counties.
- USDA National Agriculture Imagery Program (NAIP) aerial imagery dated 2022.
- NOAA Atlas 14 “Precipitation-Frequency Atlas of the United States”, Volume 11, Version 2.0 – Texas, dated September 27, 2018.
- 2018 Upper Coast LiDAR topography DEM – 1 m resolution, NAVD88 vertical datum, March 2018 acquisition, Strategic Mapping Program (Stratmap), TNRI.org.

2.6 Project Datum

The project datum for the drainage study is referenced to the North American Vertical Datum (NAVD) of 1988, 2001 adjustment. This vertical datum correlates with the current LiDAR topography and the FEMA effective modeling for Harris County and City of Tomball. The project horizontal datum is referenced to the Texas State Plane coordinate system, Texas South Central (FIPS 4204), feet. The project surface adjustment factor is 1.00013 (grid to surface).

2.7 City Infrastructure Master Plan

As part of the drainage master plan, the proposed population growth, development patterns, and roadway infrastructure improvements were considered for the proposed alternative scenarios so that drainage infrastructure can be planned to accommodate the future needs of the City.

2.7.1 Major Thoroughfare Plan

Major thoroughfare plan (MTP) is developed and used as a planning tool to identify new roadway connections and existing roadway infrastructure updates proposed to meet the community needs. These plans identify a functional classification or hierarchy system to designate a roadway’s role within the local and regional transportation network.

The current City of Tomball MTP used for this study is dated May 17, 2021. This MTP encompasses the City boundaries and its ETJ. The adjacent current 2023 City of Houston MTP was adopted by Houston City Council on September 27, 2023.

The MTPs were used to ensure that any future new roadway or widening has drainage infrastructure planned to accommodate the roadway's storm sewer depths and outfall requirements.

2.7.2 Parks Master Plan

The City parks master plan includes the listing of the existing parks and planning for future development of new parks. Currently the City owns approximately 43.5 acres of developed park land. There are also three (3) Harris County parks within the City and its ETJ.

There is potential for dual use of park land with drainage in the form of detention facilities. Other dual usage or shared areas include trails along channels and detention facilities banks. Coordination of the City's future Parks Master Plan should be performed with the implementation of drainage improvements to identify potential for partnership and dual-use. Such locations include the HCFCD J131-01-00 improvements and Broussard Park or the addition of a park facility within proposed detention facilities.

2.7.3 Population Growth/ Forecasting

The current approved City Master Infrastructure Plan was utilized to identify areas within the City and ETJ that will potentially experience development growth in the near future. Associated within population growth and forecasting include the basin impact fees and improvement prioritization.

2.8 Definition

- Watershed – Area draining to a main channel such as Spring Creek or Willow Creek. These streams are designated as individual watersheds within HCFCD.
- Basins – Area draining to a tributary of the main stem. Alternatively, a subwatershed to the HCFCD watersheds. The basin areas represent the drainage areas of the City's primary drainage channels.
- Sub-basin or catchment – Small drainage areas within the Basin areas that are collected by small ditches or storm sewer systems.
- FEMA – Federal Emergency Management Agency.
- HCFCD – Harris County Flood Control District.
 - HCFCD is a special purpose district created by the Texas Legislature in 1937. The HCFCD jurisdictional boundaries coincide with Harris County. The HCFCD does not issue development permits, does not act as floodplain administrator in the NFIP, and has limited regulatory jurisdiction over drainage and flood-related matters in Harris County.

2.9 FEMA Effective Floodplain

The City of Tomball is a participating municipality within the National Flood Insurance Program. The effective mapping and detail modeling for the flood hazard areas within the City correlate with Harris County and Montgomery County, Texas.

The initial CCO for the City of Tomball was dated May 1976 with the final CCO dated June 1984. The initial countywide FIS effective date was September 28, 1990.

The current effective remapping was updated as part of the TSARP investigations performed between 2001 and 2004. The corresponding FIS and FIRM mapping are dated effective June 18, 2007. This current effective mapping has been updated various times for Harris County through the tenth revision dated November 15, 2019.

The City limits and ETJ are encompassed on FEMA FIRM Panels No. 48201-220L, 240M, 235M, 230L, 210L within Harris County, and 48339C-0515G, 495G, and 675G within Montgomery County.

The City of Tomball initial hydrologic and hydraulic analyses for the original Flood Insurance Study (FIS), effective December 18, 1984 were prepared by the Galveston District COE for FEMA under Inter-Agency Agreement No. H-10-77, Project Order No. 1 and amendments thereto. That work was completed in June 1982. Portions of the analyses were updated by the HCFCD to reflect rapid development and improvements made to the watersheds. That work was completed in September 1983.

2.10 Agency Coordination and Public Outreach

As part of the DMP efforts, CSE assisted City Staff with conducting multiple meetings with outside agencies such as HCFCD, HC Precinct 3, HC Precinct 4, and TxDOT. These agencies' available studies, planning, plans, and projects related to the City's drainage infrastructure planning were also included within the coordination efforts.

CSE performed a public meeting in February 2025 to present the drainage master plan to the public and City Council. Additional public meetings for the drainage impact fee study were not conducted at the direction of City Staff.

2.10.1 Public Meeting – February 3rd, 2025

CSE presented a brief overview of the investigations, analyses, findings, and capital improvement projects that address the City's drainage infrastructure needs during a City Council Workshop. This presentation included a roadmap of the hydrologic and hydraulic methodologies used to identify the City's drainage issues, the process used to evaluate alternatives, present selective solutions, as well as provide an overview of the drainage criteria manual updates that are being proposed. The cover sheet for this presentation is provided in **Figure 2-1**.



FIGURE 2-1. DRAINAGE MASTER PLAN CITY COUNCIL PRESENTATION

3.0 GIS APPLICATION

Geographic Information Systems (GIS) provides a powerful workspace for storing, compiling, overlaying, integrating, updating and exchanging, analyzing, displaying, and managing geospatial data. It provides a consistent method for watershed and stream network delineations using digital elevation models (DEMs) of land-surface terrain. GIS provided a vital role, from GIS data manipulation to geospatial data layers creation, in developing this project. This section presents the GIS applications, data, layers, and geodatabases utilized in the project development of the Drainage Master Plan.

ESRI ArcGIS 10.2 was used to facilitate the various engineering workflows required for the project development, including base mapping, topographic data development, drainage system delineations, drainage and hydrologic parameter extraction, hydrologic and hydraulic model development and analyses, and drainage system inventory. The suite of ArcGIS tools utilized for this project include Spatial Analyst, 3D Analyst, ArcHydro, HEC-GeoHMS, HEC-GeoRAS, and other ArcGIS extensions.

Digital base maps were compiled from various sources, such as: City of Tomball, Harris County, Harris County Flood Control District, Houston-Galveston Area Council, Texas Natural Resource Information Systems (TNRIS), TWDB, FEMA, NOAA, and USGS. The available datasets were compiled using conversion, spatial referencing, and integration operations. GIS base map data layers for this project included raster aerial photographs, vector street maps, political boundaries (cities, counties, districts), floodplain delineations, and stream and drainage ditch centerlines.

3.1 Datum and Coordinate System

The common datum, projection, and coordinate system for this project are:

- Horizontal Datum - North American Datum 1983 (NAD83) (Feet)
 - Coordinate System - State Plane Texas South Central: 4204
- Vertical Datum - North American Vertical Datum 1988 (NAVD88)
 - Datum Adjustment – 2001 adjusted

3.2 GIS Feature Layers

As part of the engineering efforts in developing the Drainage Master Plan, a set of GIS data layers were created, which provide a digital version of the Drainage Master Plan. The GIS data layers can be updated by incorporating future drainage projects and provide an easy way to locate drainage features such as:

- Watersheds and Subwatershed Basins
- Drainage Ditch Centerline
- Drainage Detention Basins

- Drainage Ditch Cross-Culvert Structure Inventory Locations
- Existing Storm Sewer Systems
- FEMA Effective Flood Hazard Areas
- Flooding Concerns and Documented Flooding Locations
- Flood Inundation Areas – 100year
- Recorded Repetitive Flood Claim Locations
- Drainage Ditch Capacity Reaches
- Drainage Ditch Improvement Reaches
- Proposed Cross-Culvert Improvement Locations
- Proposed Storm Sewer Improvement Reaches
- Proposed Detention Basins
- Impact Fee Subdivision Tracking Database
- Street Map
- Soil Map
- Land Use Map
- City Boundary
- County Boundary
- Major Thoroughfare Plan Infrastructure
- LiDAR Topography DEM
- Digital Aerial Photos

3.3 LiDAR DEM

Automated extraction of topographic parameters from DEMs has been recognized as a viable alternative to traditional surveys and manual evaluation of topographic maps, particularly as the quality and coverage of DEM data increase. A continuous DEM dataset was developed based on tiled LiDAR datasets obtained from Texas Natural Resource Information System (TNRIS). The referenced dataset includes the 2018 Upper Coast LiDAR topography DEM. This DEM dataset was a part of the Strategic Mapping Program (Stratmap) which has a March 2018 acquisition date. The DEM was produced with a 50 cm resolution and the vertical datum is referenced to NAVD88.

By examining the high-resolution LiDAR DEM imagery, natural streams and drainage ditches are generally well defined by the LIDAR data. However, the DEM required processing for hydrologic analyses by the removal of stream crossings (culverts and bridges), fill associated with development since the LiDAR acquisition date, and the inclusion of existing drainage infrastructure (channel and large trunklines) which were constructed after the LiDAR acquisition date. These modifications were performed within HEC-RAS's RasMapper program as part of terrain modification tools.

The LiDAR DEM dataset for the study area was developed based on the tiled LiDAR datasets obtained from TNRIS. The LiDAR DEM was further refined based on recent construction since the LiDAR acquisition date within the study area, such as the M121-01-00 channel.

3.4 Aerial Photographs

Aerial photographs for the study area were obtained from Texas Natural Resources Information Services (TNRIS). The ortho-imagery dataset was acquired by USGS as part of the National Agriculture Imagery Program (NAIP). The aerial photographs are dated May 2022 and are produced with 60 cm (2.0 foot) resolution. Additional information was collected utilizing Google Earth imagery for Harris County as well as Google Street View.

4.0 HYDROLOGY

4.1 Subwatershed Basins

City of Tomball is divided into multiple subwatershed basins within the Spring Creek and Willow Creek watersheds. These subwatersheds are referenced as “basins” throughout this report. Each basin is served by a mainstem channel with various tributaries, identified by HCFCD unit number nomenclature. The basin name is based on the mainstem channel identification. The City and its ETJ are drained by these basins’ streams and associated tributaries to either the receiving Spring Creek and Willow Creek.

4.2 Major Drainage Basins

The City and its ETJ are located within the Spring Creek and Willow Creek watersheds. The major drainage basins, subwatershed basins of these streams, include:

BASIN MAIN STEM DITCH UNIT NO	MAIN STEM DITCH/ STREAM NAME	BASIN DRAINAGE AREA
WILLOW CREEK WATERSHED		
M100-00-00	WILLOW CREEK	54 sq. mi.
M112-00-00	TRIBUTARY 6.52 TO WILLOW CREEK	2,455 ac
M116-00-00	TRIBUTARY 8.16 TO WILLOW CREEK	1,169 ac
M118-00-00	--	1,013 ac
M121-00-00	LATERALS: M121-01-00 (M121W) & M121-02-00 (M121E)	1,848 ac (M121W - 958 ac & M121E - 647 ac)
M124-00-00	TRIBUTARY 13.50 TO WILLOW CREEK	2,660 ac
M125-00-00	--	787 ac
SPRING CREEK WATERSHED		
J100-00-00	SPRING CREEK	284 sq. mi.
J131-00-00	BOGGS GULLY	2,543 ac
J132-00-00	--	50 ac
J133-00-00	--	248 ac

4.2.1 Willow Creek (HCFCD M100-00-00)

Willow Creek (M100-00-00) is a tributary of Spring Creek. It drains northeastward for a length of approximately 20 miles, from its headwaters west of Tomball to its confluence with Spring Creek. The stream’s watershed encompasses approximately 54 square miles.

4.2.2 Spring Creek (HCFCD J100-00-00)

Spring Creek (J100-00-00) forms the northern boundary of Harris County, bordering Montgomery and Waller Counties. The watershed drains approximately 284 square miles in an easterly direction to its confluence with the West Fork of the San Jacinto River upstream of Lake Houston.

4.3 Drainage Area Delineations

Drainage area delineations for City’s major basins are based on the TSARP hydrologic subarea delineations for Willow Creek and Spring Creek. These basin delineations were refined and subdivided based on high resolution LIDAR topographic data, aerial photography, as-built plans, and field investigations.

4.4 Hydrologic Methods

Multiple hydrologic methods are utilized for flow computations based on drainage area size. These methods, including HCFCD Clark’s Unit Hydrograph Method and Rational Method duplicate the methodologies utilized by Harris County and Harris County Flood Control District. The hydrologic parameters such as flow lengths, slopes, and time of concentrations were developed based on the LiDAR DEM dataset.

4.4.1 HCFCD Clark’s Unit Hydrograph Method

Since the City’s subbasins are incorporated within the HCFCD watershed models, the hydrologic analysis for the subbasins utilized HCFCD methodology and parameter computations. This includes the Clark’s Hydrograph Method within HEC-HMS (v.4.11) to compute the runoff discharges along the streams. The HCFCD parameter computations and methodology were detailed within the HCFCD Hydrology and Hydraulics Guidance Manual (2009) and the HCFCD Policy Criteria & Procedure Manual (2004, updated 2018). The following presents the parameters and supporting calculation methods used for the HCFCD Clark’s Hydrograph Method.

Rainfall depths are based on the “NOAA Atlas 14, Volume 11 Precipitation-Frequency Atlas of the United States, Texas”. The Atlas 14 rainfall depths were obtained from the NOAA Atlas 14 Point Precipitation Frequency Estimates: TX and are published within HCFCD PCPM. The City of Tomball is located within Harris County Region 1. The 24-hour rainfall depths utilized in the hydrologic analysis are presented in **Table 4-1**. For comparison purposes against previously rainfall data, the pre-Atlas 14 rainfall depths are also provided in **Table 4-1**. As shown, the 24-hour rainfall totals have significantly increased for all storm events within the Tomball area. This includes 3.9 inch increase for the 100-year storm event.

TABLE 4-1. RAINFALL DEPTHS: 24-HOUR TOTALS – HARRIS COUNTY, REGION 1

STORM EVENT (YR)	PRE-ATLAS 14 RAINFALL DEPTHS (IN)	ATLAS 14 RAINFALL DEPTHS (IN)
2	4.1	4.8
5	5.8	6.5
10	7.1	8.2
25	9.0	10.9
50	10.6	13.4
100	12.4	16.3
500	17.1	24.2

Land Use of the contributing drainage area was determined from recent aerals. The watershed is mostly developed (88-percent) which consists of a mixture of residential, multi-family, and commercial areas. A significant portion of the watershed has been developed within the past 20 years; therefore, a higher than typical amount of the existing development has on-site detention. The HCFCD parameters account for this development with detention.

Infiltration losses were computed using the Green and Ampt Loss Method with parameters documented within HCFCD effective Clear Creek Watershed HEC-HMS modeling. The loss parameters for the HEC-HMS inputs are provided in **Table 4-2**. The percent impervious for each subarea was determined from aerals.

TABLE 4-2. WATERSHED SOIL DATA

PARAMETER	VALUE
METHOD	Initial Deficit
INITIAL DEFICIT	0.10
SUCTION (IN)	12.45
CONDUCTIVITY (IN/HR)	0.024

Time of Concentrations & Storage (TC, TC&R) parameters were determined by utilizing the HCFCD parameter calculations for the Clark's Method TC&R and TC values. These parameters are listed in **Table 4-3**.

TABLE 4-3. WATERSHED PARAMETER DESCRIPTION

PARAMETER	ID	UNIT
Drainage Area	DA	Sq. Mile
Watershed Length	L	Mile
Length to Centroid	Lca	Mile
Channel Slope	S	Ft/ Mile
Overland Slope	So	Ft/ Mile
Urban Development	DLU	%
Channel Improvement	DCI	%
Channel Conveyance	DCC	%
Ponding	DPP	%
Development Affected by Detention	DET	%
Impervious	IMP	%

4.4.2 Rational Method

Peak discharge for drainage areas smaller than 200 acres were computed using the Rational Method. The Rational Method parameters include the drainage area, runoff coefficient (C-value), time of concentration, and rainfall; Rational Method equation is provided in *Equation 1*.

$$Q = CIA \quad \text{Equation 1}$$

In which: Q (cfs) is the computed peak runoff discharge,
C is the runoff coefficient,
I (in/hr) is the rainfall intensity,
A (ac) is the drainage area

Time of Concentrations were determined by utilizing the a velocity method based on travel time. Travel time for flow path each segment was computed and summed. A ten-minute (10 min) minimum time of concentration was considered for developed drainage areas and 15 minutes for undeveloped drainage areas.

Runoff coefficients (C-value) for the roadway and contributing drainage areas are based on land use types. The drainage area development types and impervious cover were determined and measured from aeriels. The representative imperviousness of each landuse type is shown in **Table 4-4**. Drainage area composite C-values were computed from representative runoff coefficients (C-values).

TABLE 4-4. LAND USE IMPERVIOUSNESS & RUNOFF COEFFICIENTS

Land Use Description	Imp (%)	Runoff Coeff 'C'
Pavement/Sidewalk	100	0.90
Grass/ Undeveloped	0	0.30
Development Strip	65	0.65
Light Industrial	65	0.65
Dense Industrial, Commercial, & Business Districts	80	0.80
Developed w/ Detention	40	0.35
Residential	40	0.50

Rainfall Intensity calculations for the Rational Method are dependent on the time of concentration and the intensity coefficients (e, b, and d), which are storm frequency and location specific. The intensity coefficients were taken from the HCFCD Atlas 14 PCPM IDF Curves Update Technical Memorandum by HDR, Inc. for HCFCD, which are based on rainfall frequency-duration data contained in the NOAA Atlas 14 Point Precipitation Frequency. These values are consistent with Harris County for Region 1, which includes the City of

Tomball. The equation for computing the rainfall intensity is provided in Equation 2. The multiple frequency intensity coefficient values utilized for Tomball are shown in **Table 4-5**.

$$I = \frac{b}{(d+T_c)^e} \quad \text{Equation 2}$$

In which: T_c (min) is the time of concentration,
 I (in/hr) is the rainfall intensity
 e, b, d are coefficients based on rainfall frequency-duration curves

**TABLE 4-5. RATIONAL METHOD E, B, D COEFFICIENTS:
 HARRIS COUNTY, REGION 1**

Coefficient	2-year	5-year	10-year	25-year	50-year	100-year	500-year
e (in)	0.7372	0.7058	0.6819	0.6446	0.617	0.587	0.5111
b	48.27	51.78	54.26	54.97	54.84	53.93	50.89
d (mins)	9.3	8.19	7.44	6.27	5.45	4.53	2.69

Peak Discharges were computed for multiple frequencies including 2-, 5-, 10-, 25-, 50-, and 100-year storm events for contributing drainage areas to each cross-drainage structure.

5.0 HYDRAULICS

5.1 Major Drainage Systems

The City and its ETJ are located within the Spring Creek and Willow Creek watersheds. The major drainage ditches serve as outfall, receiving systems for the City's internal drainage systems. These drainage ditches are listed in **Table 5-1**.

TABLE 5-1. MAJOR DRAINAGE SYSTEMS

DITCH UNIT NO	DITCH/ STREAM NAME	DITCH OWNER	FEMA MAPPING
WILLOW CREEK WATERSHED			
M100-00-00	WILLOW CREEK	HCFC	DETAIL STUDY, AE/FWY
M112-00-00	TRIBUTARY 6.52 TO WILLOW CREEK	HCFC	DETAIL STUDY, AE/FWY
M116-00-00	TRIBUTARY 8.16 TO WILLOW CREEK	HCFC	DETAIL STUDY, AE/FWY
M118-00-00	--	COT	N/A
M121-00-00	--	HCFC	N/A
M121-01-00	M121 WEST	COT	N/A
M121-02-00	M121 EAST	COT	N/A
M124-00-00	TRIBUTARY 13.50 TO WILLOW CREEK	HCFC	DETAIL STUDY, AE/FWY
M125-00-00	--	HCFC	N/A
SPRING CREEK WATERSHED			
J100-00-00	SPRING CREEK	HCFC	DETAIL STUDY, AE/FWY
J131-00-00	BOGGS GULLY	HCFC	DETAIL STUDY, AE/FWY
J131-01-00	TRIBUTARY 1.25 TO BOGGS GULLY	HCFC	DETAIL STUDY, AE/FWY
J132-00-00	--	HCFC	N/A
J133-00-00	--	HCFC	N/A

5.2 Hydraulic Methodologies

Hydraulic methods utilized for channel analysis consist of HEC-RAS 1D and/or 2D unsteady modeling. For storm sewer analysis, various methods can be utilized, including steady and unsteady state methods. The steady state methods, such as GeoPAK, ORD DU, HouStorm, StormCAD, and spreadsheet, are to be utilized for design capacity and HGL calculations. Unsteady methods, including programs such as EPA-SWMM, XP-SWMM, and ICM, are utilized for analysis calculations and extreme event (100-year) design computations. This DMP utilized 1D/2D HEC-RAS, EPA-SWMM, and spreadsheet storm sewer calculations for determination of existing and proposed drainage systems.

5.3 Overall 2d HEC-RAS Model

The City overall area was analyzed using a 2D HEC-RAS model to determine overland flood patterns, potential flooding problematic areas, and identify locations of ponding and inundation. The 2D HEC-RAS model utilized a rain-on-mesh in conjunction with landuse and

soils to determine runoff volumes. **Figures 5-1 and 5-2** illustrate the 2D modeling mesh utilized for the overall Tomball modeling.

The terrain model for the 2D HEC-RAS model was generated from the 2018 LiDAR DEM. Modifications to the terrain model were performed to better represent the existing drainage and infrastructure within the City. These modifications included cutting through roadways to represent cross-culverts, incorporating construction such as subdivisions since the LiDAR flight, and cutting the terrain to represent major drainage facilities (eg. channels and large boxes). Breaklines were utilized within the mesh to represent high points and flow path locations as well as to coordinate the mesh faces with the direction of flow along channels and significant flow paths.




FIGURE 5-1. 100-YEAR PEAK INUNDATION DEPTHS




FIGURE 5-2. 100-YEAR PEAK INUNDATION DEPTHS OVERLAID ON LIDAR TOPO

6.0 FLOOD RISK AREAS


Flood risk areas are identified by various methods. These include detailed hydraulic modeling, inundation mapping based on modeling, residential complaints and reporting, FEMA flood claim records, historic rainfall events and highwater marks, and City personnel input and identification of areas. Additionally, future infrastructure improvements, major thoroughfare plan, and critical infrastructure (hospitals, emergency response facilities) were considered within the assessment for this Drainage Master Plan.

6.1 Historic Flooding Events

Tomball has experienced numerous flooding events. As part of the study, repetitive flood losses, reported street floodings, and recorded highwater were utilized to aid in the identification of flood problematic areas. As part of recent historic rainfall events, HCFCD recorded information within Harris County, including the Tomball area. These include Tax Day April 2016, Tropical Storm Allison June 5 – 9, 2001 and Hurricane Harvey August 25 – 29, 2017.

6.1.1 Tropical Storm Allison: June 5 – 9, 2001

TS Allison rainfall totals, as documented within *Off the Charts! The Tropical Storm Allison Public Report* by HCFCD, included a 12-hour peak rainfall of 10-12 inches within the Tomball area. The rainfall totals for the storm event are illustrated in **Figure 6-1**.



6.1.2 Memorial Day Flood: May 27, 2016

The 24 Hour Rainfall Totals – Storm Frequency (Source HCFCO), are shown in the following figures for the Memorial Day, May 2016 flood. Within the Tomball area, 9 – 11 inches were recorded. For a 12- hour peak rainfall time duration, this storm represented over a 100-year event (> 1% AEP). The rainfall totals for the storm event are illustrated in **Figure 6-2**.





FIGURE 6-2. MEMORIAL DAY FLOOD RAINFALL

6.1.3 Hurricane Harvey: August 27 – 30, 2017

Recent significant events include **Hurricane Harvey**, dated August 27 – 30, 2017. Within the City of Tomball, approximately 347 properties were inundated. The measured 4-day peak rainfall within the City of Tomball for this event exceeded a 1000-year storm event (0.1% AEP). The rainfall totals for the storm event are illustrated in **Figure 6-3**.

Along Willow Creek, record flooding occurred from SH 249 downstream to the stream's confluence with Spring Creek. This flood event surpassed the previous record floods of October 1994 and April (Tax Day) 2016 events. The water levels along Willow Creek exceeded the October 1994 event by 2 – 3 feet. Upstream of SH 249, the water levels were still considered flood stages, but did not exceed previous recorded events of October 1994 and Tax Day 2016 events. At SH 249 in Tomball and downstream reaches, the stream's water levels were generally between the 100-year (1%) and 500-year (0.2%) storm events. Upstream of SH 249, the stream water levels were generally below the 50-year (2%) storm event.

Spring Creek at SH 249 exceeded the previous record flood level of 2016 Memorial Day flood event by approximately 1 foot with flood stages above the 100-year for the majority of the stream's reach.





FIGURE 6-3. HURRICANE HARVEY RAINFALL



6.2 Reported Flooded Streets

The City of Tomball has records of reported street flooding locations for recent storm events. These reports are made by residents and by City police department. The following table lists the street flooding locations reported during Hurricane Harvey, as reported by the City police department.

TABLE 6-1. REPORTED STREET FLOODING LOCATIONS: HARVEY 2017

LOCATIONS <i>(Harvey – August 2017 Storm Event)</i>	
Agg-Persimmon	Tomball Cemetery Road - 22100 block
Streets around Tomball Little League Fields	Zion - 12900 block
Belmont at Cherry	Cherry Laurel at South Cherry
Cherry Street: 1900 block to the 2600 block	Hicks at SH 249
FM 2920 Calvert-Park	South Magnolia - 400 block
FM 2920 - 11200 block	Coral RV Park on South Cherry
Flax Court	29200 Quinn
Persimmon - 1100 block	Main and Peach
Holderrieth at SH 249	Huffsmith-Kohrville and Mahaffey
Hicks - 1500 block	SH 249 at the Spring Creek Bridge
Huffsmith-Kohrville - 22300 block	14128 Buckingham Lane
Lawrence - 900 block	Dartford Square - 1100 South Cherry
Lovett-Carrell	200 West Main
Holderrieth at South Cherry	

A recent storm event occurred on May 2, 2024, which included approximately 4.9 – 5.7 inches within 6 hours within the City. This equated to an approximate 10- to 25-year storm event. The City provided the following locations as reported street flooding locations.

TABLE 6-2. REPORTED STREET FLOODING LOCATIONS: MAY 2, 2024

LOCATIONS	FLOODING DESCRIPTIONS
300 Belmont St	Water to Bottom of Vehicles
300 Willowick St	Roadway Flooded
11200 FM 2920 Rd	Eastbound Lane Submerged
Hicks East Of Tomball Pkwy	Approx 1 Foot of Water in Roadway
Calvert/FM 2920	Standing Water
Surrey Ct / Lovett St	Roadway Fully Under Water; Cars Submerged
Agg Rd / Medical Complex	High Water
FM 2920/FM 2978 SW Corner	High Water – Lanes Submerged; Drivers Having To Use Outside Lanes
Agg Rd Between S Persimmon & S Cherry St	Water Covering the Road
Pine St / Oxford	High Water
Holderreith / S Cherry	Water Impassable
Holderreith at SH 249 & from Railroad to Huffsmith-Kohrville	Shutdown From Construction Crew
400 Holderrieth Blvd	Water on Road
100 School St	Submerged
S Magnolia / James St	Roadway Underwater
Tomball Pkwy/Hicks	2 Ft of Water on Roadway
Fm 2920 / Calvert	Westbound Lanes Unpassable
S Persimmon @ Medical Complex N And S	Underwater Northbound & Southbound lanes
Lovett / Misty Meadows	Water In Roadway

7.0 MITIGATION / IMPROVEMENTS STRATEGIES

A comprehensive and systematic approach is required to effectively investigate and provide improvement strategies to reduce the existing flood risks within flood-prone areas. This approach includes investigating the individual components of the overall drainage system, analyzing deficiencies and adequacies within the system, and proposed alternative improvements and mitigation strategies to provide flooding relief, reduce damages, and implement drainage infrastructure for future needs. As part of the Drainage Master Plan, each basin was analyzed to determine the associated flood risks and inadequacies for existing and future conditions.

The improvements were analyzed as individual components and then combined into overall alternative scenarios to provide a comprehensive and cohesive drainage system for each basin. It is imperative that all these components are assessed collectively as a cohesive system scenario to ensure comprehensive flood risk management. By addressing each aspect of the drainage and flood mitigation infrastructure, the City of Tomball can significantly enhance its resilience to flooding and protect its residents and assets. The proposed alternative scenarios are developed and presented to aid in developing the City's infrastructure planning and capital improvement program.

7.1 Improvement Components

The individual drainage improvement elements considered and/or analyzed as part of this study include:

1. **Channel Improvements:** Enhance the capacity of outfall channels by widening and deepening them to improve flow efficiency.
2. **Flow Diversion:** Construct new diversion channels to redirect excess stormwater away from critical areas.
3. **Lateral Ditch Improvements:** Improve lateral ditches to handle larger volumes of runoff and enhance overall drainage efficiency.
4. **Major Storm Sewer Corridors:** Construct large storm sewer systems along major roadways to provide conveyance corridors with adequate capacity to handle adjacent contributing areas and improvements during significant storm events.
5. **Regional Detention Basin (RDF):** Build regional detention basins to attenuate peak flows, reduce water surface elevations along a drainage system, and reduce peak flow impacts to receiving channels. Facilities can be utilized
6. **Backflow Prevention Devices:** Install backflow prevention devices at outfall channels to prevent reverse flows from floodway systems into local drainage systems.
7. **Stream Crossing Modifications:** Modify stream hydraulic crossing structures to improve their capacity and reduce flood risks.

8. **Regular Maintenance Programs:** Implement regular maintenance programs for all drainage infrastructure to ensure optimal performance and prevent blockages.
9. **Integration of Green Infrastructure:** Integrate green infrastructure solutions, such as bioswales, rain gardens, and permeable pavements, to increase infiltration and reduce surface runoff.
10. **Enforcement of Floodplain Management Regulations:** Enforce strict floodplain management regulations to control development and minimize flood risks in vulnerable areas.
11. **Zoning Ordinances:** Implement zoning ordinances that restrict development in high-risk flood areas and promote the use of open spaces for flood mitigation.
12. **Early Flood Warning System:** Develop and deploy an early flood warning system to provide real-time data and alerts, allowing for timely evacuation and flood response actions.
13. **Optimized Operation/Diversion Policy:** Develop a dynamic diversion/splitting policy to optimize real-time operation of the flow splitting rule between North Floodway and Arroyo Colorado.

Additionally, various alternative mitigation measures were evaluated to reduce flood inundation within identified flood-prone areas. These measures include:

- Enhancing outfall channels to improve flow efficiency and capacity.
- Implement City's updated storm sewer criteria enhancements, including 25-year storm sewer design.
- Constructing regional detention basins (RDF) to attenuate peak flows and reduce the burden on the outfall systems.
- Modifying stream crossings to reduce excessive head loss and align with the channel design conveyance capacity.

Proposed mitigation and improvement measures developed as part of the drainage master plan are presented for each basin in the following sections.

7.2 Proposed Alternatives and CIP

The proposed alternatives for each basin are described in the following Basin Sections. Additionally, each basin alternative scenario is presented in the exhibits and appendices with cost.

7.3 Challenges with Implementing CIP Projects

This DMP is a planning level study meant as a comprehensive evaluation of the existing drainage conditions throughout the city to develop alternative improvements to adequately address the City's drainage infrastructure needs. Preliminary design and final engineering efforts to address the identified problems and implement these CIP projects will encounter

general challenges. Overcoming these challenges will require further research and design efforts. General challenges facing these CIP projects are listed below.

- Avoidance and/or relocation of existing public utilities (water, wastewater, natural gas)
- Avoidance and/or relocation of underground, private utilities (telecommunication)
- Avoidance and/or relocation of oil/gas petrochemical facilities (pipelines, wells, etc.)
- Limitations during construction activities due to overhead facilities
- Traffic control during construction around existing development may limit access and require longer schedules due to phased construction approaches
- Acquisition of right-of-way and/or easements for drainage improvements
- Additional maintenance of new or improvement drainage infrastructure

8.0 M116 BASIN

The M116 Basin represents the contributing drainage area to the M116 channel (HCFCD M116-00-00), which comprises of approximately 1,168 acres located in the eastern portion of the study area. The basin is located within the City of Tomball, City of Tomball ETJ, and unincorporated Harris County. The M116 basin is generally bounded by FM 2920 (Main Street) to the north and east, Hufsmith-Kohrville Road (HKR) to the west, and Willow Creek (M100-00-00) to the south. The M116 basin generally drains in the northwest to southeast direction towards Willow Creek. The M116 Basin delineation is shown in the Basin Exhibits.

The M116 basin drainage area is served by HCFCD Unit No. M116-00-00, which outfalls to Willow Creek beyond the City's ETJ to the east of the City. The M116 basin is formed from a portion of the TSARP subwatershed M116A_C. Portions of this subwatershed were removed and included within the M118 Basin due to recent development and implementation of the M518 regional detention basin.

8.1 Basin Description

The M116 basin is part of the Willow Creek Watershed. The M116 Basin drainage area is served by HCFCD M116-00-00 channel. The M116-00-00 channel is routed behind Klein ISD Elementary School, east of Willow Creek Estates, and through the County Club Greens subdivision and golf course. The channel reach between Mahaffey Road and County Club Greens is narrow, not located in right-of-way or easement, and does not adhere to current HCFCD standards. Portions through County Club Green include wet amenity features and control structures.

A substantial portion of the contributing drainage area for M116 west of HKR has been diverted to the recently constructed M118 Basin drainage system. As the M118 Basin drainage infrastructure is continued to be constructed, additional contributing area to the M116 Basin will be furthered diverted from west of HKR.

8.1.1 Drainage Inventory

The existing M116 Basin drainage system is served by the mainstem HCFCD M116-00-00 channel. The existing M116 channel is an earthen, trapezoidal shallow channel. The downstream reaches of the channel are overgrown with heavy vegetation and trees. The side slopes are steep with erosion at the cut bank reaches. The channel runs through the Tomball Country Club, running through the golf course lakes, and is crossed by several golf cart bridges. Upstream of Mahaffey Road, the channel has been rectified and widened to provide drainage for adjacent development and the upstream Hufsmith-Kohrville Road outfall.

8.1.2 Crossing Structures

The following table presents the inventory of the drainage crossings within the M116-00-00 Channel.

TABLE 8-1. M116 DRAINAGE CROSSING INVENTORY

Station	Crossing Name	Existing Structure
--	Mahaffey Road	2- 4' x 2' RCB
6869.1	Tomball Country Club Road	3- 90" RCP
6207.1	Golf Cart Bridge	54" RCP
5674.8	Golf Cart Bridge	38' Bridge
5393.0	Golf Cart Bridge	34' Bridge
5125.0	Golf Cart Bridge	32' Bridge
4761.1	Golf Cart Bridge	3- 48" RCP & 2- 30" RCP
4440.6	Shop Access Bridge	48' Bridge
4263.8	Shop Access Bridge	40' Bridge
2717.6	Walden Way	3-36" RCP

8.2 Basin History

Prior to extensive development within the basin, the drainage area consisted mostly of wooded areas within the downstream reaches near Willow Creek and agricultural areas within the upstream reaches. North of Spell Road, the basin extended across Hufsmith-Kohrville Road (HKR) west to South Persimmon Street and north to FM 2920 (Main St.).

Upstream of HKR and north of Mahaffey Road, no defined channel existed and the drainage area generally sheetflowed from north of FM 2920 (Main St) in a south-southeasterly directions towards the HKR and Mahaffey Road intersection. South of Mahaffey Road, small swales and ditches collected and conveyed runoff towards HKR. Small swales and ditches east of HKR directed the flow from HKR eastward towards the M116 channel upper reaches.

Over the past several decades, the basin has experienced extensive changes. These include channel improvements, major crossing structures, and development. The following presents a brief description and timeline of the major changes within the basin.

- Pre 1980:
 - Development within the basin was limited to sparse large residential tracts and agricultural land.
 - Country Club Greens golf course was built along the upper reaches of M116 channel.
- 1986 Comprehensive Plan Update – Extension of the natural channel upstream to HKR with an earthen, six-foot bottom width trapezoidal section. The original M116 basin comprised of a drainage area of 2,074 acres.

- The 1996, 2002, and 2007 Infrastructure Master Plans all proposed the extension of M116-00-00 and some form of detention west of HKR to serve upper portions of the basin.
- The 2009 Medical Complex Drive Preliminary Engineering Report (Segment 5&6) identified segment 6 to continue the Medical Complex Drive from HKR and connect to FM 2920 along Mahaffey Road. The report proposed a detention pond adjacent to Medical Complex Drive to mitigate impacts to M116-00-00.
- In 2011, channel improvements for the upper reaches were improved as part of the Klein ISD Multi-School Site development project.
- In 2011, the culvert crossing at Mahaffey Road was constructed.
- 2012 DMP indicated no future improvements
- M118 Master Drainage Study and M118 Preliminary Engineering Report.
 - Report and proposed drainage improvements presented to divert drainage area west of HKR away from M116 basin towards M118 channel.
- Construction of Medical Complex Drive and S. Persimmons St
 - Roadways were constructed with 100-year capacity storm sewer systems designed to divert flow from M116 Basin to M118 Basin.

8.3 Outside Agency Projects & Coordination

Coordination with Harris County, HCFCD, and TxDOT was performed to identify recent and future projects within the basin. The following project were identified:

- Hufsmith-Kohrville Road (HKR) Road Segment 6 (UPIN 14104MF08T01) – FM 2920 to Mahaffey (recently constructed)
- Hufsmith-Kohrville Road (HKR) Road Segment 5 (future)
- TxDOT State Highway Improvement FM 2978 (CSJ 3050-03-005) (recently constructed)
- HCFCD Coordination Meeting Minutes (March 18, 2024): M116-00-00 has no identified improvement projects. M500-10-00 Stormwater Detention Basin is flood reduction project located upstream of the confluence of M116-00-00 and M100-00-00.
- HC Pct 3 Coordination Meeting Minutes (March 26, 2024): Mahaffey Road is not currently in their CIP.

8.4 Drainage Issues & Problematic Areas

The primary sources of house and road flooding in the M116 basin include:

- Rising water from Willow Creek
- Backwater from Willow Creek into M116 channel, impeding the channel's conveyance capacity

- Limited drainage infrastructure and depth upstream of the golf course.

As the basin continues to transform from rural areas into urban and commercial development, the impacts of the flooding, including roadway inundation, will increase based on the current state of the channel.

8.4.1 Historic Flooding

Since the effective floodplain delineation is located only along the downstream reaches of M116, a majority of the recorded structure floodings have occurred outside of the FEMA floodplain. The major flood events and number of houses flooded within the basin was collected from the City of Tomball and Harris County. These are listed below.

<u>Event</u>	<u>Number of Houses Flooded (estimate)</u>	<u>Rainfall Frequency (year)</u>
October 1994	94	10-25
TS Allison 2001	77	10-25
Tax Day 2016	240	25-100
Memorial Day 2016	130	10-25
Harvey Aug 2017	310 + 200*	50-500+

* Number flooded for the first time on the watershed border east of Huffsmith-Kohrville Road.

8.4.2 Channel Capacity

The channel capacity increases going upstream along the channel from its confluence with Willow Creek. This is due in part to the development relative construction of the channel extension north of Mahaffey Road to HKR. However, the reach between Mahaffey and the golf course is restricted and has limited capacity. Additionally, downstream of the golf course, the channel capacity is dramatically reduced due to the limited channel size and no significant channel improvements or even selective clearing along the reach. Upstream of HKR, the basin has limited to no drainage infrastructure, resulting in shallow swale or sheetflow conditions for drainage.

8.4.3 FM 2920 At HKR Road

City staff has indicated that conveyance from FM 2920 to HKR Road was blocked during the construction of the HKR intersection with FM 2920. A visual inspection of 1978 aerial imagery reveals a cross-culvert under FM 2920 was installed. Historical USGS maps indicate a natural drainage path conveying runoff from the north to south direction and ultimately toward Willow Creek. Current contour elevation data show virtually no slope along the southern roadside ditch of FM 2920, thus both FM 2920 roadside ditches would fill up with water before the spilling eastward toward HKR and continue to HCFCD Channel M116-00-00 and Willow Creek (M100-00-00).

A review of the HKR Segment 6 construction plans called for the removal of the culverts and regarding the FM 2920 southern roadside ditch back to the west. Furthermore, it appears the drainage system along HKR was not programmed to accept any drainage from FM 2920.

From the review of FM 2978 (CSJ 3050-03-005) construction plans, a cross culvert was planned at the FM 2920 intersection, allowing the pass through of the northern FM 2920 roadside ditch. However, upon field reconnaissance, CSE was unable to locate the presence of this culvert.

Therefore, both northern and southern drainage ditches do not have an outfall location. Once both roadside ditches stage up with runoff, contour elevation data suggests the nearest relief is a man-made drainage ditch located on private property that directs the flow to FM 2978 and ultimate Spring Creek. Based on a drainage study in 2009 for private property, the watershed diversion was coordinated with the FM 2978 construction plans and HCFCD.

8.4.4 M116 Channel South of Mahaffey

The M116-00-00 channel south of Mahaffey Road is located between Estates at Willow Creek and Lincoln Manufacturing, Inc. The Estates at Willow Creek plat provided a 140-foot-wide drawing easement adjacent to Mahaffey Road in the northeast corner of the subdivision, however the 11.98-acre Lincoln Manufacturing, Inc. development to the east did not convey a drainage easement. Therefore, the M116-00-00 channel converges into a small, non-conforming ditch upstream of Country Club Greens.

8.5 Proposed Alternatives

Currently, HCFCD has not identified any improvement needs for HCFCD M116-00-00 and does not anticipate any plans within the near future. However, improvements were considered within the basin due to the existing channel limited capacity near Mahaffey Road and no drainage outfall along FM 2920 west of FM 2978

8.5.1 M116-00-00 Channel Improvement/ Re-alignment

The M116 channel crossing at Mahaffey Road has limited capacity, no drainage ROW/ easement, and no defined channel infrastructure downstream (south) of Mahaffey Road to the Country Club Greens. Proposed channel improvements were investigated to provide capacity and outfall depth for this reach. The improvement would accommodate Mahaffey Road and future Medical Complex Blvd expansion as well as any future, adjacent development. The improvement includes re-routing or diverting the M116-00-00 channel to an underground storm sewer along Mahaffey Road eastward to a new downstream channel section. The channel would proceed south to ultimately align with the existing M116-00-00 channel at Country Club Greens subdivision. This will establish a channel conveyance corridor and outfall depth within an easement for future maintenance access.

8.5.2 FM 2920 & FM 2978 Intersection

Area along FM 2920 west of FM 2978 and the highways' intersection do not currently have a drainage outfall. Further coordination meetings with Texas Department of Transportation and Harris County Pct. 3 are required to alleviate the drainage concern and outfall needs. Potential improvements to be explored with the agencies include a cross-culvert under FM 2978 to provide drainage to M112-00-00, connections to FM 2978 storm sewer system, and/or hydraulic connection to HKR roadside ditches to provide an outfall.

9.0 M118 BASIN

The M118 Basin represents the contributing drainage area to the M118 (City Ditch) channel, located in the southeastern portions of the City. The M118 Basin comprises of approximately 1,003 acres. The M118 basin is generally bounded by Burlington Northern and Santa Fe Railroad (BNSF) tracks along the western perimeter, Timkin Road to the north, Tomball ISD facility to the northeast, Hufsmith-Kohrville Road (HKR Road) to the east, and Willow Creek (M100-00-00) to the south. The M118 Basin generally drains in a north to south direction towards Willow Creek. The M118 Basin delineation is shown in the Basin Exhibits.

9.1 Basin Description

The M118 basin is part of the Willow Creek Watershed. The M118 Basin drainage area is served by City's M118-00-00 channel, M118-01-00 trunkline storm sewer within S. Persimmon Street ROW, and City's M518-01 Detention Basin. The M118 channel is routed through the detention basin which outfalls to Willow Creek east of the BNSF tracks and west of Hufsmith-Kohrville Road. The M118 Basin was formed from the upper reaches of M116 Basin and Willow Creek subareas with the construction of the M118 channel and S. Persimmon trunkline.

The M118 Basin was previously not suitable for significant development due to lack of conveyance, drainage ditches, and available outfall depth. Until recently, the M118 Basin consisted mostly of undeveloped rural and agricultural land with scattered rural residential sites. The M118 channel and storm sewer trunkline drainage system was developed to provide drainage for the basin including future roadway infrastructure and development. Upon implementation of the basin drainage systems, development began and can be served by the regional detention basin. Upon construction of the M118 channel and the S. Persimmon trunkline, portions of the previous M116 Basin has redirected into the M118 Basin.

9.1.1 Drainage Inventory

The existing M118 Basin drainage system includes the M518-01 detention basin, M118 channel, and S. Persimmon St. box culvert trunkline. The M518-01 detention facility is located south of Holderrieth Road at the basin's confluence with Willow Creek. The detention facility serves as regional detention for the M118 Basin, providing mitigating storage volume for the construction of the M118 drainage infrastructure (channel and storm sewers) and development within the basin. M118-00-00 is an earthen, trapezoidal channel that extends from the M518-01 basin north past S. Persimmon St. As part of the Persimmon St construction, a dual 10' x 8' RCB trunkline was constructed to provide 100-year conveyance within the basin.

The estimated current volume of M518-01 basin is 287 ac-ft using a static water surface elevation of 137 and a 100-yr water surface elevation of 145.

9.1.2 Crossing Structures

The following table presents the inventory of the drainage crossings within the M118 Channel.

TABLE 9-1. M118 DRAINAGE CROSSING INVENTORY

Ditch ID	Station	Crossing Name	Existing Structure	NBI
M118-00-00	50+90	S. Persimmon Street	3 - 10'x8' RCBs	121020W06008076
M118-00-00	33+82	Holderrieth Road	3 - 10'x8' RCBs	121020W32218079

9.2 Basin History

The primary conveyance vision for the M118 Basin was originally prepared in 1986 as a drainage ditch transversing the service area between BNSF Railroad and Hufsmith-Kohrville Road. Conveyance improvements were continually reported in following studies, however channel improvements began in the mid to late 2000s with construction south of Holderrieth Road. Excavation and removal of the current M518-01 regional detention basin initiated as a third-party borrow pit.

9.2.1 Basin Delineation

Basin Delineations

The M118 Basin is formed from a portion of the TSARP subwatershed M116A_C and the northwestern portion of TSARP subwatershed M110G; refer to HCFCD TSARP Watershed History for subwatershed delineation description. As part of previous drainage studies, the M118 was delineated based on topography, physical/ geometric constraints, development patterns, and planned drainage infrastructure.

M118 Basin drainage areas are based on previous studies, such as the referenced M118 Preliminary Engineering Report 2004, M118 Master Drainage Plan 2012, and S. Persimmons and Medical Complex Blvd Study 2018. Further delineation refinement and subdivision was performed using 2018 LiDAR topographic data, aeriels, existing drainage, field visit and record drawings obtained from City and HCFCD.

Land use was determined based on a combination of City provided Existing Land Use Map, Future Land Use Map, site observations, previous studies, record drawings, and aerial photographs.

Basin Drainage Development

The M118 channel and M518 detention facility were constructed to provide drainage infrastructure and regional detention facility for the future M118 Basin development. Extension of the M118 channel north of Holderrieth Road commenced during the

development of the Tomball Business and Technology Park. As development spurred in upper reaches of the M118 Basin with the use of pumped detention ponds, the need for an ultimate conveyance network cultivated. A secondary conveyance system for the M118 Basin was completed via the S. Persimmon Street storm sewer trunk line, designated as M118-01-00. A CDBG-DR project extended conveyance further north to Lizzie Lane, thus spurring development along the drainage corridor by solving some of the M118 Basin deficiencies.

Changes to the M118 Basin have occurred since the 2018 S. Persimmon St & Medical Complex Blvd Drainage Study. Major changes include the Raburn Reserve development, private development along S. Persimmon Street and within the Tomball Business and Technology Park, Holderrieth Road widening, and continued excavation of the M518-01 stormwater detention basin.

Existing Basin Conditions

The main drainage artery for the basin is the M118-00-00 channel. As previously discussed, the M118-01-00 storm sewer trunk line provided a conveyance solution for upper reaches of the basin. Existing drainage areas were delineated for the entire M118 Basin as shown in Basin Exhibits.

The storm sewer trunk line under S. Persimmon Street, identified as M118-01-00, requires a separated hydraulic analysis to identify flood prone urban areas, overflows, ponding areas, and identification of potential system improvements. The trunkline system was analyzed and sized using EPA-SWMM as part of the roadway project to account for the extreme event sizing for the system as well as the hydrograph attenuation, backwater and HGL restrictions for the project. For this system, the peak flows were generated using the Rational Method based on pre-Atlas 14 rainfall intensities.

Future Basin Conditions

Future basin conditions include roadway improvements within the basin. From coordination with the City and Harris County, these potential infrastructure improvements include:

- Hufsmith-Kohrville Road reconstruction and widening from Willow Creek north to Mahaffey Road. Segments of this roadway within the M118 basin are currently being planned to outfall into the M118 Channel and M118 Basin.
- S. Persimmon Street reconstruction and widening from Medical Complex Blvd north to FM 2920. As part of this roadway improvements, the drainage corridor trunkline system under S. Persimmon will be extended north.
- Agg Road reconstruction and widening from the railroad to S Persimmon St as part of the Medical Complex Blvd major thoroughfare plan.

Additionally, the M118 Basin is expected further land development throughout the basin as drainage infrastructure is provided to accommodate development needs and storm sewer depths.

9.2.2 Basin Development History

The City's future land plan for the M118 Basin highlights an industrial theme and over recent years, the basin has undergone a substantial transformation. These include channel improvements, major roadway improvements, and the implementation of regional detention.

- Pre 1980 – Mainly undeveloped, rural and agricultural land with minimal residential structures.
- Construction of Tomball Business and Technology Park began in 2014 to extend M118-00-00 upstream of Holderrieth Road and expand the M518-01 Basin.
- Construction of S. Persimmon Street & Medical Complex Blvd (E&P 2017-10005) was completed in 2022 for the installation of M118-01-00 storm sewer trunkline system down S. Persimmon Street. This conveyance system included 2-10'X8' RCBs from M118-00-00 up to Medical Complex, 1-10'x8' RCB north of Medical Complex, and 6'x6' RCB's for east and west laterals along Medical Complex for based on pre-Atlas 14 rainfall depths.
- M518-01 Excavation and Removal originally began in the early 2000s allowing third-party contractors to excavate the future detention pond and utilize it as a borrow pit. In 2018, the M518-01 regional detention basin design was modified by changing the basin to a wet-bottom facility, allowing the excavation and removal to continue and increasing the storage volume of the detention basin to 299 acre-feet. Modifications to the detention basin geometry using revised boundary survey provides a design storage volume of 295 acre-feet.
- CDBG Persimmon & Lizzie Lane Drainage Improvements Project (E&P 2019-10015 and GLO 19-076-029-B386) extended the 10' X 8' RCB trunkline system along S. Persimmon Street from Medical Complex Boulevard north to Sutton Lane. Storm sewer was downsized to 54" RCP with vertical drops up to the City's outfall channel excavated as part of Lizzie Lane improvements (E&P 2003-10020) installed in 2004.

9.2.3 Previous Drainage Studies

The following presents a brief description and timeline of the major changes within the basin.

- 1996 Infrastructure Master Plan
- 1999 HCFCD Willow Creek Study did not address M118 as a separate drainage area not did the study recommend improvements for "Ditch C"
- M118-00-00 Drainage Study in the Willow Creek Watershed

- 1986 Comprehensive Plan Update – Identified in the report as “Ditch C”, the M118 Basin has an estimated contributing area of 934 acres generally bound by BNSF tracks to the west, a projection of Lizzie Lane to the north, HKR to the east and Willow Creek to the south. “Ditch C” was planned with a varying bottom width (35 feet to 6 feet) between S. Persimmon Street and HKR up to the projection of Mahaffey Road for a total of 9,200 lineal feet from the mouth of Willow Creek. Bridges were proposed at Agg Road and Holderrieth Road.
- 2002 Infrastructure Master Plan – This plan continued the proposal of the M118-00-00 channel up to the projection of Agg Road as well as implementation of subregional detention for “Ditch C” accounting for 150 acres of development.
- 2004 Preliminary Engineering Report for the Proposed M118-00-00 Channel Alignment was prepared for the proposed detention basin and M118-00-00 Channel extending up to Sutton Lane. The report was unavailable at the time of this report.
- 2007 Infrastructure Master Plan – This plan made no modifications to the proposed channel and subregional detention improvements identified for M118-00-00.
- 2009 Preliminary Engineering Report reanalyzed the M118 Basin to provide conveyance and regional detention to allow for future development with no adverse impacts to Willow Creek. This report delineated the M118 Basin drainage area of 741 acres with similar boundaries, notably the projection of Mahaffey Road as the northern limits of the service area. The report assumed the small lot residential and commercial use for the developed service area. Identified roadway crossings were proposed as bridge crossings instead of multiple box culverts.
- 2009 Medical Complex Drive Preliminary Engineering Report identified Segment 4 of Medical Complex Drive (MCD) to extend from BNSF Railroad to HKR. The report proposed a detention pond parallel to the BNSF tracks as the M118-00-00 channel did not extend up to the limits of the roadway.
- 2012 M118 Drainage Master Plan provided an overview of the M118 Basin characteristics and updated project progress. The report indicated no current flooding issues of concern for the M118 Basin and stated the full capacity of channel and detention facility and channel improvements are not required to serve existing drainage requirements. At the time of this report, the improved channel south of Holderrieth was mostly complete and the TEDC was expected to fund the channel construction north of Holderrieth Road as part of a planned business park.
- 2012 Drainage Master Plan & Capital Recovery Fee Determination identified the M118 Basin consisting of an area of approximately 732 acres. The report stated M118-00-00 channel and detention basin were under construction with the expectation of the channel construction completed by 2014.
- 2014 M118-00-00 Impact Analysis evaluated the phased construction of the M118-00-00 channel and detention basin to drainage and regional detention for future

development west of Hufsmith-Kohrville Road and south of Medical Complex Drive. The analysis proposed the first phase of construction to include the ultimate, dry-bottom detention basin and construction of the channel past S. Persimmon Street. The second and ultimate phase included extension of M118-00-00 up to Medical Complex Drive. The report stated the 230-acre-feet of storage volume fully mitigated impacts of the developed flow to Willow Creek.

- 2018 S. Persimmon St & Medical Complex Blvd Drainage Study modified the conveyance route for the central and upper reaches of M118 Basin by proposing an alternative for an underground 100-yr conveyance network along S. Persimmon Street. This drainage study also expanded the ultimate service area to 980 acres. Furthermore, a 150-foot-wide development strip was incorporated for the M118-01-00 service areas east of S. Persimmon Road south of MCD due to the ultimate M118-00-00 service area extending up to MCD.
- 2021 Willow Creek Watershed Plan Summary Report by HCFCD noted the City of Tomball's ongoing effort to complete the M118-00-00 to assist in reducing flood levels and providing outfall depths for development. M118-00-00 was not identified as a problem area.

9.3 Outside Agency Projects & Agency Coordination

As previously discussed, agency coordination was performed with Harris County and Harris County Flood Control District. The following include the current and future construction activities within the basin area:

- HKR Road Segment 4 (north of Holderrieth Rd to Mahaffey Rd) is in design
 - HC Pct 3 Coordination Meeting Minutes (March 26, 2024): Medical Complex Drive was not programmed to accept Hufsmith-Kohrville road drainage. A separate outfall to M118-00-00 was identified in DMP along an un-improved right-of-way (M118 CIP 7)
- HKR Road Segment 3B (north of Ezekiel Rd to Holderrieth Rd) is in design
- Holderrieth Road Drainage Improvements Project (UPIN 18104MF0R901) is completed
- M500-10-01-E001 – F106 Boudreaux Stormwater Detention Basin is in design
- HC Pct 3 Coordination Meeting Minutes (March 26, 2024): Mahaffey Road is not currently in their CIP.

9.4 Drainage Issues & Problematic Area

Prior to the construction of the M118 channel and Persimmon St. conveyance trunkline system, the natural drainage patterns within the M118 Basin was to drain northwest to southeast towards either M116-00-00 or southerly to Willow Creek via overland sheetflow

and shallow flow paths. Since the basin did not have natural drainage systems, it experienced drainage issues associated with

- Upper reaches of the M118 Basin (Lizzie Lane) lack conveyance and outfall depth
- Tracts that cannot hydraulically connect to M118-01-00 due to the lack of an available outfall until M118-00-00 is extended north

9.4.1 Historic Flooding

The M118 Basin has a history of poor drainage and localized ponding due to the lack of drainage infrastructure. Historic flood and repetitive losses recorded are low in the area, but can be attributed to an overall lack of development.

Upper Reaches (Lizzie Lane)

Older residential lots located along Lizzie Lane experienced ponding, which is due to shallow roadside ditches along Lizzie Lane and no receiving storm sewer or drainage channel. The City's Lizzie Lane project (E&P 2003-10020) proposed an outfall channel south of Lizzie Lane. At the time, this aligned with the proposed M116-00-00 channel alignment documented in the 2002 Infrastructure Master Plan. However, the outfall channel terminated at S. Persimmon Street as the M116-00-00 channel only existed east of Mahaffey Road and did not extend west of Hufsmith-Kohrville Road.

Further improvements were performed for the area as part of a HUD CDBG-DR grant. The grant request was submitted following the 2016 Tax Day and Memorial Day flood events and approved through the Texas GLO. The smaller, more localized drainage areas prohibited storm water from draining effectively during these heavy rainfall events which inundated the drainage system. The funding was provided to improve storm water conveyance and reduce the impact of future flooding. The proposed grant project included extension of the storm sewer trunk line (10'x8' box and 54-inch pipe) as well as roadside ditch improvements up to the existing M118-01-01 channel south of Lizzie Lane.

S. Persimmon Street

S. Persimmon Street was improved as part of the extension of Medical Complex Drive Segment 4B (E&P 2017-10005) from the M118-00-00 Channel crossing up to Medical Complex Drive. Pre-project photographs of S. Persimmon Street show inundated roadside ditches and localized ponding on private property. Based on overland topography, tracts along S. Persimmon Street were in localized low-lying areas.

9.5 Proposed Alternatives

Proposed alternative components investigated include detention basins, storm sewer, and drainage channels. The following present the evaluated proposed components:

- M518-01 Stormwater Detention Basin

- The existing detention facility needs to be configured for final, ultimate storage capacity.
- M118-01-01 Channel Improvements
 - Reconstruction of the existing Lizzie Lane detention facility located just south of Lizzie Lane. The facility will be deepened to provide additional conveyance and storage capacity to serve upper portions of the basin
- M518-02 Stormwater Detention Basin
 - Construct a sub-regional stormwater detention basin to within the upper portions of the M118 Basin to partially reduce impacts to the Persimmon St trunkline system.
- M118-01-00 Persimmon St. trunkline extension
 - Extension of the existing 10' x 8' RCB along Persimmon St from north of Medical Complex Blvd to proposed M518-02 Basin.
- Agg Road/ Pitchford Rd trunklines
 - Storm sewer trunkline proposed along Agg Road west of Persimmon/ Medical Complex Blvd intersection, connecting the area to the S. Persimmon trunkline.
 - Storm sewer trunkline proposed along Pitchford Road to service the western portion of the basin. The trunkline will connect to the proposed Agg Road system.
 - Lateral connections from Pitchford Rd to M118-01-00 were determined to be unfeasible due to capacity restraints in the upper portions of the storm sewer system.
- M118-00-00 Channel extension
 - Existing channel to be extended from Tomball Business and Technology Park north to Medical Complex Blvd. The channel will serve the area between Persimmon St. and Hufsmith-Kohrville Road.

These projects are further detailed below and listed with the coordinated CIP alternative ID number.

9.5.1 (1) M518-01 Detention Basin

Complete excavation, bank construction and final stabilization of the wet-bottom regional detention pond to achieve ultimate storage capacity of 295 acre-feet to serve the entire M118 Basin. The detention pond banks have been modified from the 2018 Original M118 Amenity Lake based on a revised boundary survey and anticipation of Hufsmith-Kohrville Road widening.

9.5.2 (2) M118-00-00 Channel Extension to Medical Complex Drive

Acquire right-of-way and construct the upper reach of M118-00-00 channel from the Tomball Business and Technology Park to Medical Complex Drive to provide outfall depth

and 100-year conveyance. This channel will be connected to upper reaches of the basin with a hydraulic connection to Medical Complex Drive (see M118 CIP #3).

9.5.3 (3) Medical Complex Drive Storm Sewer Extension to M118-00-00

Construct new storm sewer from Medical Complex Drive to the head of M118-00-00 (M118 CIP #2) within an unimproved right-of-way. The storm sewer will provide a secondary outfall for the M118-01-01 trunkline and function as split flow between M118-01-00 and M118-00-00 in an effort to relieve the existing conveyance system along S. Persimmon Street.

9.5.4 (4) M118-01-00 (S. Persimmon) Storm Sewer Extension to Lizzie Lane

Utilizing the existing 54-inch storm sewer previously installed, extend a parallel storm sewer trunkline along S. Persimmon Street from the termination of a 10'x8' RCB (near Sutton Lane) to north of Lizzie Lane. The 10'x7' storm sewer will provide additional conveyance capacity to the upper portions of the basin. Improvements are assumed to take place with roadway reconstruction and expansion.

9.5.5 (5) M118-01-01 Channel Improvements (Phase 1)

Excavate and deepen an existing drainage channel serving Lizzie Lane. Channel improvements will relieve Lizzie Lane during smaller storm events. Replace existing outfall connection to existing 54" storm sewer to provide maximum depth. Phased construction will depend on timing of extension for M118-01-00 storm sewer along S. Persimmon Street (M118 CIP #4) and development to the west. Install ultimate outfall structure and plug barrel(s) as required for future M118 #8.

Replace existing Lizzie Lane cross culverts and hydraulically connect M118-01-01 and M118-01-01 Lateral via culverts.

This project will require coordination with the East Water Plant expansion project.

9.5.6 (6) S. Pitchford Storm Sewer Extension

Construct storm sewer trunkline down S. Pitchford Road to provide conveyance for upper reaches of the M118 Basin. Improvements are assumed to take place with roadway reconstruction.

9.5.7 (7) M118-00-00 Underground Alternate

Based on timing of development and widening of Hufsmith-Kohrville Road, a storm sewer trunkline may replace the M118-00-00 channel extension within the limits of an unimproved right-of-way. Storm sewer would be sized to convey the 100-year design storm event and outfall into the existing M118-00-00 channel at the Tomball Business and Technology Park. This project will require coordination with Harris County Precinct 3.

9.5.8 (8A) M518-02 Detention Basin

Acquire tract south of M118-01-01 and existing CenterPoint transmission towers to partially mitigate runoff impacts on M118-01-00 storm sewer from private development improvements adjacent to the BNSF Railroad. Construct inflow and outflow structures connection M118-01-01 channel and M118-01-00 storm sewer. Service to the upper and westernmost portions of the basin will include storm sewer within an unimproved right-of-way south of Lizzie Lane.

Inclusion of both M518-02 stormwater detention ponds into the ultimate design will provide additional relief for upper portions of the M118 Basin and M118-01-00 storm sewer system.

9.5.9 (8B) M118-01-01 Channel Improvements (Phase 2) and M518-02 Detention Pond

Acquire additional right-of-way to extend Phase 1 M118-01-01 channel west toward BNSF railroad. Acquire or allow private development to construct M518-02 (B) detention facility. Upon construction of ultimate channel and detention improvements, utilize ultimate outflow structure to M118-01-00 storm sewer system.

10.0 M121 BASIN

The M121 Basin represents the contributing drainage area to the M121, M121W, and M121E channels. The M121 Basin encompasses approximately 1848 acres located in the central/southern portions of the study area. The M121 basin is generally bounded by Business 249 to the southwest, Tomball Intermediate School, Tomball Regional Hospital and Lawrence Street to the northwest, FM 2920 to the north, Burlington Northern and Santa Fe Railroad (BNSF) tracks along the east perimeter, and Willow Creek (M100-00-00) to the south. The M121 Basin generally drains from north to south towards Willow Creek. The M121 Basin delineation is shown in the Basin Exhibits.

10.1 Basin Description

The M121 Basin drainage area is served by two north-south lateral channels currently owned by City of Tomball, M121-01-00 (commonly known as M121 West or M121W) and M121-02-00 (commonly known as M121 East or M121E), that diverge into the M121 main stem (HCFCD M121-00-00). The lateral channels (M121W & M121E) subbasins are generally bisected by South Cherry Street. The HCFCD M121-00-00 channel commences at Holderrieth Boulevard. The M121 Basin is formed exclusively from TSARP catchment M100F2. Refer to HCFCD TSARP Watershed History for subwatershed delineation description. The M121 Basin is served by a regional stormwater detention basin M500-01 owned by HCFCD, which was implemented to offset the proposed construction of the M121W (M121-01-00) channel. *The current M500-01 stormwater detention basin has no additional capacity for future development or floodplain mitigation.*

10.1.1 Drainage Inventory

M500-01 is located south of Holderrieth Road adjacent to the City's South Wastewater Treatment Plant and is a dry-bottom detention facility with a temporary outfall structure. M121-00-00 is a natural, moderately vegetated channel commencing at the confluence with M100-00-00 and terminating at the Holderrieth Road bridge structure. M121-01-00 is mostly an earthen, trapezoidal channel except for a portion adjacent to Holderrieth Road where it is lined with concrete. M121-01-01 and M121-01-02 are natural triangular ditches at shallow depths. M121-02-00 is a trapezoidal channel with a wide bottom, lined with concrete adjacent to Holderrieth Road and earthen north of Holderrieth Road.

10.1.2 Crossing Structures

The following table presents the inventory of the drainage crossings within the M121 Basin channels.

TABLE 10-1. M121 DRAINAGE CROSSING INVENTORY

Ditch ID	Station	Crossing Name	Existing Structure	NBI
M121-00-00	2600	Holderrieth Road	Two-Span Bridge	121020AA0659005
M121-01-00	3048	Private Driveway	5 - 10'x8' RCB	None
M121-01-00	4812	Holderrieth Road	5 - 10'x8' RCB	121020W32218108
M121-01-00	6630	Everpine Trail	5 - 10'x8' RCB	121020W38377109
M121-01-00	6882	Drop Structure	Inline Sheet Pile	n/a
M121-01-00	8563	Theiss Lane	3 - 10'x8' RCB	121020W63954110
M121-01-00	11023	Medical Complex Drive	3 - 10'x8' RCB	121020W05947107
M121-02-00	2950	Private Driveway	6 - 6'x7'	None
M121-02-00	4107 4896 5663	Utility Crossings	7 - 36" RCP	None

10.2 Basin History

The conveyance vision for the M121 Basin has existed since the early Comprehensive Plans for the City of Tomball, two lateral channels bisecting the basin. Development within the M121 Basin has been active in recent years following the City's CIP projects for implementing the M121-01-00 channel.

10.2.1 Basin Development History

- Pre 1980 – Old Town Tomball southern limits were developed to Graham Drive and Anna Street with areas south generally undeveloped, rural and agricultural land with minimal residential or commercial structures.
- In 1996, the City entered into an interlocal agreement with Harris County Flood Control District to implement a regional flood control plan. Per the agreement, the City of Tomball will maintain ownership of the M121-01-00 (west channel) and M121-02-00 (east channel), including cost of acquisition. All acquisitions south of Holderrieth Road shall be acquired and owned by Harris County Flood Control District. Furthermore, the Agreement dictates the City of Tomball is responsible for the engineer design and construction of the M121-01-00 and M121-02-00 lateral channel and the M500-01-00 stormwater detention basin. The agreement also states neither HCFCD or the City of Tomball can acquire land adjacent to the M500-01-00 basin property until 600 ac-ft of storage volume has been achieved. Upon completion and acceptance of the channels and detention basin, the District shall assume full ownership of and responsibility of maintenance of the facilities.
- Post 1996 – Segments of M121-01-00 (M121W) channel were constructed by private development (in lieu of on-site detention) as well as multiple City CIP projects. The current condition of the M121-01-00 includes an ultimate channel width and depth from the confluence at M121-00-00 (south of Holderrieth) up to the culvert crossing

at Medical Complex Road. Portions of the channel north of Medical Complex Road were excavated; however, additional depth may be utilized for conveyance.

- Two segments of the M121-02-00 (M121E) channel were constructed by private developments upstream of Holderrieth Road; however, the ultimate channel construction was not achieved. Additionally, the constructed channel was utilized for in-line detention by the adjacent development by plugging 4 of 5 barrels of the driveway culvert crossing just north of Holderrieth Road.
- At the time of this report, the M500-01 stormwater detention basin has not been fully excavated due to environmental constraints within the basin.

10.2.2 Previous Drainage Studies

- 1982 Comprehensive Plan Report
- 1986 Comprehensive Plan Update – The M121 Basin was identified in the report as System “D” with an estimated contributing area of 1,426 acres generally bound by BNSF tracks to the east, Market Street to the north, Holderrieth Blvd to the west and Willow Creek to the south. “Ditch D” included a northerly extension of M121-00-00 across Holderrieth Road with two lateral ditches bisected by South Cherry Street. “Ditch D” continued east and north, generally along the M121-02-00 alignment up to Thesis Road. “Ditch D-1” lateral continued from the confluence west and north, generally along the M121-01-00 alignment up to Hardin Street. Detention for development was not included in the drainage improvement planning.
- 1996 Infrastructure Master Plan (Capital Improvement Plan)
- The 1998 M500-01-00 Detention Facility Final Report identified design related issues with potential jurisdictional wetlands, soil stability, and subsurface petroleum pipelines that impacted the ultimate storage volume capacity of the detention basin.
- 1999 HCFCD Willow Creek Study
- 2002 Infrastructure Master Plan – Both lateral channels, M121-01-00 and M121-02-00 were still in planning stages. M121-01-00 (identified as Ditch “D-1”, or M121 West) was realigned south of Holderrieth Road before the confluence with M121-00-00. M121-02-00 (identified as Ditch “D”, or M121 East) remained planned as a northern extension of M121-00-00. M500-01 detention facility was planned as sub-regional detention, not full regional detention. Construction plans for M500-01 were in review of HCFCD.
- 2004 Preliminary Engineering Report for the Proposed M121-00-00
- 2007 Infrastructure Master Plan
- 2009 M121 Preliminary Engineering Report
 - Recommended channel improvements allowing for full development in the M121 basin. A major portion (volume) of M500 (M121 Detention - 258.38 acres) had been excavated by private parties under contract with HCFCD who

owns and administers this facility. The proposed improvements were constructed to alleviate localized flooding and to provide drainage infrastructure for new development in this area while eliminating the need for on-site stormwater detention.

- 2009 Medical Complex Drive Preliminary Engineering Report
- 2012 Drainage System Impact Analysis Report
- 2012 Drainage Master Plan & Capital Recovery Fee Determination
- 2018 M121 West Channel Drainage Study was a supplement to the 2009 M121 Preliminary Engineering Report and 2012 M121 Drainage System Impact Analysis Report.
- 2021 Willow Creek Watershed Plan Summary Report

10.3 Outside Agency Projects & Agency Coordination

The M500-01-00 stormwater detention facility was originally a part of an interlocal agreement with HCFCD. The development agreement included details of the purchasing and ownership of the channels and detention basins within the watershed, as previously described within this section.

Harris County Flood Control District is in the preliminary design phase of implementing the M120 Stormwater Detention Facility downstream of the M121 Basin. Per the Willow Creek Watershed Plan Summary Report, selective clearing and implementation of the M120 facility are recommended and two sites within the M121 Basin adjacent to M100-00-00 (Willow Creek) were identified as potential opportunities for detention, floodplain preservation and habitat preservation. These two locations are similarly identified in this report as M521-01 and M521-02.

10.4 Drainage Issues & Problematic Area

Prior to the implementation of the M500-01 based and M121-01-00 lateral, the M121 basin has a history of poor drainage due to the floodplain of Willow Creek and lack of available outfall depth to spur urbanization. Prior to the M121-01-00 construction, portions of the channel were being pumped during and after small rain events as a hydraulic connection did not exist due to the presence of underground oil/gas pipelines and existing roadways.

M121-02-00 service area is facing similar issues by lacking a feasible outfall and natural drainage path to incite development. Much of the M121-02-00 service area between Agg Road, S. Cherry Street, and Holderrieth Road is drained via overland sheet flow.

10.4.1 Historic Flooding

The M121 Basin has a history of poor drainage until the implementation of the M500-01 basin and construction of the M121-01-00 channel. The area along Holderrieth Road is still susceptible to flooding from Willow Creek. Specific problematic locations include:

S. Cherry Street

S. Cherry Street two-lane asphalt roadway owned by Harris County Precinct 3 with shallow roadside ditches. Side streets along this minor arterial are typically two-lane asphalt roads with roadside ditches. Due to lack of depth for conveyance to M121-01-00, the roadside ditches lack capacity to convey runoff.

Magnolia Street

Per LiDAR, Magnolia Street is relatively lower than the adjacent north-south streets contributing to M121-01-00 in the Old Town Area. During recent rain events, it is evident that the roadside ditches gradually drain toward Magnolia Street. When the roadside ditches were observed bank full, the overflow was generally directed down Pine Street toward Hardin Street ditch.

Belmont Street (Keystone Townhomes)

Belmont Street west of S. Cherry Street experiences constant flooding. Belmont Street is situated lower than S. Cherry Street, therefore lacking the hydraulic head to convey runoff underground away from the pavement and structures. Existing storm sewer consists of 17-in x 13-in arched pipe. A flap gate was installed on the existing storm sewer outfall to prevent S. Cherry Street roadside ditches from backing up into the development. The townhomes require constant pumping to prevent structural flooding.

Cherry Place Court (Cherry Laurel Ln, Juniper Ct, and Hawthorne Ct)

Cherry Laurel Drive has two storm sewer outfalls: east outfall at S. Cherry Street (24-inch pipe) and west outfall at S. Pine Street (19-inch x 30-inch arched pipe). Lack of outfall depth in the S. Cherry Street and S. Pine Street roadside ditches results in the neighborhood regularly being inundated even during smaller storm events. Cherry Laurel Street also has small grate inlets along the north side of the street, which do not meet current design criteria and are significantly smaller than needed. Juniper Ct and Hawthorne Ct have a curb cut opening to outfall into the existing Hardin Street ditch. Due to the limited outfall depth, large storm events have the potential pond within the cul-de-sacs.

BNSF Railroad Cross Culvert Overflow

The BNSF Mainline has a cross culvert located approximately 400 feet south of the CenterPoint Energy substation spur. Overflow from the east side of the tracks (upper portions of the M118 Basin) spills into the M121 Basin behind St. Anne's Catholic Church and ultimately down Mulberry, causing street ponding along Mulberry and Agg Road.

M121-02-00 (Eastern Lateral)

Downstream reaches of the M121-02-00 channel have been built by private development. The original construction of M121-02-00 was utilized for in-line detention due to lack of regional detention volume availability in M500-01. Only one of the six cross culverts at the

time of original development was opened with the remainder plugged. Utility crossings of the channel were left in place and not lowered to the ultimate depth, therefore restricting the conveyance capacity of the channel. Recent development north included an extension of the M121-02-00 channel and modification of the 6 – 6'x7' culvert crossing.

Agg Road

Agg Road is a two-lane asphalt roadway with shallow roadside ditches. Per the City's MTFP and the Medical Complex PER, this major arterial is to be widened. Shallow ditches have the potential to cause roadway base failures. A private stormwater detention facility serving Cherry Meadows Subdivision is located on the south side of Agg Road. This facility includes a pumped discharge into the roadside ditch and causes street ponding.

Thesis Lane

The contributing area for Thesis Lane includes Johnson Road and Tomball Industrial Park. The cross culvert under Thesis Lane (2 – 4'x2' boxes) are located adjacent to the Thesis Attaway Nature Center. These cross culverts are undersized to convey this contributing area and currently direct runoff south behind Walmart and Woodleaf Reserve before entering the M121-01-00 channel.

10.5 Proposed Alternatives

Proposed alternative components investigate expansion and construction of new detention facilities, storm sewer improvements, and reconstruction/construction of drainage channels. The following presents the evaluated proposed components:

- M500-01 Stormwater Detention Basin
 - Completion of the original basin design intent was to provide 600 ac-ft of storage volume, per the Interlocal Agreement with HCFCD, and reconstruct the facility to a wet-bottom pond to increase storage capacity.
- M521-01 and M521-02 Stormwater Detention Basin
 - M521-01 Basin is intended to mitigate the improvements of the M121-02-00 ultimate channel to offset any potential adverse impact to M100-00-00 (Willow Creek). A large portion of the excavation has been completed as part of a private mining operation; however, the existing pit is currently privately owned will require acquisition and conversion to a basin configuration.
 - M521-02 Basin is addition stormwater detention facility proposed to provide additional regional detention, provide floodplain preservation, and contribute to the City's Master Park Plan including recreational activities. This basin location has also been identified by HCFCD as part of Willow Creek's overall flood reduction plan.

- M121-01-01 and M121-01-02 Sub Lateral Channels
 - Formally known as the “Hardin Street Ditch”, these sub lateral channels provide additional outfall depth opportunity for upstream improvements to hydraulically connect to the M121-01-00 channel.
- Old Town Storm Sewer Improvements
 - Construct storm sewer systems to relieve the southern portions of Old Town Tomball and reduce the area that is prone to localized ponding.
- S. Cherry Street Trunkline Systems
 - Construct storm sewer improvements such that S. Cherry Street will convey the appropriate design storm event and connect to the M121-01-00 and M121-02-00 channels.
 - S. Cherry Street improvements south of Medical Complex Drive and Agg Road have an opportunity to connect to either M121-01-00 or M121-02-00 due to recent upgrades for Holderrieth Road. Due to cover constraints along Thesis Road, which is generally draining from west to east, an outfall to M121-01-00 is not a feasible solution due to likely storm sewer cover constraints.
- Mulberry Storm Sewer Improvements
 - Construct storm sewer improvements along Mulberry to provide a relief from the BNSF cross-culvert overflow and a gravity outfall opportunity for the Copper Cove development.
- Thesis Lane Storm Sewer Improvements
 - Construct storm sewer improvements to direct stormwater toward the M121-01-00 channel.

10.5.1 (1) M500-01-00 Detention Pond Improvements (Ultimate Condition)

M500-01-00 Detention Pond is a regional facility that was originally constructed as part of a phased approach for the M121 Basin during the implementation of M121-01-00 west lateral. Portions of the detention facility have been excavated to serve as a dry-bottom detention pond and a temporary outfall pipe has been installed in the southeast corner of the pond.

The ultimate strategy for the M500-01 detention pond is to reconstruct the existing facility to a wet-bottom detention pond with the permanent outflow structure and emergency spillway in the southeast corner adjacent to M100-00-00 (Willow Creek). Reconstruction includes removal of an existing peninsula adjacent to the South Wastewater Plant and bank repair along northern boundaries of the pond. Environmentally sensitive areas within the pond exist from previous jurisdictional determinations and will need to be accounted for in the

ultimate engineering design. Conversion to a wet-bottom detention pond will provide an added storage capacity of 86 acre-feet. Upon completion, the stormwater detention facility can be transferred to HCFCD per the Interlocal Agreement previously mentioned.

10.5.2 (2) M121-01-00 (M121 West – Segment C) Channel Reconstruction from Medical Complex Drive to Hardin Street

The upper reach of M121-01-00, the western lateral to M121-00-00, is proposed to be reconstructed from Medical Complex Drive, upstream of the 3-10'x6' RCB culvert crossing, to Hardin Street. The reconstruction includes lowering the channel to the ultimate depth in order to accommodate future improvements planned upstream. The reconstruction will provide approximately 2 feet of additional depth at Hardin Street. An existing CenterPoint Energy transmission tower exists adjacent to the channel and proper separation will need to be evaluated during final engineering design.

Additionally, a private pumped detention within the Dartford Square Apartment Complex, would have an opportunity to replace their existing stormwater pump system with a new gravity outfall to M121-01-00.

10.5.3 (3) M121-01-01 (Hardin Street East) Channel Construction to Cherry Street

M121-01-01, the eastern lateral of M121-01-00, consists of a concrete-lined channel construction from its confluence with M121-01-00 to Cherry Street. Steeper sides slopes and concrete lining should be implemented to avoid relocation and replacement of existing City-owned and private utilities within the Hardin Street ROW.

Channel construction is the framework for upstream storm sewer improvements along Cherry Laurel (M121 #4), Juniper Ct (M121 #4), Hawthorn Ct (M121 #4), Hampton Place (M121 #5), S. Cherry Street (M121 #6), Magnolia Street (M121 #7), and S. Pine Street (M121 #18).

10.5.4 (4) Cherry Laurel Storm Sewer Improvements

Cherry Place Subdivision has three outfalls consisting of S. Pine Street, S. Cherry Street, and Hardin Street. All outfalls are programmed to drain to the proposed M121-01-01 channel. The Cherry Place Subdivision improvements consist of: 1) storm sewer improvements along Juniper Ct and Hawthorne Ct, including two curb inlets and storm sewer outfalls to M121-01-01; 2) Cherry Laurel Drive storm sewer improvements, including reconstruction of system along the northern curblin from intersection of Juniper Ct to Pine Street and replacement of curb inlets; and 3) Cherry Laurel Drive proposed storm sewer to outfall to the eastern half of S. Pine Street. The Pine Street outfall system is planned to be installed in combination with Hampton Place Storm Sewer Improvements (M121 #5).

10.5.5 (5) Hampton Place Storm Sewer Improvements

The existing Hampton Place development outfalls to S. Cherry Street roadside ditch via curb inlets and culverts at driveway connections. The proposed improvements consist of curb inlet replacement and redirection of storm sewer trunkline in a southwest direction towards the back of the development along S. Oak Street. The proposed storm sewer ultimately outfalling to the east side of S. Pine Street toward M121-01-01. A drainage easement will be required for storm sewer installation within an undeveloped portion of Lot 14 Block 1.

An outfall to M121-01-01 is proposed along the east side of Pine Street (west side reserved for Pine Street proposed improvements). An independent outfall from future Pine Street improvements (M121 #18) is proposed due to the timing of Pine Street roadway reconstruction.

10.5.6 (6) South Cherry Street Storm Sewer Improvements (From Market Street to Hardin Street)

Cherry Street is classified as minor arterial per the City's Major Thoroughfare Plan (MTFP). Based on topography and field visits, the roadway serves as the natural conveyance corridor for Old Town Tomball south of FM 2920 and west of the BNSF Railroad. The proposed improvements along Cherry Street include a storm sewer trunkline from Market Street to the headwater of M121-01-01.

Portions of Old Town Tomball within the service area of S. Cherry Street naturally drain east towards the BNSF Railroad ditch. To serve this drainage, a ditch independent of the BNSF railroad ditch is proposed to collect street runoff and convey it to McPhail Street. A lateral is proposed to convey this drainage to the S. Cherry Street storm sewer trunkline. To avoid right-of-way acquisition, the proposed collection ditch adjacent to the BNSF railroad is within a City-owned tract.

The improvements can be implemented independently with roadside ditch interceptors and street repair for the trunkline along Cherry, or it can be implemented in conjunction with Harris County Precinct 3 roadway reconstruction of Cherry Street, which will likely consist of a curb and gutter roadway section. Laterals alongside the street should be considered during future planning and engineering design to complement side street drainage.

10.5.7 (7) Magnolia Street Storm Sewer Improvements

Magnolia Street is a natural low point for the drainage area from Malone Street to James Street. Magnolia Street and adjacent streets are currently served by roadside ditches and driveway culverts. The proposed storm sewer improvements include the construction of a trunkline to relieve the service area and provide increased conveyance capacity. Per the City Staff, roadway reconstruction is not anticipated at this time; therefore, reconstruction will include roadside ditch interceptors and leads to the proposed trunkline. The downstream

reach of the trunkline will be installed within the City of Tomball Public Works tract for a direct outfall connection to the proposed M121-01-01 ditch.

10.5.8 (8) M121-01-02 (Hardin Street West) Channel Construction to School Street

M121-01-02, the western lateral of M121-01-00, construction consists of a concrete-lined channel within the Hardin Street ROW from the confluence with M121-01-00 to School Street. Steeper sides slopes and concrete lining should be implemented to avoid relocation and replacement of existing City-owned and private utilities within the Hardin Street ROW. Implementation of this project includes upsizing the culvert crossing at School Street.

10.5.9 (9) Theis Lane Storm Sewer Improvements

Theis Lane is classified as a minor arterial per the City's MTFP. Previous construction of the M121-01-00 channel cross culvert under Theis Lane included a service area up to and including Johnson Road as well as an 8'x8' box culvert for an outfall connection to M121-01-00. Project implementation includes removal of a cross culvert under Theis Lane adjacent to the Theis Attaway Nature Center that naturally drains behind the Walmart detention pond. The storm sewer trunkline proposed down Theis is programmed to be included as part of roadway reconstruction.

Additionally, the Tomball Industrial Park pumped detention facility would have an opportunity to replace their existing stormwater pump system with a new gravity outfall to the Thesis Lane storm sewer trunkline.

10.5.10 (10) M521-01-00 Detention Pond Improvements (Ultimate Condition)

The M521-01-00 Detention Pond will require land acquisition of an existing mining pit as well as land adjacent to the BNSF Railroad Mainline. The proposed basin tracts are adjacent to M100-00-00 (Willow Creek) and will serve as mitigation for the M121-02-00 channel improvements. A permanent outfall structure will need to be implemented. Multiple wells and pipelines exist on the property and will need to be coordinated/mitigated upon land acquisition. Final engineering and design may evaluate an equalizer pipe between M500-01 and M521-01 to aid in optimizing and balancing the storage volumes of the detention facilities due to the topography elevation differences within the area.

10.5.11 (11) M121-02-00 (M121 East) Channel Extension to Agg Road

The ultimate construction of M121-02-00 will require land acquisition for existing portions of the channel as well as limits of the channel extension. Channel construction is the framework for upstream storm sewer improvements along S. Cherry Street (M121 #12), Agg Road (M121 #12), Mulberry Street (M121 #13), and S. Cherry Street (M121 #14). In addition, the channel will provide outfall depth for future development between S. Cherry Street and the BNSF railroad. Channel construction will include utility and pipeline relocations. The reach upstream of the planned M121 #14 outfall from S. Cherry Street includes a concrete

drop structure to limit the channel width and while providing sufficient depth for an upstream outfall for M121 #12 and M121 #13 projects.

10.5.12 (12) S. Cherry St & Agg Rd (Anna Street to M121-02-00) Storm Sewer

Construction of a storm sewer along S. Cherry Street south of M121-01-01 to Medical Complex Drive and along Agg Road. The ultimate design includes capacity for Mulberry storm sewer improvements (M121 #13). The improvements can be implemented independently with roadside ditch interceptors and street repair or construction in conjunction with Harris County Precinct 3 roadway reconstruction, which will likely consist of a curb and gutter roadway section. Additionally, the Cherry Meadows Subdivision pumped detention facility would have an opportunity to replace their existing stormwater pump system with a new gravity outfall to the Agg Road storm sewer trunkline.

10.5.13 (13) Mulberry Street Storm Sewer

Construction of a storm sewer along Mulberry St and connect to the Agg Road proposed storm sewer system (M121 #12). The improvements will help alleviate overflow from BNSF culvert crossing behind St. Anne's Catholic Church. The improvements can be implemented independently with roadside ditch interceptors and street repair or construction in conjunction with a roadway reconstruction project, such as a curb and gutter roadway section conversion. Additionally, the Copper Cove pumped detention facility would have an opportunity to replace the existing stormwater pump system with a gravity outfall to the Mulberry storm sewer trunkline.

10.5.14 (14) S. Cherry Street (Agg Rd to Cherrywood Estates) Storm Sewer to M121-02-00

Construction of a storm sewer improvements along S. Cherry Street. The storm sewer outfall to M121-02-00 will require land acquisition for a drainage easement north of Cherrywood Estates. The outfall will likely require coordination and/or relocation of oil/gas pipelines for connection to M121-02-00. The improvements can be implemented independently using roadside ditch interceptors and street repair or in conjunction with Harris County Precinct 3 roadway reconstruction, which will potentially consist of a curb and gutter roadway section.

10.5.15 (15) Medical Complex Drive Storm Sewer Reconstruction

Construction of a parallel storm sewer system along Medical Complex Drive and connect into the M121-01-00 cross culverts.

10.5.16 (16) Michel Road Storm Sewer Reconstruction

Construction of a new storm sewer system along Michel Road to provide sufficient outfall depth for future development. The new system should investigate utilizing the existing storm sewer outfall to M121-01-00.

10.5.17 (17) M521-02 Detention Pond

The M521-02-00 Detention Pond will require land acquisition of existing agricultural properties located within the effective floodplain. The tracts are adjacent to M100-00-00 (Willow Creek) and have the potential for multi-use benefits, including but not limited to, additional regional detention storage volume, floodplain preservation and mitigation volume, and recreational uses. Multiple wells and pipelines exist on the property and will need to be coordinated/mitigated upon land acquisition. Coordination should be performed with HCFCD for final engineering and design as the basin shall have potential joint agency benefits.

10.5.18 (18) S. Pine Street Storm Sewer Improvements

Improvements include the construction of a new storm sewer system along S. Pine Street as well as an outfall to M121-01-01 along west side of Pine Street (east side is reserved for Belmont and Cherry Laurel drainage improvements, as described above). The proposed Pine Street storm sewer improvement is provide a trunkline to relieve the service area and provide increased conveyance capacity. The improvements are anticipated be implemented in conjunction roadway reconstruction, such as a potential conversion to a curb and gutter roadway section.

11.0 M124 BASIN

The M124 Basin represents the contributing drainage area to the M124 channel, which is located within the western and northwestern portions of the City of Tomball and its ETJ. The basin encompasses approximately 2,930 acres. The basin extends from just south of the Lone Star College – Tomball Campus south to its confluence with Willow Creek. The basin includes drainage areas to the east and west of SH 249 freeway and is bounded primarily by J131 and M125 Basins to the east, J133 and Spring Creek Basins to the north, and Telge Road/ Cemetery Road to the west. The M124 Basin delineation is shown in the Basin Exhibits.

The drainage area is served by HCFCD channel M124-00-00 which outfalls to Willow Creek to the west of SH 249. The basin is the largest of the Tomball area basins draining to Willow Creek and includes a substantial area in the ETJ and unincorporated Harris County.

11.1 Basin Description

Much of M124 to be undeveloped or lightly developed with dense commercial development in the vicinity of the SH 249/West Main Street interchange and along FM 2920. The M124 basin consists of two distinctive subbasins, generally divided by SH 249. North of SH 249, the basin is generally bounded by SH 249 to the west, Baker Road to the north, and Lawrence Street to the northwest, FM 2920 to the north, Burlington Northern and Santa Fe Railroad (BNSF) tracks along the east perimeter, and Willow Creek (M100-00-00) to the south. The M124 Basin generally drains in the north to south direction towards Willow Creek.

The M124 Basin drainage area is served by a single north-south mainstem channel, HCFCD M124-00-00. Lateral drainage to the mainstem channel is conveyed generally by roadside ditches and overland sheetflow.

11.1.1 Drainage Inventory

The drainage basin has three (3) distinctive reaches: upper reach (upstream of SH 249), mid-reach (between SH 249 and FM 2920), and lower reach (downstream of FM 2920). Upper reach consists of a small drainage channel that reaches from Brown Road downstream to SH 249. Within the upper reach, a regional stormwater basin M524-01 lies in line along the channel north of Hicks Road.

Recent construction by HCFCD for the mid-reach portion of the M124-00-00 channel (M124-00-00-E001) includes the first phase of the HCFCD channel widening project. The channel widening is north of the existing SH 249 two detention basins owned and maintained by TxDOT and private detention ponds serving the Tomball Town Center shopping center.

The lower reach of M124-00-00 consists of a roadside ditch along Treichel Road into a natural alignment for conveyance to M100-00-00 (Willow Creek).

11.1.2 Crossing Structures

The following table presents the inventory of the M124 channel drainage crossings.

TABLE 11-1. M124 DRAINAGE CROSSING INVENTORY

Ditch ID	Crossing Name	Existing Structure	NBI
M124-00-00	Brown Road	2 – 5'x3' RCBs	N/A
M124-00-00	Detention Pond	2 – 4'x2' RCBs	N/A
M124-00-00	Hicks Road	4 – 6'x3' RCBs	None (NBI Required)
M124-00-00	Private Driveway	5 – 6'x3' RCBs	None (NBI Required)
M124-00-00	Business 249	7 – 6'x3' RCBs	121020072003050
M124-00-00	SH 249 Frontage (NB)	Bridge (Single Span)	121020072003035
M124-00-00	SH 249 Main Lane	Bridge (Single Span)	121020072003037
M124-00-00	SH 249 Frontage (SB)	Bridge (Single Span)	121020072003034
M124-00-00	FM 2920	4 – 6'x3' RCBs	121020294101006
M124-00-00	Treichel Road	3 – 8'x7' RCBs	121020AA0644001

11.2 Basin History

- In 2002, a letter report for the construction of M124-00-00 (identified as Ditch “G” in the report) east of SH 249 to Brown-Hufsmith Road proposed conveyance and detention improvements to offset the impacts associated with the Brown-Hufsmith Road implementation.
- 2005 Business 249 Culvert Crossing added 2 – 6'x3' RCB culverts to the existing 5 – 6'x3' RCB culverts.
- A 2007 Detention Study Report for M124-00-00 (identified in the report as Ditch M124A) was prepared for a private development prior to the construction of M124-00-00 improvements east of SH 249 and Brown-Hufsmith Road as the development was reliant on the outfall provided by the M124-00-00 planned improvements. The report proposed an off-line stormwater detention basin to serve the development, however the construction of this pond was never substantially completed or able to provide the additional storage capacity. A development agreement was in place for the City to take over the maintenance of the pond and manage storage credits for future development within the service area.
- 2008 Willow Creek Tributary M124-00-00 Feasibility Study for Extension Improvements evaluated how to extend the M124-00-00 channel from SH 249 back to the existing M124-00-00 channel south of Treichel Road, with no recommendations made outside of the City Limits or up to Willow Creek. The selected alternative was to route the new channel through HCFCD property south of FM 2920 and mitigate impacts of channel improvements and loss of floodplain storage by development with a detention basin south of Treichel Road. The report

stated a full level of service could not be met due to constraints downstream of M124-00-00 outside of City Limits.

- 2015 SH 249 from FM 2920 to Spring Creek: Hydrologic and Hydraulic Analysis for M124-00-00 evaluated and assess the existing drainage conditions in the M124-00-00 watershed to develop alternatives that alleviate flooding and accommodate the anticipated reconstruction/expansion of SH 249 (Tomball Tollway Phase 2) and limits of FM 2920 within the M124 Basin. The objective of the report was to increase the level of service of M124-00-00. The report's preferred solution was to construct a 25-year level-of-service channel with mitigation included only for Tomball Tollway Phase 2 and FM 2920 Widening Drainage Improvements. However, overtopping and flooding issues along FM 2920 would need to be resolved in a separate project as the existing roadway drainage system is currently undersized.
- The 2018 Master Drainage Concept Plan for M124-00-00 & Preliminary Design Report for Drainage and Mitigation of Tomball Tollway Phase II Improvements along M124-00-00 was prepared to provide initial drainage improvements to serve the expansion of Tomball Tollway Phase II Improvements and identify a channel alignment and detention system that contains the existing 100-year floodplain from SH 249 to HCID #17.
- 2020 M124-00-00-E0001 Channel Improvements and Detention Basin Phase 1 construction plans were prepared. Construction included partial excavation of the ultimate M124-00-00 channel (ultimate depth not achievable due to current depth constraints downstream of FM 2920) and construction of M524 detention basins.
- The 2021 Channel Conveyance Improvements along HCFCD Unit No. M124-00-00 from SH 249 to Willow Creek PER (M124-00-00-E002) further refined the 2018 MDCP and extend the analysis of M124-00-00 to the confluence at Willow Creek. With the objective to increase the channel's level of service to 100-year event, 4 miles of channel improvements and regional detention were evaluated and proposed. The ultimate condition for M124-00-00 will consist of 14 stormwater detention basins and widening and deepening of the channel (average 10-feet deep) to achieve the 100-year level of service.

11.3 Outside Agency Projects & Agency Coordination

HCFCD has developed a proposed plan for improvements of the M124 channel from SH 249 downstream to its confluence with Willow Creek. The proposed improvements are being constructed to alleviate localized flooding and to provide drainage infrastructure for new development in this area while eliminating the need for on-site stormwater detention.

HCFCD currently has a project along HCFCD M124-00-00, which includes channel improvements from downstream (west) of SH 249 to its confluence with Willow Creek. The project is in cooperation with Harris County Precinct 4, Harris County Toll Road Authority

(HCTRA), TXDOT, Harris County Improvement District 17, and City of Tomball. The project also includes regional detention facilities to offset the channel improvement impacts.

The proposed project provides flood level reduction and outfall depth along the channel for development and roadways. Additionally, the project will provide outfall and reduce flooding on FM 2920.

Phase I of the project has been completed, which includes limited channel improvements upstream of FM 2920. Phase II design and right-of-way acquisition are currently underway. Funding for the M124 project is from the HCFCFCD 2018 Bond Program, Project F-37.

See **Figure 11-1** for the M124 CIP phased construction concepts, which were extracted from the HCFCFCD M124 project reports.




FIGURE 11-1. M124 CIP PHASED CONSTRUCTION CONCEPTS

11.4 Drainage Issues & Problematic Area

11.4.1 Historic Flooding

The M124 Basin has a history of poor drainage and flooding due to the lack of drainage depth and capacity within the existing channel.

[FM 2920](#)

FM 2920 is frequently overtopped by the M124 channel east of SH 249 near Calvert and Treichel Roads, which requires TxDOT to close the highway during these flooding events. Several studies have been conducted by TxDOT, City, and HCFCD to determine potential improvements to provide relief. The proposed HCFCD M124-00-00-E0002 and TxDOT FM 2920 Widening projects are expected to provide the necessary drainage improvements to eliminate the highway overtopping.

[SH249 Bypass Basins](#)

TxDOT detention ponds serving SH 249 Bypass and the M124-00-00 channel just upstream of SH 249 have been observed to constantly retain water and provide limited conveyance capacity. This has results in frequent overtopping at the Hicks Road cross culvert. It is anticipated that the HCFCD M124-00-00-E0002 and TxDOT FM 2920 Widening Projects will help provide relief to this area.

[Pine County Subdivision](#)

Pine County Subdivision is located on the west side of the City of Tomball corporate boundaries along Tomball Cemetery Road. A drainage easement exists on the west side of lots fronting Tomball Cemetery Road that is used to capture and convey runoff from the Pine Cone Lane and Pine Bark Lane cul-de-sacs. Based on visual observations, overgrown vegetation and planting has occurred within said drainage easement, blocking the intended sheet flow pattern and causing localized flooding.

[Overflow from Baker Drive](#)

Based on aerial imagery, a low-lying area between Baker Drive and Sherwood Forest Subdivision (approximately 2,150 feet east of SH 249) has existed for many years, eventually transforming into a pond due to the elevation of Baker Drive (previously Sandy Lane) and 2-36-inch cross culverts. Downstream of the cross culverts a defined channel does not exist, therefore spreading the release of the pond with an overland flow path to Brown Road in a southerly direction.

11.5 Proposed Alternatives

11.5.1 (1) M124-00-00-E0002 (HCFCD)

HCFCD is currently in design of large-scale improvements of M124-00-00. Project limits begin at the confluence with Willow Creek and extend up to SH 249. Improvements include floodplain mitigation ponds, stormwater detention ponds, culvert crossings, and channel improvements (average of 10 feet deep) to provide floodplain relief and a level of service for the 100-year design storm event. Improvements are likely to be phased in multiple construction packages, beginning with downstream pond improvements and ultimately channel improvements up to SH 249. The timeline of construction is not available at the time of this report, however this process will take multiple years to implement the ultimate improvements.

These improvements will provide wide range benefits for the M124 Basin and will be required for any other drainage improvements between Willow Creek and SH 249 (J131#2).

11.5.2 (2) Tomball Cemetery Road & Treichel Storm Sewer to M124-00-00

Construct a storm sewer along Tomball Cemetery Road, crossing FM 2920, and down the north side of Treichel Street to the M124-00-00 improved channel. This improvement requires the implementation of the HCFCD M124-00-00 channel construction.

The Pine County Subdivision pumped detention facility may have an opportunity to optimize their existing stormwater pump system, however the the Tomball Cemetery Road storm sewer trunkline likely won't provide sufficient depth to completely eliminate the need for a pumped system.

This project will need to be coordinated with TXDOT for FM 2920 roadway improvements and Harris County Precinct 3 for local street roadway improvements.

Within the limits of the Pine Country Subdivision, planting and overgrown vegetation within the existing drainage and/or city utility easements should be removed to allow the appropriate capture and conveyance of sheet flow to the detention pond.

11.5.3 (3) M124-00-00 Channel Extension to Baker Drive

The upper reach of the existing M124-00-00 channel terminates at Brown-Hufsmith Road. Improvements within this reach of M124-00-00 were constructed as part of the Brown-Hufsmith Road roadway project and consist of an approximate 8-foot drop structure on the south side of the roadway.

This project consists of removing the drop structure for available depth upstream, reconstructing the Brown-Hufsmith culvert crossing, and extending M124-00-00 to Baker Road. A storm sewer system along Baker Road is proposed at the existing culvert crossing to provide sufficient capacity for overflow of an existing pond north of Baker Road.

In order to provide no impact to the M124-00-00 channel, alternative for mitigation may include in-line detention, expansion of the M524-01 detention basin, or additional off-line detention.

Additionally, these improvements provide an opportunity for the Springwood Estates Subdivision private detention pond to convert from a pumped to gravity outfall system. While this tract lies within the J131 Basin and a watershed diversion would likely require additional detention, the available depth provided in the M124-00-00 channel extension has the potential to allow excavation of the existing private detention pond to increase its storage capacity.

11.5.4 Future CIP Project Considerations

With downstream improvements of M124-00-00 (M124 CIP #1) deepening the channel in Phase 2 of the planned channel construction, there is opportunity for the upper reaches to be deepened. Improvements within the channel will be limited by bridge structures along SH 249 main lanes and frontage roads, as well as the culvert crossing at Business 249.

One potential solution to achieve deepening of the channel may include a vertical/rectangular channel offset through the SH 249 main lanes and frontage. Another, more economical solution is to implement a low flow “bleeder” conduit under Business 249 culvert crossing. While this solution may not have a large impact on the channel capacity, it is a lower cost solution to deepen the channel for future storm sewer along Hicks Street and potential M524-01 pond deepening for additional storage capacity.

12.0 M125 BASIN

The M125 Basin represents the contributing drainage area to the M125 channel, which is located within the western portions of the City of Tomball and its ETJ. The basin encompasses approximately 675 acres. The basin is bounded primarily by M121 West Basin to the east, J131 Basin to the north, M124 Basin to the west, and Willow Creek to the south. M125 is formed from portions of TSARP catchments M100F1 and M100F2. The drainage area is served by HCFCD channel M125-00-00, a manmade channel, which outfalls to Willow Creek west of SH 249. The M125 Basin delineation is shown in the Basin Exhibits.

12.1 Basin Description

The M125 Basin is mostly developed, consisting of residential and commercial properties. The upper portions of the basin, upstream (north) of SH 249, is considered almost fully developed, consisting of mostly commercial and multi-family development. The lower portions of the basin area, between SH 249 and Willow Creek, consist of a significant area of detention and floodplain mitigation facilities. The basin area was downstream of SH 249 was also partially developed in conjunction with the extension of Holderrieth Road to serve the Harris County Precinct office and service center facilities. The M125 channel receives runoff from the SH 249 freeway and BS 249 highway, north of the channel crossings. The M125 channel has been improved for its entire reach as part of a HCFCD project.

12.1.1 Drainage Inventory

The upper reaches of the M125-00-00 channel include an enclosed portion located within City of Tomball right-of-way. From Graham Drive to south of Michel Road, the M125-00-00 channel is an earthen, trapezoidal shaped section. M125-00-00 is enclosed beneath Business 249 and SH 249, with a short segment between the two being a concrete-lined trapezoidal channel. Downstream of SH 249, the channel remains earthen. Three ponds exist north of the M100-00-00 (Willow Creek) confluence, with one serving as a stormwater detention pond and the two remaining ponds for floodplain mitigation.

12.1.2 Crossing Structures

The following table presents the inventory of the M125 channel drainage crossings.

TABLE 12-1. M125 DRAINAGE CROSSING INVENTORY

Ditch ID	Crossing Name	Existing Structure	NBI
M125-00-00	Holderrieth Road	4 – 7'x3' RCBs	121020W20338077
M125-00-00	Humble Road	2 – 12'x10' RCBs	121020A33065013
M125-00-00	SH 249 (Enclosure)	3 – 9'x9' RCBs	121020072003047
M125-00-00	BUS 249 (Enclosure)	2 – 8'x8' RCBs	N/A
M125-00-00	Michel Road	2 – 10'x6' RCBs	121020W51086011
M125-00-00	Medical Complex Drive	2 – 10'x6' RCBs	121020W51085010

M125-00-00	Graham Drive	1 – 10'x4' RCB	N/A
M125-00-00	Barbara Street (Enclosure)	1 – 10'x4' RCB	N/A
M125-00-00	Barbara Street (Enclosure)	1 – 8'x4' RCB	N/A

12.2 Basin History

During the 1980's, the City and HCFCD partnered to design and build the tributary channel M125-00-00 to reduce existing flooding and accommodate future development and roadway improvements, including the SH 249 expressway. As part of the M125-00-00 improvements, the M525-01-00 regional detention basin was constructed to mitigate the new channel impacts to Willow Creek. The regional facility also provides mitigation to the TXDOT SH 249 project.

- In 1987, M125-00-00 channel improvement project extended the dual 8'x8' RCB culverts under Business 249 and rerouted the existing M125-00-00 channel alignment. The channel was partially excavated approximately 1,750 lineal feet north of Michel Road. The original M125-00-00 channel was kept open.
- In 1995, M125-00-00 channel improvement rectification project extended M125-00-00 from north of Stallones Road (now Medical Complex Drive) to Graham Drive. The original M125-00-00 channel remained open.
- Based on aerial imagery and the construction plans for Medical Complex Drive between SH 249, the original M125-00-00 channel was filled. Timing and justification of this activity is unknown.
- In 2005, the SH 249 Bypass proposed 3-9'x9' RCBs under the frontage roads and main lanes for the tollway. Parallel drainage along the frontage roads were hydraulically connected to the M125 box culverts, splitting flow between M125 conveyance and SH 249 conveyance.
- A 2008 Final Report for the Lower Reach of M125-00-00 Impact Mitigation Study evaluated the channel from the confluence of Willow Creek to the upstream side of SH 249 and detention options to mitigate impacts to Willow Creek. The study did not include ultimate build-out upstream for the City of Tomball. Two floodplain mitigation basin and a stormwater detention basin were evaluated.
- Construction plans in 2009 for the M525-01 Stormwater Detention Basin, two floodplain mitigation basins, and M125-00-00 Channel Improvements from Willow Creek to Graham Drive were completed. Upstream of the Business 249 culvert crossing, the channel design included a 6-foot bottom width with 3:1 side slopes, 2-10'x6' culvert crossings at Michel Road, and 2-10'x8' culvert crossing at Medical Complex Drive. The HCFCD project terminated at Graham Road.
- Construction plans for M125-00-00 from Graham Road to Barbara Street were completed by a City of Tomball CIP project proposed M125-00-00 extension with underground storm sewer. A 10'x4' RCB was extended from Graham Road to the

south side of Barbra Street, and an 8'x4' RCB was extended to the north side of Barbra Street.

- In 2013, Tomball Tollway SH 249 main lanes were constructed and plugged the 3-9'x9' RCBs from the frontage road drainage system, therefore cutting the SH 249 contributing area at the M125-00-00 culvert crossing.

12.3 Outside Agency Projects & Agency Coordination

Coordination with Harris County, HCFCD, and TxDOT indicate that there are no current CIP projects plan within the M125 Basin.

12.4 Drainage Issues & Problematic Areas

12.4.1 Historic Flooding

Since the construction and additional improvements to the M125-00-00 channel, flooding with the M125 Basin is limited to localized areas. The

[Cobble Creek Apartments and Lawrence Street](#)

The realignment of M125-00-00 in the late 1980s shifted the channel in a more northerly direction, away from the current HCA Hospital, compared to the original channel alignment. The original channel alignment represents a relative low point for this reach of the channel. The Cobble Creek Apartments were constructed prior to the HCFCD M125-00-00 project. Due to the channel high banks being higher than Lawrence Street, the enclosed portion of the original M125-00-00 tends to back up into Lawrence Street due to the elevation differential. Furthermore, the overland flow path from the HCA Hospital follows the original M125-00-00 alignment. Both of these factors cause constant flooding along Lawrence Street, placing the Cobble Creek Apartments at a high risk for structural flooding.

12.5 Proposed Alternatives

12.5.1 (1) Michel Road and Lawrence Street Storm Sewer Reconstruction

Construction of a parallel storm sewer along Lawrence and Michel Street with an outfall to M125-00-00. Install a flap gate on the existing and proposed outfall pipes to prevent backflow of the M125-00-00 channel. This improvement provides additional inlet capacity, storm sewer capacity, and reduces the potential for M125-00-00 to backflow into the system as the existing channel high banks are higher than the low point along Lawrence Street.

Construction of a parallel sewer along Medical Complex Blvd with a new outfall to M125-00-00. Add inlets to all corners of the Medical Complex Drive and Lawrence Street intersection. The additional inlets and storm sewer will divert overland flow from Lawrence Street and the Medical Center area from continuing down Lawrence Street. These improvements are to prevent street ponding and adding runoff volume to the flooding location near Cobble Creek apartments during larger storm events.

12.5.2 Future CIP Project Considerations

With the ultimate channel section of M125-00-00 being previously constructed and a majority of the basin developed, portions of the M125 Basin include older asphalt roadways with shallow roadside ditches. Lateral connections to the M125-00-00 channel via a storm sewer, either for a roadway reconstruction project or for potential redevelopment, may be implemented in order reduce localized ponding and provide outfall depth for redevelopments.

13.0 J131 BASIN

The J131 (Boggs Gully) Basin represents the contributing drainage area to the J131 channel (HCFCD J131-00-00), which is located within the northwestern portions of the City of Tomball and its ETJ. Boggs Gully basin encompasses an area of approximately 3,156 acres, generally north of FM 2920 (Main St.) including the northern portions of Old Town. The basin is bound by the Spring Creek north, FM 2978 to the east, Main Street (FM 2920) to the south, and M125 and M124 Basins to the west. The J131 Basin delineation is shown in the Basin Exhibits.

13.1 Basin Description

The basin area is served by HCFCD J131-00-00 (Boggs Gully) as a mainstem with various tributaries. Boggs Gully runs from its enclosed headwaters, serving as the outfall of FM 2920, north to its confluence with Spring Creek. HCFCD tributaries to the J131-00-00 ditch include J131-01-00, J131-03-00, J131-04-00, and J231-00-00.

HCFCD J131-01-00 is a FEMA studied stream located in the eastern portions of the basin. HCFCD J131-03-00 is a manmade channel serving the area south of Hufsmith Road and east of the BNSF RR tracks. J131-04-00 is a small roadside ditch and swale that outfalls into J131 near Ulrich Road. J231-00-00 is the original Boggs Gully alignment between BNSF RR and Zion Road prior to the Boggs Gully HCFCD CIP channel project.

The J131 Basin encompasses most of Old Town, north of FM2920, and other densely developed commercial and residential areas near the downtown area. North of Hufsmith Road, the basin consists of sparsely developed commercial and residential areas with some remaining large areas of undeveloped property, particularly in the far north and eastern areas of the basin.

13.2 Basin History

The J131 (Boggs Gully) Basin has had multiple improvement projects, including HCFCD CIP projects to improve Boggs Gully. The HCFCD projects included realignment, widening, deepening, and enclosing reaches of the basin's mainstem from Zion Road upstream to FM 2920 (Main St).

13.2.1 Drainage Inventory

[J131-00-00 \(Enclosed from FM 2920 to Inwood Street\)](#)

Boggs Gully channel was previously enclosed from FM 2920 (Main St) north to Inwood St. by HCFCD in 1986. From FM 2920 (Main St) to Hicks St., the channel enclosure consists of 10' x 6' RCB. From Hicks St. north to the box outfall into the existing Boggs Gully channel at Inwood St., the channel enclosure consists of 12' x 8' RCB.

[J131-00-00 Channel Section](#)

The proposed Boggs Gully channel reconstruction reach extends from Inwood Street downstream to Zion Road. This reconstruction was part of a HCFCF CIP project. The reconstruction included roadway crossing improvements, concrete section from upstream of Ulrich through the BNSF RR crossing, contributing ditch outfalls (eg. J131-03-00), and the realignment of the reach from Rudolph Road to upstream of Zion Road. The channel section within this reach generally consisted of an earthen, trapezoidal section with 20' bottom width, 3:1 (H:V) side slopes, and 12 foot depth.

[J231-00-00](#)

As part of the Boggs Gully CIP reconstruction project, the channel was realigned. J231-00-00 represents the channel's original alignment from just downstream of BNSF railroad crossing to the current confluence with J131-00-00. The upstream end of J231-00-00 has been hydraulically disconnected from Boggs Gully; therefore, flow within this channel is minimized to the contributing area and not upstream flow overflow from Boggs Gully.

[J131-01-00](#)

Historically, J131-01-00 crossed Zion Road via a small drainage structure, which appears on old aerals and mapping. However, this crossing has been removed and the channel does not currently cross Zion Road. The contributing flow along the channel has been redirected along Zion Road within its south roadside ditch to outfall into Boggs Gully at the Zion Road bridge crossing.

[J131-01-00 Broussard Park](#)

J131-01-00 upstream of Hufsmith Road runs through the City's Broussard Park. As part of the park's construction, the channel was partially re-aligned and wet-bottom and dry-bottom detention were constructed adjacent to the channel. However, due wetland restrictions the majority of the channel was maintained existing without any rectification.

13.2.2 Crossing Structures

The following table presents the inventory of the J131 channel drainage crossings.

TABLE 13-1. J131 DRAINAGE CROSSING INVENTORY

Ditch ID	Station	Crossing Name	Existing Structure	NBI
J131-00-00	2829	Live Oak Lane	Bridge (3-span)	None (NBI Required)
J131-00-00	5153	UPRR	Bridge (10-span)	N/A
J131-00-00	10614	Zion Road	Bridge (3-span)	121020AA0664001
J131-00-00	15644	Rudolph Road	2 - 10'x9' RCB	121020W56091001
J131-00-00	16451	BNSF	Bridge (3-span)	N/A
J131-00-00	16852	Ulrich Road	2 - 10'x9' RCB	121020W65930001
J131-00-00	18310	W. Hufsmith Road	1 - 12'x9' RCB	N/A

Ditch ID	Station	Crossing Name	Existing Structure	NBI
J131-00-00	19087	Baker Drive	1 - 12'x9' RCB	N/A
J131-00-00	20093	Inwood Street (Enclosure)	1 - 12'x8' RCB	N/A
J231-00-00	60	J131-00-00	1 - 8'x8' RCB	N/A
J231-00-00	794	Neal Drive	N/A	N/A
J231-00-00	2601	Rudolph Road	72" RCP	N/A
J131-01-00	3028	Zion Rd	Structure Non-Existing	N/A
J131-01-00	4559	Hufsmith Rd	2 - 24" RCP	N/A
J131-03-00	50	J131-00-00	1 - 12'x7' RCB	N/A
J131-03-00	270	E. Hufsmith Road	2 - 72" RCP	N/A
J131-03-00	1742	Carrell Street	2 - 72" RCP	N/A
J131-03-00	3260	FM 2920	1 - 84" CMP	N/A
J131-03-00	4196	Timkin Road	1 - 60" CMP	N/A

13.3 Outside Agency Projects & Agency Coordination

HCFCFCD is currently investigating a proposed channel improvement project along J131-01-00. The project is to eliminate the existing floodplain along the channel, provide outfall depth for future Zion Road and Hufsmith Road widenings, and reduce structural flooding along the channel. The preliminary channel conveyance improvements are documented within the *Draft Preliminary Engineering Report Project ID J131-01-00-E001* by Michael Baker International for HCFCFCD, dated April 2024.

Harris County has indicated future plans to widen Hufsmith Road within the J131 Basin. The widening would require mitigation detention along the roadway, outfall depths at J131-01-00, and floodplain/ floodway mitigation at J131-01-00 crossing.

Previous coordination with Harris County indicated plans to widen Zion Road within the basin; however, this project has been eliminated from Harris County's future plans for the foreseeable future.

13.4 Drainage Issues & Problematic Areas

The main conveyance channel, J131-00-00, also known as Boggs Gully, was constructed in to provide a 100-year conveyance for its length. However, detailed analysis by HCFCFCD and this study shows that the channel reach from J131-03-00 to Zion Road does not provide a 100-year capacity. Additionally, the tributaries of Boggs Gully are shown to be limited in capacity, including J131-01-00 and J131-03-00. Throughout the Boggs Gully Basin, localized flooding has been documented due to limited drainage systems and outfall depths of local received systems, such as roadside ditches and small channels. Specific problematic areas are further detailed in the following subsection.

13.4.1 Historic Flooding

Old Town

Old Town, north of Main St., has experienced numerous flooding events. Several properties located within the Old Town area have recorded NFIP flood claims. The area does not have sufficient internal drainage with limited/ shallow roadside ditches, undersized driveway culverts, and inadequate storm sewer systems (where these limited reaches can be found).

One of the main conveyance systems for Old Town include N. Cherry Street roadside ditches. At the intersection of Hufsmith Road, it was observed the cross culverts of Hufsmith are undersized due to the outlet velocity seen at the slope paving north of Hufsmith and the rate at which water was conveyed to J131-00-00 (Boggs Gully).

J131-01-00 Subbasin

The existing J131-01-00 channel consists of a shallow swale that is approximately 2-3 feet deep. The ditch conveys flow from upstream of Hufsmith Road near Broussard Park westerly to Zion Road where its flow continues along Zion Road roadside ditch to its outfall into Boggs Gully. The channel has a large FEMA delineated floodplain and regulatory floodway along its alignment. However, structural flooding within the subbasin is limited due to the limited number of structures.

Lovett Road/Carrell Street

The residential areas along these two roadway corridors have experienced continuous flooding. Analysis shows that the areas are located within a topographic bowl. Drainage within the area is served by roadside ditches that are restricted by size and inadequate driveway culverts. Additionally, Lovett Street is furthered confined by inadequate drainage along Hufsmith Road, which receives the northern portions of the area.

Carrell Manor and Carrell Street Baptist Church

Carrell Manor was constructed in the mid 1980's and includes a backslope swale with a relief culvert along the west side of the subdivision. Per plans, this outfall is intended to cross Carrell Street and drain toward J131-03-00. However, from visual inspection, these culverts have sunken, therefore reducing their capacity to relieve the area behind Carrell Manor lot. Per City Staff, there is a public drainage easement behind Carrell Street Baptist Church, which is adjacent to Carrell Manor subdivision. This ditch requires frequent maintenance and lacks sufficient grade and capacity under current criteria.

Hufsmith Road

Hufsmith Road exists as a two-lane asphalt roadway owned and maintained by Harris County. The roadway has limited outfall depth at several locations and small, shallow roadside ditches. Due to the large contributing area to the roadway and its shallow roadside

ditches, frequent roadway ponding occurs. Additionally, the shallow roadside ditches result in ponding to adjacent, contributing roadways and developed areas.

[Snook Lane](#)

Snook lane is identified in the MTFP as an existing minor arterial. Currently, Snook Lane is a two-lane asphalt roadway with shallow roadside ditches. Southern limits of Snook Lane drain to FM 2920 (which originally drained to M116 Basin) and northern limits drain to Hufsmith Road. Neither receiving roadway system has sufficient depths to accommodate existing or future development along Snook Lane. Therefore, the roadway experiences frequent ponding. Additionally, any development along Snook Lane requires pumped detention facilities due to the lack of outfall depth in the roadside ditches.

[J131-03-00](#)

Along upstream reaches of J131-03, north of FM 2920, observations from City Staff provided evidence of Timkin Road roadside ditches overtopping. The FM 2920 culvert crossing at J131-03 is undersized based on its contributing area and stream hydraulics. The City's sanitary sewer system to the North Treatment Plant travels along the centerline of J131-03-00 for its entire reach; this systems manhole obstructs flows and increases the potential for sanitary sewer overflows due to inundation from the channel. The 2023 Water and Wastewater Master Plan has identified a sanitary sewer project along J131-03-00 for upsizing within the proposed 5-year CIP.

[Baker Rd north of Brown Road](#)

The Tomball ISD Transportation Building, located in the southeast quadrants of the Quinn Road and Baker Drive intersection, naturally drains in a southeasterly direction towards J131-00-00 (Boggs Gully). Original development and parking lot expansion of the bus depot includes multiple dry detention ponds outfalling in a shallow ditch that drains towards Baker Drive. Connectivity to J131-00-00 continues along Baker Drive and Hufsmith Road via roadside ditches and driveway culverts. These roadside ditches and culverts are undersized, causing street ponding and limiting outfall depth for future development.

[North Sycamore and North Peach Street](#)

North Sycamore Street and Peach Street exist as two-lane asphalt roadway with shallow roadside ditches with limited conveyance to J131-00-00. With the BNSF railroad and FM 2920 existing at natural grade breaks for the J131 Basin and M118 Basin, the area has insufficient drainage causing localized street flooding during smaller storm events. Peach Street drains north and utilized an existing cross culvert north of Carrell Street, directing the roadway drainage into private pond.

Willow Street

The general retail district between FM 2920, Willow Street and Tom Keating Drive was began to redevelop in the early 2000's when a private drainage channel and cross culvert under Willow Street was constructed to hydraulically connect this undeveloped area to J131-03-00. At the downstream end of the culvert crossing under Willow Street, runoff is abruptly directed into driveway culverts. The roadside ditch wraps around the southern-most lot and ultimately drains into J131-03-00. The confluence at the downstream end of the cross culvert has repeatedly overcome the roadside ditch banks, causing localized ponding and increases the potential for structural flooding for adjacent residential properties.

FM 2920

FM 2920 is a TxDOT arterial highway that historically represents the relative basin divide between Spring Creek and Willow Creek watersheds. However, the highway has experienced continuously flooding, including the rainfall event in May 2024. Multiple street overlays with minimal storm sewer reconstruction, the existing roadside ditches and storm sewer systems are drastically undersized. Additionally, continual development along the corridor since the original storm sewer installation has diminished the facility's capacity.

At the time of this report, TxDOT is currently in design for the full reconstruction of FM 2920 from State Highway 249 to Willow Street. The reconstruction will incorporate drainage improvements to the storm sewer system, cross culverts, and all parallel drainage within the right-of-way. For this reason, proposed improvements within the highway ROW as part of this study were limited stream cross culverts.

Tomball Terrace Subdivision

The existing condition modelling revealed a low-lying area within the Tomball Terrace Subdivision, which is adjacent to J131-00-00 (Boggs Gully) between Baker Drive and Hufsmith Road. The subdivision was constructed in the early 1980's. In addition to the modeling indications, there are multiple repetitive loss claims along Pecan Street within the subdivision. The original outfall for the subdivision was constructed as a ditch to Hufsmith Street through private property to the north. Development on this private property enclosed the ditch, therefore limiting the outfall for the subdivision. Furthermore, offsite sheet flow from the south is collected in shallow ditch behind residential lots and collected in the S. Pecan Street storm sewer system. The storm sewer within the subdivision is outdated and undersized for current drainage standards, thus overloading the system.

13.5 Proposed Alternatives

13.5.1 (1) J531-01 Detention Pond Improvements

Portions of Old Town north of FM 2920 within the service area of Cherry Street are served by roadside ditches and cross culverts. The drainage solution for this area begins with the

construction of a sub-regional detention pond, J531-01, as a mitigation for increased flows from the conversion to underground storm sewer for N. Cherry Street and allocation of storm volume for future Hufsmith Rd reconstruction between J131-00-00 and the BNSF Railroad. Additional volume is available for storm sewer improvements serving N. Sycamore Road.

The City has been acquiring lots within the triangular-shaped tract, with only a few outstanding lots remaining. Once the remaining lots are acquired, excavate and construct a dry-bottom detention facility to provide storage volume and outfall depth for planned upstream improvements. Construct an outfall structure to J131-00-00. The facility may provide multi-purpose functionality in conjunction with the City's Park Master Plan.

13.5.2 (2) N Cherry Street Storm Sewer Improvements

Upon completion of the J531-01 Detention Pond project, storm sewer improvements along N Cherry will relieve local ponding by increasing the drainage system capacity with the lowered outfall depth provided in the pond. Construct a storm sewer trunk line along N Cherry Street, either in collaboration with Harris County Precinct 3 roadway reconstruction or independently of the Precinct with ditch interceptors to maintain the current roadway configuration. Lateral systems along other streets may be evaluated during the design phase and/or installed post CIP project.

13.5.3 (3) Commerce Street Storm Sewer Improvements

Construct east-west lateral systems along Commerce Street. Street to remain curb and gutter and may include potential street reconstruction. This system will be connected to the downstream proposed N. Cherry Street Storm Sewer Improvements (J131#2).

13.5.4 (4) J531-02 Detention Pond Improvements

This alternative drainage solution includes the construction of a dry-bottom detention basin on a City owned tract. The detention basin has the potential to serve future Hufsmith Road improvements and offset impacts to North Sycamore Street storm sewer improvements (J131#5B).

Environmentally sensitive areas exist within the pond tract (see *Environmental Section*) due to apparent existing oil wells and pipelines within the tract. These facilities will need to be accounted for within the utilization of this basin tract and its engineering design.

13.5.5 (5) N. Sycamore Storm Sewer Improvements

[Alternative A – Conveyance Improvements to J531-01](#)

Construct storm sewer trunkline along North Sycamore right-of-way and within an acquired drainage easement parallel to the BNSF railroad. Install a storm sewer crossing at the West Hufsmith Road rail crossing and connect storm sewer to J531-01 detention facility.

To help facilitate drainage along Peach Street, lateral connections may be implemented by the City CIP project or by private development as it is within the service boundary of the proposed trunkline.

Alternative B – Conveyance Improvements to J531-02

Construct storm sewer trunkline along North Sycamore right-of-way and within an acquired drainage easement parallel to the BNSF railroad. Install a storm sewer crossing under East Hufsmith Road and connect storm sewer to J531-02 detention facility. This solution requires the construction of the J531-02 detention facility (J131 CIP 4).

To help facilitate drainage along Peach Street, lateral connections may be implemented by the City CIP project or by private development as it is within the service boundary of the proposed trunkline.

13.5.6 (6) J131-01-00 Channel Improvements

Due to the complexity of the subbasin, multiple future infrastructure projects, and multiple agencies involved, several alternative options were conceived for the J131-01-00 subbasin. The proposed improvement options provided existing flooding relief and addressed drainage issues and provide outfall depth for future development within the subbasin. The options also considered the potential Hufsmith Road and Zion Road improvements and the roadway needs for storm sewer depth and detention. Additionally, the options included the offsetting of the effective FEMA floodplain volumes, which would be eliminated with the drainage improvements.

Any J131-01-00 option implemented will require HCFCD coordination since the District is currently investigating improving the channel to eliminate the existing floodplain along the channel.

Alternative A – J531-04 and Storm Sewer Improvements

Construction of detention facility upstream (east) of Hufsmith Road to provide floodplain storage and outfall depth for upstream potential development. Basin outfall includes large box culvert (8' x 8' RCB) to Hufsmith Road. Drainage system will bypass the existing J131-01 channel alignment with dual box culvert system (2- 10' x 8' RCB) that runs along Hufsmith Road north to Zion Road and then west along Zion Road to its outfall into Boggs Gully at the Zion Road crossing.

The project will provide floodplain relief, eliminate the existing floodplain and floodway along J131-01, and provide outfall depth for the future reconstruction of Hufsmith Road and Zion Road. The project should be coordinated with Harris County for the reconstruction of Hufsmith Road and potential reconstruction of Zion Road to ensure sufficient capacity and depth for the roadway contributing storm sewer system.

Alternative B – J531-04, J131-01-00 and Storm Sewer Improvements

Construction of detention facility upstream (east) of Hufsmith Road to provide floodplain storage and outfall depth for upstream potential development. Basin outfall includes large box culvert (8' x 8' RCB) to Hufsmith Road. The drainage system downstream of Hufsmith Road will utilize the existing J131-01-00 alignment to Zion Road, including a 10' bottom width, 10' deep trapezoidal, earthen channel. From the channel's junction with Zion Road, the system will run west along Zion Road via 2-10' x 8' RCB to its outfall into Boggs Gully at the Zion Road crossing.

The project will provide floodplain relief, eliminate the existing floodplain and floodway along J131-01, and provide outfall depth for the future reconstruction of Hufsmith Road and Zion Road. The project should be coordinated with Harris County for the reconstruction of Hufsmith Road and potential reconstruction of Zion Road to ensure sufficient capacity and depth for the roadway contributing storm sewer system.

Alternative C – J531-03, J531-04 and Storm Sewer Improvements

Construction of detention facility upstream (east) of Hufsmith Road to provide floodplain storage and outfall depth for upstream potential development. Basin outfall includes large box culvert (8' x 8' RCB) to Hufsmith Road. Drainage system will bypass the existing J131-01 channel alignment by running south along Hufsmith with a large box culvert system (10' x 8' RCB) that runs along Hufsmith Road to the existing swale roadway outfall just east of Snook Road. A detention basin along the existing flow path is proposed from Hufsmith Road north to the existing J131-01 alignment. The basin outfall will consist of a large dual box culvert system (2- 10' x 8' RCB) that runs along the existing J131-01 alignment to Zion Road and then west along Zion Road to its outfall into Boggs Gully at the Zion Road crossing. The system will also include a connection from J131-01 at its Hufsmith Road crossing (at Broussard Park) to the proposed system along Hufsmith Road.

The project will provide floodplain relief, eliminate the existing floodplain and floodway along J131-01, and provide outfall depth for the future reconstruction of Hufsmith Road and Zion Road. The project should be coordinated with Harris County for the reconstruction of Hufsmith Road and potential reconstruction of Zion Road to ensure sufficient capacity and depth for the roadway contributing storm sewer system.

13.5.7 (7) Zion Road Storm Sewer Improvements

Zion Road is maintained by Harris County Precinct 3 (Road Log ID 3F54401, 3F54402, 3F54403, and 3F54404) within the City limits. Zion Road exists today as a two-lane asphalt roadway with shallow roadside ditches and limited conveyance to J131-00-00. Due to the large contributing area of Zion Road, the drainage improvements should be sized to accommodate these flows.

Proposed improvements include construction of a storm sewer trunkline from Quinn Road to Boggs Gully (J131-00-00) bridge structure. It is anticipated the drainage infrastructure improvements will be part of roadway reconstruction by Harris County Precinct 3. As part of the project, it is likely detention will be required to mitigate increased flows generated by the storm sewer improvements. The City shall coordinate with Harris County Precinct 3 during the preliminary stages to implement upsizing of the storm sewer to meet the City's drainage criteria and design/ locate proposed detention basin.

13.5.8 (8) Hufsmith Road Storm Sewer Improvements

Hufsmith Road is maintained by Harris County Precinct 3 (Road Log ID 3I98901) within the City limits. The segment of this CIP extends from the BNSF Railroad crossing to Lovett Street, within the J131-03-00 service area. Western segments of the roadway are planned within the J531-01 service area and eastern segments are planned within the J131-01-00 service area.

Proposed improvements include construction of storm sewer from BNSF Railroad crossing to Lovett Street. Two pond locations have been identified; Pond A within a City-owned tract and Pond B adjacent to J131-03-00 and J131-00-00 channels.

The City shall coordinate with Harris County Precinct 3 during the preliminary stages to implement upsizing of the storm sewer and selected CIP alternatives for North Sycamore improvements (J131 5) and Carrell Street/Lovett Street (J131 CIP 10 and CIP 11 improvements).

13.5.9 (9) Snook Lane Storm Sewer Improvements

Construction of a storm sewer system along Snook Lane is needed to provide drainage capacity and depth along the roadway. Based on available outfall depth at FM 2920 and drainage issues along FM 2920, construction of the storm sewer system will require a watershed diversion (from M116 Basin to J131 Basin) of approximately 30.7 acres. This would require acquisition of a tract for a stormwater detention facility to offset impacts from the watershed diversion and increased peak flows from the roadway drainage improvement.

This option requires an upgraded outfall along Hufsmith Road and should be coordinated with Harris County Precinct 3 and HCFCD for Hufsmith Road improvements and J131-01-00 improvements as it is anticipated multiple detention facilities will be required to serve all of these hydraulically connected components.

13.5.10 (10 & 11) Carrell & Lovett Street Storm Sewer Improvements

Four alternatives were considered for Carrell Street Improvements and are described below. Existing conditions show a drainage divide at the intersection of Carrell Street and Lovett Street. Due to natural topography, Carrell Street currently drains west toward J131-03-00 and Lovett Street currently drains north toward Hufsmith Rd, ultimately to J131-03-00. All

alternatives include a new storm sewer within Carrell Street Baptist Church tract south of Carrell Street to improve ongoing maintenance efforts of the existing shallow swale.

[Carrell Street 10A & Lovett Street 11A](#)

Install two independent storm sewer systems along Carrell Street and Lovett Street while maintaining existing service areas. Lovett Street improvements will require the reconstruction of Hufsmith Rd and coordination with Harris County Precinct 3.

[Carrell Street 10B & Lovett Street 11B](#)

- Provide a storm sewer system serving both Carrell Street and Lovett Street independent of the Hufsmith Road reconstruction project. In order to provide outfall depth for this drainage solution, J131-03-00 requires reconstruction from the confluence with J131-00-00 to Carrell Street. Replace the existing outfall structure and remove the drop structure upstream of the J131-00-00 outfall. Reconstruct J131-03-00 to a rectangular, concrete-lined channel with a minimum 4-foot vertical drop. Concrete-lining of the entire cross-section will be required along the entire reconstruction length. Replace existing culvert crossings at Hufsmith Road and Carrell Street. Install concrete-lined drop structure upstream of Carrell Street culvert crossing.
- Install storm sewer system serving all of Carrell Street and Lovett Street. Pipe upsizing is required to achieve the hydraulic grade line one-foot below the gutter line in the northern reach of the Lovett Street system, as the storm sewer is being directed opposite of the natural topography.
- Channel reconstruction will require land acquisition between Hufsmith Rd and Carrell Street to provide maintenance berms (30-foot-wide along the western bank and 20-foot-wide along eastern bank).
- Reconstruction of the channel will require the relocation of a 15-inch wastewater line that exists within the channel bottom. This segment of sewer has been identified in the City of Tomball 2023 Water and Wastewater Master Plan as requiring upsizing (Project #5).

[Carrell Street 10C & Lovett Street 11C](#)

- Similar to alternative 10 B & 11B, provide a storm sewer system serving Carrell Street and Lovett Street independent of the Hufsmith Road reconstruction project. In order to provide outfall depth for this drainage solution, J131-03-00 will be enclosed from J131-00-00 to FM 2920 culvert crossing. While this is the most expensive solution, it minimizes the right-of-way footprint, potentially eliminates the need to additional utility easements for the sanitary sewer relocation and provides an opportunity to enhance this drainage corridor as a walking trail/path.

13.5.11 (12) Willow Street Ditch Regrade and Culvert Crossing to J131-03-00

Willow Street culvert crossing north of FM 2920 collects a private drainage easement for Commercial Property, Tom Keating Drive and southern portions of Lovett Street with an ultimate outfall to J131-03-00. Downstream of the Willow Street culvert crossing, a perpendicular bend in roadside ditches convey runoff back toward FM 2920 and bend back north toward J131-03-00.

Regrade Willow Street eastern ditch toward Texas Street, adjacent to a City-owned tract. Construct a culvert crossing under Willow Street. Excavate a new ditch toward J131-03-00 within the unimproved right-of-way of Texas Street.

13.5.12 (13) Baker Drive and Brown Road Storm Sewer to J131-00-00

Tomball ISD Transportation Facility stormwater detention pond outfalls in a southeast direction toward Baker Drive through private property. Construction of a storm sewer along Baker Drive and W. Hufsmith Road to J131-00-00 will provide outfall depth and conveyance capacity for the service area.

13.5.13 (14) FM 2920 Culvert Crossing Reconstruction

Installation of a parallel culvert crossing under FM 2920 to increase culvert capacity and relieve upstream drainage. This project requires coordination with TxDOT for FM 2920 Roadway Reconstruction project.

13.5.14 (15) Stanolind Road Culvert Crossing

Replace the existing culvert to provide positive drainage and relieve localize ponding near BNSF Railroad Tracks.

13.5.15 (16) Pecan Street Outfall Reconstruction

Reconstruction of curb inlets at the existing Pecan Street outfall. Remove and replace existing arch pipe outfall at Pecan Street. Construction of the outfall within a new drainage easement directly into J131-00-00.

13.5.16 (17) Hicks Street and Inwood Drive Diversion from Tomball Terrace Subdivision

To reduce the off-site sheet flow directed into the Tomball Terrace Subdivision and continual inundation observed and reported along Pecan Street, construct a new storm sewer system along Hicks Street, Inwood Street, and reconstruct storm sewer along the east side of Baker Drive with a new outfall downstream of the culvert crossing at J131-00-00. Construct a new ditch within City right-of-way along southern edge of Tomball Terrace Subdivision and route north to new Hicks Street storm sewer. Replace existing curb inlets at Baker Drive intersections with Inwood Street and North Pecan Street.

14.0 J132 BASIN

The J132 Basin services the area north of Zion Road east and east of the BNSF railroad. The J132 basin encompasses approximately 50 acres. As part of the J132 Basin area, a separate J132A Basin was delineated to represent the area north of Zion Road and west of the BNSF. The J132A Basin encompasses approximately 125 acres. The J132 and J132A Basin delineations are shown in the Basin Exhibits.

14.1 Basin Description

The basin is divided into two subbasins by the BNSF railroad. East of the railroad, the drainage system consists of roadside ditches that drain to the shallow J132-00-00 ditch, which runs south to north to its outfall into Spring Creek. The channel serves the Hunterwood Subdivision. The J132-00-00 ditch has previously been rectified by the City of Tomball.

West of the railroad, the J132A channel is a natural channel that runs from the north end of Martens Road north adjacent to the BNSF alignment to Spring Creek. The drainage system consists of a natural ravine style drainage channel. The upper portions of the subbasin include residential development with the lower (northern) portions of the subbasin consisting of rural residential tracts. The J132A Basin serves the Country Meadow subdivision as well as the east side of Quinn Road north of Zion Road.

There are some inter-connections between the J132 and J132A basins with flow paths towards the BNSF railroad and cross-culverts under the railroad. These connections provide an overflow connectivity from J132 Basin to J132A within the upper portions of the J132 Basin area.

14.2 Basin History

The J132-00-00 channel was a natural conveyance path based on historical topographical surveys and aerial imagery. With the BNSF Railroad immediately to the west, it served as a general flow path toward Spring Creek. As part of Hunterwood Subdivision development (approved plans 1984), the channel was improved and new outfall installed to J100-00-00 (Spring Creek).

14.2.1 Drainage Inventory

The J132 channel, per as-built drawings, was designed with a flat-bottom width of 4 feet and a top width of approximately 40 feet at a relatively gentle slope at the downstream reach and a v-shaped ditch in the upstream reaches with a steep slope of over 0.01 ft/ft gradient. Small ditch laterals run from Lost Creek Road to the J132-00-00 channel, serving as the roadway outfall systems. A multiple barrel, 3-36" RCP structure is located at Julia Lane crossing. The

channel outfall consists of 2-36" CMP that are constructed with an approximate 40 foot drop into Spring Creek.

The J132 channel is a well-defined, natural channel that deepens into a ravine style section as it approaches its confluence with Spring Creek. No roadways cross the channel.

14.2.2 Crossing Structures

The following table presents the inventory of the J132 channel drainage crossings.

TABLE 14-1. J132 DRAINAGE CROSSING INVENTORY

Ditch ID	Crossing Name	Existing Structure	NBI
J132-00-00	Outfall to J100-00-00	2 – 36" CMP	N/A
J132-00-00	Julia Lane	3 – 36" RCP	N/A

14.3 Outside Agency Projects & Agency Coordination

No improvements were identified by HCFCD for this channel.

14.4 Drainage Issues & Problematic Area

No drainage problems were identified for these two channel areas.

14.5 Proposed Alternatives

Although no capacity increase is proposed along the channel, a stability project is recommended to re-establish the channel configuration and reduce future failures and maintenance issues.

15.0 J133 BASIN

The J133 Basin services the area east of SH 249 to Quinn Road from north of Baker Road, across Zion Road, north to Spring Creek. The J133 Basin is approximately 248 acres. Improvements along this channel and within the basin have previously been performed by the City of Tomball and the adjacent development. The J133 Basin delineation is shown in the Basin Exhibits.

15.1 Basin Description

Based on aeriels and landuse maps, the J133 Basin is mostly developed. Hydraulic analysis for the J133 channel shows that the drainage ditch has 100-year capacity for the ditch length. However, a field review of the basin locations showed erosion/ stability issues along the channel reach; this finding was supported by City officials.

As part of the J133 Basin, the Tomball Hills Subdivision was investigated. This area lies immediately to the west of the J133 Basin and is served by a storm sewer system that outfalls directly into Spring Creek downstream of SH 249. This area delineation is also shown with the J133 Basin in the Basin Exhibits.

15.2 Basin History

Improvements to the J133-00-00 channel were completed in the early 1990s as part of a City CIP project. The channel was designed with a 6-foot-wide flat bottom and includes multiple drop structures along the reach upstream of the culvert crossing. Channel improvements included an enclosed reach, connecting area south of Zion Road. Quinn Road acts as the general basin divide between the J131 Basin and the J133 Basin.

Immediately following improvements to the channel, the North Star Subdivision commenced construction, including a phased, multi-cell detention facility that outfalls to J133-00-00 downstream of the culvert crossing and into an unimproved reach of the channel.

Sherwood Forest Subdivision began constructing homes prior to the 1980s and before Zion Road was installed. Based on historical topographic maps, the subdivision generally drained either north to J133-00-00 or south to the M124 Basin. Spring Pines Estates was constructed in the early 2000s and included a detention pond at the upstream end the J133-00-00 enclosed section. This detention facility has had multiple erosion failures over the years, impacting the adjacent sanitary sewer system. The last pond remediation was completed in 2016, which diverted Sherwood Forest runoff directly into the J133-00-00 enclosed section under Zion Road.

Immediately adjacent to the J133 Basin is the Tomball Hills Subdivision. This neighborhood was constructed in the late 1970s along J100-00-00 (Spring Creek) and SH 249 (originally SH

149). The subdivision has relatively steep gradients as it abuts the southern bank of Spring Creek. The outfall for the subdivision is located at the cul-de-sac along Stella Lane, the northernmost portion of the development.

15.2.1 Drainage Inventory

The existing J133-00-00 is an earthen, trapezoidal channel that reaches approximately 3,900 lineal feet from north of Zion Road to Spring Creek.

15.2.2 Crossing Structures

The following table presents the inventory of the J133 channel drainage crossings.

TABLE 15-1. J133 DRAINAGE CROSSING INVENTORY

Ditch ID	Crossing Name	Existing Structure	NBI
J133-00-00	Unimproved Crossing	2 - 7' x 5' RCBs	N/A
J133-00-00	US J133-00-00	1 - 10' x 5' RCB	N/A
J133-00-00	Enclosed Reach	84" RCP	N/A
J133-00-00	Zion Road	72" RCP	N/A

15.3 Outside Agency Projects & Agency Coordination

No improvements were identified by HCFCF for this channel. Harris County Precinct indicated no roadway improvements within this basin area.

15.4 Drainage Issues & Problematic Area

The drainage area has localized drainage issues due to overflows and limited capacity of storm sewer / drainage systems. The sandy soils within the area pose additional issues through excessive erosion of the existing drainage infrastructure.

15.4.1 Historic Flooding

Localized historic flooding has been documented within Tomball Hills Subdivision, specifically along Camille Drive, and Sherwood Subdivision.

15.4.2 J133-00-00 Channel Erosion Failures

J133-00-00 channel consists of sandy, dispersive soils causing frequent erosion to the North Star Estates Subdivision. Cohesionless and dispersive soils subjected to high shear stresses, due to channel velocities, lead to significant erosion and potential instability within the channel. The City has recently implemented a mechanically-stabilized earthen wall behind a specific residential lot, however erosive issues continue in the lower and upper reaches of the J133-00-00 channel.

15.4.3 Tomball Hills Subdivision (J100)

Due to the shallow grade and lack of storm sewer along Zion Road, it appears an overflow from south of Zion Road travels down Alice Lane to the knuckle at Camille Drive. From visual observation, it appears inlet repairs have been previously implemented to assist in the collection of runoff from the contributing areas and overflow from Zion Road. Lack of inlet capacity and storm sewer capacity cause street ponding and increase the risk of potential structural flooding for residential properties located at this low point.

15.4.4 Sherwood Forest Subdivision

Sherwood Forest Subdivision has report multiple drainage and localized flooding issues. These stem from various causes such as inadequate ditch capacity, small driveway culverts, and flow path blockages. The City has previously investigated and addressed these issues through re-grading of roadside ditches, replacement of driveway culverts, addition of a detention basin at the north end of Wickerford Drive, and improvement of the area's outfall at Wickford Drive to the J133-00-00 channel.

15.4.5 Spring Pines Subdivision

Spring Pines has previously experienced drainage issues with regards to the erosion failures within its detention basin caused by overtaxing of the basin due to overflows from Sherwood Forest Subdivision. The City has previously investigated and addressed localized drainage and erosion issues through the interception and re-direction of Sherwood Forest overflow, restoring of the detention basin configuration, and basin overflow interceptor structure to reduce erosion.

15.5 Proposed Alternatives

Although no capacity increase is proposed along the channel, a stability project is recommended to re-establish the channel configuration and reduce future failures and maintenance issues.

15.5.1 (1) J133-00-00 Channel Rehabilitation

J133-00-00 channel consists of sandy, dispersive soils causing frequent erosion to the North Star Estates Subdivision. Channel rehabilitation may include soft and hard revetments to restore the channel banks and prevent future erosion. Soft revetment options may include geotextile fabric and other bio engineered, flexible channel lining systems. Hard revetments options may include gabion mattresses, low-profile retaining walls, concrete-lining, module blocks, or hardened geosynthetics. Revetment types should consider channel velocities, sheer stress, and economics for suitable solution alternatives.

15.5.2 (1) Tomball Hills Subdivision Storm Sewer

Construct two pairs of flanking inlets (west and south) as well as reconstructing the sag inlets at the Camille Drive and Alice Lane knuckle for increased inlet capacity. Construct parallel storm sewer system along northern curb line of Camille Drive and eastern side of Stella Lane curb line such that existing storm sewer system remains in place. Acquire a drainage easement for a new outfall combining the existing and proposed parallel storm sewer to J100-00-00 (Spring Creek).

During final design, alternative locations for a new outfall location may be evaluated for an economical solution.

16.0 DRAINAGE CRITERIA AND STANDARDS

The City of Tomball, Texas authorized an update to the City's Drainage Criteria Manual (DCM), which was originally published and adopted in 2011, updated in June 2021. The DCM establishes rules and regulations that must be consistently followed and enforced throughout the City for drainage design and implementation.

16.1 Disclaimer

This manual is intended to provide criteria for the most commonly encountered drainage and control designs in City of Tomball. The manual was written for users with knowledge and experience in the applications of standard engineering principles and practice of stormwater design and management. The purpose of the Drainage Criteria Manual is to provide a property owner, developer, and/ or engineer with information and instruction necessary for creating drainage plans that will promote the owner's interests and objectives while protecting the health and safety of the community.

The DCM policies and design criteria shall not create liability on the part of City of Tomball or any office or employee thereof for any flood damage, property damage, or personal injury that results from reliance on these policies or any administrative decision lawfully made.

16.2 No Adverse Impact

No adverse impact is the principle that the actions of any community or property owner, public or private, should not adversely impact on the property and rights of others. No adverse impact management offers a way to prevent the worsening of flooding and other negative impacts on the community. Adverse impacts as they relate to drainage improvements can be measured by flow rate, water surface elevation, velocity, flow type, erosion and sedimentation, or other measurable adverse impacts to a community's well-being.

For all drainage projects located in the City of Tomball and its ETJ, the following criteria must be met for drainage plan approval:

- **Peak Flow:** No increase to peak flow leaving the project. This is determined by comparing pre-project versus post-project flow rates.
- **Water Surface:** No increase to the water surface elevations upstream, downstream, or to adjacent properties as this would result in increased flooding.
- **Velocity:** No increase to the velocity so as to cause scour or erosion within or around the project site.
- **Flow type:** Consideration of flow type changes (e.g. overland sheetflow versus concentrated point discharge) with regards to receiving system and potential erosion.

16.3 Drainage Facility Maintenance

All detention facilities construction by a property owner or developer shall be maintained by the property owner or developer, their legal heir(s), grantee(s), successor(s), or assignee(s). The maintenance party responsible at the time of development must be noted on the Engineering Plans.

The maintenance of detention and drainage facilities is critical for ensuring that these facilities will operate as intended during rainfall events. The property owner or developer shall ensure that the drainage facilities are functioning as designed and being properly maintained.

The City of Tomball will not be responsible for the maintenance of any detention pond within the City unless specific criteria have been met and the City has formally accepted the facility for maintenance.

16.4 Design Criteria Manual Updates

This Design Criteria Manual update supersedes the previous document of the same name date June 7, 2021. All items listed herein are intended to supersede those documents.

The City of Tomball recognizes the need to control flooding and detain excess runoff from orderly development. Due to updates to technology and methodologies used to analyze hydrologic and hydraulic conditions, this update is intended to capture best practices in development and redevelopment while continuing to provide sufficient criteria to decrease the likelihood of flooding due to development and construction.

Below are major revisions to the DCM. A copy of the DCM can be found in **Appendix A**.

- Application of Rational Method – Calculation of Runoff Coefficient using composite C factor calculations
- Time of Concentration (Tc) Determination – Replaced area-based Tc methodology with velocity-based Tc methodology
- Added Roadway Drainage Criteria Hierarchy – Roadway classification will determine allowable ponding widths using a 25-year design storm event with design HGL one foot below gutter elevations
- Storm Sewer Placement – Storm sewer shall be placed under the outside curb or edge of pavement, as opposed to the center of the roadway, for consideration of future maintenance and traffic control
- Detention Criteria
 - A minimum 0.75 ac-ft/ac storage rate is required for all development, regardless of development size
 - Provided detention criteria for SFR tracts with a single structure based on tract size and impervious cover

- A minimum 0.75 ac-ft/ac for all development, regardless of development size
- For projects over 5 acres, either the Small Watershed Method (Malcolm's Method) or Clarks Unit Hydrograph shall be used to estimate detention volume with appropriate computer modelling software
- Approval of detention through ponding in truck courts/parking area at the discretion of City staff.
- Minimum detention pond maintenance berm widths based on pond depth.

16.5 Technical Specifications

Part of the drainage master plan included review of City drainage standards and specifications based on adjacent municipality standards, constructability, and maintenance issues and needs. The updated specifications (redlined copy) are provided in **Appendix B**. Below are descriptions of major revisions to the City drainage specifications.

Private development has been using thermoplastic pipe, specifically high-density polyethylene (HDPE) pipe and polypropylene (PP) pipe, for stormwater drainage application for many years due to the lightweight composition and cost efficiency. In the past, state and local governments did not allow such materials to be used in transportation projects, rather the conventional reinforced concrete pipe sections. However, the Texas Department of Transportation and Harris County Engineering Department have recently adopted the use of PP pipe and HDPE pipe. In general, polypropylene pipe provides a more rigid section than the HDPE option. One key component to the use of thermoplastic pipe is proper installation related to the soil envelope, or the bedding and backfill, of the drainage conduit.

Specific use of PP and HDPE pipe in lieu of current standards within City right-of-way shall be as follows:

- Storm Drain (Trunkline and Inlet Leads) – PP Pipe
- Cross Culverts – PP Pipe
- Parallel Culverts – PP Pipe or HDPE Pipe

The City's Technical Specifications and Construction Standards have been revised to accommodate the use of thermoplastic pipe within the right-of-way. Listed below are specifications that have been added and/or revised. These specifications and construction standards are included in **Appendix B**.

- Section 02505 – High Density Polyethylene (HDPE) Solid and Profile Wall Pipe
- Section 02509 – Thermoplastic Pipe Culverts and Drains
- Section 02631 – Storm Sewers
- COT STM-40 Storm Bedding and Backfill for Thermoplastic Pipe

17.0 CAPITAL IMPROVEMENT PLAN

A drainage master plan presents potential projects for future implementation to reduce existing flooding and provide drainage infrastructure for future municipal infrastructure improvements and potential development needs. The drainage Capital Improvement Plan (CIP) includes short-term and long-term strategic plans for the City's drainage infrastructure development based on cost, benefit, prioritization, and funding availability. The City's drainage CIP listing is derived from the projects proposed within the drainage master plan and categories based on a prioritization evaluation.

17.1 Proposed Project Cost Estimates

The cost for the proposed improvements for the proposed drainage improvements were estimated based on unit cost rates and quantity estimations of proposed improvement elements. Probable construction costs associated with the proposed improvements were estimated based on project bid unit cost information obtained from Texas Department of Transportation Department (TxDOT), Harris County Flood Control District (HCFCD), and local recent construction projects. The unit costs obtained include such items as: channel excavation, detention excavation, culvert/ storm sewer pipes and boxes, inlets and manholes, culvert end treatments, concrete paving, pavement cut-n-restore, and etc. A 25-percent consultant (engineering) fee and 30-percent contingency fee, both based on the preliminary project subtotal amount, were added into the cost estimate. The contingency percentage is set based on the preliminary stage of the cost estimate and the potential for unit cost escalation prior to construction. Additionally, right-of-way acquisition was included in the overall cost estimate based on acreage unit cost with a 10-percent added contingency. The itemized unit cost is provided within **Appendix C**. Detailed cost estimates for each project are provided in **Appendix C**. A CIP cost summary based on these detailed estimates is provided in **Appendix D**.

17.2 Prioritization

As part of the CIP development, prioritization of the projects was performed. A set of prioritization criteria was developed to select future drainage projects that provide a drainage benefit/ relief of existing flooding, contribute to the improvement of the community's well-being, support the development of the community, maintain the benefits of existing drainage systems, help protect natural habitat and landscapes, and provide multiple-use opportunities for flood control facilities. The prioritization criteria generally considered basic criteria such as: historical flooding, system inadequacy, downstream improvements independency, regional benefits, cost, and funding sources as well as City staff input.

The proposed CIP drainage projects were divided into CIP categories of 5-year, 10-year, and long-range planning horizons based on the prioritization evaluations and discussions with

City staff. A summary of CIP projects for the planning aforementioned planning horizons is summarized in **Table 17-1**.

TABLE 17-1. DMP CIP COST SUMMARY PER BASIN

BASIN	5-YEAR PLAN	10-YEAR PLAN	LONG-RANGE PLAN	CIP TOTAL (2024 \$)
M116	\$-	\$231,338	\$7,583,931	\$7,815,269
M118	\$4,394,715	16,166,527	\$9,621,315	\$30,182,557
M121	\$10,051,638	10,752,970	\$92,104,021	\$112,908,629
M124	\$-	\$3,837,708	\$13,705,488	\$17,543,196
M125	\$-	\$952,710	\$-	\$952,710
J100	\$-	\$845,385	\$-	\$845,385
J131	\$16,717,935	\$3,958,253	\$45,140,882	\$65,817,070
J132	\$-	\$-	\$-	\$-
J133	\$-	\$2,371,500	\$-	\$2,371,500
TOTAL	31,164,288	39,116,390	168,155,637	\$238,436,316

17.3 Financing / Funding Alternatives

Financing alternatives should be investigated by the City for the proposed drainage improvements. Additional outside funding sources are potentially available to complement the City's drainage CIP program. These include grant programs from State and Federal agencies, such as TWDB, GLO, FEMA, etc. Below are potential alternative sources for funding of the proposed drainage projects, including grants or fees from external and local funding sources. Other funding alternatives are available besides the ones detailed below.

17.3.1 Federal & State Grants

The Flood Mitigation Assistance (FMA) Program is a federal grant program administered by the Texas Water Development Board (TWDB), under an Agreement with the Federal Emergency Management Agency (FEMA). This program provides federal funding to assist States and communities in implementing measures to reduce or eliminate the long-term risk of flood damage to buildings, manufactured homes, and other structures insurable under the National Flood Insurance Program (NFIP). The FMA program was created as part of the National Flood Insurance Reform Act of 1994 (42 U.S.C. 4101) with the goal of reducing or eliminating claims under the NFIP. The FMA is a pre-disaster grant program. There are two types of work that can be funded: Planning Grants and Project Grants. The proposed drainage improvements would need to meet the specific grant standards to be eligible.

The Federal Emergency Management Agency (FEMA), through the Texas Division of Emergency Management, has provided substantial federal funding for the purchase of

flooded homes through FEMA's Pre-Disaster Mitigation (PDM) program and Hazard Mitigation Grant Program (HMGP). Federal funding for home buyout usually requires local matching funds of at least 25%. It is important to note that, although some grant funds are made available only after a disaster declaration, these buyout grants do not provide immediate flood recovery assistance. These programs typically take eight to twelve months after the flood event to even get started, and then may take place over a period of many years following a flood event.

17.3.2 Loan Financing Assistance Program

Financial assistance, in the form of low-interest rate loans administered by TWDB through the Texas Water Development Fund, is potentially available as a funding source to the City for drainage improvement projects. Potential loan repayment sources may include taxes, fees, and/or bond issuances.

17.3.3 Inter-agency Agreements/ Shared Funding

Several projects proposed will provide infrastructure improvements and benefits for adjacent agencies, such as Harris County, Harris County Flood Control District, and Texas Department of Transportation. The City may partner with the respective agency (s) to assist in funding and/ or construction of the improvements.

18.0 BASIN IMPACT FEE

The City of Tomball has multiple drainage basins with current impact fees associated with previously proposed drainage CIP projects. These basin impact fees were calculated based on the City's 2007 CIP report. These basin impact fees were adopted on May 18, 2009 by the City of Tomball. These impact fees are imposed upon new development based on a dollar per acre amount constructed within the respective drainage basin. As part of the 2007 CIP projects, impact fee rates were established with a maximum fee rate. The current basin impact fees and maximum basin fees are listed in **Table 18-1**.

TABLE 18-1. CITY OF TOMBALL CURRENT BASIN DEVELOPMENT FEES

Basin	Effective Date	Current Basin Fee	Service Unit
M118	6/01/2009	\$6,023.00	Per Acre
M121East	6/01/2009	\$6,828.71	Per Acre
M121West	6/01/2009	\$4,985.14	Per Acre
M125	6/01/2009	\$574.40	Per Acre

18.1 Collection of Basin Impact Fees


The current available records of collected basin impact fees, received through June 2024, were obtained from the City. These fee records were investigated and the total amount of impact fees received per basin are summarized in **Table 1-2**.

TABLE 18-2. CITY OF TOMBALL CURRENT BASIN DEVELOPMENT FEES

Basin	Collected Basin Fees
M118	\$440,713.72
M121East	\$51,567.62
M121West	\$1,093,876.85
M125	\$39,442.53

Known locations of impact fees collected have been identified on Basin Impact Maps included as exhibits in **Appendix E**.

EXHIBITS




Legend

- TOMBALL CITY LIMITS
- COUNTY PRECINCTS
- DITCH WATERSHEDS
- DRAINAGE DITCHES


CSE Civil Systems
Engineering, Inc.
1202 Lake Pointe Parkway
Sugar Land, TX 77478

**CITY OF TOMBALL
MASTER DRAINAGE STUDY
OVERALL DRAINAGE BASIN MAP**

DWG INFO: P:\532301_TOMBALL_MDP\CAD\532301_SUBBASIN AND PONDS.DWG



- STORM SEWER DESIGN CRITERIA**
1. DESIGN STORM EVENT: 25-YEAR
 2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
 3. 100-YR HGL: 1 FOOT BELOW GUTTER
 4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
 5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS



CIP LEGEND	
1	CHANNEL CIP
2	STORM SEWER CIP
3	DETENTION CIP

LEGEND	
	EXISTING STORM SEWER
	EXISTING CHANNEL
	EXISTING DETENTION
	BASIN BOUNDARY
	SUBBASIN BOUNDARY
	TRIBUTARY DIVIDES
	PROPOSED STORM SEWER
	PROPOSED CHANNEL
	PROPOSED DETENTION
	CITY LIMITS
	← BASIN ID
	← SUBBASIN ID
	← DRAINAGE AREA IN ACRES




CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN
M116 DRAINAGE CAPITAL IMPROVEMENTS
PLAN & SUBBASIN DELINEATION**


SCALE: 1" = 0.25 mi
EXHIBIT NO. 2

March 2025
M116 BASIN

DWG INFO: P:\532301_TOMBALL_MDP\CAD\532301_SUBBASIN AND PONDS.DWG



- STORM SEWER DESIGN CRITERIA**
1. DESIGN STORM EVENT: 100-YEAR
 2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
 3. 100-YR HGL 1 FOOT BELOW GUTTER
 4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
 5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
 6. ALL WATERSHED DETENTION ASSUMED WITHIN M518-01 AND M518-02 ULTIMATE BASINS



CIP LEGEND	
1	CHANNEL CIP
2	STORM SEWER CIP
3	DETENTION CIP

LEGEND	
	EXISTING STORM SEWER
	EXISTING CHANNEL
	EXISTING DETENTION
	BASIN BOUNDARY
	SUBBASIN BOUNDARY
	TRIBUTARY DIVIDES
	PROPOSED STORM SEWER
	PROPOSED CHANNEL
	PROPOSED DETENTION
	CITY LIMITS
	← BASIN ID
	← SUBBASIN ID
	← DRAINAGE AREA IN ACRES



CSE Civil Systems
Engineering, Inc.


**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

M118 DRAINAGE CAPITAL IMPROVEMENTS
PLAN & SUBBASIN DELINEATION


SCALE: 1" = 0.25 mi
EXHIBIT NO. 3

March 2025
M118 BASIN

DWG INFO: P:\532301_TOMBALL_MDP\CAD\532301_SUBBASIN AND PONDS.DWG



- DESIGN CRITERIA**
1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
 2. DESIGN STORM EVENT (CHANNEL): 100-YEAR
 3. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
 4. 25-YR HGL 1 FOOT BELOW GUTTER
 5. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
 6. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
 7. MITIGATION OF M121-02-00 WILL BE ACCOMMODATED IN M521-01 DETENTION POND



- CIP LEGEND**
- 1 CHANNEL CIP
 - 2 STORM SEWER CIP
 - 3 DETENTION CIP

- LEGEND**
- EXISTING STORM SEWER
 - EXISTING CHANNEL
 - EXISTING DETENTION
 - BASIN BOUNDARY
 - SUBBASIN BOUNDARY
 - TRIBUTARY DIVIDES
 - PROPOSED STORM SEWER
 - PROPOSED CHANNEL
 - PROPOSED DETENTION
 - CITY LIMITS
 - M121 BASIN ID
 - 34 SUBBASIN ID
 - 50.0 DRAINAGE AREA IN ACRES



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

**M121 DRAINAGE CAPITAL IMPROVEMENTS
PLAN & SUBBASIN DELINEATION**


SCALE: 1" = 0.25 mi

March 2025


EXHIBIT NO. 4

M121 BASIN

DWG INFO: P:\532301_TOMBALL_MDP\CAD\532301_SUBBASIN AND PONDS.DWG



STORM SEWER DESIGN CRITERIA
1. DESIGN STORM EVENT: 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
3. 100-YR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. HCFCD PROJECT M124-00-00-E002 (FROM WILLOW CREEK TO SH 249)



CIP LEGEND	
1	CHANNEL CIP
2	STORM SEWER CIP
3	DETENTION CIP

LEGEND	
	EXISTING STORM SEWER
	EXISTING CHANNEL
	EXISTING DETENTION
	BASIN BOUNDARY
	SUBBASIN BOUNDARY
	TRIBUTARY DIVIDES
	PROPOSED STORM SEWER
	PROPOSED CHANNEL
	PROPOSED DETENTION
	CITY LIMITS
	← BASIN ID ← SUBBASIN ID ← DRAINAGE AREA IN ACRES



CSE Civil Systems
Engineering, Inc.



**CITY OF TOMBALL
DRAINAGE MASTER PLAN
M124 DRAINAGE CAPITAL IMPROVEMENTS
PLAN & SUBBASIN DELINEATION**

SCALE: 1" = 0.25 mi

March 2025

EXHIBIT NO. 5

M124 BASIN



- STORM SEWER DESIGN CRITERIA**
1. DESIGN STORM EVENT: 25-YEAR
 2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
 3. 25-YR HGL - 1 FOOT BELOW GUTTER
 4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
 5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

- CIP LEGEND**
- 1 CHANNEL CIP
 - 2 STORM SEWER CIP
 - 3 DETENTION CIP

- LEGEND**
- EXISTING STORM SEWER
 - EXISTING CHANNEL
 - EXISTING DETENTION
 - BASIN BOUNDARY
 - SUBBASIN BOUNDARY
 - TRIBUTARY DIVIDES
 - PROPOSED STORM SEWER
 - PROPOSED CHANNEL
 - PROPOSED DETENTION
 - CITY LIMITS
 - BASIN ID
 - SUBBASIN ID
 - DRAINAGE AREA IN ACRES



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**


**M125 DRAINAGE CAPITAL IMPROVEMENTS
PLAN & SUBBASIN DELINEATION**

SCALE: 1" = 0.25 mi

March 2025











EXHIBIT NO. 6


M125 BASIN




CIP LEGEND	
1	CHANNEL CIP
2	STORM SEWER CIP
3	DETENTION CIP

LEGEND

	EXISTING STORM SEWER
	EXISTING CHANNEL
	EXISTING DETENTION
	BASIN BOUNDARY
	SUBBASIN BOUNDARY
	TRIBUTARY DIVIDES
	PROPOSED STORM SEWER
	PROPOSED CHANNEL
	PROPOSED DETENTION
	CITY LIMITS

	← BASIN ID
	← SUBBASIN ID
	← DRAINAGE AREA IN ACRES



**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

**J131 DRAINAGE CAPITAL IMPROVEMENTS
PLAN & SUBBASIN DELINEATION**


SCALE: 1" = 0.25 mi

March 2025

EXHIBIT NO. 7

J131 BASIN

DWG INFO: P:\532301_TOMBALL_MDP\CAD\532301_SUBBASIN AND PONDS.DWG



- DESIGN CRITERIA
1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
 2. DESIGN STORM EVENT (CHANNEL): 100-YEAR
 3. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
 4. 25-YR HGL 1 FOOT BELOW GUTTER
 5. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
 6. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

- CIP LEGEND
- | | |
|---|-----------------|
| 1 | CHANNEL CIP |
| 2 | STORM SEWER CIP |
| 3 | DETENTION CIP |

- LEGEND
- | | |
|--|------------------------|
| | EXISTING STORM SEWER |
| | EXISTING CHANNEL |
| | EXISTING DETENTION |
| | BASIN BOUNDARY |
| | SUBBASIN BOUNDARY |
| | TRIBUTARY DIVIDES |
| | PROPOSED STORM SEWER |
| | PROPOSED CHANNEL |
| | PROPOSED DETENTION |
| | CITY LIMITS |
| | BASIN ID |
| | SUBBASIN ID |
| | DRAINAGE AREA IN ACRES |



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL
DRAINAGE MASTER PLAN

J100, J132 & J133 DRAINAGE CAPITAL
IMPROVEMENTS PLAN & SUBBASIN DELINEATION

SCALE: 1" = 1,000'

March 2025

EXHIBIT NO. 8

J100, J132 & J133 BASIN

APPENDIX A

DRAINAGE DESIGN CRITERIA MANUAL

(Updated March 2025)

APPENDIX B

DRAINAGE DESIGN SPECIFICATIONS

Section 02505

HIGH DENSITY POLYETHYLENE (HDPE)
SOLID AND PROFILE WALL PIPE

PART 1 GENERAL

1.1 SECTION INCLUDES

1. High density polyethylene (HDPE) pipe for gravity sewers and drains, including fittings.
2. High density polyethylene (HDPE) pipe for sanitary sewer force mains, including fittings.
- ~~3. High density polyethylene (HDPE) pipe drains and fittings, for gravity storm sewers 12 inches through 48 inches.~~

1.2 MEASUREMENT AND PAYMENT

1. Unit Prices.
 1. No separate payment will be made for HDPE pipe under this Section. Include cost in unit prices for work, as specified in following sections:
 1. Section 02531 - Gravity Sanitary Sewers.
 2. Section 02532 - Sanitary Sewer Force Mains.
 2. Refer to Section 01270 - Measurement and Payment for unit price procedures.
2. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment for work in this Section is included in total Stipulated Price.

1.3 REFERENCES

1. AASHTO M 294 - Standard Specification for Corrugated Polyethylene Drainage Pipe, 18" - 48" diameter.
2. AASHTO Section 18 - Soil Thermoplastic Pipe Interaction Systems.
3. AASHTO Section 30 - Standard Practice for Underground Installation of Thermoplastic Pipe for Sewer and Other Gravity Flow Applications.
4. ASTM D 618 - Standard Practice for Conditioning Plastics for Testing.

5. ASTM D 1248 - Standard Specification for Polyethylene Plastics Extrusion Materials for Wire and Cable.
6. ASTM D 2321 - Standard Recommended Practice for Underground Installation of Flexible Thermoplastic Pipe.
7. ASTM D 2657 - Standard Practice for Heat Fusion Joining Polyolefin Pipe and Fittings.
8. ASTM D 2837 - Standard Test Method for Obtaining Hydrostatic Design Basis for Thermoplastic Pipe Materials.
9. ASTM D 3035 - Standard Specification for Polyethylene (PE) Plastic Pipe (DR-PR) Based on Controlled Outside Diameter.
10. ASTM D 3212 - Standard Specification for Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals.
11. ASTM D 3350 - Standard Specification for Polyethylene Plastics Pipe and Fittings Materials.
12. ASTM F 477 - Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe.
13. ASTM F 714 - Standard Specification for Polyethylene Plastic (PE) Pipe (SDR-PR) Based on Outside Diameter.

~~14. ASTM F 894 - Standard Specification for Polyethylene (PE) Large Diameter Profile Wall Sewer and Drain Pipe.~~

1.4 SUBMITTALS

1. Conform to requirements of Section 01330 - Submittal Procedures.
2. Submit shop drawings showing design of pipe and fittings, laying dimensions, fabrication, fittings, flanges, and special details.

1.5 QUALITY CONTROL

1. Provide manufacturer's certificate of conformance to Specifications.
2. Furnish pipe and fittings that are homogeneous throughout and free from visible cracks, holes, foreign inclusions, or other injurious defects. Provide pipe as uniform as commercially practical in color, opacity, density, and other physical properties.

3. City Engineer reserves right to inspect pipes or witness pipe manufacturing. Inspection shall in no way relieve manufacturer of responsibilities to provide products that comply with applicable standards and these Specifications.
 1. Manufacturer's Notification: Should City Engineer wish to witness manufacture of specific pipes, manufacturer shall provide City Engineer with minimum three weeks notice of when and where production of those specific pipes will take place.
 2. Failure to Inspect. Approval of products or tests is not implied by City Engineer's decision not to inspect manufacturing, testing, or finished pipes.

1.6 QUALIFICATIONS

1. Manufacturer: Company specializing in manufacturing the products specified in this section with documented experience of minimum 5 years of pipe installations that have been in successful, continuous service for same type of service as proposed Work.

PART 2 PRODUCTS

1.7 GENERAL

1. For sewer pipe provide HDPE pipe as follows:
 1. NEW CONSTRUCTION PIPE PRODUCTS
GRAVITY SANITARY SEWER
DIRECT BURY

INSTALLATION SPEC NO.	GENERIC NAME	TRADE NAME <u>OR</u> <u>MANUFACTURER</u>	ASTM OR AASHTO	SDR (NUMERIC MAXIMUM)	PIPE STIFFNESS (NUMERIC MINIMUM)	SIZE RANGE
02505	Solid Wall Polyethylene (HDPE)	Chevron Plexco Phillips 66 Quail Poly Pipe	ASTM F-714	DR 17 DR 21	115 46	8" - 10" 12" - 48"
02531	Polyethylene Profile Wall	Spirolite	ASTM F-894	n/a	46	18" - 120"

2. REHABILITATION CONSTRUCTION PIPE PRODUCTS
SLIPLINING OF SANITARY SEWER

INSTALLATION SPEC NO.	GENERIC NAME	TRADE NAME <u>OR</u> <u>MANUFACTURER</u>	ASTM	SDR (NUMER IC MAXIMUM)	PIPE STIFFNESS (NUMERIC MINIMUM)	SIZE RANGE
02550	Solid Wall Poly	Chevron Plexco <u>Quail Poly Pipe</u> <u>AmeriFlow by</u> <u>NAPCO</u> <u>AmeriFlow by KWH</u>	F-714	DR 21	46	8" - 48" <u>3" - 12"</u> <u>14" - 63"</u>
02550	Polyethylene Profile Wall	Spirolite	F-894	n/a	46	18" - 120"

~~2. For Residential Driveway Culverts provide HDPE as follows:~~

~~1. N-12 and N-12 HC by Advanced Drainage Systems, Inc. (ADS).~~

~~2. Sure-Lok F477 by Hancor, Inc.~~

3. Furnish solid wall pipe with plain end construction for heat joining (butt fusion) conforming to ASTM D 2657. Utilize controlled temperatures and pressures for joining to produce fused leak-free joint.
4. Furnish profile-wall gravity sewer pipe with bell-and-spigot end construction conforming to ASTM D 3212. Joining will be accomplished with elastomeric gasket in accordance with manufacturer's recommendations. Use integral bell-and-spigot gasketed joint designed so that when assembled, elastomeric gasket, contained in machined groove on pipe spigot, is compressed radially in pipe bell to form positive seal. Design joint to avoid displacement of gasket when installed in accordance with manufacturer's recommendations.
5. Furnish solid wall pipe for sanitary sewer force mains with minimum working pressure rating of 150 psi, and with inside diameter equal to or greater than nominal pipe size indicated on Drawings.
6. Furnish corrugated polyethylene pipe (CPP) for gravity storm sewer pipe. Joints shall be installed such that connection of pipe sections will form continuous line free from irregularities in flow line. Suitable joints are:

1. Integral Bell and Spigot. Bell shall overlap minimum of two corrugations of spigot end when fully engaged.
 2. Exterior Bell and Spigot. Bell shall be fully welded to exterior of pipe and overlap spigot end so that flow lines and ends match when fully engaged.
7. Jointing:
1. Gaskets:
 1. Meet requirements of ASTM F 477. Use gasket molded into circular form or extruded to proper section and then spliced into circular form. When no contaminant is identified, use gaskets of properly cured, high-grade elastomeric compound. Basic polymer shall be natural rubber, synthetic elastomer, or blend of both.
 2. Pipes allowed to be installed in potentially contaminated areas, where free product is found near elevation of proposed sewer, shall have the following gasket materials for noted contaminants:

CONTAMINANT	GASKET MATERIAL REQUIRED
Petroleum (diesel, gasoline)	Nitrile Rubber
Other Contaminants	As recommended by pipe manufacturer

2. Lubricant. Use lubricant for assembly of gasketed joints which has no detrimental effect on gasket or on pipe, in accordance with manufacturer's recommendations.

1.8 MATERIALS FOR SANITARY SEWER

1. Pipe and Fittings: High density, high molecular weight polyethylene pipe material meeting requirements of Type III, Class C, Category 5, Grade P34, as defined in ASTM D 1248. Material meeting requirements of cell classification in accordance with ASTM D 3350 are also suitable for making pipe products under these specifications.
2. Other Pipe Materials: Materials other than those specified in Paragraph 2.02A, Pipe and Fittings, may be used as part of profile construction, e.g., as core tube to support shape of profile during processing, provided that these materials are compatible with base polyethylene material and are completely encapsulated in finished product and in no way compromise performance of pipe products in intended use. Examples of suitable material include polyethylene and polypropylene.

~~1.9 MATERIALS FOR RESIDENTIAL DRIVEWAY CULVERTS~~

- ~~1. Pipe and Fittings: High density, high molecular weight polyethylene HDPE virgin compound material meeting requirements of cell class outlined in AASHTO M 294, AASHTO MP7 and ASTM D 3350.~~
- ~~2. Types: CPP shall meet one or both of following:~~
 - ~~1. Type S: Outer corrugated wall with smooth inner liner.~~
 - ~~2. Type D: Inner and outer smooth walls braced circumferentially or spirally with projections or ribs.~~
- ~~3. Lubricant: Use lubricant for assembly of gasketed joints, which has no detrimental effect on gasket or on pipe, in accordance with manufacturer's recommendations.~~

1.10.9 TEST METHODS FOR SANITARY SEWER

1. Conditioning. Conditioning of samples prior to and during tests are subject to approval by City Engineer. When referee tests are required, condition specimens in accordance with Procedure A in ASTM D 618 at 73.4 degrees F plus or minus 3.6 degrees F and 50 percent relative humidity plus or minus 5 percent relative humidity for not less than 40 hours prior to test. Conduct tests under same conditions of temperature and humidity unless otherwise specified.
2. Flattening. Flatten three specimens of pipe, prepared in accordance with Paragraph 2.05A, in suitable press until internal diameter has been reduced to 40 percent of original inside diameter of pipe. Rate of loading shall be uniform and at 2 inches per minute. Test specimens, when examined under normal light and with unaided eye, shall show no evidence of splitting, cracking, breaking, or separation of pipe walls or bracing profiles.
3. Joint Tightness. Test for joint tightness in accordance with ASTM D 3212, except replace shear load transfer bars and supports with 6-inch-wide support blocks that can be either flat or contoured to conform to pipe's outer contour.
4. Purpose of Tests. Flattening and joint tightness tests are not intended to be routine quality control tests, but rather to qualify pipe to a specified level of performance.

~~1.11~~ TEST METHODS FOR RESIDENTIAL DRIVEWAY CULVERTS

- ~~1. Pipe stiffness at 5% deflection, when determined in accordance with ASTM D 2412, shall be as specified in Section 7.4 of AASHTO M 294.~~

~~2.5. Minimum inner wall thickness shall be as specified in Section 7.2.2 of AASHTO M 294.~~

1.12.10 MARKING

1. Mark each standard and random length of pipe in compliance with these Specifications with following information:
 1. Pipe size.
 2. Pipe class.
 3. Production code.
 4. Material designation.

PART 3 EXECUTION

~~1.13~~1.11 INSTALLATION

1. Conform to requirements of following Sections:
 1. Section 02550 - Sliplining Sanitary Sewers.
 2. Section 02531 - Gravity Sanitary Sewers.
 3. Section 02532 - Sanitary Sewage Force Mains.
 4. Section 02533 - Acceptance Testing for Sanitary Sewers.
2. Install pipe in accordance with the manufacturer's recommended installation procedures.
3. HDPE pipe is not approved in applications requiring augering of pipe.
4. Bedding and backfill: Conform to requirements of Section 02317 - Excavation and Backfill for Utilities.

END OF SECTION

Section 02509

**THERMOPLASTIC PIPE CULVERTS
AND DRAINS**

PART 1 G E N E R A L

1.01 SECTION INCLUDES

- A. Corrugated High-Density Polyethylene (HDPE) pipe for culverts, including fittings.
- B. Polypropylene (PP) pipe for storm sewers.

1.02 MEASUREMENT AND PAYMENT

- A. Unit Prices.
 - 1. No separate payment will be made for HDPE or PP pipe under this Section. Include cost in unit prices for work, as specified in following sections:
 - a. Section 02631 - Storm Sewers.
 - 2. Refer to Section 01270 - Measurement and Payment for unit price procedures.
- B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment for work in this Section is included in total Stipulated Price.

1.03 REFERENCES

- A. AASHTO M 294 - Standard Specification for Corrugated Polyethylene Pipe, 300 mm to 1500 mm (12 in. to 60 in.) Diameter
- B. AASHTO M 330 - Standard Specification for Polypropylene Pipe, 300 mm to 15000 mm (12 in. to 60 in.) Diameter
- C. AASHTO Standard Specifications for Highway Bridges
- D. ASTM D 3212 - Standard Specification for Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals.
- E. ASTM D 3350 - Standard Specification for Polyethylene Plastics Pipe and Fittings Materials.
- F. ASTM F 477 - Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe.

- G. Plastic Pipe Institute Drainage Handbook

1.04 SUBMITTALS

- A. Conform to requirements of Section 01330 - Submittal Procedures.
- B. The Contractor shall submit a certificate of compliance of the pipe product that is manufactured in accordance with AASHTO M330. Supplying manufacturing facilities shall be in compliance with AASHTO's National Transportation Product Evaluation Program (NTPEP) for the specified pipe product.
- C. Submit manufacturer's installation specifications before beginning work. Maximum fill depth and backfill requirements shall be included in the manufacturer's installation specifications.

1.05 QUALITY CONTROL

- A. Provide manufacturer's certificate of conformance to Specifications.
- B. Furnish pipe and fittings that are homogeneous throughout and free from visible cracks, holes, foreign inclusions, or other injurious defects. Provide pipe as uniform as commercially practical in color, opacity, density, and other physical properties.
- C. Engineer reserves right to inspect pipes or witness pipe manufacturing. Inspection shall in no way relieve manufacturer of responsibilities to provide products that comply with applicable standards and these Specifications.
 - 1. Manufacturer's Notification: Should City Engineer wish to witness manufacture of specific pipes, manufacturer shall provide City Engineer with minimum three weeks notice of when and where production of those specific pipes will take place.
 - 2. Failure to Inspect. Approval of products or tests is not implied by City Engineer's decision not to inspect manufacturing, testing, or finished pipes.

PART 2 P R O D U C T S

2.01 PIPE DESIGN

- A. A "Thermoplastic Pipe Installation" detail sheet must be signed and sealed by a registered Professional Engineer licenses to practice in the State of Texas and be included in the Contract Documents when thermoplastic pipe is specified. The specifying Professional Engineer is required to confirm the conditions for the project and structural adequacy of the pipe system.

The Plastic Pipe Institute publishes an online design manual that contains information related to all aspects of design and construction of thermoplastic pipe. For structural design of plastic pipe systems see the Plastic Pipe Institute Handbook, Chapter 7 "Structural Design" (www.plasticpipe.org). Additionally, thermoplastic pipe suppliers also have

information on the use of their products.

When specifying plastic pipe on a project, the specifying Design Engineer must be aware of minimum depth of fill required and how these are measured for different pipe and pavement types.

1. Corrugated High Density Polyethylene (HDPE) Pipe

The specifying Design Engineer is responsible for ensuring that depth of fill is not less than 18 inches for pipe diameters up to 36 inches or 24 inches for pipe diameters over 36 inches. The depth of fill is measured as the distance from the top of pipe to the bottom of the flexible pavement, or from the top of the pipe to the top of rigid pavement.

2. Polypropylene Pipe

The specifying Design Engineer is responsible for ensuring that depth of fill is not less than 12 inches for pipe diameters up to 48 inches or 24 inches for pipe diameters over 60 inches. The depth of fill is measured as the distance from the top of pipe to the bottom of the flexible pavement, or from the top of the pipe to the top of rigid pavement.

Polypropylene pipes are stiffer than corrugated high-density polyethylene (HDPE) pipes which provide for more resilience against installation related deflection and is preferred for use over HDPE on transportation projects.

2.02 CORRUGATED HIGH-DENSITY POLYETHYLENE (HDPE) PIPE

- A. Corrugated high-density polyethylene pipe and fittings shall meet the requirements of AASHTO M 294.
- B. Raw Materials: Corrugated high-density polyethylene pipe and fittings manufactured from virgin polyethylene (PE) compounds shall meet the requirements of cell class 435400C as defined and described in ASTM D3350, except that the maximum allowable carbon black content is 4 percent. The PE compound used shall meet the environmental stress crack resistance according to the NCLS test set forth in AASHTO M 294.
- C. Designation Type: For corrugated high-density polyethylene pipes used in gravity flow drainage applications, use Type S (outer corrugated wall with smooth inner liner).
- D. Section Properties: The minimum wall thickness of the inner walls of Type S pipe shall meet the requirements of AASHTO M 294, Section 7.2.2. The pipe stiffness requirement of 5 percent deflection shall conform to AASHTO M 294, Section 7.4.

2.03 POLYPROPYLENE (PP) PIPE

- A. Polypropylene pipe and fittings shall meet the requirements of AASHTO M 330.

- B. Raw Materials: Polypropylene compounds used to manufacture the pipe and fittings shall meet the minimum properties of AASHTO M 330, Section 6.1.1.
- C. Designation Type: Polypropylene pipes used in gravity flow drainage applications shall be Type S (outer corrugated wall with smooth inner liner).
- D. Section Properties: The minimum wall thickness of the inner walls for Type S pipe shall meet the requirements of AASHTO M 330, Section 7.2.2. The pipe stiffness at 5 percent deflection will meet the requirements in Section 7.4 of AASHTO M 330.

2.04 PIPE TESTING

- A. The manufacturer shall perform the appropriate test procedures on representative samples of each type of pipe furnished and shall verify that the pipe complies with the specifications. A certificate of compliance shall be submitted to Engineer for review and approval. A document with the following information shall be provided: manufacturing plant, date of manufacture, pipe unit mass, material distribution, pipe dimensions, water inlet area, pipe stiffness, pipe flattening, brittleness, ASTM resin cell classification, and workmanship. Pipe shall be supplied by manufacturers and locations that are listed on TxDOT's Material Product List for Thermoplastic pipe, joints, and fittings.

2.05 PIPE INSPECTION

- A. The quality of materials, the process of manufacture, and the finished pipe will be subject to inspection and approval by Engineer at the manufacturing plant. In addition, the finished pipe will be subject to further random inspection by Engineer at the project site before and during installation, and prior to acceptance. The Engineer is responsible for ensuring the integrity of the installed pipes. The Engineer will ensure the pipe, bedding, structural backfill and stable foundation are installed and inspected correctly.

2.06 JOINTS

- A. Joints shall be installed so that the connection of the pipe sections form a continuous line free from irregularities in the flowline.
- B. Joints and Fittings shall meet the following requirements:
 - 1. Integral Bell and Spigot: The bell shall overlap a minimum of two (2) corrugations of the spigot end when fully engaged. The spigot end shall have an O-ring gasket and meet the requirements of ASTM F477.
 - 2. Exterior Bell and Spigot: Fully weld the bell to the exterior of the pipe and overlap the spigot end so that the flow lines and ends match when fully engaged. The spigot end shall have an O-ring gasket and meet the requirements of ASTM F477.
 - 3. Split Couplers: For soil-tight joint connections only, join pipe with coupling bands covering at least two full corrugations on the ends of each pipe being joined.

C. The following are joint and fitting type definitions:

1. Soil-tight Joints: Joints shall meet the soil-tightness definition in AASHTO "Standard Specifications for Highway Bridge," Section 26.4.2.4.
2. Watertight Joints: Joints shall meet the requirements of ASTM D3212.
3. If no joint type is specified in the Contract Documents, a soil-tight joint shall be provided.

2.07 MARKINGS

A. Thermoplastic pipe, fittings, and couplings furnished shall be clearly marked as follows with pipe marked at ten (10) foot intervals:

1. Manufacturer's name or trademark
2. Nominal size
3. Specification designation (i.e. AASHTO M 294 or AASHTO M 330)
4. Manufacturing plant's designation code, and date manufactured.

2.08 END SECTIONS

A. Type II Precast Safety End Treatments shall be provided for thermoplastic pipe installations beneath and adjacent to roadways. TxDOT's PSET-SC standard shall be used for cross drainage structures and TxDOT's PSET- SP standard shall be used for parallel drainage structures. Refer to City Standard Details for end section requirements.

PART 3 EXECUTION

3.01 HANDLING AND STORING PIPE

A. Pipe shall be stored above ground on adequate blocking. Pipe shall be kept clean and fully drained during storage. Handle and store thermoplastic pipe in accordance with the pipe manufacturer's instructions. Proper handling methods shall be used for hoisting and lowering the pipe into the trench.

3.02 EXCAVATION

A. Conform to requirements of Section 02317 - Excavation and Backfill for Utilities. Use bedding as indicated on Drawings. Special precautions in placing and compacting the backfill shall be taken to avoid any movement of the pipe or damage to the joints. Damaged pipe shall be removed and replaced by the Contractor at no expense to the City.

- B. Minimum Trench Width: Provide enough trench width for the pipe installation and to ensure enough working room to properly and safely place and compact material placed under haunches of the pipe and other embedment materials. Provide a space between the pipe and trench wall that is greater than that of the compaction equipment used in the pipe zone.
1. When using Type I backfill, the minimum allowable trench width is the pipe outside diameter plus 12 inches.
 2. When using Type II or Type III backfill, the minimum allowable trench width is specified in Table 1.

TABLE 1
MINIMUM TRENCH WIDTH

Nominal Pipe Diameter (in.)	Minimum Trench Width (in.)
18	44
24	54
30	66
36	78
42	84
48	90
60	103

3.03 TRENCHLESS INSTALLATION

- A. Thermoplastic pipe is not approved for augering of pipe.

3.04 INSTALLATION

- A. Laying Pipe

1. Unless approved by City, pipe sections shall not be placed in the presence of water or when trench conditions or weather is unsuitable for such work. Lay pipe sections on the bedding at the outlet end with the spigot or tongue end pointing downstream and proceed toward the inlet end with separate sections properly joined together, true to the established lines and grades. Sections of pipe shall be lowered into the trench without damaging the pipe or disturbing the bedding and the sides of the trench. The ends of the pipe shall be cleaned before mitting, matching, and laying the pipe to form a continuous, uniform conduit. The joint assembly shall be completed in accordance to the recommendations of the pipe manufacturer. Foreign matter or earth and bedding material shall be prevented from entering the pipe during and after pipe laying operation. Pipe that is not in alignment or shows excessive settlement after laying shall be removed and re-laid without extra compensation.

2. Lay multiple installation of thermoplastic pipe with the centerlines of the individual barrels parallel. Unless otherwise shown on the Contract Documents, the clear distance between outer surfaces of adjacent pipes shall conform to the minimum requirements of Table 2.

TABLE 2
MINIMUM CLEAR DISTANCE BETWEEN PIPES

Nominal Pipe Diameter (in.)	Minimum Clear Distance Between Pipes (in.)
18	14
24	17
30	20
36	23
42	26
48	29
60	32

- B. Installing Pipe in Embankment: If any portion of the pipe projects above the existing ground level, an embankment shall be constructed as shown on the Contract Documents or as directed by City, for a minimum distance outside each side of the pipe location of 5 times the diameter and to a minimum elevation of 2 feet above the top of the pipe. Excavate the trench in accordance with Section 02317 - Excavation and Backfill for Utilities.
- C. Reusing Existing Appurtenances
 1. When existing appurtenances are specified for reuse in the Contract Documents, the portion to be reused shall be separated from the existing culvert and moved to the new position previously prepared, by approved methods.
 2. Connections shall conform to the requirements for joining sections of pipes as indicated in this Section or as shown in the Contract Documents. Headwalls and aprons for pipes attached to the headwall that are damaged during moving operations shall be repaired to their original condition, at no expense to the City. The Contractor has the option to remove and dispose of the existing headwalls and aprons and construct new headwalls at no expense to the City, in accordance with the pertinent specification and design indicated in the Contract Documents or as furnished by the City.
- D. Sewer Connections and Stub Ends. Connect pipe sewer to existing sewer or sewer appurtenances as shown on the Contract Documents or as directed by the City. Mortar or concrete the bottom of existing structures, if necessary, to eliminate any drainage pockets created by the new connection. Any damage to existing structures, which are to remain in service from making the pipe sewer connection, shall be restored to the satisfaction of the City. Stub ends for connection to future work not shown on the Contract Documents shall be sealed by installing watertight plugs into the free end of the pipe. Stub end seals shall be

included in the cost of the pipe.

E. Backfilling

F. Protecting the Pipe

1. Unless otherwise shown on the Contact Documents, or permitted in writing, heavy earthmoving equipment shall not be operated over the structure until a minimum of 4 feet of permanent or temporary compacted fill is placed over the top of the structure.
2. Before adding each new layer of loose backfill material, an inspection shall be made of the inside periphery of the structure for local or unequal deformation caused by improper construction methods until a minimum of 12 inches of cover is obtained. Evidence of local or unequal deformation will be reason for corrective measures to be completed when directed by the City.

G. Thermoplastic pipe damaged by the Contractor shall be removed and replaced at no expense to the City.

3.05 INSPECTION AND ACCEPTANCE

A. Conform to requirements of following Sections:

1. Section 02631 – Storm Sewers.

B. Inspection

1. The Contractor shall visually inspect pipes for damage, deflection (out of roundness), joint tightness, evidence of soil intrusion, and vertical alignment (ponding). If the pipe run is 30 feet or less in length, not under a roadway, and the initial visual inspection did not indicate any deflection or other deficiencies, additional testing described below shall be waived, unless otherwise noted. The Contractor shall use high intensity lights, laser distant measuring devices, and other equipment to facilitate visual inspection.
2. Final inspection shall be performed a minimum of 30 days after the backfill has been completed or earlier as needed to allow roadway surfacing when approved. Two test mandrels shall be available for each size of pipe. Size mandrels based on the inside diameter as outlined in ASTM F2881, Table 2. Metal mandrels shall have at least nine fixed fins evenly distributed around the circumference. A mandrel sized at 95% the pipe diameter shall be pulled through the entire length. If the 95% mandrel cannot be pulled entirely through, a mandrel sized at 92.5% the pipe diameter shall be pulled through the pipe. Additionally, if the 95% mandrel cannot be pulled entirely through the pipe or there is a substantial disruption in ease of mandrel movement through the pipe, visually inspect installed pipe utilizing a remote operated camera mounted on vehicle or sled able to move through the pipe.

Check for joint separation, cracks, tears, buckling, deflection, and out of roundness, evidence of soil intrusion and vertical alignment (ponding water).

3. The Contractor shall notify the City when inspections are to occur.
 4. The Contractor shall provide a letter to the City stating the thermoplastic pipes were installed, inspected, and tested in compliance with the Contract Documents. The letter shall include copies of inspections and mandrel test results.
- C. Remediation: The Contractor shall develop a plan to address all deficiencies of joint separation, damage, evidence of soil intrusion, vertical alignment, and when pipe deflection exceeds 5% of the nominal pipe diameter.
1. Joints: Remediate pipe showing evidence of crushing at the joints. Note differential movement, improper joint sealing, movement or settlement of pipe sections, and leakage in the inspection report. Remediate joint separation of greater than 1 inch. Repair or replace pipe sections where soil migration through the joint is occurring.
 2. Cracks or Tears: Remediate cracks or splits in the interior wall of the pipe. Use remediation methods in conformance with recommendations of the pipe manufacturer and accepted and authorized by the City.
 3. Buckling, Bulging, and Racking: Note in the inspection report flat spots or dents at the crown, sides, or flowline of the pipe due to racking. Note area of wall buckling and bulging in the inspection report. The City will determine if corrective action is necessary.
 4. Deflection: Where pipe deflection exceeds 5% of the nominal diameter, submit to the City for review and approval an evaluation utilizing a Professional Engineer taking into consideration the severity of the deflection, structural integrity, environmental condition, and the design service life of the pipe. Remediate or replace pipe where the evaluation finds the deflection could be problematic or where pipe deflection exceeds 7.5% of the nominal diameter.

END OF SECTION

Section 02631

STORM SEWERS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. New storm sewers and appurtenances, modifications to existing storm sewer system and installation of roadside ditch culverts.

1.02 MEASUREMENT AND PAYMENT

- A. Unit Prices.

1. Payment for storm sewers, including elliptical or box, installed by open-cut, augered with or without casing, or tunneling is on linear foot basis. Measurement for storm sewers and roadside ditch culverts will be taken along center line of pipe from center line to center line of manholes or from end to end of culverts. Payment will be made for each linear foot installed complete in place, including connections to existing manholes and inlets.
2. Payment for storm sewer leads, including elliptical leads, is on a linear foot basis.
3. Payment for corrugated metal pipe storm sewer outfall, including timber bents, is on a linear foot basis.
4. Refer to Section 01270 - Measurement and Payment for unit price procedures.

- B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment for Work in this Section is included in total Stipulated Price.

1.03 SUBMITTALS

- A. Conform to requirements of Section 01330 - Submittal Procedures.
- B. Submit manufacturer's literature for product specifications and installation instructions.
- C. Submit proposed methods, equipment, materials, and sequence of operations for sewer construction. Plan operations to minimize disruption of utilities to occupied facilities or adjacent property.

1.04 QUALITY ASSURANCE

- A. The Condition for acceptance shall be watertight storm sewer that is watertight both in pipe-

to-pipe joints and in pipe-to-manhole connections.

- B. Provide manufacturer's certification to Specifications.

1.05 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Comply with manufacturer's recommendations.
- B. Handle pipe, fittings, and accessories carefully with approved handling devices. Do not drop or roll pipe off trucks or trailers. Do not use materials cracked, gouged, chipped, dented, or otherwise damaged shall not be used materials for installation.
- C. Store pipe and fittings on heavy timbers or platforms to avoid contact with ground.
- D. Unload pipe, fittings, and appurtenances as close as practical to location of installation to avoid unnecessary handling.
- E. Keep interiors of pipe and fittings free of dirt and foreign matter.
- F. Store PVC pipe out of direct sunlight.

PART 2 PRODUCTS

2.01 PIPE

- A. Provide piping materials for storm sewers shall be of sizes and types specified unless otherwise indicated on Drawings.
- B. In diameters where material alternatives are available, provide pipe from single manufacturer for each pipe diameter, unless otherwise approved by City Engineer or otherwise shown on Drawings.
- C. Existing pipe that has been removed during construction cannot be reused.

2.02 PIPE MATERIAL SCHEDULE

- A. Use pipe materials that conforming to requirements specified in one or more of the following sections as shown on the Drawings.

~~1. Section 02506—Polyvinyl Chloride Pipe. Not allowed in the following applications:~~

~~3. Potentially Petroleum Contaminated Areas (PPCA).~~

~~4. Augering/jacking~~

~~6.1.~~ 02611 - Reinforced Concrete Pipe.

~~7.2.~~ Section 02641 - Monolithic Reinforced Concrete Sewers.

~~8.3.~~ Section 02612 - Precast Reinforced Concrete Box Sewers.

~~4.~~ Section 02642 - Corrugated Metal Pipe use only where Corrugated Metal Pipe is shown on Drawings.

~~9.5.~~ Section 02509 – Thermoplastic Plastic Pipe and Drains

B. Provide pipe meeting minimum class, dimension ratio, or other criteria indicated.

C. Pipe materials other than those listed above shall not be used for storm sewers.

2.03 BEDDING, BACKFILL, AND TOPSOIL MATERIAL

A. Bedding and Backfill Material: Conform to requirements of Sections 02317 - Excavation and Backfill for Utilities, Section 02320 - Utility Backfill Material, and Section 2321 - Cement Stabilized Sand.

B. Topsoil: Conform to requirements of Section 02911 - Topsoil.

C. Use cement stabilized sand material for bedding and backfill in the pipe zone for all storm sewers.

D. Above the pipe zone, use select backfill material up to pavement for storm sewers larger than 36 inches in diameter

PART 3 EXECUTION

3.01 PREPARATION

A. Prepare traffic control plans and set up street detours and barricades in preparation for excavation when construction will affects traffic. Conform to requirements of Section 01555 - Traffic Control and Regulation.

B. Provide barricades, flashing warning lights, and signs for excavations. Conform to requirements of Section 01555 - Traffic Control and Regulation. Maintain barricades and warning lights for streets and intersections while Work is in progress or where traffic is affected by Work.

C. Immediately notify agency or company owning utility lines, which are damaged, broken, or disturbed. Obtain approval from City Engineer and agency for repairs or relocations, either

02631-3

02-01-0804-25-24

temporary or permanent.

DRAFT

- D. Remove old pavements and structures, including sidewalks and driveways in accordance with requirements of Section 02221 - Removing Existing Pavements and Structures.
- E. Install and operate dewatering and surface water control measures in accordance with Section 01578 - Control of Ground Water and Surface Water.

3.02 EXCAVATION

- A. Earthwork. Conform to requirements of Section 02317 - Excavation and Backfill for Utilities. Use bedding as indicated on Drawings.
- B. Line and Grade. Establish required uniform line and grade trench from benchmarks identified by City Engineer. Maintain this control for minimum of 100 feet behind and ahead of pipe-laying operation. Use laser beam equipment to establish and maintain proper line and grade of Work. Use of appropriately sized grade boards, which are substantially, supported also acceptable.
- C. Trench Excavation. Excavate pipe trenches to level as indicated on Standard Details. Backfill excavation with specified bedding material to level of lower one-third of pipe barrel. Tamp and compact backfill to provide bedding at indicated grade. Form bedding foundation to minimum depth of one-eighth of pipe diameter, but not less than 6 inches.

3.03 PIPE INSTALLATION

- A. Install in accordance with pipe manufacturer's recommendations and as specified in this section.
- B. Install pipe only after excavation is completed, bottom of trench is shaped, bedding material is installed, and trench has been approved by City Engineer.
- C. Install pipe to line and grade indicated on Drawings. Place pipe so that it has continuous bearing of barrel on bedding material with no voids, and is laid in trench so interior surfaces of pipe follows grades and alignments indicated.
- D. Install pipe with bells of pipe facing upstream of anticipated flow.
- E. Form concentric joint with each section of adjoining pipe to prevent offsets.
- F. Place and drive home newly laid sections with a sling or come-a-long winches to eliminate damage to sections. Unless otherwise approved by City Engineer, provide end protection to prevent damage while using backhoes or similar powered equipment to drive home newly laid sections.

- G. Keep interior of pipe clean as installation progresses. Where cleaning after laying pipe is difficult because of small pipe size, use suitable swab or drag inside pipe and pull it forward past each joint immediately after joint has been completed.
- H. Keep excavations free of water during construction and until final inspection.
- I. When work is not in progress, cover exposed ends of pipes with pipe plug specifically designed to prevent foreign material from entering pipe.
- J. For PVC Pipe:
 - 1. Provide a minimum cover as per City Standard detail from top of pavement to top of pipe, but no less than 2 feet below ditch flowline.
 - 2. Accomplish transitions to different material of pipe in a manhole or inlet box. No adapter, coupling for dissimilar pipe, or saddle connections allowed.
 - 3. Provide pipe sections in standard lengths with minimum length of 13 feet. Pipe may be field modified to shorten length no less than 4 feet, unless otherwise approved by City Engineer. Field modify pipe per manufacturer's recommendations.
 - 4. No beveling at joint allowed. Cut to be perpendicular to longitudinal axis.
 - 5. Provide gasketed bell and spigot joints installed per manufacturer's recommendations. Gasketed pipe joints; clean and free of debris, show no leakage after installation.

3.04 PIPE INSTALLATION OTHER THAN OPEN CUT

- A. A. Conform to requirements of Section 02448 - Pipe and Casing Augering for Sewers where required.
- B. Conform to requirements of Section 02441 - Microtunneling and Pipe-Jacking Tunnels where required.
- C. Not allowed for plastic sewer pipe.

3.05 INSTALLATION OF APPURTENANCES

- A. Construct manholes to conform to requirements of Sections 02081 - Cast-in-place Concrete Manholes, Section 02082 - Precast Concrete Manholes, and Section 2087 - Brick Manholes for Storm Sewers. Install frames, grate rings, and covers to conform to requirements of Section 02084 - Frames, Grates, Rings, and Covers.
- B. Install ~~PVC~~ pipe culverts with approved end treatments. Approved end treatments include concrete headwalls, wingwalls and collars. Refer to City Standards detail for end treatment requirements.

- C. Install inlets, headwalls, and wingwalls to conform to requirements of Section 02632 - Cast-in-place Inlets, Headwalls, and Wingwalls and Section 02633 - Precast Concrete Inlets, Headwalls, and Wingwalls.
- D. Rehabilitate existing manholes to conform to requirements of Section 02555 - Manhole Rehabilitation. Adjust manhole covers and inlets to grade conforming to requirements of Section 02086 - Adjusting Manholes, Inlets, and Valve Boxes to Grade.
- E. Dimension for Type C and Type E manholes shall be as shown on Drawings.

3.06 INSPECTION AND TESTING

- A. Perform post installation television inspection in accordance with Section 02531 - Gravity Sanitary Sewers.
- B. Mandrel Testing. Perform a mandrel test in accordance with Section 02533 - Acceptance Testing for Sanitary Sewers.
- C. Pipe & Joint Leakage Test. Perform low-pressure air test or water test (an exfiltration test) in Section 02533 - Acceptance Testing for Sanitary Sewers.

3.07 BACKFILL AND SITE CLEANUP

- A. Backfill trench after pipe installation is inspected and approved by City Engineer.
- B. Backfill and compact soil in accordance with Section 02317 - Excavation and Backfill for Utilities.
- C. Repair and replace removed or damaged pavement and sidewalks as specified in Section 02951 - Pavement Repair and Resurfacing.
- D. In unpaved areas, grade surface as uniform slope to natural grade as indicated on Drawings. Provide minimum of 4 inches of topsoil and seed according to requirements of Section 02921 - Hydromulch Seeding, or Section 02922 - Sodding, as required.


END OF SECTION

APPENDIX C

CIP PACKETS

APPENDIX C – M116

CIP PACKETS




Drainage CIP - Opinion of Probable Construction Cost					
Basin	M116	CIP Project No.	1A	Phase	
Project Name		M116-00-00 Diversion			
Project Category					
Project Description					
Channel diversion and construction to provide appropriate conveyance capacity.					
Project Justification					
Channel capacity constraints due to inadequate right-of-way and easement.					
Potential Funding Opportunities					
Participation from HCFCD and Harris County Precinct 3					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	M116-00-00	1750	LF	\$ 410	\$ 717,500
		SUBTOTAL			\$ 717,500
		CONTINGENCY		30%	\$ 215,250
		CONSULTANT		25%	\$ 179,375
2	LAND ACQUISITION (FEE)	6.08	AC	\$ 217,800	\$ 1,323,783
		SUBTOTAL			\$ 1,323,783
		CONTINGENCY		10%	\$ 132,378
ESTIMATED PROJECT TOTAL COST:					\$ 2,568,286

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




Drainage CIP - Opinion of Probable Construction Cost					
Basin	M116	CIP Project No.	2	Phase	
Project Name		FM 2920 & FM 2978/Hufsmith-Kohrville Culverts			
Project Category					
Project Description					
Construct cross culvert under Hufsmith-Kohrville Road along south side of FM 2920 and FM 2978 along the north side of FM 2920.					
Project Justification					
Provide outfall for westbound and eastbound FM 2920 roadside ditches.					
Potential Funding Opportunities					
TxDOT					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	475	LF	\$ 130	\$ 61,750
2	STM MH (SM)	1	EA	\$ 6,000	\$ 6,000
3	24" SET	3	EA	\$ 5,000	\$ 15,000
4	PAVEMENT REPAIR - CONC	475	LF	\$ 140	\$ 66,500
SUBTOTAL					\$ 149,250
CONTINGENCY				30%	\$ 44,775
CONSULTANT				25%	\$ 37,313
ESTIMATED PROJECT TOTAL COST:					\$ 231,338

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: M116-00-00
SUBBASIN: A

SCALE: 1" = 200'	March 2025
EXHIBIT NO. 2	M116 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M116	CIP Project No.	1B	Phase	
Project Name		Mahaffey Road Storm Sewer			
Project Category					
Project Description					
Construct storm sewer along Mahaffey Road to connect upstream M116-00-00 to M116-00-00 diverted channel.					
Project Justification					
Increase culvert crossing level of service.					
Potential Funding Opportunities					
Harris County Precinct 3 and HCFCD potential contribution.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	10'x6' RCB	2050	LF	\$ 1,450	\$ 2,972,500
2	STM JB (LG)	4	EA	\$ 23,500	\$ 94,000
3	DITCH INTERCEPTOR	4	EA	\$ 9,100	\$ 36,400
4	PAVEMENT REPAIR - ASP	950	LF	\$ 140	\$ 133,000
SUBTOTAL					\$ 3,235,900
CONTINGENCY				30%	\$ 970,770
CONSULTANT				25%	\$ 808,975
ESTIMATED PROJECT TOTAL COST:					\$ 5,015,645


CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.

APPENDIX C – M118

CIP PACKETS



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 100-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



(IN FEET)

1 INCH = 600 FT.



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M118-00-00
SUBBASIN: B

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 1


M118 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M118	CIP Project No.	1	Phase	
Project Name		M518-01 Detention Pond			
Project Category					
Project Description					
Complete excavation, bank construction and final stabilization of the wet-bottom regional detention pond to achieve ultimate storage capacity of 295 acre-feet to serve the entire M118 Basin.					
Project Justification					
Regional detention pond ultimate storage volume required for full development of the M118 Basin.					
Potential Funding Opportunities					
Tomball Economic Development Corporation funding assistance.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	M518-01	45	AC-FT	\$ 40,000	\$ 1,800,000
SUBTOTAL					\$ 1,800,000
CONTINGENCY				30%	\$ 540,000
CONSULTANT				25%	\$ 450,000
ESTIMATED PROJECT TOTAL COST:					\$ 2,790,000

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA


1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 100-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 381,685 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)

1 INCH = 1000 FT.



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M118-00-00
SUBBASIN: A1

SCALE: 1" = 1" = 1000'

March 2025

EXHIBIT NO. 2


M118 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M118	CIP Project No.	2	Phase	
Project Name		M118-00-00 Channel Extension to Medical Complex Blvd			
Project Category					
Project Description					
Acquire right-of-way and construct the upper reach of M118-00-00 channel from the Tomball Business and Technology Park to Medical Complex Drive to provide outfall depth and 100-year conveyance.					
Project Justification					
Provide an outfall for upper reaches of the basin outside the service area of the M118-01-00 (S. Persimmon) storm sewer system. Provide hydraulic connection to Medical Complex Drive (M118 CIP 3)/					
Potential Funding Opportunities					
Private development.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	M118-00-00	2650	LF	\$ 410	\$ 1,086,500
		SUBTOTAL			\$ 1,086,500
		CONTINGENCY		30%	\$ 325,950
		CONSULTANT		25%	\$ 271,625
2	LAND ACQUISITION (FEE)	8.76	AC	\$ 217,800	\$ 1,908,425
		SUBTOTAL			\$ 1,908,425
		CONTINGENCY		10%	\$ 190,843
ESTIMATED PROJECT TOTAL COST:					\$ 3,783,343

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 100-YEAR HGL: 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 0 SF

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 500 FT.



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: M118-00-00
SUBBASIN: MC_E1

SCALE: 1" = 1" = 500'

March 2025

EXHIBIT NO. 3


M118 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M118	CIP Project No.	3	Phase	
Project Name		Medical Complex Blvd Storm Sewer Extension to M118-00-00			
Project Category					
Project Description					
Construct new storm sewer from Medical Complex Drive to the head of M118-00-00 (M118 CIP #2) within an unimproved right-of-way.					
Project Justification					
The storm sewer will provide a secondary outfall for the M118-01-01 trunkline and function as split flow between M118-01-00 and M118-00-00 in an effort to relieve the existing conveyance system along S. Persimmon Street.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	6'x6' RCB	500	LF	\$ 820	\$ 410,000
2	STM JB (LG)	2	EA	\$ 23,500	\$ 47,000
3	OUTFALL TIE-IN	1	EA	\$ 10,000	\$ 10,000
		SUBTOTAL			\$ 467,000
		CONTINGENCY		30%	\$ 140,100
		CONSULTANT		25%	\$ 116,750
ESTIMATED PROJECT TOTAL COST:					\$ 723,850

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.


All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 100-YEAR HGL: 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 48,418 SF

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
		← DRAINAGE AREA ID
		← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 600 FT.



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: M118-00-00
SUBBASIN: N_1, N_2WB, N_EW

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 4


M118 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M118	CIP Project No.	4	Phase	
Project Name		M118-00-00 (S. Persimmon)Storm Sewer Extension to Lizzie Lane			
Project Category					
Project Description					
Utilizing the existing 54-inch storm sewer previously installed, extend a parallel storm sewer trunkline along S. Persimmon Street from the termination of a 10'x8' RCB (near Sutton Lane) to north of Lizzie Lane.					
Project Justification					
The storm sewer will provide additional conveyance capacity to upper reaches of the basin such to utilize the regional detention within M518-01.					
Potential Funding Opportunities					
Improvements are assumed to take place with roadway reconstruction and expansion, thereofre land acqusitions is excluded from cost estimate.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	6'x5' RCB	360	LF	\$ 750	\$ 270,000
2	10'x7' RCB	2760	LF	\$ 1,525	\$ 4,209,000
3	STM JB (MED)	1	EA	\$ 12,000	\$ 12,000
4	STM JB (LG)	5	EA	\$ 23,500	\$ 117,500
5	CURB INLET	36	EA	\$ 8,600	\$ 309,600
6	OUTFALL TIE-IN	1	EA	\$ 10,000	\$ 10,000
		SUBTOTAL			\$ 4,928,100
		CONTINGENCY		30%	\$ 1,478,430
		CONSULTANT		25%	\$ 1,232,025
ESTIMATED PROJECT TOTAL COST:					\$ 7,638,555

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 100-YEAR HGL: 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 0 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 600 FT.



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M118 (M118-01-00)
SUBBASIN: N_1WB

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 5


M118 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M118	CIP Project No.	5	Phase		
Project Name		M118-01-01 Channel Improvements (Phase 1)				
Project Category						
Project Description						
Excavate and deepen existing City drainage channel by reconstructing outfall connection to S. Persimmon storm sewer system. Construct lateral channel from Lizzie Lane to M118-01-01 and upgrade Lizzie Lane cross culvert.						
Project Justification						
Provide relief for upper portions of M118 Basin, specifically Lizzie Lane.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	30" RCP	360	LF	\$ 185	\$ 66,600	
2	54" RCP	120	LF	\$ 420	\$ 50,400	
3	8'x4' RCB	100	LF	\$ 950	\$ 95,000	
4	M118-01-01	1680	LF	\$ 380	\$ 638,400	
5	M118-01-01 LATERAL	250	LF	\$ 360	\$ 90,000	
6	PIPELINE RELOCATION	3	EA	\$ 30,000	\$ 90,000	
7	PAVEMENT REPAIR - ASP	35	LF	\$ 140	\$ 4,900	
		SUBTOTAL			\$ 1,035,300	
		CONTINGENCY			30%	\$ 310,590
		CONSULTANT			25%	\$ 258,825
ESTIMATED PROJECT TOTAL COST:					\$ 1,604,715	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 100-YEAR HGL: 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 33,865 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN


BASIN: M118-00-00
SUBBASIN: N_W2A, MC_W

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 6

M118 BASIN



(IN FEET)


1 INCH = 600 FT.

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M118	CIP Project No.	6	Phase	
Project Name		S. Pitchford Storm Sewer Extension			
Project Category					
Project Description					
Construct storm sewer trunkline down S. Pitchford Road. Drainage improvements are assumed to take place with roadway reconstruction.					
Project Justification					
Provide conveyance for upper reaches of the M118 Basin.					
Potential Funding Opportunities					
Private development pro-rata contribution.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	6'x6' RCB	1140	LF	\$ 820	\$ 934,800
2	8'x7' RCB	720	LF	\$ 1,150	\$ 828,000
3	9'x7' RCB	780	LF	\$ 1,420	\$ 1,107,600
4	10'x8' RCB	1740	LF	\$ 1,560	\$ 2,714,400
5	STM MH (MED)	1	EA	\$ 7,500	\$ 7,500
6	STM JB (MED)	5	EA	\$ 12,000	\$ 60,000
7	STM JB (LG)	4	EA	\$ 23,500	\$ 94,000
8	OUTFALL TIE-IN	2	EA	\$ 10,000	\$ 20,000
9	DITCH INTERCEPTOR	30	EA	\$ 9,100	\$ 273,000
10	PAVEMENT REPAIR - ASP	1200	LF	\$ 140	\$ 168,000
		SUBTOTAL			\$ 6,207,300
		CONTINGENCY		30%	\$ 1,862,190
		CONSULTANT		25%	\$ 1,551,825
ESTIMATED PROJECT TOTAL COST:					\$ 9,621,315

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA


1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 100-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 76,036 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)

1 INCH = 1000 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M118-00-00
SUBBASIN: HK_1, A1

SCALE: 1" = 1" = 1000'

March 2025

EXHIBIT NO. 7


M118 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M118	CIP Project No.	7	Phase		
Project Name		M118-00-00 Underground Alternate				
Project Category						
Project Description						
Based on timing of development and widening of Hufsmith-Kohrville Road, a storm sewer trunkline may replace the M118-00-00 channel extension within the limits of an unimproved right-of-way.						
Project Justification						
Alternative to M118-00-00 channel construction and opportunity for stormwater outfall for Hufmsith Kohville roadway improvements.						
Potential Funding Opportunities						
Harris County Precinct 3 and/or private development.						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	9'x7' RCB	5200	LF	\$ 1,420	\$ 7,384,000	
2	STM JB (LG)	6	EA	\$ 23,500	\$ 141,000	
		SUBTOTAL			\$ 7,525,000	
		CONTINGENCY			30%	\$ 2,257,500
		CONSULTANT			25%	\$ 1,881,250
3	LAND ACQUISITION (ESMT)	1.75	AC	\$ 130,680	\$ 228,108	
		SUBTOTAL			\$ 228,108	
		CONTINGENCY			10%	\$ 22,811
ESTIMATED PROJECT TOTAL COST:					\$ 11,914,669	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA


1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 100-YEAR HGL: 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 578,887 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)

1 INCH = 600 FT.



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M118 (M118-01-00)
SUBBASIN: N_1WA & N_1WB

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 8


M118 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M118	CIP Project No.	8A	Phase	
Project Name		M518-02 Detention Pond (Alt A)			
Project Category					
Project Description					
Construct underground storm sewer from western tracts to head of M118-01-01. Construction sub-regional detention pond M518-02 and outfall structure to existing S. Persimmon St. storm sewer system.					
Project Justification					
Provide outfall for tract adjacent to BNSF railroad and partially mitigate increase runoff for future development.					
Potential Funding Opportunities					
Private development.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	90	LF	\$ 130	\$ 11,700
2	6'x6' RCB	960	LF	\$ 820	\$ 787,200
3	M518-02	9.4	AC-FT	\$ 40,000	\$ 376,000
4	STM MH (SM)	1	EA	\$ 6,000	\$ 6,000
5	OUTFALL TIE-IN	1	EA	\$ 10,000	\$ 10,000
6	STM JB (MED)	3	EA	\$ 12,000	\$ 36,000
		SUBTOTAL			\$ 1,226,900
		CONTINGENCY		30%	\$ 368,070
		CONSULTANT		25%	\$ 306,725
7	LAND ACQUISITION (FEE)	2.22	AC	\$ 217,800	\$ 483,442
		SUBTOTAL			\$ 483,442
		CONTINGENCY		10%	\$ 48,344
ESTIMATED PROJECT TOTAL COST:					\$ 2,433,482

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 100-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 578,887 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



(IN FEET)

1 INCH = 600 FT.

3A
50.0
DRAINAGE AREA ID
DRAINAGE AREA IN ACRES



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M118 (M118-01-00)
SUBBASIN: N_1WA & N_1WB

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 8

M118 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M118	CIP Project No.	8B	Phase		
Project Name		M118-01-01 Channel Improvements (Phase 2) and M518-02 Det. Pond (Alt B)				
Project Category						
Project Description						
Extend M118-01-01 to western tract along unimproved ROW. Construct M518-02 upstream of M118-01-01.						
Project Justification						
Provide outfall for tract adjacent to BNSF railroad and partially mitigate increase runoff for future development.						
Potential Funding Opportunities						
Private development.						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	M118-01-01 EXTENSION	840	LF	\$ 310	\$ 260,400	
2	M518-02	17.9	AC-FT	\$ 40,000	\$ 716,000	
		SUBTOTAL			\$ 976,400	
		CONTINGENCY			30%	\$ 292,920
		CONSULTANT			25%	\$ 244,100
3	LAND ACQUISITION (M118-01-01)	2.12	AC	\$ 217,800	\$ 462,154	
4	LAND ACQUISITION (M518-02)	8.34	AC	\$ 217,800	\$ 1,817,263	
		SUBTOTAL			\$ 2,279,417	
		CONTINGENCY			10%	\$ 227,942
ESTIMATED PROJECT TOTAL COST:					\$ 4,020,779	


CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.

APPENDIX C – M121

CIP PACKETS




DESIGN CRITERIA

1. DESIGN STORM EVENT (DETENTION): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

DRAINAGE AREA ID
 DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 500 FT.



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: M121 (M121W)
SUBBASIN: HS-EIB & HS-EIC

SCALE: 1" = 500'

March 2025

EXHIBIT NO. 1


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	1	Phase	
Project Name		M500-01 Detention Pond Excavation Ultimate Condition)			
Project Category					
Project Description					
Reconstruct existing stormwater detention pond to a wet-bottom facility, including removal of existing peninsula and bank repair along northern and eastern highbanks. Install ultimate outfall to Willow Creek (M100-00-00).					
Project Justification					
Increase storage capacity by 86 ac-feet and complete M500-01 Stormwater Detention Basin.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	M500-01	86	AC-FT	\$ 60,000	\$ 5,160,000
2	Outfall Structure	1	EA	\$ 25,000	\$ 25,000
3	Side Weir	1	EA	\$ 20,000	\$ 20,000
		SUBTOTAL			\$ 5,205,000
		CONTINGENCY		30%	\$ 1,561,500
		CONSULTANT		25%	\$ 1,301,250
ESTIMATED PROJECT TOTAL COST:					\$ 8,067,750

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.


All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



**M121-01-00
CHANNEL RECONSTRUCTION
10' DEEP, 15' BW, 95' TW,
4:1 SS, @ 0.1%**

- DESIGN CRITERIA**
 1. DESIGN STORM EVENT (CHANNEL): 100-YEAR
 2. MITIGATION PROVIDED IN M500-01

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	← DRAINAGE AREA ID	
	← DRAINAGE AREA IN ACRES	



CSE Civil Systems Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: M121 (M121-01-00)
 SUBBASIN: HS_E, HS_W, C1, & C_W

SCALE: 1" = 1" = 300'

March 2025

EXHIBIT NO. 2


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	2	Phase	
Project Name		M121-01-00 (M121 WEST) Channel Reconstruction From Medical Complex Drive to Hardin Street			
Project Category					
Project Description					
Reconstruct and reestablish channel side slopes and bottom from upstream of Medical Complex Drive crossing to head of M121-01-00 at M121-01-01 and M121-01-02 laterals.					
Project Justification					
Reconstruct channel reach at ultimate depth to provide outfall depth for planned upstream improvements.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	M121-01-00	1980	LF	\$ 160	\$ 316,800
		SUBTOTAL			\$ 316,800
		CONTINGENCY		30%	\$ 95,040
		CONSULTANT		25%	\$ 79,200
ESTIMATED PROJECT TOTAL COST:					\$ 491,040

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (CHANNEL): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
3. MITIGATION PROVIDED IN M500-01

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



34
50.0
DRAINAGE AREA ID
DRAINAGE AREA IN ACRES

(IN FEET)
1 INCH = 250 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121-01-00)
SUBBASIN: HS_E & HW_W

SCALE: 1" = 250'

March 2025

EXHIBIT NO. 3 & 8


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	3	Phase	
Project Name		M121-01-01 (Hardin Street East) Channel Construction to Cherry Street			
Project Category					
Project Description					
Construct eastern lateral of M121-01-00 from M121-01-00 to Cherry Street within limits of Hardin Street right-of-way. Concrete-lined channel construction proposed to limit disturbance of existing City infrastructure within Hardin Street.					
Project Justification					
Provide conveyance for upper reaches of M121 Basin and relieve existing flooding by providing outfall depth for upstream improvements.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	M121-01-01	1600	LF	\$ 550	\$ 880,000
2	UTILITY CONFLICTS	6	EA	\$ 10,000	\$ 60,000
3	PIPELINE RELOCATION	1	EA	\$ 14,000	\$ 14,000
		SUBTOTAL			\$ 954,000
		CONTINGENCY		30%	\$ 286,200
		CONSULTANT		25%	\$ 238,500
ESTIMATED PROJECT TOTAL COST:					\$ 1,478,700

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.


Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until 2024 and project funding



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 10,040 SF



(IN FEET)
1 INCH = 250 FT.

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121-01-00)
SUBBASIN: HS_E2A & HS_E2B

SCALE: 1" = 250'

March 2025

EXHIBIT NO. 4 & 5


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	4	Phase	
Project Name		Cherry Laurel Storm Sewer Improvements			
Project Category					
Project Description					
Install outfall strucutres to M121-01-01 lateral by replacing existing curb opening with standard curb inlet and storm sewer.					
Project Justification					
Provide local flooding relief and upgrade outfall structure to accommodate appropriate storm events.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	350	LF	\$ 130	\$ 45,500
2	CURB INLET (NO LEADS)	5	EA	\$ 6,000	\$ 30,000
3	PAVEMENT REPAIR - CONC	275	LF	\$ 140	\$ 38,500
				SUBTOTAL	\$ 75,500
				CONTINGENCY	30% \$ 22,650
				CONSULTANT	25% \$ 18,875
ESTIMATED PROJECT TOTAL COST:					\$ 117,025

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.


Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 10,040 SF



(IN FEET)
1 INCH = 250 FT.

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121-01-00)
SUBBASIN: HS_E2A & HS_E2B

SCALE: 1" = 250'

March 2025

EXHIBIT NO. 4 & 5


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M121	CIP Project No.	5	Phase		
Project Name		Hampton Place Storm Sewer Improvements				
Project Category						
Project Description						
Redirect multi-family complex storm sewer outfall to M121-01-00 by replacing existing inlets and constructing new storm sewer system.						
Project Justification						
Relieve flooding for multi-family complex with new outfall.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	30" RCP	1050	LF	\$ 185	\$ 194,250	
2	36" RCP	650	LF	\$ 200	\$ 130,000	
3	STM MH (SM)	7	EA	\$ 6,000	\$ 42,000	
4	CURB INLET	4	EA	\$ 8,600	\$ 34,400	
5	PAVEMENT REPAIR - CONC	1100	LF	\$ 140	\$ 154,000	
		SUBTOTAL			\$ 554,650	
		CONTINGENCY			30%	\$ 166,395
		CONSULTANT			25%	\$ 138,663
6	LAND ACQUISITION (ESMT)	0.23	AC	\$ 130,680	\$ 30,123	
		SUBTOTAL			\$ 30,123	
		CONTINGENCY			10%	\$ 3,012
ESTIMATED PROJECT TOTAL COST:					\$ 892,843	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA


1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

3A
50.0

← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN


BASIN: M121 (M121-01-00)
SUBBASIN: HS_E1

SCALE: 1" = 1" = 500'

March 2025

EXHIBIT NO. 6

M121 BASIN



(IN FEET)


1 INCH = 500 FT.

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	6	Phase	
Project Name		S. Cherry Street Storm Sewer Improvements (From Market Street to Hardin Street)			
Project Category					
Project Description					
Construct storm sewer and roadside ditch interceptors along S. Cherry Street to M121-01-01.					
Project Justification					
Provide local flood relief for Old Town by adding conveyance capacity.					
Potential Funding Opportunities					
Harris County Precinct 3 during S. Cherry Street reconstruction					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	225	LF	\$ 130	\$ 29,250
2	30" RCP	250	LF	\$ 185	\$ 46,250
3	36" RCP	325	LF	\$ 200	\$ 65,000
4	42" RCP	325	LF	\$ 300	\$ 97,500
5	48" RCP	750	LF	\$ 380	\$ 285,000
6	6'x4' RCB	300	LF	\$ 810	\$ 243,000
7	7'x4' RCB	550	LF	\$ 900	\$ 495,000
8	9'x4' RCB	550	LF	\$ 1,350	\$ 742,500
9	STM MH (SM)	4	EA	\$ 6,000	\$ 24,000
10	STM MH (MED)	1	EA	\$ 7,500	\$ 7,500
11	STM JB (SM)	2	EA	\$ 8,000	\$ 16,000
12	STM JB (MED)	1	EA	\$ 12,000	\$ 12,000
13	STM JB (LG)	4	EA	\$ 23,500	\$ 94,000
14	DITCH INTERCEPTOR	34	EA	\$ 9,100	\$ 309,400
15	DITCH CONSTRUCTION	950	LF	\$ 50	\$ 47,500
16	PAVEMENT REPAIR - ASP	850	LF	\$ 140	\$ 119,000
		SUBTOTAL			\$ 2,632,900
		CONTINGENCY			30% \$ 789,870
		CONSULTANT			25% \$ 658,225
ESTIMATED PROJECT TOTAL COST:					\$ 4,080,995

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. DRAINAGE ESMT = 17,661 SF (TRACT OWNED BY CITY OF TOMBALL)

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

DRAINAGE AREA ID
DRAINAGE AREA IN ACRES



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN


BASIN: M121 (M121-01-00)
SUBBASIN: HS_E3 & HS_E4

SCALE: 1" = 1" = 400'

March 2025

EXHIBIT NO. 7

M121 BASIN



(IN FEET)


1 INCH = 400 FT.

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M121	CIP Project No.	7	Phase		
Project Name		Magnolia Street Storm Sewer Improvements				
Project Category						
Project Description						
Construct storm sewer system along S. Magnolia Street and retain existing roadside ditches. Outfall to M121-01-01 through City of Tomball Public Works property.						
Project Justification						
Increase capacity and relieve flooding in Old Town. Insufficient right-of-way and fully developed corridor for open channel conveyance.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	36" RCP	360	LF	\$ 200	\$ 72,000	
2	48" RCP	360	LF	\$ 380	\$ 136,800	
3	4'x4' RCB	320	LF	\$ 500	\$ 160,000	
4	5'x4' RCB	360	LF	\$ 480	\$ 172,800	
5	6'x4' RCB	620	LF	\$ 810	\$ 502,200	
6	STM MH (SM)	1	EA	\$ 6,000	\$ 6,000	
7	STM MH (MED)	1	EA	\$ 7,500	\$ 7,500	
8	STM JB (SM)	1	EA	\$ 8,000	\$ 8,000	
9	STM JB (MED)	6	EA	\$ 12,000	\$ 72,000	
10	DITCH INTERCEPTOR	18	EA	\$ 9,100	\$ 163,800	
11	PAVEMENT REPAIR - ASP	700	LF	\$ 140	\$ 98,000	
		SUBTOTAL			\$ 1,399,100	
		CONTINGENCY			30%	\$ 419,730
		CONSULTANT			25%	\$ 349,775
6	LAND ACQUISITION (ESMT)	0.41	AC	\$ -	\$ -	
		SUBTOTAL			\$ -	
		CONTINGENCY			10%	\$ -
ESTIMATED PROJECT TOTAL COST:					\$ 2,168,605	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA


1. DESIGN STORM EVENT (CHANNEL): 100-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
3. MITIGATION PROVIDED IN M500-01

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 250 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121-01-00)
SUBBASIN: HS_E & HW_W

SCALE: 1" = 250'

March 2025

EXHIBIT NO. 3 & 8


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	8	Phase	
Project Name		M121-01-02 (HARDIN STREET WEST) CHANNEL TO SCHOOL STREET			
Project Category					
Project Description					
Construct M121-01-03 (western lateral of M121-01-00) to School Street along Hardin Street right-of-way. Install School Street cross culvert.					
Project Justification					
Provide conveyance for upper reaches of M121 Basin and relieve existing flooding by providing outfall depth for upstream improvements.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	M121-01-02	680	LF	\$ 550	\$ 374,000
2	5'x3' RCB	80	LF	\$ 605	\$ 48,400
3	CURB INLET (NO LEADS)	2	EA	\$ 6,000	\$ 12,000
4	UTILITY CONFLICTS	5	EA	\$ 10,000	\$ 50,000
5	PAVEMENT REPAIR - ASP	30	LF	\$ 140	\$ 4,200
6	PIPELINE RELOCATION	3	EA	\$ 14,000	\$ 42,000
		SUBTOTAL			\$ 530,600
		CONTINGENCY		30%	\$ 159,180
		CONSULTANT		25%	\$ 132,650
ESTIMATED PROJECT TOTAL COST:					\$ 822,430

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.


Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS



(IN FEET)
1 INCH = 500 FT.

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

DRAINAGE AREA ID
 DRAINAGE AREA IN ACRES



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: M121 (M121W)
SUBBASIN: HS-EIB & HS-EIC

SCALE: 1" = 500'

March 2025

EXHIBIT NO. 9


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M121	CIP Project No.	9	Phase		
Project Name		Theis Lane Storm Sewer Reconstruction				
Project Category						
Project Description						
Removal of cross culvert under Thesis Lane adjacent to Thesis Attaway Nature Center and construct storm sewer trunkline along Thesis Lane.						
Project Justification						
Increase capacity of minor arterial as part of roadway reconstruction and relieve runoff behind Walmart and Woodleaf Reserve subdivision.						
Potential Funding Opportunities						
Improvements assumed to take place with roadway reconstruction and expansion, therefore pavement repair and land acquisitions are excluded from cost estimate.						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	4'x4' RCB	650	LF	\$ 500	\$ 325,000	
2	6'x6' RCB	2080	LF	\$ 820	\$ 1,705,600	
3	STM JB (SM)	2	EA	\$ 8,000	\$ 16,000	
4	STM JB (MED)	3	EA	\$ 12,000	\$ 36,000	
5	CURB INLET	18	EA	\$ 8,600	\$ 154,800	
6	OUTFALL TIE-IN	1	EA	\$ 10,000	\$ 10,000	
		SUBTOTAL			\$ 2,247,400	
		CONTINGENCY			30%	\$ 674,220
		CONSULTANT			25%	\$ 561,850
ESTIMATED PROJECT TOTAL COST:					\$ 3,483,470	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.


All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (DETENTION): 100-YEAR
2. MITIGATE IMPROVEMENTS TO M121-02-00 CHANNEL CONSTRUCTION
3. LAND ACQUISITION (FEE) = 4,713,967 SF

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	← DRAINAGE AREA ID	← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 500 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121W)
SUBBASIN: HS-EIB & HS-EIC

SCALE: 1" = 500'

March 2025

EXHIBIT NO. 10

M121 BASIN


Drainage CIP - Opinion of Probable Construction Cost						
Basin	M121	CIP Project No.	10	Phase		
Project Name		M521-01 Detention Pond				
Project Category						
Project Description						
Acquire existing sand pit and tract adjacent to BNSF Railroad. Construction dry-bottom detention facility.						
Project Justification						
Mitigate runoff impacts for M121-02-00 channel construction.						
Potential Funding Opportunities						
HCFCD Partnership						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	M521-01	332	AC-FT	\$ 40,000	\$ 13,280,000	
2	Outfall Structure	1	EA	\$ 25,000	\$ 25,000	
3	Side Wier	1	EA	\$ 20,000	\$ 20,000	
		SUBTOTAL			\$ 13,325,000	
		CONTINGENCY			30%	\$ 3,997,500
		CONSULTANT			25%	\$ 3,331,250
4	LAND ACQUISITION (FEE)	108.22	AC	\$ 87,120	\$ 9,427,934	
		SUBTOTAL			\$ 9,427,934	
		CONTINGENCY			10%	\$ 942,793
ESTIMATED PROJECT TOTAL COST:					\$ 31,024,477	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

Pricing excludes reloaction of pipelines and abandonment of wells.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



- DESIGN CRITERIA**
1. DESIGN STORM EVENT (CHANNEL): 100-YEAR
 2. MITIGATION PROVIDED IN M521-01

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121-02-00)
SUBBASIN: B & C

SCALE: 1" = 1"=800'

March 2025

EXHIBIT NO. 11

M121 BASIN


(IN FEET)
1 INCH = 800 FT.

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	11	Phase	
Project Name		M121-02-00 (M121 East) Channel Extension to Agg Road			
Project Category					
Project Description					
Construct ultimate M121-02-00 (M121 East) channel from Holderreith Road to Agg Road.					
Project Justification					
Provide conveyance and outfall depth for eastern reaches of M121 Basin. Provide opportunity for upstream storm sewer improvements.					
Potential Funding Opportunities					
Potential private development partnership.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	M121-02-00	5400	LF	\$ 650	\$ 3,510,000
2	PIPELINE RELOCATION	8	EA	\$ 32,000	\$ 256,000
		SUBTOTAL			\$ 3,510,000
		CONTINGENCY		30%	\$ 1,053,000
		CONSULTANT		25%	\$ 877,500
3	LAND ACQUISITION (FEE)	15.28	AC	\$ 217,800	\$ 3,328,025
		SUBTOTAL			\$ 3,328,025
		CONTINGENCY		10%	\$ 332,803
ESTIMATED PROJECT TOTAL COST:					\$ 9,101,328

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



CSE Civil Systems Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: M121 (M121-02-00)
SUBBASIN: C_W & C_N

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 12 & 13


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	12	Phase	
Project Name		S. Cherry Street & Agg Road (from Anne Street to M121-00-00) Storm Sewer			
Project Category					
Project Description					
Construction storm sewer improvements along Cherry Street and Agg Road. Cost assumes improvements are installed without roadway reconstruction.					
Project Justification					
Increase conveyance capacity and relieve local flooding. Provide outfall depth for future development.					
Potential Funding Opportunities					
Partnership with Harris County Precinct 3 during roadway reconstruction project.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	48" RCP	980	LF	\$ 380	\$ 372,400
2	4'x4' RCB	780	LF	\$ 500	\$ 390,000
3	5'x5' RCB	780	LF	\$ 670	\$ 522,600
4	6'x5' RCB	60	LF	\$ 750	\$ 45,000
5	7'x6' RCB	480	LF	\$ 1,020	\$ 489,600
6	9'x6' RCB	1140	LF	\$ 1,450	\$ 1,653,000
7	STM MH (MED)	2	EA	\$ 7,500	\$ 15,000
8	STM JB (SM)	1	EA	\$ 8,000	\$ 8,000
9	STM JB (MED)	2	EA	\$ 12,000	\$ 24,000
10	STM JB (LG)	4	EA	\$ 23,500	\$ 94,000
11	DITCH INTERCEPTOR	22	EA	\$ 9,100	\$ 200,200
12	PAVEMENT REPAIR - ASP	1500	LF	\$ 140	\$ 210,000
		SUBTOTAL			\$ 4,023,800
		CONTINGENCY		30%	\$ 1,207,140
		CONSULTANT		25%	\$ 1,005,950
ESTIMATED PROJECT TOTAL COST:					\$ 6,236,890

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 600 FT.



CSE Civil Systems Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: M121 (M121-02-00)
SUBBASIN: C_W & C_N

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 12 & 13


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	13	Phase	
Project Name		Mulberry Street Strom Sewer			
Project Category					
Project Description					
Construct storm sewer along Mulberry Street and connect with M121 CIP #11.					
Project Justification					
Provide flooding relief and increased conveyance capacity for developments along Mulberry Street. Relieve BNSF cross culvert overflow.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	3'x3' RCB	840	LF	\$ 395	\$ 331,800
2	4'x4' RCB	660	LF	\$ 500	\$ 330,000
3	6'x5' RCB	420	LF	\$ 750	\$ 315,000
4	STM JB (SM)	2	EA	\$ 8,000	\$ 16,000
5	STM JB (MED)	2	EA	\$ 12,000	\$ 24,000
6	DITCH INTERCEPTOR	10	EA	\$ 9,100	\$ 91,000
7	PAVEMENT REPAIR - ASP	200	LF	\$ 140	\$ 28,000
		SUBTOTAL			\$ 1,135,800
		CONTINGENCY		30%	\$ 340,740
		CONSULTANT		25%	\$ 283,950
ESTIMATED PROJECT TOTAL COST:					\$ 1,760,490

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

- DESIGN STORM EVENT (STORM SEWER): 25-YEAR
- HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
- STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
- STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
- ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
- MITIGATION PROVIDED IN M521-01
- PROPOSED ACQUISITION (ESMT) = 25,715 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 500 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121-02-00)
SUBBASIN: B_W

SCALE: 1" = 1" = 500'

March 2025

EXHIBIT NO. 14


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	14	Phase	
Project Name		S. Cherry Street (from Agg Road to Cherrywood Estates) Storm Sewer to M121-02-00			
Project Category					
Project Description					
Construct storm sewer along S. Cherry Street to Cherrywood Estates. Cost assumes improvements are installed without roadway reconstruction.					
Project Justification					
Increase conveyance capacity and relieve local flooding. Provide outfall depth for future development.					
Potential Funding Opportunities					
Partnership with Harris County Precinct 3 during roadway reconstruction project.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	48" RCP	1100	LF	\$ 380	\$ 418,000
2	5'x4' RCB	300	LF	\$ 480	\$ 144,000
3	6'x4' RCB	900	LF	\$ 810	\$ 729,000
4	7'x4' RCB	500	LF	\$ 900	\$ 450,000
5	8'x4' RCB	1400	LF	\$ 950	\$ 1,330,000
6	STM MH (MED)	2	EA	\$ 7,500	\$ 15,000
7	STM JB (MED)	3	EA	\$ 12,000	\$ 36,000
8	STM JB (LG)	3	EA	\$ 23,500	\$ 70,500
9	DITCH INTERCEPTOR	20	EA	\$ 9,100	\$ 182,000
10	PAVEMENT REPAIR - ASP	750	LF	\$ 140	\$ 105,000
		SUBTOTAL			\$ 3,479,500
		CONTINGENCY		30%	\$ 1,043,850
		CONSULTANT		25%	\$ 869,875
11	LAND ACQUISITION (ESMT)	0.59	AC	\$ 130,680	\$ 77,140
		SUBTOTAL			\$ 77,140
		CONTINGENCY		10%	\$ 7,714
ESTIMATED PROJECT TOTAL COST:					\$ 5,478,078

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. MITIGATION PROVIDED IN M500-01

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

DRAINAGE AREA ID
 DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 250 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121-01-00)
SUBBASIN: C_W2

SCALE: 1" = 250'

March 2025

EXHIBIT NO. 15


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	15	Phase	
Project Name		Medical Complex Drive Storm Sewer Reconstruction			
Project Category					
Project Description					
Construct parallel storm sewer trunkline along Medical Complex Drive with an outfall connection to M121-01-00 cross culverts.					
Project Justification					
Increase capacity of roadway to meet updated drainage stanards and relieve street ponding.					
Potential Funding Opportunities					
Potential private development partnership.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	30" RCP	1125	LF	\$ 185	\$ 208,125
2	36" RCP	425	LF	\$ 200	\$ 85,000
3	STM MH (SM)	5	EA	\$ 6,000	\$ 30,000
4	OUTFALL TIE-IN	1	EA	\$ 10,000	\$ 10,000
6	PAVEMENT REPAIR - ASP	140	LF	\$ 140	\$ 19,600
		SUBTOTAL			\$ 352,725
		CONTINGENCY		30%	\$ 105,818
		CONSULTANT		25%	\$ 88,181
ESTIMATED PROJECT TOTAL COST:					\$ 546,724

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.


All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. DEVELOPMENT WILL REQUIRE ON-SITE DETENTION
4. 25-YEAR HGL 1 FOOT BELOW GUTTER
5. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
6. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	← DRAINAGE AREA ID	
	← DRAINAGE AREA IN ACRES	



(IN FEET)
1 INCH = 300 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121-01-00)
SUBBASIN: B_W1

SCALE: 1" = 300'

March 2025

EXHIBIT NO. 16


M121 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	16	Phase	
Project Name		Michel Road Storm Sewer Reconstruction			
Project Category					
Project Description					
Construction storm sewer along Michel Street within existing roadside ditch.					
Project Justification					
Provide outfall depth for future development.					
Potential Funding Opportunities					
Potential private development partnership.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	560	LF	\$ 130	\$ 72,800
2	30" RCP	540	LF	\$ 185	\$ 99,900
3	36" RCP	690	LF	\$ 200	\$ 138,000
4	48" RCP	590	LF	\$ 380	\$ 224,200
5	STM MH (SM)	5	EA	\$ 6,000	\$ 30,000
6	STM MH (MED)	2	EA	\$ 7,500	\$ 15,000
7	DITCH INTERCEPTOR	8	EA	\$ 9,100	\$ 72,800
8	PAVEMENT REPAIR - ASP	100	LF	\$ 140	\$ 14,000
9	OUTFALL TIE-IN	1	EA	\$ 10,000	\$ 10,000
		SUBTOTAL			\$ 676,700
		CONTINGENCY		30%	\$ 203,010
		CONSULTANT		25%	\$ 169,175
ESTIMATED PROJECT TOTAL COST:					\$ 1,048,885

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: M121 (M121W)
SUBBASIN: HS-EIB & HS-EIC

SCALE: 1" = 500'

March 2025

EXHIBIT NO. 17

M121 BASIN


Drainage CIP - Opinion of Probable Construction Cost					
Basin	M121	CIP Project No.	17	Phase	
Project Name		M521-02 Detention Pond			
Project Category					
Project Description					
Construct detention pond.					
Project Justification					
Provide regional detention for M121 Basin and/or floodplain mitigation from Willow Creek.					
Potential Funding Opportunities					
HCFCD and Grants					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	M521-02	230	AC-FT	\$ 40,000	\$ 9,200,000
2	Outfall Structure	1	EA	\$ 25,000	\$ 25,000
3	Side Wier	1	EA	\$ 20,000	\$ 20,000
		SUBTOTAL			\$ 9,245,000
		CONTINGENCY		30%	\$ 2,773,500
		CONSULTANT		25%	\$ 2,311,250
4	LAND ACQUISITION (FEE)	87.24	AC	\$ 217,800	\$ 19,001,478
		SUBTOTAL			\$ 19,001,478
		CONTINGENCY		10%	\$ 1,900,148
ESTIMATED PROJECT TOTAL COST:					\$ 35,231,375

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

Pricing excludes reloaction of pipelines and abandonment of wells.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN


BASIN: M121 (M121-01-00)
SUBBASIN: HS_E3

SCALE: 1" = 400'

March 2025

EXHIBIT NO. 18

M121 BASIN



(IN FEET)

1 INCH = 400 FT.

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M121	CIP Project No.	18	Phase		
Project Name		S. Pine Street Storm Sewer Improvements (From Malone Street to Hardin Street)				
Project Category						
Project Description						
Construct a storm sewer system along Pine Street while maintaining existing roadside ditches. Improvements are assumed as part of roadway reconstruction.						
Project Justification						
Increase capacity of conveyance system to improved channel to relieve flooding in Old Town.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	24" RCP	300	LF	\$ 130	\$ 39,000	
2	30" RCP	120	LF	\$ 185	\$ 22,200	
3	36" RCP	320	LF	\$ 200	\$ 64,000	
4	3'x3' RCB	300	LF	\$ 395	\$ 118,500	
5	4'x3' RCB	820	LF	\$ 450	\$ 369,000	
6	5'x4' RCB	200	LF	\$ 480	\$ 96,000	
7	STM MH (SM)	3	EA	\$ 6,000	\$ 18,000	
8	STM MH (MED)	2	EA	\$ 7,500	\$ 15,000	
9	STM JB (SM)	4	EA	\$ 8,000	\$ 32,000	
10	STM JB (MED)	2	EA	\$ 12,000	\$ 24,000	
11	CURB INLET	30	EA	\$ 8,600	\$ 258,000	
		SUBTOTAL			\$ 1,055,700	
		CONTINGENCY			30%	\$ 316,710
		CONSULTANT			25%	\$ 263,925
ESTIMATED PROJECT TOTAL COST:					\$ 1,636,335	


CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.


Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.

APPENDIX C – M124


CIP PACKETS





DESIGN CRITERIA

1. DESIGN STORM EVENT (CHANNEL): 100-YEAR
2. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
3. MITIGATION FOR INCREASED FLOW....
4. LAND ACQUISITION = 0 SF



(IN FEET)
1 INCH = 600 FT.

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	← DRAINAGE AREA ID	← DRAINAGE AREA IN ACRES



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: M124-00-00
SUBBASIN: 5 & 6

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 3

M124 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M124	CIP Project No.	2	Phase		
Project Name		Tomball Cemetery Road & Treichel Storm Sewer to M124-00-00				
Project Category						
Project Description						
Construct storm sewer along Tomball Cemetery Road, crossing FM 2920, and along the north side of Treichel Street to the M124-00-00 improved channel. Construction						
Project Justification						
Provide flooding relief for Pine Country Subdivision, increase capacity from roadside ditches, and provide outfall depth for future development.						
Potential Funding Opportunities						
TxDOT and/or Harris County Precinct 3 joint venture.						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	7'X4' RCB	940	LF	\$ 900	\$ 846,000	
2	8'X4' RCB	2275	LF	\$ 950	\$ 2,161,250	
3	9'X4' RCB	2500	LF	\$ 1,350	\$ 3,375,000	
4	10'X4' RCB	1520	LF	\$ 1,300	\$ 1,976,000	
5	STM JB (LG)	16	EA	\$ 23,500	\$ 376,000	
6	PAVEMENT REPAIR - ASP	200	LF	\$ 140	\$ 28,000	
7	PIPELINE RELOCATION	1	EA	\$ 30,000	\$ 30,000	
8	OUTFALL STRUCTURE	2	EA	\$ 25,000	\$ 50,000	
		SUBTOTAL			\$ 8,842,250	
		CONTINGENCY			30%	\$ 2,652,675
		CONSULTANT			25%	\$ 2,210,563
ESTIMATED PROJECT TOTAL COST:					\$ 13,705,488	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M124	CIP Project No.	3	Phase		
Project Name		M124-00-00 Channel Extension to Baker Drive				
Project Category						
Project Description						
Removing existitng drop structure south of Brown-Hufsmith, reconstructing Brown-Hufsmith culvert crossing, and M124-00-00 channel extension to Baker Drive. Construct storm sewer to replace existing culvert crossing at Baker Drive.						
Project Justification						
Provide flooding relief and outfall depth for future development. Collect and convey overflow from existing private pond north of Baker Drive.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	M124-00-00	1700	LF	\$ 410	\$ 697,000	
2	7'x6' RCB	450	LF	\$ 1,020	\$ 459,000	
3	9'x6' RCB	150	LF	\$ 1,450	\$ 217,500	
4	STM JB (LG)	2	EA	\$ 23,500	\$ 47,000	
6	PAVEMENT REPAIR - ASP	525	LF	\$ 140	\$ 73,500	
		SUBTOTAL			\$ 1,494,000	
		CONTINGENCY			30%	\$ 448,200
		CONSULTANT			25%	\$ 373,500
7	LAND ACQUISITION	6.35	AC	\$ 217,800	\$ 1,383,644	
		SUBTOTAL			\$ 1,383,644	
		CONTINGENCY			10%	\$ 138,364
ESTIMATED PROJECT TOTAL COST:					\$ 3,837,708	


CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.

APPENDIX C – M125

CIP PACKETS



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 2,260 SF

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
CITY LIMITS		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

← DRAINAGE AREA ID
 ← DRAINAGE AREA IN ACRES



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN


BASIN: M125
SUBBASIN: A6_E

SCALE: 1" = 250'

March 2025

EXHIBIT NO. 1

M125 BASIN



(IN FEET)
1 INCH = 250 FT.

Drainage CIP - Opinion of Probable Construction Cost						
Basin	M125	CIP Project No.	1	Phase		
Project Name		Cobble Creek Apartments				
Project Category						
Project Description						
Construct parallel storm sewer along Lawrence Street and Michel Road to M125-00-00. Construct inlets at Medical Complex Drive and Lawrence Street intersection with parrallel storm sewer along Medical Complex Drive to M125-00-00.						
Project Justification						
Relieve low-lying apartment complex from structural flooding and divert overland flow from Medical Complex.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	36" RCP	340	LF	\$ 200	\$ 68,000	
2	48" RCP	700	LF	\$ 380	\$ 266,000	
3	54" CMP	240	LF	\$ 180	\$ 43,200	
4	STM MH (MED)	2	EA	\$ 7,500	\$ 15,000	
5	STM MH (LG)	5	EA	\$ 9,000	\$ 45,000	
6	CURB INLET	10	EA	\$ 8,600	\$ 86,000	
7	FLAP GATE	2	EA	\$ 10,000	\$ 20,000	
8	PAVEMENT REPAIR - CONC	576	LF	\$ 140	\$ 80,640	
		SUBTOTAL			\$ 623,840	
		CONTINGENCY			30%	\$ 187,152
		CONSULTANT			25%	\$ 155,960
9	LAND ACQUISITION	0.05	AC	\$ 130,680	\$ 6,780	
		SUBTOTAL			\$ 6,780	
		CONTINGENCY			10%	\$ 678
ESTIMATED PROJECT TOTAL COST:					\$ 974,410	


CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.

APPENDIX C – J131

CIP PACKETS



DESIGN CRITERIA


- DESIGN STORM EVENT: 100-YEAR
- HYDROLOGY - PEAK FLOWS DETERMINED FROM RATIONAL METHOD BASED ON EXISTING AND FUTURE LAND USE MAPS
- SMALL WATERSHED METHOD USED TO ESTIMATE DETENTION VOLUME FOR INCREASED FLOWS (MINIMUM VOLUME = SWM + 20%)
 - STORAGE VOLUME REQUIRED FOR J131_A5 SUBBASIN = 22.8 AC-FT
 - STORAGE VOLUME REQUIRED FOR J131_B1_S1 SUBBASIN = 13.1 AC-FT
 - STORAGE VOLUME REQUIRED FOR HUFSMITH RD = 2.8 AC-FT (1,5500 LF OF 80' ROW @ 1 AC-FT/AC)
- TOTAL STORAGE VOLUME REQUIRED = 38.7 AC-FT
- TOTAL LAND ACQUISITION = 20, 623 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

3A
50.0

← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)

1 INCH = 300 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J131-00-00
SUBBASIN: A5

SCALE: 1" = 1" = 300'

March 2025

EXHIBIT NO. 1


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	1	Phase	
Project Name		J531-01 Detention Pond Improvements			
Project Category					
Project Description					
Acquire remaining parcel within City-owned triangular tract between Hufsmith Road, Ulrich Road and BNSF Railroad. Construction sub-regional dry detention pond on City owned property. Acquisition efforts for remaining parcels are not included in cost estimate.					
Project Justification					
Mitigate increased flows for future storm sewer additions along Cherry Street, Commerce Street and Hufmsith Road. Relieve flooding for Old Town.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	J531-01 DETENTION POND	49	AC-FT	\$ 40,000	\$ 1,960,000
2	OUTFALL STRUCTURE	1	EA	\$ 25,000	\$ 25,000
		SUBTOTAL			\$ 1,985,000
		CONTINGENCY		30%	\$ 595,500
		CONSULTANT		25%	\$ 496,250
3	LAND ACQUISITION (FEE)	0.54	AC	\$ 435,600	\$ 234,000
		SUBTOTAL			\$ 234,000
		CONTINGENCY		10%	\$ 23,400
ESTIMATED PROJECT TOTAL COST:					\$ 3,334,150

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

Pricing excludes reloaction of pipelines and abandonment of wells.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. MITIGATION PROVIDED IN J531-01

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



(IN FEET)
1 INCH = 600 FT.



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: J131-00-00
SUBBASIN: A5

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 2 & 3


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	2	Phase	
Project Name		N. Cherry Street Storm Sewer Improvements (From Commerce Street to Hufsmith Rd)			
Project Category					
Project Description					
Construct storm sewer and roadside ditch interceptors along N. Cherry Street to J531-01. Cost assumes improvements will be installed without roadway reconstruction.					
Project Justification					
Provide local flood relief for Old Town by adding conveyance capacity.					
Potential Funding Opportunities					
Partnership with Harris County Precinct 3 during roadway reconstruction.					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	42" RCP	570	LF	\$ 300	\$ 171,000
2	48" RCP	270	LF	\$ 380	\$ 102,600
3	4'x4' RCB	350	LF	\$ 500	\$ 175,000
4	5'x4' RCB	390	LF	\$ 480	\$ 187,200
5	6'x4' RCB	660	LF	\$ 810	\$ 534,600
6	7'x4' RCB	525	LF	\$ 900	\$ 472,500
7	STM MH (SM)	1	EA	\$ 6,000	\$ 6,000
8	STM MH (MED)	1	EA	\$ 7,500	\$ 7,500
9	STM JB (SM)	1	EA	\$ 8,000	\$ 8,000
10	STM JB (MED)	2	EA	\$ 12,000	\$ 24,000
11	STM JB (LG)	2	EA	\$ 23,500	\$ 47,000
12	DITCH INTERCEPTOR	18	EA	\$ 9,100	\$ 163,800
13	PAVEMENT REPAIR - ASP	2765	LF	\$ 140	\$ 387,100
		SUBTOTAL			\$ 2,286,300
		CONTINGENCY		30%	\$ 685,890
		CONSULTANT		25%	\$ 571,575
ESTIMATED PROJECT TOTAL COST:					\$ 3,543,765

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. MITIGATION PROVIDED IN J531-01

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



(IN FEET)
1 INCH = 600 FT.



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: J131-00-00
SUBBASIN: A5

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 2 & 3


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	3	Phase	
Project Name		Commerce Street Storm Sewer Improvements			
Project Category					
Project Description					
Construct storm sewer improvements along Commerce Street from Pine Street to Elm Street.					
Project Justification					
Provide local flood relief for Old Town by adding inlet conveyance capacity.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	150	LF	\$ 130	\$ 19,500
2	30" RCP	600	LF	\$ 185	\$ 111,000
3	36" RCP	240	LF	\$ 200	\$ 48,000
4	CURB INLET	16	EA	\$ 8,600	\$ 137,600
5	STM MH (MED)	1	EA	\$ 7,500	\$ 7,500
6	PAVEMENT REPAIR - ASP	1260	LF	\$ 140	\$ 176,400
		SUBTOTAL			\$ 500,000
		CONTINGENCY		30%	\$ 150,000
		CONSULTANT		25%	\$ 125,000
ESTIMATED PROJECT TOTAL COST:					\$ 775,000

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.


Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



- DESIGN CRITERIA**
1. DESIGN STORM EVENT: 100-YEAR
 2. HYDROLOGY - PEAK FLOWS DETERMINED FROM RATIONAL METHOD BASED ON EXISTING AND FUTURE LAND USE MAPS
 3. SMALL WATERSHED METHOD USED TO ESTIMATE DETENTION VOLUME FOR INCREASED FLOWS (MINIMUM VOLUME = SWM + 20%)
 - 3.1. STORAGE VOLUME REQUIRED FOR J131_B1_S1 = 13.1 AC-FT
 - 3.2. STORAGE VOLUME REQUIRED FOR J132_B1_S2 = 5.6 AC-FT
 - 3.3. TOTAL STORAGE VOLUME REQUIRED = 18.7 AC-FT

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



(IN FEET)
1 INCH = 300 FT.



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J131-00-00
SUBBASIN: B1_S1 & B1_S2

SCALE: 1" = 1" = 300'

March 2025

EXHIBIT NO. 4

J131 BASIN


Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	4	Phase	
Project Name		J531-02 Detention Pond Improvements			
Project Category					
Project Description					
Construction of dry-bottom stormwater detention pond on City-owned tract.					
Project Justification					
Alternative drainage solution to serve future Hufsmith Road roadway reconstruction and North Sycamore Street storm sewer improvements.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	J531-02 DETENTION POND	26.8	AC-FT	\$ 40,000	\$ 1,072,000
2	OUTFALL STRUCTURE	1	EA	\$ 25,000	\$ 25,000
SUBTOTAL					\$ 1,097,000
CONTINGENCY				30%	\$ 329,100
CONSULTANT				25%	\$ 274,250
ESTIMATED PROJECT TOTAL COST:					\$ 1,700,350

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

Pricing excludes reloaction of pipelines and abandonment of wells.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. MITIGATION PROVIDED IN J531-01
7. LAND ACQUISITION (ESMT) = 20,720 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
3A		
50.0		



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J131-00-00
SUBBASIN: B1_S1

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 5A

J131 BASIN


(IN FEET)
1 INCH = 600 FT.

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	5A	Phase		
Project Name		N. Sycamore Storm Sewer Alternate 1				
Project Category						
Project Description						
Construct storm sewer along N. Sycamore Street to J531-01 detention pond.						
Project Justification						
Relieve local flooding due to limited conveyance capacity to J131-00-00. Provide outfall depth for future development and future roadway improvements.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	30" RCP	300	LF	\$ 185	\$ 55,500	
2	48" RCP	360	LF	\$ 380	\$ 136,800	
3	48" RCP (railroad)	150	LF	\$ 760	\$ 114,000	
4	4'x4' RCB	840	LF	\$ 500	\$ 420,000	
5	5'x4' RCB	420	LF	\$ 480	\$ 201,600	
6	6'x4' RCB	120	LF	\$ 810	\$ 97,200	
7	7'x4' RCB	450	LF	\$ 900	\$ 405,000	
8	STM MH (SM)	2	EA	\$ 6,000	\$ 12,000	
9	STM JB (SM)	2	EA	\$ 8,000	\$ 16,000	
10	STM JB (MED)	2	EA	\$ 12,000	\$ 24,000	
11	STM JB (LG)	2	EA	\$ 23,500	\$ 47,000	
12	DITCH INTERCEPTOR	8	EA	\$ 9,100	\$ 72,800	
13	PAVEMENT REPAIR - ASP	1000	LF	\$ 140	\$ 140,000	
		SUBTOTAL			\$ 1,741,900	
		CONTINGENCY			30%	\$ 522,570
		CONSULTANT			25%	\$ 435,475
14	LAND ACQUISITION (ESMT)	0.48	AC	\$ 130,680	\$ 62,157	
		SUBTOTAL			\$ 62,157	
		CONTINGENCY			10%	\$ 6,216
ESTIMATED PROJECT TOTAL COST:					\$ 2,768,318	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. MITIGATION PROVIDED IN J531-02
7. LAND ACQUISITION (ESMT) = 20,720 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	DRAINAGE AREA IN ACRES



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN


BASIN: J131-00-00
SUBBASIN: B1_S1 & B1_S2

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 5B

J131 BASIN




(IN FEET)
1 INCH = 600 FT.

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	5B	Phase		
Project Name		N. Sycamore Storm Sewer Alternate 2				
Project Category						
Project Description						
Construct storm sewer along N. Sycamore Street to J531-01 detention pond.						
Project Justification						
Alternative solution to relieve local flooding due to limited conveyance capacity to J131-00-00. Provide outfall depth for future development and future roadway improvements.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	30" RCP	300	LF	\$ 185	\$ 55,500	
2	48" RCP	360	LF	\$ 380	\$ 136,800	
3	4'x4' RCB	840	LF	\$ 500	\$ 420,000	
4	5'x4' RCB	420	LF	\$ 480	\$ 201,600	
5	6'x4' RCB	690	LF	\$ 810	\$ 558,900	
6	7'x4' RCB	120	LF	\$ 900	\$ 108,000	
7	STM MH (SM)	1	EA	\$ 6,000	\$ 6,000	
8	STM MH (MED)	1	EA	\$ 7,500	\$ 7,500	
9	STM JB (SM)	2	EA	\$ 8,000	\$ 16,000	
10	STM JB (MED)	3	EA	\$ 12,000	\$ 36,000	
11	STM JB (LG)	1	EA	\$ 23,500	\$ 23,500	
12	DITCH INTERCEPTOR	6	EA	\$ 9,100	\$ 54,600	
13	PAVEMENT REPAIR - ASP	1000	LF	\$ 140	\$ 140,000	
		SUBTOTAL			\$ 1,764,400	
		CONTINGENCY			30%	\$ 529,320
		CONSULTANT			25%	\$ 441,100
14	LAND ACQUISITION (ESMT)	0.48	AC	\$ 130,680	\$ 62,157	
		SUBTOTAL			\$ 62,157	
		CONTINGENCY			10%	\$ 6,216
ESTIMATED PROJECT TOTAL COST:					\$ 2,803,193	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.


All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



- DESIGN CRITERIA**
1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
 2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
 3. 25-YEAR HGL 1 FOOT BELOW GUTTER
 4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
 5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
 6. LAND ACQUISITION (ESMT) = 484,993 SF

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		

DRAINAGE AREA ID
 DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 400 FT.



CSE Civil Systems Engineering, Inc.

**CITY OF TOMBALL DMP
CIP DETAIL LAYOUTS**

BASIN: J131-00-00
SUBBASIN:

SCALE: 1" = 400'

March 2025

EXHIBIT NO. 6A

J131 BASIN


Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	6A	Phase		
Project Name		J131-01 Alternate 1				
Project Category						
Project Description						
Construct storm sewer along Hufsmith Rd and Zion Road. Construct J531-04 detention and mitigation pond. Improvements assumed to be in correlation with Harris County Precinct 3 roadway improvements for Hufsmith and Zion.						
Project Justification						
Relieve flooding, mitigate J131-01 floodplain, and provide outfall depth for future development.						
Potential Funding Opportunities						
HCFCD and/or Harris County Precinct 3 joint venture						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	24" RCP	440	LF	\$ 130	\$ 57,200	
2	6'x6' RCB	1240	LF	\$ 820	\$ 1,016,800	
3	8'x8' RCB	740	LF	\$ 1,250	\$ 925,000	
4	10'x8' RCB	7040	LF	\$ 1,560	\$ 10,982,400	
5	STM MH (SM)	1	EA	\$ 6,000	\$ 6,000	
6	STM JB (MED)	2	EA	\$ 12,000	\$ 24,000	
7	STM JB (LG)	9	EA	\$ 23,500	\$ 211,500	
8	CURB INLET	28	EA	\$ 8,600	\$ 240,800	
10	J531-04	82.2	AC-FT	\$ 40,000	\$ 3,288,000	
		SUBTOTAL			\$ 16,751,700	
		CONTINGENCY			30%	\$ 5,025,510
		CONSULTANT			25%	\$ 4,187,925
11	LAND ACQUISITION (J531-04)	11.02	AC	\$ 217,800	\$ 2,400,458	
12	LAND ACQUISITION (ESMT)	0.11	AC	\$ 130,680	\$ 14,704	
		SUBTOTAL			\$ 2,415,162	
		CONTINGENCY			10%	\$ 241,516
ESTIMATED PROJECT TOTAL COST:					\$ 28,621,813	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.


Pricing excludes reloaction of pipelines and abandonment of wells.


All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



- DESIGN CRITERIA**
1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
 2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
 3. 25-YEAR HGL 1 FOOT BELOW GUTTER
 4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
 5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
 6. LAND ACQUISITION (ESMT) = 675,388 SF

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	





CSE Civil Systems Engineering, Inc.

**CITY OF TOMBALL DMP
CIP DETAIL LAYOUTS**

BASIN: J131-00-00
SUBBASIN:

SCALE: 1" = 400'	March 2025
EXHIBIT NO. 6B	J131 BASIN



Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	6B	Phase	
Project Name		J131-01 Alternate 2			
Project Category					
Project Description					
Construct storm sewer along Hufsmith Rd and Zion Road. Construct J531-04 detention and mitigation pond. Construct J131-02 between Zion and Hufsmith. Improvements assumed to be in correlation with Harris County Precinct 3 roadway improvements for Hufsmith and Zion.					
Project Justification					
Relieve flooding, mitigate J131-01 floodplain, and provide outfall depth for future development.					
Potential Funding Opportunities					
HCFCD and/or Harris County Precinct 3 joint venture					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	440	LF	\$ 130	\$ 57,200
2	48" RCP	320	LF	\$ 380	\$ 121,600
2	6'x6' RCB	1240	LF	\$ 820	\$ 1,016,800
3	8'x8' RCB	740	LF	\$ 1,250	\$ 925,000
4	10'x8' RCB	4160	LF	\$ 1,560	\$ 6,489,600
5	STM MH (SM)	1	EA	\$ 6,000	\$ 6,000
6	STM MH (MED)	1	EA	\$ 7,500	\$ 7,500
7	STM JB (MED)	2	EA	\$ 12,000	\$ 24,000
8	STM JB (LG)	9	EA	\$ 23,500	\$ 211,500
9	CURB INLET	26	EA	\$ 8,600	\$ 223,600
11	J131-02-00	1640	LF	\$ 410	\$ 672,400
12	J531-04	82.2	AC-FT	\$ 40,000	\$ 3,288,000
		SUBTOTAL			\$ 13,043,200
		CONTINGENCY		30%	\$ 3,912,960
		CONSULTANT		25%	\$ 3,260,800
13	LAND ACQUISITION (J531-04)	11.02	AC	\$ 217,800	\$ 2,400,458
14	LAND ACQUISITION (ESMT)	0.11	AC	\$ 130,680	\$ 14,704
15	LAND ACQUISITION (J131-02-00)	4.37	AC	\$ 217,800	\$ 951,978
		SUBTOTAL			\$ 3,367,140
		CONTINGENCY		10%	\$ 336,714
ESTIMATED PROJECT TOTAL COST:					\$ 23,920,814

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.


Pricing excludes reloaction of pipelines and abandonment of wells.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



- DESIGN CRITERIA**
1. DESIGN STORM EVENT (STORM SEWER): 100-YEAR
 2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
 3. 25-YEAR HGL 1 FOOT BELOW GUTTER
 4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
 5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
 6. LAND ACQUISITION (ESMT) = 655,005 SF

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



CSE Civil Systems Engineering, Inc.

**CITY OF TOMBALL DMP
CIP DETAIL LAYOUTS**

BASIN: J131-00-00
SUBBASIN:

SCALE: 1" = 400'	March 2025
EXHIBIT NO. 6C	J131 BASIN


Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	6C	Phase	
Project Name		J131-01 Alternate 3			
Project Category					
Project Description					
Construct storm sewer along Hufsmith Rd and Zion Road. Construct J531-03 and J531-04 detention and mitigation ponds. Improvements assumed to be in correlation with Harris County Precinct 3 roadway improvements for Hufsmith and Zion.					
Project Justification					
Relieve flooding, mitigate J131-01 floodplain, and provide outfall depth for future development.					
Potential Funding Opportunities					
HCFCD and/or Harris County Precinct 3 joint venture					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	440	LF	\$ 130	\$ 57,200
2	48" RCP	1000	LF	\$ 380	\$ 380,000
3	6'x6' RCB	440	LF	\$ 820	\$ 360,800
4	8'x8' RCB	740	LF	\$ 1,250	\$ 925,000
5	9'x7' RCB	400	LF	\$ 1,420	\$ 568,000
6	10'x8' RCB	4960	LF	\$ 1,560	\$ 7,737,600
7	STM MH (SM)	1	EA	\$ 6,000	\$ 6,000
8	STM MH (LG)	1	EA	\$ 9,000	\$ 9,000
9	STM JB (MED)	1	EA	\$ 12,000	\$ 12,000
10	STM JB (LG)	11	EA	\$ 23,500	\$ 258,500
11	CURB INLET	33	EA	\$ 8,600	\$ 283,800
13	J531-03	14.7	AC-FT	\$ 40,000	\$ 588,000
14	J531-04	82.2	AC-FT	\$ 40,000	\$ 3,288,000
		SUBTOTAL			\$ 14,473,900
		CONTINGENCY		30%	\$ 4,342,170
		CONSULTANT		25%	\$ 3,618,475
15	LAND ACQUISITION (J531-04)	11.02	AC	\$ 217,800	\$ 2,400,458
16	LAND ACQUISITION (ESMT)	0.45	AC	\$ 130,680	\$ 58,162
17	LAND ACQUISITION (J531-03)	3.57	AC	\$ 217,800	\$ 777,638
		SUBTOTAL			\$ 3,236,259
		CONTINGENCY		10%	\$ 323,626
ESTIMATED PROJECT TOTAL COST:					\$ 25,994,429

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

Pricing excludes reloaction of pipelines and abandonment of wells.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN


BASIN: J131-00-00
SUBBASIN: A5

SCALE: 1" = 1" = 1000'

March 2025

EXHIBIT NO. 7

J131 BASIN




(IN FEET)
1 INCH = 1000 FT.

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	7	Phase	
Project Name		Zion Road Storm Sewer Improvements			
Project Category					
Project Description					
Construct storm sewer along Zion Road. Improvements assumed to be part of roadway reconstruction.					
Project Justification					
Provide increased conveyance and relieve local flooding.					
Potential Funding Opportunities					
Harris County Precinct 3					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	400	LF	\$ 130	\$ 52,000
2	30" RCP	400	LF	\$ 185	\$ 74,000
3	36" RCP	1150	LF	\$ 200	\$ 230,000
4	36" RCP (railroad)	100	LF	\$ 400	\$ 40,000
5	42" RCP	500	LF	\$ 300	\$ 150,000
6	60" RCP	800	LF	\$ 400	\$ 320,000
7	72" RCP	1800	LF	\$ 650	\$ 1,170,000
8	7'x6' RCB	950	LF	\$ 1,020	\$ 969,000
9	STM MH (SM)	5	EA	\$ 6,000	\$ 30,000
10	STM MH (MED)	2	EA	\$ 7,500	\$ 15,000
11	STM MH (LG)	3	EA	\$ 9,000	\$ 27,000
12	STM JB (LG)	2	EA	\$ 23,500	\$ 47,000
13	CURB INLET	20	EA	\$ 8,600	\$ 172,000
		SUBTOTAL			\$ 3,296,000
		CONTINGENCY		30%	\$ 988,800
		CONSULTANT		25%	\$ 824,000
ESTIMATED PROJECT TOTAL COST:					\$ 5,108,800

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA


1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
7. LAND ACQUISITION (ESMT) = 59,941 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



(IN FEET)
1 INCH = 600 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J131 (J131-03-00)
SUBBASIN: E1 & E2

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 8


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	8	Phase		
Project Name		Hufsmith Road Storm Sewer Improvements				
Project Category						
Project Description						
Construct storm sewer down Hufsmith Road between BNSF Railroad and Lovett Street. Improvements assumed to be incorporated as part of roadway reconstruction.						
Project Justification						
Provide increased conveyance and relieve local flooding.						
Potential Funding Opportunities						
Harris County Precinct 3						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	24" RCP	750	LF	\$ 130	\$ 97,500	
2	48" RCP	780	LF	\$ 380	\$ 296,400	
3	4'x4' RCB	300	LF	\$ 500	\$ 150,000	
4	5'x4' RCB	960	LF	\$ 480	\$ 460,800	
5	5'x5' RCB	600	LF	\$ 670	\$ 402,000	
6	6'x5' RCB	510	LF	\$ 750	\$ 382,500	
7	7'x6' RCB	540	LF	\$ 1,020	\$ 550,800	
8	STM MH (SM)	1	EA	\$ 6,000	\$ 6,000	
9	STM MH (LG)	1	EA	\$ 9,000	\$ 9,000	
10	STM JB (SM)	5	EA	\$ 8,000	\$ 40,000	
11	STM JB (MED)	1	EA	\$ 12,000	\$ 12,000	
12	STM JB (LG)	2	EA	\$ 23,500	\$ 47,000	
13	CURB INLET	22	EA	\$ 8,600	\$ 189,200	
14	HUFSMITH POND A	13.4	AC-FT	\$ 40,000	\$ 536,000	
15	HUFSMITH POND B	2.8	AC-FT	\$ 40,000	\$ 112,000	
16	OUTFALL STRUCTURE	2	EA	\$ 25,000	\$ 50,000	
		SUBTOTAL			\$ 3,341,200	
		CONTINGENCY			30%	\$ 1,002,360
		CONSULTANT			25%	\$ 835,300
18	LAND ACQUISITION (FEE)	1.38	AC	\$ 217,800	\$ 299,702	
		SUBTOTAL			\$ 299,702	
		CONTINGENCY			10%	\$ 29,970
ESTIMATED PROJECT TOTAL COST:					\$ 5,508,533	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT POND OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. DETENTION PROVIDED IN SNOOK DETENTION POND FOR WATERSHED DIVERSION
7. LAND ACQUISITION (ESMT) = 231,028 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



(IN FEET)
1 INCH = 600 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J131-01-00
SUBBASIN: A

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 9


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	9	Phase		
Project Name		Snook Lane Storm Sewer Improvements				
Project Category						
Project Description						
Construct storm sewer improvements along Snook Lane. Construct detention pond near Hufsmith Road. Improvements assumed to be installed as part of roadway reconstruction and require improvements to Hufsmith Road for outfall depth.						
Project Justification						
Watershed diversion from M116 to J131 due to issues along FM 2920 and lack of outfall depth for future improvements. Stormwater detention pond to offset runoff impacts for watershed diversion and roadway improvements.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	24" RCP	360	LF	\$ 130	\$ 46,800	
2	30" RCP	600	LF	\$ 185	\$ 111,000	
3	48" RCP	1350	LF	\$ 380	\$ 513,000	
4	5'x4' RCB	960	LF	\$ 480	\$ 460,800	
5	6'x5' RCB	450	LF	\$ 750	\$ 337,500	
6	STM MH (SM)	3	EA	\$ 6,000	\$ 18,000	
7	STM MH (LG)	2	EA	\$ 9,000	\$ 18,000	
8	STM JB (MED)	3	EA	\$ 12,000	\$ 36,000	
9	CURB INLET	22	EA	\$ 8,600	\$ 189,200	
10	SNOOK DETENTION POND	27	AC-FT	\$ 40,000	\$ 1,080,000	
11	OUTFALL STRUCTURE	2	EA	\$ 150	\$ 300	
		SUBTOTAL			\$ 1,730,300	
		CONTINGENCY			30%	\$ 519,090
		CONSULTANT			25%	\$ 432,575
12	LAND ACQUISITION (FEE)	5.30	AC	\$ 217,800	\$ 1,155,140	
		SUBTOTAL			\$ 1,155,140	
		CONTINGENCY			10%	\$ 115,514
ESTIMATED PROJECT TOTAL COST:					\$ 3,952,619	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
7. LAND ACQUISITION (ESMT) = 15,316 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		

ZONE AE/FLOODWAY
 ZONE AE (100-YR)
 ZONE X (500-YR)

3A
 50.0

← DRAINAGE AREA ID
 ← DRAINAGE AREA IN ACRES



CSE Civil Systems
 Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN


BASIN: J131 (J131-03-00)
 SUBBASIN: D

SCALE: 1" = 1" = 500'

March 2025

EXHIBIT NO. 10A

J131 BASIN




(IN FEET)
 1 INCH = 500 FT.

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	10A	Phase		
Project Name		Carrell Street Storm Sewer Improvements				
Project Category						
Project Description						
Construct storm sewer along Carrell Street and southern segments of Lovett Street to J131-03-00. Construct storm sewer to around Carrell Street Baptist Church.						
Project Justification						
Relieve local flooding and provide conveyance capacity. Construct storm sewer to decrease ongoing maintance cost at Carrell Street Baptist Church.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	36" RCP	1050	LF	\$ 200	\$ 210,000	
2	42" RCP	375	LF	\$ 300	\$ 112,500	
3	4'x4' RCB	650	LF	\$ 500	\$ 325,000	
4	5'x4' RCB	550	LF	\$ 480	\$ 264,000	
5	6'x4' RCB	750	LF	\$ 810	\$ 607,500	
6	STM MH (SM)	5	EA	\$ 6,000	\$ 30,000	
7	STM JB (SM)	2	EA	\$ 8,000	\$ 16,000	
8	STM JB (MED)	5	EA	\$ 12,000	\$ 60,000	
9	DITCH INTERCEPTOR	18	EA	\$ 9,100	\$ 163,800	
10	PAVEMENT REPAIR - ASP	2850	LF	\$ 140	\$ 399,000	
		SUBTOTAL			\$ 2,187,800	
		CONTINGENCY			30%	\$ 656,340
		CONSULTANT			25%	\$ 546,950
11	LAND ACQUISITION (ESMT)	0.35	AC	\$ 130,680	\$ 45,948	
		SUBTOTAL			\$ 45,948	
		CONTINGENCY			10%	\$ 4,595
ESTIMATED PROJECT TOTAL COST:					\$ 3,441,633	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. DESIGN STORM EVENT (CHANNEL): 100-YR
3. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
4. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
5. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
6. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



(IN FEET)
1 INCH = 500 FT.



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: J131 (J131-03-00)
SUBBASIN: E1

SCALE: 1" = 1" = 500'

March 2025

EXHIBIT NO. 11A


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	11A	Phase		
Project Name		Lovett Street Storm Sewer Improvements				
Project Category						
Project Description						
Construct storm sewer along Lovett Street to Hufsmith Road.						
Project Justification						
Provide local flooding relief and conveyance capacity.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	36" RCP	650	LF	\$ 200	\$ 130,000	
2	42" RCP	350	LF	\$ 300	\$ 105,000	
3	48" RCP	375	LF	\$ 380	\$ 142,500	
4	4'x4' RCB	400	LF	\$ 500	\$ 200,000	
5	STM MH (SM)	2	EA	\$ 6,000	\$ 12,000	
6	STM MH (MED)	1	EA	\$ 7,500	\$ 7,500	
7	STM JB (SM)	2	EA	\$ 8,000	\$ 16,000	
8	DITCH INTERCEPTOR	10	EA	\$ 9,100	\$ 91,000	
9	PAVEMENT REPAIR - ASP	1800	LF	\$ 140	\$ 252,000	
		SUBTOTAL			\$ 956,000	
		CONTINGENCY			30%	\$ 286,800
		CONSULTANT			25%	\$ 239,000
ESTIMATED PROJECT TOTAL COST:					\$ 1,481,800	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. DESIGN STORM EVENT (CHANNEL): 100-YR
3. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
4. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
5. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
6. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
7. LAND ACQUISITION (ESMT) = 15,316 SF
8. LAND ACQUISITION (FEE) = 23,872 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 500 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J131 (J131-03-00)
SUBBASIN: D

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 10B & 11B


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	10B-11B	Phase	
Project Name		Carrell Street / Lovett Street / J131-03 Channel Improvements			
Project Category					
Project Description					
Construct storm sewer along Carrell Street and Lovett Street to J131-03-00 independent of Hufsmith roadway reconstruction. Construct storm sewer to around Carrell Street Baptist Church. Reconstruct J131-03 to a concrete-lined channel with a vertical drop of 5 feet.					
Project Justification					
Relieve local flooding and provide conveyance capacity. Construct storm sewer to decrease ongoing maintance cost at Carrell Street Baptist Church.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	640	LF	\$ 130	\$ 83,200
2	36" RCP	1200	LF	\$ 200	\$ 240,000
3	48" RCP	400	LF	\$ 380	\$ 152,000
4	5'x4' RCB	580	LF	\$ 480	\$ 278,400
5	6'x4' RCB	490	LF	\$ 810	\$ 396,900
6	7'x4' RCB	1020	LF	\$ 900	\$ 918,000
7	8'x4' RCB	80	LF	\$ 950	\$ 76,000
8	8'x7' RCB	240	LF	\$ 1,150	\$ 276,000
9	9'x7' RCB	150	LF	\$ 1,420	\$ 213,000
10	10'x7' RCB	100	LF	\$ 1,525	\$ 152,500
11	STM JB (LG)	3	EA	\$ 23,500	\$ 70,500
12	INLET - TYPE E	3	EA	\$ 5,000	\$ 15,000
13	DITCH INTERCEPTOR	26	EA	\$ 9,100	\$ 236,600
14	PAVEMENT REPAIR - ASP	1300	LF	\$ 140	\$ 182,000
15	J131-03	1500	LF	\$ 1,470	\$ 2,205,000
		SUBTOTAL			\$ 5,495,100
		CONTINGENCY		30%	\$ 1,648,530
		CONSULTANT		25%	\$ 1,373,775
16	LAND ACQUISITION (ESMT)	0.35	AC	\$ 130,680	\$ 45,948
17	LAND ACQUISITION (J131-03)	0.55	AC	\$ 217,800	\$ 119,358
		SUBTOTAL			\$ 165,306
		CONTINGENCY		10%	\$ 16,531
ESTIMATED PROJECT TOTAL COST:					\$ 8,699,242

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. DESIGN STORM EVENT (CHANNEL): 100-YR
3. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
4. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
5. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
6. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 500 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J131 (J131-03-00)
SUBBASIN: D

SCALE: 1" = 1"=600'

March 2025

EXHIBIT NO. 10C & 11C


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	10C-11C	Phase		
Project Name		Carrell Street / Lovett Street / J131-03 Channel Enclosure Improvements				
Project Category						
Project Description						
Construct storm sewer along Carrell Street and Lovett Street to J131-03-00 independent of Hufsmith roadway reconstruction. Construct storm sewer to around Carrell Street Baptist Church. Enclose J131-03 with storm sewer.						
Project Justification						
Relieve local flooding and provide conveyance capacity. Construct storm sewer to decrease ongoing maintance cost at Carrell Street Baptist Church.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	24" RCP	640	LF	\$ 130	\$ 83,200	
2	36" RCP	1200	LF	\$ 200	\$ 240,000	
3	48" RCP	400	LF	\$ 380	\$ 152,000	
4	5'x4' RCB	580	LF	\$ 480	\$ 278,400	
5	6'x4' RCB	490	LF	\$ 810	\$ 396,900	
6	7'x4' RCB	1020	LF	\$ 900	\$ 918,000	
7	8'x4' RCB	80	LF	\$ 950	\$ 76,000	
8	8'x7' RCB	240	LF	\$ 1,150	\$ 276,000	
9	10'x7' RCB	3560	LF	\$ 1,525	\$ 5,429,000	
10	12'x7' RCB	400	LF	\$ 1,800	\$ 720,000	
11	STM JB (LG)	3	EA	\$ 23,500	\$ 70,500	
12	STM JB (EX LG)	3	EA	\$ 60,000	\$ 180,000	
13	INLET - TYPE E	3	EA	\$ 5,000	\$ 15,000	
14	DITCH INTERCEPTOR	26	EA	\$ 9,100	\$ 236,600	
15	PAVEMENT REPAIR - ASP	1300	LF	\$ 140	\$ 182,000	
		SUBTOTAL			\$ 9,253,600	
		CONTINGENCY			30%	\$ 2,776,080
		CONSULTANT			25%	\$ 2,313,400
16	LAND ACQUISITION (ESMT)	0.35	AC	\$ 130,680	\$ 45,948	
		SUBTOTAL			\$ 45,948	
		CONTINGENCY			10%	\$ 4,595
ESTIMATED PROJECT TOTAL COST:					\$ 14,393,623	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA


1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 967 SF

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		

- ZONE AE/FLOODWAY
- ZONE AE (100-YR)
- ZONE X (500-YR)

DRAINAGE AREA ID
 DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 400 FT.



CSE Civil Systems Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: J131 (J131-03-00)
SUBBASIN: D

SCALE: 1" = 1" = 400'

March 2025

EXHIBIT NO. 12


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	12	Phase		
Project Name		Willow Street Ditch Regrade and Culvert Crossing to J131-03-00				
Project Category						
Project Description						
Regrade roadside ditch allow Willow to new culvert crossing at Texas Street unimproved right-of-way to J131-03-00.						
Project Justification						
Increase conveyance capacity, repair erosive storm sewer conditions, and relieve flooding at adjacent residential structures.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	REMOVE EX. 4'x2' RCB	75	LF	\$ 30	\$ 2,250	
2	4'x4' RCB	60	LF	\$ 500	\$ 30,000	
3	PROPOSED DITCH	280	LF	\$ 100	\$ 28,000	
4	STM HW	2	EA	\$ 10,000	\$ 20,000	
5	PAVEMENT REPAIR - ASP	60	LF	\$ 140	\$ 8,400	
		SUBTOTAL			\$ 88,650	
		CONTINGENCY			30%	\$ 26,595
		CONSULTANT			25%	\$ 22,163
6	LAND ACQUISITION	0.02	AC	\$ -	\$ -	
		SUBTOTAL			\$ -	
		CONTINGENCY			10%	\$ -
ESTIMATED PROJECT TOTAL COST:					\$ 137,408	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA


1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. DESIGN STORM EVENT (CHANNEL): 100-YR
3. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
4. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
5. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
6. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		



← DRAINAGE AREA ID
← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 400 FT.



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: J131 (J131-00-00)
SUBBASIN: D

SCALE: 1" = 1" = 400'

March 2025

EXHIBIT NO. 13


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	13	Phase	
Project Name		Baker Drive & Brown Road Storm Sewer to J131-00-00			
Project Category					
Project Description					
Construct storm sewer along Baker Drive and Brown Road to J131-00-00. Improvements are assumed to be independent of roadway reconstruction.					
Project Justification					
Relieve local flooding and provide outfall depth for TISD Transportation Facility and increase conveyance.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	60" RCP	1100	LF	\$ 400	\$ 440,000
2	STM MH (LG)	3	EA	\$ 9,000	\$ 27,000
3	DITCH INTERCEPTOR	8	EA	\$ 9,100	\$ 72,800
4	OUTFALL TIE-IN	1	EA	\$ 10,000	\$ 10,000
5	PAVEMENT REPAIR - ASP	1210	LF	\$ 140	\$ 169,400
		SUBTOTAL			\$ 719,200
		CONTINGENCY		30%	\$ 215,760
		CONSULTANT		25%	\$ 179,800
ESTIMATED PROJECT TOTAL COST:					\$ 1,114,760

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. DESIGN STORM EVENT (CHANNEL): 100-YR
3. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
4. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
5. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
6. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



(IN FEET)
1 INCH = 100 FT.



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: J131 (J131-00-00)
SUBBASIN: D

SCALE: 1" = 1" = 100'

March 2025

EXHIBIT NO. 10A


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	14	Phase	
Project Name		FM 2920 (Main Street) Culvert Crossing Reconstruction			
Project Category					
Project Description					
Construct parallel culvert crossing along J131-03-00 under FM 2920.					
Project Justification					
Increase conveyance capacity.					
Potential Funding Opportunities					
TxDOT					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	84" RCP	255	LF	\$ 1,500	\$ 382,500
2	J131-03-00 CHANNEL LINING	2	EA	\$ 32,000	\$ 74,400
				SUBTOTAL	\$ 456,900
				CONTINGENCY	30%
					\$ 137,070
				CONSULTANT	25%
					\$ 114,225
ESTIMATED PROJECT TOTAL COST:					\$ 708,195

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.


Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



- DESIGN CRITERIA**
1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
 2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
		← DRAINAGE AREA ID
		← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 200 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DMP CIP DETAIL LAYOUTS

BASIN: J131-00-00
SUBBASIN: C2_E

SCALE: 1:200_XREF

March 2025

EXHIBIT NO. 15


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J131	CIP Project No.	15	Phase	
Project Name		Stanolind Road Culvert Crossing			
Project Category					
Project Description					
Replace existing culvert crossing.					
Project Justification					
Provide positive drainage and relieve localize ponding.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	REMOVE STRUCTURE (PIPE)	60	LF	\$ 120	\$ 7,200
2	24" RCP	60	LF	\$ 130	\$ 7,800
2	ROADSIDE DITCH	500	LF	\$ 40	\$ 20,000
3	24" SET	2	EA	\$ 5,000	\$ 10,000
4	PAVEMENT REPAIR - ASP	25	LF	\$ 140	\$ 3,500
				SUBTOTAL	\$ 48,500
				CONTINGENCY	30%
					\$ 14,550
				CONSULTANT	25%
					\$ 12,125
ESTIMATED PROJECT TOTAL COST:					\$ 75,175

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. LAND ACQUISITION (ESMT) = 4,202 SF


LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		

ZONE AE/FLOODWAY
 ZONE AE (100-YR)
 ZONE X (500-YR)



DRAINAGE AREA ID
 DRAINAGE AREA IN ACRES



(IN FEET)
 1 INCH = 300 FT.



CSE Civil Systems
 Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J131-00-00
 SUBBASIN: A4S

SCALE: 1" = 1" = 300'

March 2025

EXHIBIT NO. 16


J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	16	Phase		
Project Name		Tomball Terrace Outfall to J131-00-00 Reconstruction (Pecan Street)				
Project Category						
Project Description						
Reconstruct outfall from N. Pecan Street to J131-00-00.						
Project Justification						
Relieve flooding along N. Pecan Street.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
1	REMOVE EX. 29" x 18" Arch	155	LF	\$ 30	\$ 4,650	
2	36" RCP	380	LF	\$ 200	\$ 76,000	
3	42" CMP	135	LF	\$ 140	\$ 18,900	
4	STM MH (SM)	3	LF	\$ 6,000	\$ 18,000	
5	CURB INLET	2	EA	\$ 8,600	\$ 17,200	
6	PAVEMENT REPAIR - CONC	26	LF	\$ 140	\$ 3,640	
		SUBTOTAL			\$ 138,390	
		CONTINGENCY			30%	\$ 41,517
		CONSULTANT			25%	\$ 34,598
7	LAND ACQUISITION	0.10	AC	\$ 130,680	\$ 12,606	
		SUBTOTAL			\$ 12,606	
		CONTINGENCY			10%	\$ 1,261
ESTIMATED PROJECT TOTAL COST:					\$ 228,371	

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.




DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS
3. STORM SEWER 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT CHANNEL OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS

LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



(IN FEET)
1 INCH = 300 FT.



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**

BASIN: J131-00-00
SUBBASIN: A4S

SCALE: 1" = 1" = 300'

March 2025

EXHIBIT NO. 17

J131 BASIN

Drainage CIP - Opinion of Probable Construction Cost						
Basin	J131	CIP Project No.	17	Phase		
Project Name		Hicks Street and Inwood Drive Storm Sewer				
Project Category						
Project Description						
Construct storm sewer						
Project Justification						
Redirect runoff from south of Tomball Terrace Subdivision to J131-00-00 along Hicks Street and Inwood Drive.						
Potential Funding Opportunities						
Opinion of Probable Construction Cost						
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	
2	24" RCP	78	LF	\$ 130	\$ 10,140	
2	30" RCP	195	LF	\$ 185	\$ 36,075	
2	36" RCP	255	LF	\$ 200	\$ 51,000	
2	42" RCP	980	LF	\$ 300	\$ 294,000	
2	48" RCP	350	LF	\$ 380	\$ 133,000	
3	60" RCP	265	LF	\$ 400	\$ 106,000	
3	60" CMP	100	LF	\$ 200	\$ 20,000	
4	STM MH (SM)	1	LF	\$ 6,000	\$ 6,000	
4	STM MH (MED)	3	LF	\$ 7,500	\$ 22,500	
4	STM MH (LG)	4	LF	\$ 9,000	\$ 36,000	
5	CURB INLET	4	EA	\$ 8,600	\$ 34,400	
5	DITCH INTERCEPTOR	2	EA	\$ 9,100	\$ 18,200	
3	PROPOSED DITCH	650	LF	\$ 50	\$ 32,500	
6	PAVEMENT REPAIR - CONC	78	LF	\$ 140	\$ 10,920	
		SUBTOTAL			\$ 800,595	
		CONTINGENCY			30%	\$ 240,179
		CONSULTANT			25%	\$ 200,149
ESTIMATED PROJECT TOTAL COST:					\$ 1,240,922	


CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.

APPENDIX C – J133

CIP PACKETS



- DESIGN CRITERIA**
1. DESIGN STORM EVENT (CHANNEL): 100-YEAR
 2. HYDROLOGY - RATIONAL METHOD BASED ON EXISTING LAND USE MAPS

LEGEND		
DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		
ZONE AE/FLOODWAY		
ZONE AE (100-YR)		
ZONE X (500-YR)		
	DRAINAGE AREA ID	
	DRAINAGE AREA IN ACRES	



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J133 (J133-00-00)
SUBBASIN:

SCALE: 1" = 1" = 500'

March 2025

EXHIBIT NO. 1

J133 BASIN

(IN FEET)
1 INCH = 500 FT.

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J133	CIP Project No.	1	Phase	
Project Name		J133-00-00 Channel Rehabilitation			
Project Category					
Project Description					
Channel rehabilitation from Zion Road to Spring Creek.					
Project Justification					
Existing dispervie soils cause frequent erosion and bank failure near North Star Estates Subdivision.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	SOFT REVETMENT	1100	LF	\$ 300	\$ 330,000
2	HARD REVETMENT	2400	LF	\$ 500	\$ 1,200,000
SUBTOTAL					\$ 1,530,000
CONTINGENCY				30%	\$ 459,000
CONSULTANT				25%	\$ 382,500
ESTIMATED PROJECT TOTAL COST:					\$ 2,371,500


CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.

APPENDIX C – J100

CIP PACKETS



DESIGN CRITERIA

1. DESIGN STORM EVENT (STORM SEWER): 25-YEAR
2. HYDROLOGY - RATIONAL METHOD BASED ON FUTURE LAND USE MAPS
3. 25-YEAR HGL 1 FOOT BELOW GUTTER
4. STARTING HYDRAULIC GRADE LINE - TOP OF PIPE AT OUTFALL
5. ACTUAL PIPE VELOCITIES LESS THAN 7 FPS
6. TOTAL LAND ACQUISITION = 17,920 SF


LEGEND

DESCRIPTION	EXISTING	PROPOSED
STORM SEWER		
STORM INLET		
STORM MANHOLE		
DITCH		
CHANNEL		
DETENTION POND		
BASIN BNDY		
SUBBASIN BNDY		
STM SWR SERVICE AREA		
DRAINAGE AREA BNDY		
LAND ACQUISITION		

- ZONE AE/FLOODWAY
- ZONE AE (100-YR)
- ZONE X (500-YR)



- ← DRAINAGE AREA ID
- ← DRAINAGE AREA IN ACRES



(IN FEET)
1 INCH = 400 FT.



CSE Civil Systems
Engineering, Inc.

CITY OF TOMBALL DRAINAGE MASTER PLAN

BASIN: J100-00-00
SUBBASIN: TOMBALL HILLS

SCALE: 1" = 400'

March 2025

EXHIBIT NO. 1

J100 BASIN

Drainage CIP - Opinion of Probable Construction Cost					
Basin	J100	CIP Project No.	1	Phase	
Project Name		Tomball Hills Subdivision			
Project Category					
Project Description					
Construct new sag inlets and flanking inlets at Camille Drive and Alice Lane kunckle. Construct parallel storm sewer along Camille Drive and Stella Lane with new outfall to J100-00-00.					
Project Justification					
Prevent structural flooding and relieve street ponding at Camille Drive and Alice Lane knuckle.					
Potential Funding Opportunities					
Opinion of Probable Construction Cost					
ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	24" RCP	100	LF	\$ 130	\$ 13,000
2	30" RCP	1260	LF	\$ 185	\$ 233,100
3	48" RCP	300	LF	\$ 380	\$ 114,000
4	STM MH (SM)	5	EA	\$ 6,000	\$ 30,000
4	STM MH (MED)	1	EA	\$ 7,500	\$ 7,500
6	CURB INLET	8	EA	\$ 8,600	\$ 68,800
7	OUTFALL STRUCTURE	1	EA	\$ 10,000	\$ 10,000
8	PAVEMENT REPAIR - CONC	230	LF	\$ 140	\$ 32,200
		SUBTOTAL			\$ 508,600
		CONTINGENCY		30%	\$ 152,580
		CONSULTANT		25%	\$ 127,150
9	LAND ACQUISITION	0.40	AC	\$ 130,680	\$ 51,868
		SUBTOTAL			\$ 51,868
		CONTINGENCY		10%	\$ 5,187
ESTIMATED PROJECT TOTAL COST:					\$ 845,385

CSE's opinion of probable construction cost provided is based on the best available information at the time of preparation and standard cost estimating practices. It is understood that this is a conceptual cost estimate and the Engineers shall not be liable to the Owner or a third party for the accuracy of the project or any part thereof. Final engineering and design shall be performed to accurately reflect ground and project conditions.

Land acquisition is based on parcel data received from the City and is a preliminary estimation. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

All values are in 2024 dollars. An inflation rate of 4% should be allocated to each year until formal project funding.

APPENDIX D

CIP COST SUMMARY

ALTERNATIVE SCENARIO OPTION IN GRAY ARE NOT INCLUDED IN TOTAL COST

LAND ACQUISITION SUMMARY TABLE								
BASIN	CIP PROJECT	ACQUISITION TYPE	HCAD NO	OWNER	TRACT AREA	PROPOSED ACQUISITION AREA (SF)	COST (\$/SF)	TOTAL CIP LAND COST
J100	1	ESMT	1129570000029	EWING GREGORY A & KATHRYN A	454,766	17,289	\$ 3	\$ 51,868
J131	1	FEE	0352970030026	ALI SYED	1,200	1,200	\$ 10	\$ 234,000
		FEE	0352970010077	ALI SYED	600	600	\$ 10	
		FEE	0352970050159	GORDON CLYDE ESTATE	600	600	\$ 10	
		FEE	0352970050160	ALI SYED	600	600	\$ 10	
		FEE	0352970050006	ALI SYED	2,400	2,400	\$ 10	
		FEE	0352970020002	ALI SYED	1,200	1,200	\$ 10	
		FEE	0352970030151	TANDEM ENERGY CORPORATION	6,000	6,000	\$ 10	
		FEE	0352970030105	ALI SYED	3,000	3,000	\$ 10	
		FEE	0352970030109	BOYKIN MADELYN JOHNSON ET AL	1,200	1,200	\$ 10	
J131	5A	ESMT	0430490000004	DISTRICT & URBAN TX INC	569,267	18,954	\$ 3	\$ 62,157
		ESMT	0430490000003	LOPEZ LUCRETIA	8,877	1,765	\$ 3	
J131	5B	ESMT	0430490000004	DISTRICT & URBAN TX INC	569,267	18,954	\$ 3	\$ 62,157
		ESMT	0430490000003	LOPEZ LUCRETIA	8,877	1,765	\$ 3	
J131	6A	FEE	0450340010214	RMDMG LTD	480,092	480,092	\$ 5	\$ 2,415,162
		ESMT	0450340010060	STOKLEY MELVIN LEE	4,901	4,901	\$ 3	
J131	6B	FEE	0450340010214	RMDMG LTD	480,092	480,092	\$ 5	\$ 3,367,140
		ESMT	0450340010060	STOKLEY MELVIN LEE	4,901	4,901	\$ 3	
		FEE	1450450010002	GALZA INDUSTRIAL	40,256	40,256	\$ 5	
		FEE	1452520010002	LEAL SERGIO	29,553	29,553	\$ 5	
		FEE	0450340010165	CENTERPOINT ENERGY HOU ELE	8,481	8,481	\$ 5	
		FEE	0450340010050	LANGDON TROY W & BARBARA	13,619	13,619	\$ 5	
		FEE	0450340010185	BURCHFIELD MICHAEL D & LYETTE J	49,328	49,328	\$ 5	
		FEE	0450340010096	BURCHFIELD MICHAEL D & LYNETTE J	3,827	3,827	\$ 5	
		FEE	0450340010040	BREAUX RICHARD A & CHRISTINA A	12,901	12,901	\$ 5	
J131	6C	FEE	0450340010214	RMDMG LTD	480,092	480,092	\$ 5	\$ 3,236,259
		ESMT	0450340010060	STOKLEY MELVIN LEE	4,901	4,901	\$ 3	
		FEE	0450340010223	OLE SPEC LTD	155,528	155,528	\$ 5	
		ESMT	0450340010185	BURCHFIELD MICHAEL D & LYETTE J	7,555	7,555	\$ 3	
		ESMT	0352820000178	RODANO DANIEL G	4,229	4,229	\$ 3	
J131	8	FEE	0450340010040	BREAUX RICHARD A & CHRISTINA A	2,702	2,702	\$ 3	\$ 299,702
		FEE	1409120010003	HARVEY DARRIN & ROXANE	59,940	59,940	\$ 5	
J131	9	FEE	0450340010070	OLE SPEC LTD	116,330	116,330	\$ 5	\$ 1,155,140
		FEE	0450340010065	OLE SPEC LTD	114,698	114,698	\$ 5	
J131	10A	ESMT	0352830000102	IGLESIA BAUTISTA FUENTE DE VIDA ETERNA	8,121	8,121	\$ 3	\$ 45,948
		ESMT	1270990000001	PROTESTANT EPISCOPAL CHURCH COUNCIL OF TOMBALL	7,196	7,196	\$ 3	
J131	10B	ESMT	0352830000102	IGLESIA BAUTISTA FUENTE DE VIDA ETERNA	8,121	8,121	\$ 3	\$ 165,306
		ESMT	1270990000001	PROTESTANT EPISCOPAL CHURCH COUNCIL OF TOMBALL	7,196	7,196	\$ 3	
		FEE	0352830000271	TOMBALL TIMBER TRAILS LLC	1,893	1,893	\$ 5	
J131	10C	FEE	0352830000092	VALADEZ AMADEO JR & MARINELA	21,978	21,978	\$ 5	\$ 45,948
		ESMT	0352830000102	IGLESIA BAUTISTA FUENTE DE VIDA ETERNA	8,121	8,121	\$ 3	
J131	12	ESMT	1270990000001	PROTESTANT EPISCOPAL CHURCH COUNCIL OF T	7,196	7,196	\$ 3	
J131	16	ESMT	0352830000106	CITY OF TOMBALL	13,280	967	\$ -	\$ -
J131	16	ESMT	0402700010061	SPECIALIZED PAINT & BODY LLC	77,319	4,202	\$ 3	\$ 12,606
M116	1A	FEE	0440550010074, 0440550010209	OBANNION KAREN & RAYMOND	1,252,461	216,729	\$ 5	\$ 1,083,643
		FEE	0440550010208	MCCOWN JOSEPH B OBANNION MOLLY S	86,711	40,927	\$ 5	\$ 204,637
		FEE	0440550010088	ESTATES OF WILLOW CREEK HOA	7,101	7,101	\$ 5	\$ 35,503
M118	2	FEE	03529200000521	WILKERSON MELODY	49,521	49,521	\$ 5	\$ 1,908,425
		FEE	03529200000529	GRAPPE JAMES R & CAROLYN	2,704	2,704	\$ 5	
		FEE	03529200000530	RANDALL JOHN W JR & TRACY A	173,398	173,398	\$ 5	
		FEE	03529200000528	DIXON WENDY L & RONALD O JR	26,335	26,335	\$ 5	
		FEE	03529200000538	MLADENKA PAUL	38,723	38,723	\$ 5	
		FEE	03529200000390	PASSAFUMA PHILLIP	48,854	48,854	\$ 5	
M118	7	FEE	03529200000389	PASSAFUMA ROBERTA	42,150	42,150	\$ 5	\$ 228,108
		ESMT	03529200000530	RANDALL JOHN W JR & TRACY A	68,965	68,965	\$ 3	
M118	8A	ESMT	1342060000003	RALCO HOUSTON LTD	7,071	7,071	\$ 3	
M118	8A	FEE	03528800000413	JOHNSON ROY E	96,688	96,688	\$ 5	\$ 483,442
M118	8B	FEE	03528800000252	CENTERPOINT ENERGY HOU ELE	75,197	75,197	\$ 5	
		FEE	04303700000001	TANDEM ENERGY CORPORATION	17,233	17,233	\$ 5	
M118	8B	FEE	1277310020004	MARTIN MARIETTA MATERIALS SOUTHWEST INC	25,169	25,169	\$ 5	\$ 2,279,417
		FEE	1277310020005	MARTIN MARIETTA MATERIALS SOUTHWEST INC	338,284	338,284	\$ 5	



LAND ACQUISITION SUMMARY TABLE								
BASIN	CIP PROJECT	ACQUISITION TYPE	HCAD NO	OWNER	TRACT AREA	PROPOSED ACQUISITION AREA (SF)	COST (\$/SF)	TOTAL CIP LAND COST
M121	5	ESMT	1156610010014	KEYSTONE TOWNHOMES LLC	13,211	6,418	\$ 3	\$ 30,123
		ESMT	1156610010013	TAMIROWOOD TOMBALL LLC	13,227	523	\$ 3	
		ESMT	1400140010001	TAMIROWOOD TOMBALL LLC	68,489	3,100	\$ 3	
M121	7	ESMT	0352840000123	CITY OF TOMBALL	187,657	17,661	\$ -	\$ -
M121	10	FEE	0440580000080	MUELLER ALLEN H	2,213,742	2,213,742	\$ 2	\$ 9,427,934
		FEE	0440580000085	MY FAMILY LLC	3,112,274	2,500,225	\$ 2	
M121	11	FEE	1287800010004	HOLDERRIETH ROAD LAND HOLDINGS LP	46,653	13,053	\$ 5	\$ 3,328,025
		FEE	0440580000190	TURRUBIARTES JOSE	1,643,996	86,119	\$ 5	
		FEE	0440580000108	WALL JANICE F	1,171,657	102,558	\$ 5	
		FEE	0352860000418	NGUYEN LONG	490,651	77,565	\$ 5	
		FEE	0352860000233	WALL JANICE F	703,789	59,152	\$ 5	
		FEE	0352860000277	NGUYEN JAMES HOAI & TIFFANY	485,807	76,987	\$ 5	
		FEE	0352860000228	NWAIWU JUDE	812,653	30,824	\$ 5	
		FEE	0352860000226	SPOTTSWOOD SONJA	43,560	12,620	\$ 5	
		FEE	0352860000227	KISHLA KISHELLE MYERS	139,514	21,787	\$ 5	
		FEE	0352860000223	NWAIWU JUDE	435,265	67,816	\$ 5	
		FEE	0352860000224	MCNEILL JAMES T JR	218,991	13,904	\$ 5	
		FEE	0352860000221	AGG ROAD ASSOCIATES LP	217,771	33,789	\$ 5	
		FEE	0352860000220	AGG ROAD ASSOCIATES LP	434,245	35,778	\$ 5	
M121	14	FEE	0352860000219	AGG ROAD ASSOCIATES LP	217,717	33,653	\$ 5	
M121	14	ESMT	0440580000108	WALL JANICE F	1,129,075	25,713	\$ 3	\$ 77,140
		FEE	0440580000195	LANG CAROLYN	1,313,703	1,313,703	\$ 5	
		FEE	0440580000040	MIDKIFF JAMES J	1,641,123	1,064,984	\$ 5	\$ 19,001,478
M121	17	FEE	0440580000185	MICHEL FAMILY IRREVOCABLE TRUST	3,902,762	1,421,609	\$ 5	
		FEE	1308830010001	HAFFNER RONALD & AMY N	337,813	81,821	\$ 5	
		FEE	0402700030008	TOMBALL UNITED METHODIST CHURCH	29,728	9,847	\$ 5	
		FEE	0402700030007	TOMBALL UNITED METHODIST CHURCH	61,127	61,127	\$ 5	\$ 1,383,644
M124	3	FEE	0402700030006	TOMBALL UNITED METHODIST CHURCH	58,282	27,653	\$ 5	
		FEE	0402700010039	TOMBALL UNITED METHODIST CHURCH	431,640	96,281	\$ 5	
M125	1	ESMT	1048040000001	MANDVIWALA MUSTAFA	55,757	2,260	\$ 3	\$ 6,780
TOTAL								\$ 50,631,693

*Land acquisition costs is based on parcel data received from the City and is a preliminary estimate. CSE has not evaluated, researched, or appraised property for rights-of-way and easements necessary for the construction and maintenance of the proposed improvements.

APPENDIX E

IMPACT FEE EXHIBITS

DWG INFO: P:\532301_TOMBALL_MDP\CAD\532301_SUBBASIN AND PONDS.DWG



CHANNEL DESIGN CRITERIA
1. DESIGN STORM EVENT: 100-YEAR
2. MITIGATION WITHIN M518-01 ULTIMATE BASIN

IMPACT FEE NOTES ①
1. PARTIAL IMPACT FEE PAID

IMPACT LEGEND

COLLECTED FEES

IMPACT FEE (SEE NOTES)

LEGEND

EXISTING STORM SEWER

EXISTING CHANNEL

EXISTING DETENTION

BASIN BOUNDARY

SUBBASIN BOUNDARY

TRIBUTARY DIVIDES

PROPOSED STORM SEWER

PROPOSED CHANNEL

PROPOSED DETENTION

CITY LIMITS

BASIN ID

SUBBASIN ID

DRAINAGE AREA IN ACRES

M121
34
50.0



CSE Civil Systems
Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN**
M118 DRAINAGE IMPACT FEE AND CHANNEL
DELINEATION


SCALE: 1" = 0.25 mi

March 2025

EXHIBIT NO. 14

M118 BASIN

DWG INFO: P:\532301_TOMBALL_MDP\CAD\532301_SUBBASIN AND PONDS.DWG



CHANNEL DESIGN CRITERIA
1. DESIGN STORM EVENT: 100-YEAR
2. MITIGATION WITHIN M500 BASINS

IMPACT FEE NOTES
1. PARTIAL IMPACT FEE PAID
2. IMPACT FEE SWAP BETWEEN M121-01-00 AND M121-02-00

IMPACT LEGEND

COLLECTED FEES
IMPACT FEE (SEE NOTES)

LEGEND

EXISTING STORM SEWER
EXISTING CHANNEL
EXISTING DETENTION
BASIN BOUNDARY
SUBBASIN BOUNDARY
TRIBUTARY DIVIDES
PROPOSED STORM SEWER
PROPOSED CHANNEL
PROPOSED DETENTION
CITY LIMITS
BASIN ID
SUBBASIN ID
DRAINAGE AREA IN ACRES



CSE Civil Systems Engineering, Inc.

CITY OF TOMBALL
DRAINAGE MASTER PLAN
M121 IMPACT FEE AND CHANNEL
DELINEATION



SCALE: 1" = 0.25 mi

March 2025

EXHIBIT NO. 15

M121 BASIN

DWG INFO: P:\532301_TOMBALL_MDP\CAD\532301_SUBBASIN AND PONDS.DWG



CHANNEL DESIGN CRITERIA
1. DESIGN STORM EVENT: 100-YEAR
2. MITIGATION WITHIN M525-01 BASIN

IMPACT LEGEND
COLLECTED FEES
IMPACT FEE (SEE NOTES)

LEGEND
EXISTING STORM SEWER
EXISTING CHANNEL
EXISTING DETENTION
BASIN BOUNDARY
SUBBASIN BOUNDARY
TRIBUTARY DIVIDES
PROPOSED STORM SEWER
PROPOSED CHANNEL
PROPOSED DETENTION
CITY LIMITS
BASIN ID
SUBBASIN ID
DRAINAGE AREA IN ACRES



CSE Civil Systems Engineering, Inc.

**CITY OF TOMBALL
DRAINAGE MASTER PLAN
M125 IMPACT FEE AND CHANNEL
DELINEATION**

SCALE: 1" = 0.25 mi

March 2025

EXHIBIT NO. 16

M125 BASIN