

PRIMARY PROJECT LIST
Tupelo Capital Improvements Mill & Overlay Program
2021 Annual Bid

No.	STREET NAME	B.O.P.	E.O.P.	Approx. Length (ft)	Approx. Width (ft)	Approx. Mill Area (SY)	Approx. Asphalt Pavement (Tons)	NOTES
PRIMARY STREET LIST								
1	Brea burn Ln	Beginning	End	310	20	30	3	Mill @ Tie Ins Only
2	St Andrews Cir (Jet out)	Beginning	End	142	15	10	1	Mill @ Tie Ins Only
3	Broadmoor Ln	Beginning	End	305	24	813	89	Mill @ Tie Ins Only; Pre-Leveling may be req'd.
4	Fairway Ln	Beginning	End	264	24	704	77	Mill @ Tie Ins Only
5	Ridgewood Ln	Beginning	End	468	24	1248	137	Mill @ Tie Ins Only; Pave apron at end
6	Walnut Ln	Beginning	End	145	20	322	35	Mill @ Tie Ins Only
7	Lakewood Ln	Beginning	End	645	24	1720	189	Mill @ Tie Ins Only; Pre-Leveling may be req'd.
8	Cypress Ln	Beginning	End	215	22	526	58	Mill @ Tie Ins Only
9	Winged Foot Rd	Beginning	End	267	22	653	72	Mill @ Tie Ins Only; Pre-Leveling may be req'd.
10	Briarwood Ln	Beginning	End	540	22	1320	145	Mill @ Tie Ins Only
11	Poplar Ln	Beginning	End	168	20	373	41	Mill @ Tie Ins Only
12	Elmwood Ln	Beginning	End	689	22	1684	185	Mill @ Tie Ins Only
13	Mt Vernon Rd	Beginning	End	4350	23	11117	1223	Mill @ Tie Ins Only; Pre-Leveling may be req'd.
14	Rook Rd	W. Main St.	N. Gloster St.	1000	20	2222	244	Mill @ Tie Ins Only
15	N Gun Club Rd	W. Jackson St.	Gun Club Rd.	3000	25	8333	917	Mill @ Tie Ins Only; M/F digout areas (approx. 400 sy)
16	Cressant St	W. Main St.	N. Gloster St.	790	28	2458	270	Full width Mill & Overlay
17	Bartlett Ln	S. Green St.	Hwy 45 ROW	298	32	1060	117	Full width Mill & Overlay
18	Lambard Dr	Beginning	End	2640	27	7920	871	Full width Mill & Overlay: Mill to gutter & overlay 1.5"
19	Vassar Dr	Beginning	End	810	30	2700	297	Full width Mill & Overlay: Mill to gutter & overlay 1.5"
20	James Dr	Beginning	End	810	30	2700	297	Full width Mill & Overlay: Mill to gutter & overlay 1.5"
21	Lar-Eli-Do Dr	Beginning	End	810	30	2700	297	Full width Mill & Overlay; Mill to gutter & overlay 1.5"
22	Trice St	Beginning	End	835	18	1670	184	Full width Mill & Overlay

PRIMARY PROJECT LIST
Tupelo Capital Improvements Mill & Overlay Program
2021 Annual Bid

No.	STREET NAME	B.O.P.	E.O.P.	Approx. Length (ft)	Approx. Width (ft)	Approx. Mill Area (SY)	Approx. Asphalt Pavement (Tons)	NOTES
23	Osborne St	Beginning	End	880	21	2053	226	Full width Mill & Overlay
24	Valley View Dr	Beginning	End	880	30	2933	323	Full width Mill & Overlay
25	Valley View Cir	Beginning	End	260	28	809	89	Full width Mill & Overlay
26	William Dr	Beginning	End	1820	30	6067	667	Full width Mill & Overlay
27	Kathryn Cir	Beginning	End	190	24	507	56	Full width Mill & Overlay
28	Hinton Cir	Beginning	End	150	28	467	51	Full width Mill & Overlay
29	Shady Wood	Beginning	End	582	28	1811	199	Full width Mill & Overlay
30	Bobwhite	Beginning	End	2720	28	8462	931	Full width Mill & Overlay
31	Pinecrest Dr	Beginning	End	2450	30	8167	898	Full width Mill & Overlay
32	Hillcrest Dr	Beginning	End	1000	35	3889	428	Full width Mill & Overlay
33	Overdale Dr	Beginning	End	367	22	897	99	Full width Mill & Overlay
34	Greenview Dr	Beginning	End	850	26	2456	270	Full width Mill & Overlay
35	N Commerce St	Beginning	End	2470	24	6587	725	Full width Mill & Overlay to red corner marker
36	Old Humane Society Rd	Beginning	End	600	24	1600	276	Mill @ Tie Ins Only
37	N Feemster Lake RD (P)	Bridge	Eason Blvd.	1550	24	4133	455	Mill @ Tie Ins Only, including existing bridges
38	Morganwood Rd (P)	City Limits	Seam	540	22	1320	145	Mill @ Tie Ins Only, including existing bridges
39	Priscilla Ln	Beginning	End	1200	22	2933	323	Mill @ Tie In at Eason Blvd.
40	Tyler Willis Ln	Beginning	End	2000	22	4889	538	Mill @ Tie Ins Only
41	Auston St	Beginning	End	2100	22	5133	565	Mill @ Tie Ins Only; M/F digout areas (approx. 200 sy)
42	Ethan Cv	Beginning	End	315	21	735	81	Mill @ Tie Ins Only; M/F digout areas (approx. 250 sy)
43	Seth St	Beginning	End	800	22	1956	215	Overlay only
44	McKenna Cv	Beginning	End	1000	22	2444	269	Overlay only
45	Bentley Ave	Beginning	End	1100	22	2689	296	Overlay only

PRIMARY PROJECT LIST
Tupelo Capital Improvements Mill & Overlay Program
2021 Annual Bid

No.	STREET NAME	B.O.P.	E.O.P.	Approx. Length (ft)	Approx. Width (ft)	Approx. Mill Area (SY)	Approx. Asphalt Pavement (Tons)	NOTES
46	Wayside St	Beginning	End	1215	21	2835	312	Full width Mill & Overlay
47	Charleston Garden Dr	Beginning	End	2100	28	6533	719	Full width Mill & Overlay
48	Charleston Blvd (P)	C.G. Dr.	Market St.	1580	28	4916	541	Full width Mill & Overlay
49	Market St (P)	Charleston Blvd.	C.G. Dr.	752	28	2340	257	Full width Mill & Overlay
50	Whitmoore Ln	Beginning	End	500	28	1556	171	Full width Mill & Overlay
51	Traceland Dr (P)	Big Lots P.L.	Dead End	721	24	1923	211	Mill @ Tie Ins Only; M/F digout areas (approx. 450 sy)
52	Pete St	Beginning	End	300	29	967	106	Mill @ Tie Ins Only; M/F digout areas (approx. 50 sy)
53	Saddle Creek Dr	Beginning	End	320	32	1138	125	Full width Mill & Overlay; stop shy of Main St.
54	Dogwood Dr (P)	Springlake Dr.	Honeysuckle Dr.	1000	30	3333	367	Full width Mill & Overlay; intersection to seam
55	Teakwood	Beginning	End	884	32	3143	346	Mill @ Tie Ins Only; M/F digout areas (approx. 200 sy)
56	Mahogany Dr	Jackson St.	Teakwood	1187	32	4220	464	Full width Mill & Overlay
57	Sourwood	Beginning	End	550	32	1956	215	Mill @ Tie Ins Only; M/F digout areas (approx. 350 sy)
57	Evelyn St	Beginning	End	1875	28	5833	642	Full width Mill & Overlay
58	Wilemon St	Beginning	End	330	28	1027	113	Full width Mill & Overlay
59	Parkwood Dr	Beginning	End	910	24	2427	267	Full width Mill & Overlay
60	Woodmere Cir	Beginning	End	300	24	800	88	Full width Mill & Overlay
61	Wood Dale Dr	Beginning	End	300	24	800	88	Full width Mill & Overlay
62	Woodglen Dr	Beginning	End	300	24	800	88	Full width Mill & Overlay; M/F digout areas (app. 50 sy)
63	S Green St (P)	Gloster St.	Mitchell Rd.	2500	32	8889	978	Full width Mill & Overlay
64	S Green St (P)	Shell St.	Dead End	2500	24	6667	733	Full width Mill & Overlay: Shell to seam at cul de sac

NOTES: Based on funding, schedule, Owner preference, etc., streets may be added to or removed from the Project List as directed by the Owner. All streets included on the project list, including revisions, shall be completed by the Contractor as part of the Contract.; All milling & overlay areas shall be coordinated with Engineer prior to execution by the Contractor. Areas for milling & overlay may be adjusted in the field as required or preferred by the Owner and/or Engineer.

END OF SECTION