


<u>PLANT MATERIAL LIST</u>


ID	BOTANICAL NAME	COMMON NAME	SIZE	QTY	R00
EXISTI	NG PLANTS				
	PERENNIALS				
	GRASSES				
	SHRUBS				
PROPC	OSED PLANTS				
AS	ACER SACCHARUM 'GREEN MOUNTAIN'	GREEN MOUNTAIN SUGAR MAPLE	2 1/2" CAL		В&
АМ	AMELANCHIER CANADENSIS 'AUTUMN BRILLIANCE'	AUTUMN BRILLIANCE SERVICEBERRY	2 1/2" CAL		В&
СА	CORNUS ALBA 'BAILHALO'	IVORY HALO DOGWOOD	NO. 5, 36" SPREAD MIN.		CON
СН	COTONEASTER HORIZONTALIS	ROCKSPRAY COTONEASTER	NO. 5 36" SPREAD MIN.		CON
JC	JUNIPERUS CHINENSIS 'PFITZER'	CHINESE JUNIPER	NO. 5 36" SPREAD MIN.		CON
HP	HEMEROCALLIS 'PURPLE DE ORO'	PURPLE DE ORO DAYLILY	NO. 1 CONT.		CON
			·	TOTAL	POINT

------ LANDSCAPE EDGING



GENERAL LAND 1. CONTRACTOR SHALL E CONTRACTOR SHALL ALS

<u>PLANT MATERI</u> 1. ALL PLANT MATERIAL



N

1 INCH = 20 FT

GENERAL LANDSCAPE NOTES 1. CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY LOCATION OF ALL PRIVATE AND PUBLIC UTILITY LINES WHICH AFFECT THIS SITE. CONTRACTOR SHALL ALSO NOTIFY ALL UTILITY COMPANIES PRIOR TO THE COMMENCEMENT OF ANY SITE WORK.	DATE	
2. CONTRACTOR SHALL REVIEW PLANTING SPECIFICATIONS AND PLANTING DETAILS BEFORE BEGINNING WORK. 3. CONTRACTOR SHALL VISIT THE PROJECT SITE AND BECOME FAMILIAR WITH CONDITIONS UNDER WHICH WORK SHALL BE IMPLEMENTED PRIOR TO	BY e the sole e d or	
BIDDING. 4. CONTRACTOR SHALL NOTIFY CONTRACT OFFICER OF ANY DISCREPANCIES IN THE EXISTING CONDITIONS OR WITHIN THE PLANS PRIOR TO	ument are all be used	
BEGINNING WORK. 5. PLANTING BEDS SHALL HAVE FINISHED GRADES SMOOTHED TO ELIMINATE PONDING OR STANDING WATER. CONTRACTOR SHALL MAINTAIN A MINIMUM 2% DRAINAGE AWAY FROM BUILDINGS AND PAVING INTO DRAINAGE STRUCTURE OR TO STREET. CONTRACTOR SHALL NOTIFY OWNER IMMEDIATELY OF ANY CONFLICTS IN MAINTAINING DRAINAGE. IRRIGATION SYSTEM SHALL BE DESIGNED TO ELIMINATE OVERSPRAY ONTO BUILDINGS, STRUCTURES AND MONUMENT SIGNS.	own on this doct for use on this doct action hereon sh	
6. CONTRACT OFFICER SHALL APPROVE ALL FINISH GRADING PRIOR TO PLACEMENT OF ANY PLANT MATERIAL.	tion as sh breated sh her inform	
7. CONTRACTOR SHALL IMMEDIATELY, UPON THE AWARD OF THE CONTRACT, LOCATE, ORDER AND PURCHASE (OR HAVE HELD) ALL PLANT MATERIAL REQUIRED BY THESE PLANS AND SPECIFICATIONS.	TION Her information details or of	
 8. CONTRACTOR SHALL NOTIFY CONTRACT OFFICER FOR OBSERVATION AT THE FOLLOWING TIMES: IRRIGATION MAINLINE AND LATERALS PRIOR TO BACKFILL AND PRESSURE TEST TREE LOCATIONS PRIOR TO PLANTING IRRIGATION COVERAGE PRIOR TO PLANT PLACEMENT PLANT APPROVAL AND SPOTTING PRIOR TO PLANT TO PLANTING PRE-MAINTENANCE APPROVAL 	DESCRIPTION s, details and other inf re created, developed, designs, plans, details	
-POST-MAINTENANCE / FINAL APPROVAL 9. CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY REPAIRS MADE NECESSARY THROUGH THE ACTIONS/NEGLIGENCE OF THEIR CREW.	signs, plar R and we concepts	
10. SHRUB AND GROUNDCOVER MASS QUANTITIES ARE SHOWN ON PLANS. UNDERPLANT ALL TREES WITH THE ADJACENT SHRUB AND/OR GROUNDCOVER AS INDICATED BY THE PLANS. PLANTS SHALL BE INSTALLED WITH TRIANGULAR SPACING. PLANT GROUNDCOVERS TO WITHIN 36" OF TREE TRUNK OR 12" OF SHRUB STEMS.	ne concepts, de property of JF None of the	
11. PLANT SYMBOLS TAKE PRECEDENCE OVER PLANT QUANTITIES SPECIFIED. WHERE SHRUB SYMBOLS ARE MASSED, CONTRACTOR SHALL MAINTAIN A CONSISTENT ON CENTER, TRIANGULAR SPACING AS SPECIFIED IN LEGEND. CONTRACTOR SHALL VERIFY PLANT TOTALS FOR BID PURPOSES.		
12. ALL ROCKS AND DEBRIS ONE INCH (1") AND LARGER SHALL BE REMOVED FROM PLANTING AREAS TO A DEPTH OF 1'-0" AND THEN FROM THE SITE TO A LEGAL SITE OF DISPOSAL. WHERE GRASS IS TO BE PLANTED, ALL ROCKS AND DEBRIS ONE HALF INCH (1/2") AND LARGER SHALL BE REMOVED.	. CI01	
 13. PLANTING SOIL SHALL BE A THOROUGHLY GROUND AND BLENDED MIXTURE OF EQUAL PARTS OF THE FOLLOWING MATERIALS: ONE THIRD (1/3) TOPSOIL, ONE THIRD (1/3) PEAT MOSS AND ONE THIRD (1/3) SAND. ALL PLANTED AREAS SHALL RECEIVE A MINIMUM OF 6" OF TOPSOIL. 14. PRIOR TO PLANT INSTALLATION, CONTRACTOR SHALL IRRIGATE ALL PLANTING AREAS NORMALLY FOR TWO WEEKS TO GERMINATE WEEDS. CONTRACTOR SHALL THEN APPLY CONTACT HERBICIDE TO WEEDS ONLY PER MANUFACTURER, MONSANTO 'ROUND-UP' OR APPROVED EQUAL. 	E S SKI Fort Wayne, I p: 260.422.253	
15. PLANT MATERIAL MAY BE REJECTED AT ANY TIME BY CONTRACT OFFICER DUE TO CONDITION, FORM OR DAMAGE BEFORE OR AFTER PLANTING.		
 16. ALL PLANT MATERIAL TO BE PLANTED WITH PLANTING TABLETS ACCORDING TO THE MANUFACTURER'S INSTRUCTION AND AS FOLLOWS: BALLED & BURLAPPED PLANT MATERIAL USE TWO (2) 21 GRAM TABLETS PER EACH 1/2" CALIPER 7 GALLON CONTAINER PLANT MATERIAL, USE THREE (3) 21 GRAM TABLETS PER PLANT 5 GALLON CONTAINER PLANT MATERIAL, USE TWO (2) 21 GRAM TABLETS PER PLANT 3,2, AND 1 GALLON CONTAINER PLANT MATERIAL, USE ONE (1) 21 GRAM TABLETS PER PLANT PLANTING TABLETS SHALL BE AGRIFORM 20-10-5, PLANTING TABLETS PLUS MINORS STOCK NO. 90026 	J O R A F R A F R A F P E P: 574.232.4388	
(21 GRAMS) OR APPROVED EQUAL. 17. ALL PLANT MATERIAL SHALL RECEIVE GRANULAR PLANT FOOD TO THE SURFACE OF THE PLANT BEDS INCLUDING GROUND COVER BEDS WHICH DO NOT CONTAIN MANURE OR PLANTING TABLETS. THE PLANT FOOD SHALL BE SPREAD OVER THE ROOT AREA STARTING 6" FROM THE TRUNK AND EXTENDING TO THE DRIP LINE OF EACH PLANT OR TO THE OUTER EDGE OF THE PLANT BED, WHICHEVER LARGER, AT THE RATE OF 2 POUNDS PER 100 SQ FT.		
18. CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION OF ALL LANDSCAPE PLANT MATERIAL TO THE LATEST HORTICULTURAL PRACTICE STANDARDS.	Elkhart, IN	
 19. ALL PLANTING BEDS SHALL HAVE A 3 INCH (3") DEPTH OF SHREDDED HARDWOOD MULCH APPLIED AFTER INSTALLATION OF PLANT MATERIAL. MULCH SHALL BE PEST & DISEASE FREE PLANT MATERIAL AND BE FREE OF TWIGS, LEAVES, STONES, CLAY OR OTHER FOREIGN MATERIAL. CONTRACTOR SHALL SUBMIT SAMPLE OF MULCH TO CONTRACT OFFICER FOR APPROVAL PRIOR TO INSTALLATION. 20. ALL DESIGNATED PERIMETER PLANTING AREAS SHALL HAVE 4 INCHES (4") PROFESSIONAL GRADE BLACK ANODIZED ALUMINUM EDGING 		
INSTALLED PER MANUFACTURE'S SPECIFICATIONS. 21. CONTRACTOR SHALL BE RESPONSIBLE FOR A MINIMUM ONE (1) YEAR GUARANTEE TIME FOR THE REPLACEMENT OF ANY PLANT MATERIAL	PRELIMINARY FOR REVIEW PURPOSES ONLY	
WHICH DIES AFTER THE DATE OF INSTALLATION ON SITE. THE REPLACEMENT PLANT MATERIAL SHALL BE EQUAL IN SIZE AND QUALITY TO THE PLANT MATERIAL SHOWN ON THE LANDSCAPE PLANS. ALL COSTS FOR THE REMOVAL OF DEAD PLANTS AND THEIR REPLACEMENTS SHALL BE BORNE BY THE CONTRACTOR.		
22. SUBSTITUTIONS OF PLANT MATERIAL SHALL BE PERMITTED UPON WRITTEN SUBMISSION THAT SPECIFIED PLANT(S) ARE UNAVAILABLE OR UNACCEPTABLE DUE TO HARDINESS. SUBSTITUTE PLANT MATERIAL SHALL BE EQUAL IN SIZE, CHARACTERISTICS AND CONDITION OF MATERIAL BEING REPLACED. OWNER SHALL BE NOTIFIED AND APPROVE ALL SUBSTITUTIONS PRIOR TO THEIR INSTALLATION.		
23. PRIOR TO PLANTING, CONTRACTOR SHALL SUBMIT IRRIGATION DESIGN DRAWINGS FOR REVIEW. IRRIGATION SYSTEM SHALL BE FULLY OPERATIONAL, AND ALL LANDSCAPE AREAS SHALL BE IRRIGATED, UNLESS DIRECTED OTHERWISE. IRRIGATION CONTRACTOR SHALL INSTALL ALL REQUIRED IRRIGATION STRUCTURES, PIPES, VALVES, ETC. WHICH ARE TO BE PLACED UNDER ANY PAVED AREAS PRIOR TO PAVEMENT INSTALLATION. IRRIGATION CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS INCURRED IF IRRIGATION EQUIPMENT IS REQUIRED TO BE INSTALLED AFTER PAVEMENT IS PLACED ON SITE. IRRIGATION CONTRACTOR SHALL HAVE ALL IRRIGATION PLANS APPROVED BY OWNER PRIOR TO ANY INSTALLATION. IRRIGATION CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH THE UTILITY CONTRACTOR FOR LOCATION OF IRRIGATION CONNECTION TO WATER SYSTEM.	WI 53094 WI 53543	
24. CONTRACTOR SHALL INSPECT BACKFILL AND PLACEMENT OF TOPSOIL TO DETERMINE WHETHER OR NOT A "HARDPAN" SITUATION EXISTS OR COULD EXIST DUE TO PREVIOUS SOIL CONDITIONS, PLACEMENT OF AND COMPACTION OF FILL DURING CONSTRUCTION, OR ANY OTHER CONTRIBUTING FACTOR PRIOR TO INSTALLATION OF PLANT MATERIALS. IF SUCH A SITUATION IS FOUND OR ANTICIPATED, IT SHOULD BE BROUGHT TO THE ATTENTION OF JPR AND/OR OWNER IMMEDIATELY, AND PRIOR TO THE INSTALLATION OF PLANT MATERIAL, FOR A REMEDY. CONTRACTOR RESPONSIBLE FOR PLANT REPLACEMENT IF PLANT MATERIAL IS PLANTED IN A "HARDPAN" SITUATION.	ATERTOWN, ON HIGHLAND,	
25. DIMENSIONS FOR HEIGHTS, SPREAD AND CALIPER OF TREES SPECIFIED ON THE PLANT LIST ARE GENERAL GUIDES FOR THE MINIMUM DESIRED SIZE OF EACH PLANT. EACH PLANT SHALL HAVE A UNIFORM AND CONSISTENT SHAPE AS IT PERTAINS TO THE LATEST EDITION OF AMERICAN STANDARD FOR NURSERY STOCK. PLANT MATERIAL WHICH FAILS TO CONFORM TO THE SPECIFICATIONS IS SUBJECT TO REJECTION BY OWNER/JPR.	ATIO	
SEEDING NOTES 1. ALL DISTURBED AREAS TO BE DRILL SEEDED WITH THE FOLLOWING GRASS SEED MIXTURE: <u>TYPE</u> <u>% BY WEIGHT</u> <u>% BY PURITY</u> <u>% BY GERMINATION</u> KENTUCKY BLUE GRASS <u>36</u> 85 RED FESCUE <u>30</u> 98 85 MANHATTAN PERENNIAL RYE 17 98 90 NORLEA PERENNIAL RYE 17 98 90	N, WI DDT CORPORA	
2. TURF SEED INSTALLATION: SOW SEED WITH DRILL SEEDING MACHINE. EVENLY DISTRIBUTE SEED BY SOWING EQUAL QUANTITIES IN TWO DIRECTIONS AT RIGHT ANGLES TO EACH OTHER. DO NOT USE WET SEED OR SEED THAT IS MOLDY OR OTHERWISE DAMAGED. DO NOT SEED AGAINST EXISTING TREES. LIMIT EXTENT OF SEED TO OUTSIDE EDGE OF PLANTING SAUCER.	TERTOWN UILDING	
 SOW SEED AT A TOTAL RATE OF 4 LB/1000 SQ FT. RAKE SEED LIGHTLY INTO TOP 1/8 INCH OF SOIL, ROLL LIGHTLY, AND WATER WITH FINE SPRAY. PROTECT SEEDED AREAS WITH SLOPES EXCEEDING 1:3 WITH EROSION—CONTROL BLANKETS INSTALLED AND STAPLED ACCORDING TO MANUFACTURER'S WRITTEN INSTRUCTIONS. PROTECT SEEDED AREAS WITH SLOPES NOT EXCEEDING 1:3 BY HYDROMULCH. SPREAD UNIFORMLY AT A MINIMUM RATE OF 1 1/2 TONS/ACRE TO FORM A CONTINUOUS BLANKET OVER SEEDED AREAS. 	NATE N BUI SITE	
3. SATISFACTORY SEEDED TURF: AT END OF MAINTENANCE PERIOD (90 DAYS), A HEALTHY, UNIFORM, CLOSE STAND OF GRASS HAS BEEN ESTABLISHED, FREE OF WEEDS AND SURFACE IRREGULARITIES, WITH COVERAGE EXCEEDING 90 PERCENT OVER ANY 10 SQ FT AND BARE SPOTS NOT EXCEEDING 3 INCHES BY 3 INCHES (3" X 3").		
PLANT MATERIAL NOTES	CLE DRIVE F	
 ALL PLANT MATERIAL TO MEET AMERICAN STANDARDS FOR NURSERY STOCK, 1990 EDITION/ HORTIS THIRD 1076 CORNELL UNIVERSITY. ALL LANDSCAPE AREAS TO BE 100% IRRIGATED WITH AN UNDERGROUND AUTOMATIC IRRIGATION SYSTEM. 		
3. PLANT CONTAINER SIZES ARE SHOWN AS GUIDELINES ONLY (MINIMUM HEIGHT AND SPREAD REQUIREMENTS RULE). PLANT HEIGHT AND SPREAD SPECIFICATIONS ARE MINIMUMS, ON CENTER (O.C.) SPECIFICATIONS ARE MAXIMUMS.	1722	
	DESIGNED BY: MM	
	DRAWN BY:	
	MM	
	MM DATE: MAY 2023	
40	DATE: MAY 2023 JOB NUMBER: 2022-0168	
	DATE: MAY 2023	