



1897 Broadway Rd
(608)253-3371

715 Morgan street PO 247
(920)696-3580

08-16-2023

Watertown Senior Center
514 S. 1st street
Watertown, WI 53094

Estimator: Chris Lawton
Project: Automatic standby generator
SIZE: 150KW 600amp

Provided is an estimate to supply, install, and test a Generac Liquid cooled generator for the above listed location. After Killo watt review and a site visit United Electric proposes to install a 150KW generator. The 150KW generator presented is large enough to handle the existing load. United Electric understands the purpose of this installation is to provide the city of Watertown with an emergency place of assembly in the event such a building is needed. With the potential need for such an event the 150KW generator gives the city not only ample power for their day-to-day function but also enough capacity to handle additional power needs without overloading the generator. Included you will find a line item for the gas installation. Richter heating and cooling was contacted to provide a gas installation cot. The gas installation cost is included within this proposal and the proposed estimate is 100% complete with no tax included.

United Electric is a Generac Elite Dealer and provides over 22 years of experience installing and maintaining Generac generators. We have ben a trusted installer on Liquid cooled generators with multiple municipalities:

Randoph wastewater
City of Wisconsin Dells

Village of Reeseville
Ho-chunk Nation

City of Baraboo
Village of Fall River

Generator, parts, and listed accessories included :

- 150KW Generac RG15090GNAC
- 600 amp 120/208v 3phase automatic transfer switch
- 1 Exide Battery
- Battery heater kit for cold weather
- Extreme cold weather block heater kit
- Mobil link remote 5G monitoring accessory (annual subscription required for activation \$69.99/year)
- 12" reinforced concrete pad
- Electrical Permit
- Electrician & Generac Generator tech
- Gas Installation
- All associated materials needed
- Testing and owner training

Warranty standard 5-year limited warranty. Options for additional purchase are available. Extended warranties available:

5-year extended warranty	\$788,10
7-year extended warranty	\$1486.60
10-year extended warranty	\$2115.85

The current lead time on the proposed 150KW Generac generator part # RG15090GNAC is 34-38 weeks. United Electric quotes lead time on current manufacturer information. United Electric is not responsible for shipping delays. The proposed transfer switch shows a 22–26-week lead time.

Day of installation the Senior center would be without power for approximately 6-8 hours.

Thank you for the opportunity to quote this project. Please review all given information and contact me directly if you have any further questions. I look forward to providing the City of Watertown with this complete installation and continuing a transparent relationship with our local municipalities.

Total estimated Cost: \$77,743.00

Chris Lawton
(608)963-2630
chris@unitedelectricwi.com