

EXHIBIT A

The scope of work to be completed within the FDOT right-of-way, which work will become FDOT property, consists of the following work to be constructed within the area highlighted in red in the sketch below:

1. 20 TN Type SP asphalt (174 SY, 2" thick)
2. 262 SY optional base Group 9
3. 262 SY 12" stabilized subgrade LBR 40 OR 6" additional base in lieu of.
4. 157 LF valley gutter
5. 117 LF Type F curb and gutter
6. 68 SY 4" concrete sidewalk
7. 54 SF detectable warning mat
8. 28 LF reinforced concrete pipe 12"
9. 1 mitered end section, 12" round, CD
10. 10 SY 4" non-reinforced concrete ditch pavement
11. 197 SY performance turf, sod
12. 2 EA single post signs, less than 12 SF
13. 94 LF 24" white thermoplastic striping
14. 125 LF 12" white thermoplastic striping
15. 228 LF 6" yellow thermoplastic striping
16. 1 EA thermoplastic white preformed traffic arrow

