

LOCATION MAP



S.F.	AC.	%
16,515.00	0.379	10.82%
65,738.93	1.509	43.06%
15,074.04	0.346	9.87%
35,681.25	0.819	23.37%
2,710.56	0.062	1.78%
16,944.22	0.389	11.10%
152,664	3.50	100.00%
152,664	SF	
60D5	850	DDOV/
	REQ.	PROV.
· · ·		97
· ·	366	890
(SECTION 4.15)		I
1/20 OF 96LF	5	6
1/10 OF 96 SF	76	85
(SECTION 4.16)		
1/20 OF 206 LF	10	16
1/10 OF 206 SF	103	181
(SECTION 4.13)		
1/25 LF	14	14
3' HT.	YES	YES
(SECTION 4.13)		
1/25 LF	9	10
3' HT.	YES	YES
(SECTION 4.13)		1
1/25 LF	12	13
3' HT.	YES	YES
	16,515.00 65,738.93 15,074.04 35,681.25 2,710.56 16,944.22 152,664 IS2,664 IS2,664	16,515.00 0.379 65,738.93 1.509 15,074.04 0.346 35,681.25 0.819 2,710.56 0.062 16,944.22 0.389 152,664 3.50 IS2,664 152,664 3.50 IS2,664 IS2,664

(SECTION 4.12) 84 TREES 6 9 (SECTION 4.12) 60% OF REQ. MIN. 31 40 60% OF REQ. MIN. 220 624

** CANOPY TREE SUBSTITUTE IS 3:1 RATIO. EXCEPTION FOR ROYAL, BISMARCK, PHOENIX, AND CANARY. (7.D.2B) [ORD. 2018-002]

LEGEND

ADA	AMERICANS WITH DISABILITIES
LB	LANDSCAPE BUFFER
DE	DRAINAGE EASEMENT
R	RADIUS
OH	OVER HANG
SB	SETBACK
SW	SIDEWALK
TYP	TYPICAL
LSEV	LOW SPEED ELECTRIC VEHICLE

PROJECT TEAM

PROPERTY OWNER: MINTO PBLH, LLC 16604 TOWN CENTER PKWY. WESTLAKE, FL 33470 PHONE: 954-973-4490

KONOVER SOUTH, LLC 431 FAIRWAY DR SUITE 201 DEERFIELD BEACH, FL 33441 PHONE: (954) 354-8282

SITE PLANNER/LANDSCAPE ARCHITECT: COTLEUR & HEARING 1934 COMMERCE LANE, JUPITER, FL 33458 PHONE: 561-747-6336

CUHACI & PETERSON 2600 MAITLAND CENTER PARKWAY, MAITLAND, FL 32751 PHONE: (407) 661-9100

CIVIL ENGINEER: THOMAS ENGINEERING GROUP 6300 NW 31ST AVENUE FORT LAUDERDALE, FL 33309 PHONE: 954-202-7000

ADA SIGN

STOP SIGN

DO NOT ENTER

O GREASE TRAP

TRANSFORMER

SURVEYOR: GEOPOINT SURVEYING, INC 4152 WEST BLUE HERON BLVD, SUITE 105 RIVIERA BEACH, FLORIDA 33404 PHONE: 561-444-2720

TRAFFIC ENGINEER: PINDER TROUTMAN CONSULTING, INC. 2005 VISTA PARKWAY, SUITE 111 WEST PALM BEACH, FL 33411-6700 PHONE: 561-296-9698

SEMINOLE IMPROVEMENT **DISTRICT – ENGINEER :** CAULFIELD & WHEELER, INC. 7900 GLADES ROAD, SUITE 100 BOCA RATON, FL 33434 PHONE: 561-392-1991





LANDSCAPE SPECIFICATIONS

1. GENERAL LANDSCAPE REQUIREMENTS

LANDSCAPE CONTRACT WORK INCLUDES, BUT IS NOT LIMITED TO, SOIL PREPARATION, FINE OR FINISH GRADING, FURNISHING AND INSTALLING PLANT MATERIAL, WATERING, STAKING, GUYING AND MULCHING.

PLANT SIZE AND QUALITY TREES, PALMS, SHRUBS, GROUNDCOVERS:

PLANT SPECIES AND SIZES SHALL CONFORM TO THOSE INDICATED ON THE DRAWINGS, NOMENCLATURE SHALL CONFORM TO STANDARD PLANT NAMES, 1942 EDITION. ALL NURSERY STOCK SHALL BE IN ACCORDANCE WITH GRADES AND STANDARDS FOR NURSERY PLANTS PARTS I & II, LATEST EDITION PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER

SERVICES, UNLESS SPECIFIED OTHERWISE. ALL PLANTS SHALL BE FLORIDA GRADE NUMBER 1 OR BETTER AS DETERMINED BY THE FLORIDA DIVISION OF PLANT INDUSTRY. TIGHTLY KNIT PLANT, SO TRAINED OR FAVORED IN ITS DEVELOPMENT THAT FIRST APPEARANCE IS UNQUESTIONABLE AND IT IS OUTSTANDINGLY SUPERIOR IN FORM, NUMBER OF BRANCHES, COMPACTNESS AND SYMMETRY. ALL PLANTS SHALL BE FRESHLY DUG, SOUND, HEALTHY, AND STAMMETRT. ALL PLANTS SHALL BE PRESHLT DOG, SOUND, HEALTHT, VIGOROUS, WELL BRANCHED AND FREE OF DISEASE AND INSECT EGGS AND LARVAE AND SHALL HAVE ADEQUATE ROOT SYSTEMS. TREES AND PALMS FOR PLANTING ROWS SHALL BE UNIFORM IN SIZE AND SHAPE. ALL MATERIALS SHALL BE SUBJECT TO APPROVAL BY THE LANDSCAPE ARCHITECT. THE PLANTS FURNISHED SHALL BE NORMAL FOR THE VARIETY AND FLORIDA NUMBER 1.

ALL CONTAINER GROWN MATERIAL SHALL BE HEALTHY, VIGOROUS, WELL-ROOTED PLANTS AND ESTABLISHED IN THE CONTAINER IN WHICH THEY ARE SOLD. THE PLANTS SHALL HAVE TOPS OF GOOD QUALITY AND BE IN A HEALTHY GROWING CONDITION.

AN ESTABLISHED CONTAINER GROWN PLANT SHALL BE TRANSPLANTED INTO A CONTAINER AND GROWN IN THAT CONTAINER SUFFICIENTLY LONG ENOUGH FOR THE NEW FIBROUS ROOTS TO HAVE DEVELOPED SO THAT THE ROOT MASS WILL RETAIN ITS SHAPE AND HOLD TOGETHER WHEN REMOVED FROM THE

STANDARD PLANTING MIXTURE SHALL BE ONE (1) PART RECYCLED ORGANIC MATERIAL ADDED TO THREE (3) PARTS EXISTING NATIVE SOIL.

REPLACEMENT SOIL SHALL BE USED AS SPECIFIED TO REPLACE EXISTING SOILS THAT ARE DETERMINED BY THE LANDSCAPE ARCHITECT TO BE UNSUITABLE FOR PLANTING, IE. ROAD BASE, PAVEMENT, ETC. REPLACEMENT SOIL MIX SHALL CONTAIN 60% SAND AND 40% MUCK. SAND SHALL BE 100% CLEAN NATIVE SAND SCREENED TO 1/4" AND MUCK SHALL BE 100% CLEAN ORGANIC NATIVE MUCK SCREENED TO 1/2". ALL SOIL SHALL BE MIXED PRIOR TO DFI IVERY ON SITE

MULCH SHALL BE COCO BROWN DYED B GRADE MULCH. ALL MULCH IS TO BE APPLIED TO A DEPTH OF 3", EXCEPT AS WITHIN 6" OF PLANT STEMS.

FERTILIZER IN BACKFILL MIXTURE FOR ALL PLANTS SHALL CONSIST (MILORGANITE ACTIVATED SLUDGE MIXED WITH THE BACKFILL AT A RATE OF NOT LESS THAN 50 LBS. PER CUBIC YARD.

FERTILIZER FOR TREES AND SHRUBS SHALL UTILIZE AN 8-2-12+4 ANALYSIS, PLUS MICRO NUTRIENTS. 100 PERCENT OF THE (N) NITROGEN, (K) POTASSIUM, (MG) MAGNESIUM, AND (B) BORON MUST BE IN CONTROLLED RELEASE FORM. THE (MN) MANGANESE AND (FE) IRON SOURCES MUST BE WATER SOLUBLE (SULFATED OR CHELATED).

FERTILIZER WILL BE APPLIED PER THE MANUFACTURERS RECOMMENDATIONS. "FLORIDA EAST COAST PALM SPECIAL" SHALL BE APPLIED TO ALL PALMS AT THE RATE RECOMMENDED BY THE MANUFACTURER. FIELD GROWN TREES AND PALMS PREVIOUSLY ROOT PRUNED SHALL OBTAIN A

ROOT BALL WITH SUFFICIENT ROOTS FOR CONTINUED GROWTH WITHOUT RESULTING SHOCK.

CONTRACTOR SHALL NOT MARK OR SCAR TRUNK IN ANY FASHION. PLANTS SHALL BE WATERED AS NECESSARY OR WITHIN 24 HOURS AFTER

NOTIFICATION BY THE LANDSCAPE ARCHITECT. THE LOCATIONS OF PLANTS, AS SHOWN IN THESE PLANS, ARE APPROXIMATE. THE FINAL LOCATIONS MAY BE ADJUSTED TO ACCOMMODATE UNFORESEEN FIELD CONDITIONS. MAJOR ADJUSTMENTS TO THE LAYOUT ARE TO BE APPROVED BY THE LANDSCAPE ARCHITEC

ALL PLASTIC FABRIC SHALL BE REMOVED FROM PLANT MATERIAL AT TIME OF INSTALLATION. TREES MUST BE STAKED AS SHOWN ON THE PLANTING DETAILS WITHIN 24 HOURS OF PLANTING. STAKES TO REMAIN FOR A MINIMUM OF 9 MONTHS, BUT NO LONGER THAN 18 MONTHS. CONTRACTOR IS RESPONSIBLE FOR

MAINTENANCE AND REMOVAL OF THE STAKES. ALL TREES MUST BE PRUNED AS PER LANDSCAPE ARCHITECT'S DIRECTION.

SABAL PALMS MAY BE HURRICANE CUT. ALL SHRUBS, TREES AND GROUND COVER WILL HAVE IMPROVED SOIL AS PER PLANTING SOIL NOTES. THE SOILS SHALL BE PLACED IN THE HOLE DURING PLANTING. TOP DRESSING ONLY IS NOT ACCEPTABLE.

DO NOT ALLOW AIR POCKETS TO FORM WHEN BACKFILLING. ALL TREES SHALL BE SPIKED IN UTILIZING WATER AND A TREE BAR.

IF LANDSCAPE CONTRACTOR SHALL WATER, MULCH, WEED, PRUNE, AND OTHERWISE MAINTAIN ALL PLANTS, INCLUDING SOD, UNTIL COMPLETION OF CONTRACT OR ACCEPTANCE BY LANDSCAPE ARCHITECT. SETTLED PLANTS SHALL BE RESET TO PROPER GRADE, PLANTING SAUCERS RESTORED, AND DEFECTIVE WORK CORRECTED.

THE LANDSCAPE CONTRACTOR SHALL AT ALL TIMES KEEP THE PREMISES FREE FROM ACCUMULATION OF WASTE MATERIALS OR DEBRIS CAUSED BY HIS CREWS DURING THE PERFORMANCE OF THE WORK. UPON COMPLETION OF THE THE CONTRACTOR SHALL PROMPTLY REMOVE ALL WASTE MATERIALS, DEBRIS, UNUSED PLANT MATERIAL, EMPTY PLANT CONTAINERS AND ALL EQUIPMENT FROM THE PROJECT SITE.

UPON COMPLETION OF THE WORK, THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT AND REQUEST A FINAL INSPECTION. ANY ITEMS THAT ARE JUDGED INCOMPLETE OR UNACCEPTABLE BY THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE SHALL BE CORRECTED BY THE LANDSCAPE CONTRACTOR WITHIN 14 DAYS.

ALL LABOR AND MATERIAL FOR SOIL AMENDMENTS AND FERTILIZER THAT I REQUIRED TO INSURE THE SUCCESSFUL ESTABLISHMENT AND SURVIVAL OF HE PROPOSED VEGETATION, AS WELL AS ALL THE COST FOR THE REMOVAL OF UNSUITABLE OR EXCESS BACKFILL MATERIAL, SHALL BE INCLUDED IN THE CONTRACTOR'S BID TO PERFORM THE WORK REPRESENTED IN THIS PLAN SET. 2. PLANTING TREES

EXCAVATE PIT AS PER PLANTING DETAILS.

BACKFILL AROUND BALL WITH STANDARD PLANTING MIXTURE AND SLIGHTL COMPACT, WATER THOROUGHLY AS LAYERS ARE PLACED TO ELIMINATE VOIDS AND AIR POCKETS. BUILD A 6" HIGH BERM OF STANDARD PLANTING MIXTURE BEYOND EDGE OF EXCAVATION. APPLY 3" (AFTER SETTLEMENT) OF MULCH EXCEPT WITHIN 6" OF TRUNK.

PRUNE TREE TO REMOVE DAMAGED BRANCHES ONLY. DO NOT REMOVE MORE THAN 15% OF BRANCHES. DO NOT PRUNE BACK TERMINAL LEADER. GUY AND STAKE TREE IN ACCORDANCE WITH THE STAKING DETAILS IMMEDIATELY AFTER PLANTING.

3. PLANTING SHRUBS

LAYOUT SHRUBS TO CREATE A CONTINUOUS SMOOTH FRONT LINE AND FILL IN EXCAVATE PIT OR TRENCH TO 1-1/2 TIMES THE DIAMETER OF THE BALLS OR

ONTAINERS OR 1'-0" WIDER THAN THE SPREAD OF ROOTS FOR POSITIONING T PROPER HEIGHT. BACKFILL AROUND PLANTS WITH STANDARD PLANTING MIXTURE, COMPACTED TO ELIMINATE VOIDS AND AIR POCKETS. FORM GRADE SLIGHTLY DISHED AND BERMED AT EDGES OF EXCAVATION. APPLY 3" OF MULCH EXCEPT WITHIN 6" OF STEMS.

4. PLANTING GROUND COVER

LOOSEN SUBGRADE TO DEPTH OF 4" IN AREAS WHERE TOPSOIL HAS BEEN STRIPPED AND SPREAD SMOOTH.

SPACE PLANTS AS OTHERWISE INDICATED. DIG HOLES LARGE ENOUGH TO ALLOW SPREADING OF ROOTS. COMPACT BACKFILLTO ELIMINATE VOIDS AND LEAVE GRADE SLIGHTLY DISHED AT EACH PLANT. WATER THOROUGHLY. APPLY 3" OF MULCH OVER ENTIRE PLANTING BED, LIFTING PLANT FOLIAGE ABOVE MULCH.

DURING PERIODS OF HOT SUN AND/OR WIND AT TIME OF PLANTING, PROVIDE PROTECTIVE COVER FOR SEVERAL DAYS OR AS NEEDED.

5. PLANTING LAWNS

SODDING: SOD TYPE SPECIFIED ON PLANT LIST SHALL BE MACHINE STRIPPED NOT MORE THAN 24 HOURS PRIOR TO LAYING.

LOOSEN SUBGRADE TO DEPTH OF 4" AND GRADE WITH TOPSOIL EITHER PROVIDED ON SITE OR IMPORTED STANDARD PLANTING MIX TO FINISH DESIGN ELEVATIONS. ROLL PREPARED LAWN SURFACE. WATER THOROUGHLY, BUT DO NOT CREATE MUDDY SOIL CONDITION.

FERTILIZE SOIL AT THE RATE OF APPROXIMATELY 10 LBS. PER 1,000 S.F. SPREAD FERTILIZER OVER THE AREA TO RECEIVE GRASS BY USING AN APPROVED DISTRIBUTION DEVICE CALIBRATED TO DISTRIBUTE THE APPROPRIATE QUANTITY. DO NOT FERTILIZE WHEN WIND VELOCITY EXCEEDS 15 M.P.H. THOROUGHLY MIX FERTILIZER INTO THE TOP 2" OF TOPSOIL.

AY SOD STRIPS WITH TIGHT JOINTS, DO NOT OVERLAP, STAGGER STRIPS 1 DFFSET JOINTS IN ADJACENT COURSÉS. WORK SIFTED STANDARD PLANTING MIXTURE INTO MINOR CRACKS BETWEEN PIECES OF SOD AND REMOVE EXCESS SOIL DEPOSITS FROM SODDED AREAS. SOD ON SLOPES GREATER THAN 3:1 SHALL BE STAKED IN PLACE. ROLL OR STAMP LIGHTLY AND WATER THOROUGHLY WITH A FINE SPRAY IMMEDIATELY AFTER PLANTING.

6. MISCELLANEOUS LANDSCAPE WORK

LANDSCAPE MAINTENANCE

REPRESENTATIVE. INCLUDE WATERING, WEEDING, CULTIVATING, RESTORATION OF GRADE, MOWING AND TRIMMING GRASS, PRUNING TREES AND SHRUBS, PROTECTION FROM INSECTS AND DISEASES, FERTILIZING AND SIMILAR OPERATIONS AS NEEDED TO INSURE NORMAL GROWTH AND GOOD HEALTH FOR LIVE PLANT MATERIAL.

PLANT MATERIAL SUBSTITUTION

NO SUBSTITUTION OF PLANT MATERIAL, TYPE OR SIZES WILL BE PERMITTED WITHOUT AUTHORIZATION FROM THE LANDSCAPE ARCHITECT. PLANTING BED PREPARATION

MAINTAIN LANDSCAPE WORK UNTIL FINAL ACCEPTANCE IS ISSUED BY THE OWNER'S

ALL PLANTING BEDS SHALL BE PROPERLY PREPARED PRIOR TO THE COMMENCEMENT OF ANY PLANTING. PLANTING AREAS, INCLUDING LAWNS SHALL BE FREE OF ALL WEEDS AND NUISANCE VEGETATION. IF TORPEDO GRASS (PANICUM REPENS) IS PRESENT OR ENCOUNTERED DURING PLANTING, THE LANDSCAPE CONTRACTOR SHALL STOP ALL PLANTING UNTIL IT CAN BE DEMONSTRATED THAT IT HAS BEEN COMPLETELY REMOVED OR EDDICATED. THERE SHALL BE NO EXCEPTIONS TO THIS PROVISION OR ERADICATED. THERE SHALL BE NO EXCEPTIONS TO THIS PROVISION.

ALL LANDSCAPE ISLANDS AND BEDS WILL BE FREE OF SHELL ROCK AND CONSTRUCTION DEBRIS AND WILL BE EXCAVATED TO A DEPTH OF 30 INCHES OR TO CLEAN, NATIVE SOIL AND FILLED WITH THE SPECIFIED REPLACMENT SOIL.

ALL LANDSCAPE ISLANDS WILL BE FREE OF SHELL ROCK AND CONSTRUCTION DEBRIS AND WILL BE EXCAVATED TO A DEPTH OF 30 INCHES OR TO CLEAN, NATIVE SOIL AND FILLED WITH THE SPECIFIED REPLACEMENT SOIL. LANDSCAPE WARRANTY

THE LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL PLANT MATERIAL FOR A PERIOD OF SIX (6) MONTHS FROM THE DATE OF CONDITIONAL ACCEPTANCE IN WRITING FROM THE LANDSCAPE ARCHITECT. AT THE TIME OF CONDITIONAL ACCEPTANCE, THE SIX (6) MONTH PERIOD SHALL COMMENCE. ANY MATERIALS WHICH HAVE DIED OR DECLINED TO THE POINT WHERE THEY NO LONGER MEET FLORIDA #1 CONDTION DURING THIS PERIOD SHALL BE PROMPTLY REPLACED WITH SPECIMENS THAT MEET THE MINIMUM REQUIREMENTS CALLED FOR ON THE DRAWINGS. THE LANDSCAPE CONTRACTOR SHALL NOT BE HELD DEFORMED NOT BE HELD RESPONSIBLE FOR THE DRAWINGS. THE DATAGENE CONTRACTOR SHALL NOT BE HELD RESPONSIBLE FOR THE DEATH OR DAMAGE RESULTING FROM ACTO OF GOD SUCH AS LIGHTNING, VANDALISM, AND AUTOMOBILES OR FROM NEGLIGENCE BY THE OWNER. CONTRACTOR SHALL BE RESPONSIBLE FOR WATERING AND OTHERWISE MAINTAINING PLANTS UP TO THE FINAL ACCEPTANCE, UNLESS A WRITTEN AGREEMENT WITH THE LANDSCAPE ARCHITECT PROVIDES FOR A DIFFERENT ARRANGEMENT.

IRRIGATION

ALL LANDSCAPED AREAS (INCLUDING SOD AREAS) SHALL BE IRRIGATED WITH AN UNDERGROUND AUTOMATIC SPRINKLER SYSTEM PROVIDING 100 PERCENT COVERAGE. LANDSCAPE INSTALLATION SHALL NOT OCCUR UNTIL THE IRRIGATION SYSTEM IS OPERATIONAL, UNLESS THE OWNER, THE OWNER'S REPRESENTATIVE, OR THE PROJECT LANDSCAPE ARCHITECT GRANTS APPROVAL.

GENERAL LANDSCAPE NOTES

ALL LANDSCAPING AND ABOVE GROUND STRUCTURES SHOWN HEREON ARE DESIGNED AND ARE TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH SEMINOLE IMPROVEMENT DISTRICT (S.I.D.) STREETSCAPE STANDARDS. ALL PROPOSED PLANT MATERIAL SHALL BE FLORIDA NUMBER 1 OR BETTER AS DESCRIBED IN GRADES AND STANDARDS FOR NURSERY PLANTS, PARTS I AND II, LATEST EDITION PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICE ALL PLANTED AREAS SHALL RECEIVE A 3" LAYER OF MULCH.

ALL PLANT MATERIAL SHALL BE PRUNED, IF NEEDED, TO ACHIEVE THE SHAPE AND FORM CHARACTERISTIC TO THEIR DESIGN INTENT. PRUNING TO BE IN STRICT ACCORDANCE WITH ISA STANDARDS.

ALL SOD OR SEED SHALL BE CERTIFIED (IF APPLICABLE) AND WEED AND INSECT FREE. VEGETATION REMOVAL PERMITS ARE REQUIRED PRIOR TO REMOVING, CLEARING OR STRIPPING ANY VEGETATION FROM THE PROPERTY. AT THE TIME OF BUILDING PERMIT, THE APPLICANT SHALL EXECUTE HOLD HARMLESS AGREEMENTS WITH ALL APPLICABLE UTILITIES FOR LANDSCAPING WITHIN UTILITY EASEMENTS.

THE LANDSCAPE CONTRACTOR SHALL NOT MAKE ANY SUBSTITUTIONS OR CHANGES WITHOUT THE AUTHORIZATION OF S.I.D., THE OWNER AND THE LANDSCAPE ARCHITECT.

THE LANDSCAPE CONTRACTOR SHALL REVIEW THE PROJECT DRAINAGE AND UTILITY PLANS PRIOR TO CONSTRUCTION AND AVOID ALL CONFLICTS. THE LANDSCAPE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO COMMENCING WORK. CALL SUNSHINE ONE CALL SERVICE FOR UNDERGROUND UTILITY LOCATIONS 48 HOURS PRIOR TO ANY EXCAVATION OF DIGGING 1-800-432-4470. THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PERMITS REQUIRED TO PERFORM LANDSCAPE WORK.

THE CONTRACTOR SHALL COORDINATE THE PLANTING AND TRIMMING OF STREET TREES TO ENSURE FULL VISIBILITY TO TRAFFIC CONTROL AND SAFETY

TREES SHALL BE POSITIONED TO AVOID CONFLICTS WITH SIGNAGE AND SITE LIGHTING. LARGER TREES WILL BE PROVIDED AT INTERSECTIONS WHERE DEEMED NECESSARY BY S.I.D. DESIGN REQUIREMENTS. ANY PLANT MATERIAL PLANTED WITHIN SAFE SIGHT DISTANCE TRIANGLES SHALL BE MAINTAINED IN A WAY THAT PROVIDES UNOBSTRUCTED VISIBILITY AT A LEVEL BETWEEN 30" AND 8' ABOVE THE PAVEMENT SURFACE OF THE ADJACENT

VEGETATION LOCATED WITHIN SAFE SIGHT DISTANCE TRIANGLE AREAS SHALL BE TRIMMED SO THAT NO CANOPY LIMBS OR FOLIAGE EXTEND INTO REQUIRED VISIBILITY AREA.

ALL ABOVE GROUND UTILITIES I.E. TRANSFORMERS, SWITCH BOXES, AC CONDENSERS AND ALIKE SHALL BE FULLY SCREENED FROM VIEW ON THREE SIDES WITH LANDSCAPING. THE LANDSCAPING SHALL TO THE TALLEST POINT OF SAID EQUIPMENT AT TIME OF PLANTING LOCAL UTILITY AND FIRE RESCUE CLEARANCE ZONES SHALL BE PROVIDE AROUND ALL ABOVE GROUND OR AT GRADE METERS AND EQUIPMENT.

ALL TREES SHALL BE LOCATED WITHIN A MULCH PLANTING BED WITH A MINIMUM OF TWO (2) FEET OF CLEARANCE TO THE EDGE OF THE BED. ALL SOD SHALL BE STENOTAPHRUM SECONDATUS FLORITAM-PALMETTO (ST AUGUSTINE SOD) UNLESS OTHERWISE NOTED ON PLANS. TYPE D, E OR F RAISED CONCRETE CURBING SHALL BE PROVIDED AROUND ALL PLANTING ISLANDS WITHIN VEHICULAR USE AREAS.

ALL TREES PLANTED UNDER OR ADJACENT TO FPL POWER LINES WILL COMPLY WITH THE FPL RIGHT TREE IN THE RIGHT PLACE GUIDELINES (REV 5/95) ALL TREES AND PALMS SHALL BE STAKED/GUYED IN ACCORDANCE WITH THE SPECIFICATIONS AND PLANTING DETAILS.

STREET TREE LOCATIONS SHALL BE COORDINATED WITH DRIVEWAYS, STREET LIGHTS, UTILITIES AND FIRE HYDRANTS. THE IRRIGATION SYSTEM SHALL BE DESIGNED TO PROVIDE 100% OVERLAP COVERAGE TO ALL LANDSCAPE AND SOD AREAS.

THE IRRIGATION SYSTEM SHALL BE EQUIPPED WITH A RAIN SENSOR/CUT OFF SWITCH IN ACCORDANCE WITH STATE AND LOCAL REQUIREMENTS. ALL LANDSCAPE ISLANDS SHALL INCORPORATE THE INSTALLATION OF MOUNDING OF NATIVE SOILS A MINIMUM OF SIX INCHES (6") ABOVE THE TOP OF CURB. ROYAL PALM TREES WITHIN THE ROW SHALL BE REGULARLY MAINTAINED AND TRIMMED SO FRONDS DO NOT FALL ONTO ROADWAYS

ALL LANDSCAPE ISLANDS AND MEDIANS SHALL BE EXCAVATED TO A DEPTH OF 30" MINIMUM AND BACKFILLED WITH A SOIL MIX CONSISTING IF 1/3 NATIVE SOIL, 1/3 CLEAN SAND AND 1/3 COMPOSED COW MANURE OR COMPARABLE COMPOSED ORGANIC MATERIAL. CLEARANCE BETWEEN LANDSCAPE AND UTILITIES WILL BE REVIEWED BY SEMINOLE IMPROVEMENT DISTRICT.

ROOT BARRIER NOTES

TREES SHOWN ON THIS PLAN ARE FOR GRAPHIC REPRESENTATION ONLY. TREE SPACING IS BASED ON SEMINOLE IMPROVEMENT DISTRICT (S.I.D.) STREETSCAPE STANDARDS AND THE TREES SHOWN ON THESE PLANS ATTEMPT TO ACCOMPLISH THAT SPACING WHILE MAINTAINING THE REQUIRED SETBACKS FROM S.I.D. UTILITIES. TREES MAY BE FIELD ADJUSTED TO AVOID CONFLICTS WITH DRIVEWAYS AND UNDERGROUND UTILITIES. IN ANY CASE THE TREES SHALL BE LOCATED IN THE FIELD IN ACCORDANCE WITH THE PLANTING DETAILS SHOW HEREIN.

ADDITIONALLY, LARGE TREES OR PALMS ARE TO BE INSTALLED WITH A TEN FOOT (10" SEPARATION FROM ANY WATER OR SEWER MAIN AND/OR SERVICE, HYDRANTS AND LIFT STATIONS. IF A TEN FOOT (10') SEPARATION CANNOT BE ACHIEVED, THE TREE SHALL BE INSTALLED WITH A ROOT BARRIER SYSTEM. REFER TO THE "ROOT BARRIER" DETAIL FOR INSTALLATION REQUIREMENTS. HOWEVER, IN NO CASE SHALL TREE ENCROACH INTO A SID UE WITHOUT PRIOR SID APPROVAL AND ONLY SOD CAN BE INSTALLED WITHIN 7.5' OF A FIRE HYDRANT UNLESS OTHERWISE APPROVED BY THE FIRE MARSHALL.

ALL LANDSCAPING AND ABOVE GROUND STRUCTURE SHOWN HEREIN ARE DESIGNED AND ARE TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH SEMINOLE IMPROVEMENT DISTRICT STANDARDS.

ROYAL PALM TREES PLANTED WITHIN RIGHT OF WAYS SHALL BE REGULARLY MAINTAINED SO THAT FRONDS DO NOT FALL INTO THE RIGHT OF WAY.

TREES SHALL HAVE A MINIMUM TWO FOOT SEPARATION FROM BIKE PATHS AND SIDEWALKS.

PLANT LIST <u>CODE</u> <u>QTY</u>

CANOPY TREES 10 BB BS 10 CLDS DR LI PALM TREE AM 12 OLD2 3 PEA RE 13 SP 17

SMALL PALMS CH CH2 THA

VM2

SMALL TREES


GAR2 3 JA2

CODE QTY <u>SHRUBS</u>


v -1	2
IR	1
M10	26
M15	135
GROUN	

CI	115	
CID	319	~~~~~
CLD	58	00000
FG	300	~~~~~
ĪV	155	
JAS	34	
JC	78	
MUH	23	
PD7	29	
PD	65	
SA	34	
SAV	7	

SOD



ST AUGUSTINE OR CITRA BLUE



INSTRUCTIONS.

IS	/						
	BOTANICAL NAME	COMMON NAME	CONT	CAL	SIZE	NATIVE	REMARKS
<u>s</u>							
	BUCIDA BUCERAS `SHADY LADY`	SHADY LADY BLACK OLIVE	65 GAL	5" CAL	12`-14` OA	Ν	FULL CANOPY. MATCHED.
	BURSERA SIMARUBA	GUMBO LIMBO	45 GAL	3.5" CAL	12`HT X 6`SPRD	Y	FULL CANOPY
	CLUSIA FLAVA	SMALL LEAF CLUSIA TREE	65 GAL	3" CAL	12`HT X 6`SPRD	Ν	FULL CANOPY. COLUMNAR. MATCHED.
	DELONIX REGIA	ROYAL POINCIANA	65 GAL	4" CAL	16` OA	Ν	FULL CANOPY. SPECIMEN.
	LAGERSTROEMIA INDICA `MUSKOGEE` OR `TUSKEGEE`	CREPE MYRTLE	30 GAL	2" CAL	12`HT X 4`SPRD	Ν	MULTI, LIMB UP 5`. CHERRY LAKE NURSERY.
	ADONIDIA MERRILLII	CHRISTMAS PALM	FIELD GROWN	NA	12` OA	N	FULL CANOPY, SINGLE TRUNK, MATCHED
	COCCOTHRINAX CRINITA BREVICRINIS	SHORT HAIR OLD MAN PALM	25 GAL	N.A.	4`-5` O.A	Ν	FULL CANOPY
	PTYCHOSPERMA ELEGANS	ALEXANDER PALM	FIELD GROWN	NA	9` CT	Ν	FULL CANOPY, SINGLE STEM, MATCHED
	ROYSTONEA ELATA	ROYAL PALM	FIELD GROWN	NA	8` GW	Y	FULL CANOPY, MATCHED
	SABAL PALMETTO	SABAL PALMETTO	FIELD GROWN	NA	12` CT	Y	SLICK TRUNK, PERFECTLY MATCHED
	VEITCHIA MONTGOMERYANA	MONTGOMERY PALM	FIELD GROWN	NA	12` OA	Ν	DOUBLE TRUNK, FULL CANOPY
	CHAMAEROPS HUMILIS `SILVER SELECT`	EUROPEAN FAN PALM SILVER SELECT	30 GAI	NA	4`-5` OA	N	MULTI TRUNK, FULL CANOPY
	CHAMAEROPS HUMILIS `SILVER SELECT`	EUROPEAN FAN PALM SILVER SELECT		NA	6`-7` OA	N	MULTI TRUNK, FULL CANOPY
	THRINAX MORRISII	KEY THATCH PALM	B & B	NA	5` OA	Y	FULL & THICK
	ELAEOCARPUS DECIPIENS	JAPANESE BLUEBERRY TREE	25 GAL	NA	6`-8` OA	N	STANDARD. FULL & THICK CANOPY. SINGLE STRAIGHT TRUNK. MATCHED, CHERRY LAKE. FULL TO BASE
	GARCINIA SPICATA	GARCINIA	15 GAL	NA	3` OA	N	FULL & THICK
	JATROPHA	Jatropha Bush Form	25 GAL	NA	4`-5` OA	N	FULL, SPECIMEN
	BOTANICAL NAME	COMMON NAME	<u>CONT</u>	<u>SIZE</u>	SPACE	NATIVE	REMARKS
	AGAVE AMERICANA `GAINESVILLE BLUE`	BLUE CENTURY PLANT	15 GAL	30" X 30"	AS	N	FULL & THICK
	HIBISCUS ROSA SINENSIS	WHITE WING HIBISCUS	7 GAL	24" X 24"	30" OC	Ν	FULL & THICK
	PODOCARPUS MACROPHYLLUS	PODOCARPUS	10 GAL	4`-5` OA		Ν	FULL & THICK
	PODOCARPUS MACROPHYLLUS	PODOCARPUS	15 GAL	6`-7` OA	AS	N	FULL & THICK
ERS							
~~~~	CHRYSOBALANUS ICACO	COCOPLUM	3 GAL	24" X 24"	24" OC	Y	FULL & THICK
····	ČHŘÝŠOBALANUŠ IČACO ``HOŘÍŽOŇŤAĽ	ĎŴĂŔĔ ĊŎĊŎPĹŮŇ	3 GAL	12" X 12"	24" OC	Y	ĚŮĽĽ & THĽĆK, NOT STŘĚTCHĚĎ, FLOŘIĎA FANCY
	CLUSIA FLAVA	CLUSIA	7 GAL	36" X 24"	36" OC	N	FULL & THICK
~ ~ ~	FICUS MACROPHYLLA `GREEN ISLAND`	GREEN ISLAND FICUS	3 GAL	12" X 12"	24" OC	Ň	FULL & THICK
	ILEX VOMITORIA STOKES DWARF	DWARF YAUPON HOLLY	3 GAL	14" X 14"	24" OC	Y	FULL & THICK
	JASMINUM SIMPLICIFOLIUM	WAX JASMINE	3 GAL	24" X 24"	24" OC	Ν	FULL & THICK
	JUNIPERS CONFERTA	BLUE PACIFIC SHORE JUNIPER	7 GAL	8" X 18"	24" OC	Ν	FULL & THICK
	MUHLENBERGIA CAPILLARIS	MUHLY GRASS	3 GAL	18" X 18"	30" OC	Y	FULL & THICK
	PODOCARPUS MACR. 'PRINGLES' OR 'META'	DWARF PODOCARPUS	7 GAL	12" X 18"	24" OC	Ν	FULL & THICK
	PODOCARPUS MACROPHYLLUS `DWARF PRINGLES`	DWARF PODOCARPUS	3 GAL	12" X 12"	24" OC	Ν	FULL & THICK
	SCHEFFLERA ARBORICOLA	DWARF SCHEFFLERA	3 GAL	18" X18"	30" OC	Ν	FULL & THICK
	SCHEFFLERA ARBORICOLA `TRINETTE`	DWARF VARIEGATED SCHEFFLERA	3 GAL	18" X18"	30" OC	Ν	FULL & THICK

NA

NA

NA

WEED FREE

19,799 SF STENOTAPHRUM SECANDATUM

NTS

DIAMETER OF THE HOLE SHALL BE TWICE THE BALL DIAMETER. FOR ROOT BALLS 2' AND GREATER, THE HOLE SHALL BE 2' LARGER THAN THE BALL DIAMETER BACK FILL AROUND ROOT BALL WITH STANDARD —PLANTING MIXTURE. JET IN WITH WATER HOSE TO ELIMINATE AIR POCKETS.

_MINIMUM 3 - 2"x4" WOOD BRACES SHALL BE TOE NAILED TO WOOD BATTENS

_PLANT ROOT BALL SLIGHTLY ABOVE FINISHED

__FORM SAUCER WITH 4"-6" CONTINUOUS EARTHEN RIM AROUND PLANTING HOLE

_2"x4"x24" WOOD STAKE REMAINING 3" ABOVE GRADE

-MINIMUM ROOT BALL SIZE AS PER GRADES & STANDARDS. __PLACE ROOT BALL AT BOTTOM OF PLANTING PIT ON UNDISTURBED SUBGRADE TO PREVENT SETTLING FOR REGENERATED PALMS, ROOT PRUN MINIMUM 8 WEEKS, MAXIMUM 12 WEEK

REPRESENTATION ONLY. TREE SPACING IS BASED ON DESIGN REQUIREMENTS AND THE TREES SHOWN ON THESE PLANS ATTEMPT TO ACCOMPLISH THAT SPACING WHILE MAINTAINING THE REQUIRED SETBACKS FROM UTILITIES. TREES MAY BE FIELD ADJUSTED TO AVOID CONFLICTS WITH DRIVEWAYS AND UNDERGROUND UTILITIES. IN ANY CASE THE TREES SHALL BE LOCATED IN THE FIELD IN ACCORDANCE WITH THE PLANTING DETAILS

LANDSCAPE AND ROOT BARRIER NOTE

TREES SHOWN ON THIS PLAN ARE FOR GRAPHIC

NOTE: CONTRACTOR SHALL CONTACT PALM BEACH COUNTY TRAFFIC OPERATIONS AT

561-233-3900 AND/OR SEMINOLE IMPROVEMENT DISTRICT 561-790-1742 FORTY-EIGHT (48) HOURS PRIOR TO CONSTRUCTION IF WORK IS BEING DONE

DAMAGES TO LOOPS OR ANY SIGNAL EQUIPMENT CAUSED BY CONSTRUCTION OF THIS PROJECT MUST BE REPAIRED OR REPLACED TO ORIGINAL OR BETTER CONDITION AT NO COST TO PALM BEACH COUNTY AND/OR SEMINOLE IMPROVEMENT DISTRICT.

48 HOURS BEFORE DIGGING CALL TOLL FREE 1-800-432-4770 SUNSHINE STATE ONE CALL

OF FLORIDA, INC.

WITHIN 10 FEET ON ANY SIGNAL EQUIPMENT.

NO ABRUPT TRUNK CONSTRICTIONS SKIRT SHALL BE NEAT AND MATCHED SABAL PALMS TO BE SLICK TRUNK (UNLESS OTHERWISE NOTED) SHOW HEREON. ENS SHALL BE LOCATED E HEIGHT OF THE PALM

PLANTING PIT DEPTH SHALL EQUAL DEPTH OF ROOT BALL PLUS 6" FOR SETTING LAYER OF COMPACTED STANDARD PLANTING MIXTURE. PLANTING PIT WIDTH SHALL BE TWICE THE DIAMETER OF ROOT BALL

NTS

ON ALL PALMS

-2 STEEL BANDS

-3" MULCH

—EXISTING SUBGRADE

- FORM SAUCER WITH 4"-6" CONTINUOUS EARTHEN - 2"x4"x24" WOOD STAKE DRIVEN 3" BELOW GRADE

- TWIST WIRES TO ADJUST TENSION ON GUY WIRE REMOVE BURLAP FROM TOP 1/3 OF ROOTBALL IF


PLACE 3 (DOUBLE STRANDS) 12 GAUGE GALVANIZED GUY WIRE, SPACED EQUAL DISTANCE AROUND TREE

CHED



Cotleur & Hearing Landscape Architects Land Planners Environmental Consultants

1934 Commerce Lane Suite 1 Jupiter, Florida 33458 561.747.6336 · Fax 747.1377 www.cotleurhearing.com Lic# LC-C000239



SHEET OF © COTLEUR & HEARING, INC. These drawings are the property of the architect and are not to be used for extensions or on other projects except by agreement in writing with the architect. Immediately report any discrepancies to the architect.