

**DESCRIPTION**

**COMMENCE** AT THE NORTHEAST CORNER OF SECTION 1, TOWNSHIP 43 SOUTH, RANGE 40 EAST, THENCE S.01°33'05"W, ALONG THE EAST BOUNDARY LINE OF SAID SECTION 1, A DISTANCE OF 4842.94 FEET TO THE NORTHEAST CORNER OF SECTION 12, TOWNSHIP 43 SOUTH, RANGE 40 EAST; THENCE N.88°49'03"W, ALONG THE NORTH LINE OF SAID SECTION 12, A DISTANCE OF 871.66 FEET; THENCE S.01°10'57"W, A DISTANCE OF 321.07 FEET TO A POINT ON THE SOUTH RIGHT-OF-WAY LINE PERSIMMON BOULEVARD EAST, AS SHOWN ON PERSIMMON BOULEVARD EAST-PLAT 2, RECORDED IN PLAT BOOK 128, PAGE 16 THROUGH 19, INCLUSIVE, OF SAID PUBLIC RECORDS; THENCE S.32°01'05"W, A DISTANCE OF 124.85 FEET TO A POINT ON THE BOUNDARY OF SCHOOL SITE PLAT, AS RECORDED IN PLAT BOOK 128, PAGE 20 AND 21, OF SAID PUBLIC RECORDS; THENCE THE FOLLOWING COURSE BEING ALONG THE WESTERLY AND SOUTHERLY LINE OF SAID SCHOOL SITE PLAT: THENCE S.32°15'14"W, A DISTANCE OF 330.53 FEET TO A POINT OF CURVATURE OF A CURVE CONCAVE TO THE EAST, WITH A RADIUS OF 100.00 FEET; THENCE SOUTHERLY, ALONG THE ARC OF SAID CURVE THROUGH A CENTRAL ANGLE OF 30°37'49", A DISTANCE OF 53.46 FEET; THENCE S.01°37'25"W, A DISTANCE OF 301.20 FEET; THENCE S.88°20'27"E, A DISTANCE OF 407.12 FEET; THENCE S.01°39'33"E, DEPARTING SAID SOUTHERLY LINE OF SCHOOL SITE PLAT, A DISTANCE OF 184.00 FEET TO THE **POINT OF BEGINNING**; THENCE S.57°43'57"E, A DISTANCE OF 236.29 FEET; THENCE S.12°30'00"E, A DISTANCE OF 133.64 FEET; THENCE S.32°16'03"W, A DISTANCE OF 75.13 FEET TO A POINT OF CURVATURE OF A CURVE CONCAVE TO THE NORTHWEST, WITH A RADIUS OF 854.50 FEET; THENCE SOUTHWESTERLY, ALONG THE ARC OF SAID CURVE THROUGH A CENTRAL ANGLE OF 57°57'14", A DISTANCE OF 864.31 FEET TO A POINT OF TANGENCY; THENCE N.89°46'43"W, A DISTANCE OF 108.89 FEET; THENCE S.88°56'35"W, A DISTANCE OF 67.28 FEET; THENCE N.89°46'44"W, A DISTANCE OF 437.04 FEET; THENCE N.48°50'00"W, A DISTANCE OF 125.13 FEET; THENCE N.00°57'31"E, A DISTANCE OF 53.69 FEET; THENCE N.48°50'00"W, A DISTANCE OF 346.00 FEET; THENCE N.41°10'00"E, A DISTANCE OF 125.00 FEET; THENCE S.48°50'00"E, A DISTANCE OF 57.57 FEET; THENCE N.41°10'00"E, A DISTANCE OF 50.00 FEET TO A NON-TANGENT INTERSECTION WITH A CURVE CONCAVE TO THE NORTHEAST, WITH A RADIUS OF 35.00 FEET AND A RADIAL BEARING OF N.41°10'00"E, AT SAID INTERSECTION; THENCE NORTHWESTERLY, ALONG THE ARC OF SAID CURVE THROUGH A CENTRAL ANGLE OF 50°30'00", A DISTANCE OF 30.85 FEET; THENCE N.57°26'00"E, A DISTANCE OF 134.72 FEET; THENCE S.88°20'00"E, A DISTANCE OF 13.62 FEET; THENCE S.01°40'00"W, A DISTANCE OF 33.34 FEET; THENCE S.48°50'00"E, A DISTANCE OF 215.30 FEET; THENCE S.41°10'00"W, A DISTANCE OF 125.00 FEET; THENCE S.48°50'00"E, A DISTANCE OF 149.57 FEET TO A POINT OF CURVATURE OF A CURVE CONCAVE TO THE NORTH, WITH A RADIUS OF 55.00 FEET; THENCE EASTERLY, ALONG THE ARC OF SAID CURVE THROUGH A CENTRAL ANGLE OF 40°56'44", A DISTANCE OF 39.30 FEET; THENCE S.89°46'44"E, A DISTANCE OF 202.29 FEET; THENCE S.00°13'16"W, A DISTANCE OF 50.00 FEET; THENCE S.89°46'44"E, A DISTANCE OF 100.03 FEET; THENCE N.00°13'16"E, A DISTANCE OF 50.00 FEET; THENCE S.89°46'44"E, A DISTANCE OF 109.40 FEET; THENCE N.01°40'00"E, A DISTANCE OF 385.14 FEET; THENCE N.88°20'27"W, A DISTANCE OF 110.00 FEET; THENCE N.01°40'27"E, A DISTANCE OF 50.00 FEET; THENCE N.01°39'33"E, A DISTANCE OF 125.00 FEET; THENCE S.88°20'27"E, A DISTANCE OF 685.27 FEET TO THE **POINT OF BEGINNING**.  
**CONTAINING:** 694,659 SQUARE FEET OR 15.947 ACRES, MORE OR LESS.

**SURVEYOR'S NOTES:**

- EASEMENTS, RIGHTS-OF-WAYS, SET BACK LINES, RESERVATIONS, AGREEMENTS AND OTHER SIMILAR MATTERS TAKEN FROM OWNERSHIP AND ENCUMBRANCE REPORT PREPARED BY FOUNDERS TITLE, DATED MAY 11, 2018.
  - THIS SURVEY IS LIMITED TO ABOVE GROUND VISIBLE IMPROVEMENTS ALONG AND NEAR THE BOUNDARY LINES, AND THAT NOTHING BELOW THE GROUND WAS LOCATED INCLUDING, BUT NOT LIMITED TO FOUNDATIONS (FOOTINGS), UTILITIES, ETC. (INTERIOR OCCUPATION NOT LOCATED).
  - BEARINGS SHOWN HEREON ARE GRID BEARINGS BASED ON THE NORTH BOUNDARY OF SECTION 6, TOWNSHIP 43 SOUTH, RANGE 41 EAST, HAVING A GRID BEARING OF S.89°48'53"E. THE GRID BEARINGS, AS SHOWN HEREON, REFER TO THE STATE PLANE COORDINATE SYSTEM, NORTH AMERICA DATUM OF 1983 (NAD 83 - '07) FOR THE EAST ZONE OF FLORIDA. SAID BASIS OF BEARING IS THE SAME IN THE NORTH AMERICAN DATUM OF 1983 (NAD 83 - '90).
  - THE SUBJECT PROPERTY LIES WITHIN THE CITY OF WESTLAKE, PALM BEACH COUNTY, FLORIDA, WHERE THE FLOOD ZONE IS UNDETERMINED AT THE TIME OF THIS SURVEY.
  - THIS SURVEY IS BASED ON PREVIOUS FIELD SURVEYS, DOCUMENTS OF RECORD, FOUND MONUMENTS, EXHIBITS, AND HISTORICALLY USED CORNERS, AS WELL AS THE LEGAL DESCRIPTION SHOWN HEREON. IMPROVEMENTS LIKE UTILITIES UNDER CONSTRUCTION ARE NOT LOCATED FOR THE PURPOSE OF SHOWING THE BOUNDARY OF A PROPOSED PLAT.
- THE FOLLOWING ARE REFERENCE SURVEYS USED IN DETERMINING THE BOUNDARY LOCATION FOR CALLERY JUDGE GROVES:
- THE 'M' CANAL ROAD RIGHT OF WAY MAP, RECORDED IN ROAD PLAT BOOK 6, PAGE 136.
  - BOUNDARY SURVEY OF RESIDENTIAL AT CALLERY JUDGE GROVES, PREPARED BY LIDBERG LAND SURVEYING, INC. (JOB NO.: 04-106-101C), DATED OCTOBER 5, 2007.
  - SKETCH OF SURVEY, PREPARED BY S.P. MUSICK, DATED MARCH 5, 1965.
- 6) ALL BEARINGS AND DISTANCES (UNITED STATES SURVEY FEET) AS SHOWN HEREON ARE AS DESCRIBED AND MEASURED UNLESS OTHERWISE NOTED. MEASUREMENTS MADE ARE TO THE ACCURACY STANDARD OF SUBURBAN OR 1 FOOT IN 7500 FEET.
- 7) SID AND SWCD EASEMENTS WITHIN BOUNDARY HAVE BEEN RELEASE PER O.R. 28084, PG. 0985.

**EASEMENTS AND OTHER MATTERS AFFECTING TITLE:**


- TERMS, CONDITIONS, RIGHTS AND RESERVATIONS CONTAINED IN THAT AGREEMENT BETWEEN WEST PALM BEACH WATER COMPANY AND INDIAN TRAIL RANCH, INC., RECORDED SEPTEMBER 25, 1966, IN OFFICIAL RECORDS BOOK 1156, PAGE 36 AND THAT DEED BETWEEN INDIAN TRAIL RANCH, INC. AND THE CITY OF WEST PALM BEACH, RECORDED IN OFFICIAL RECORDS BOOK 1156, PAGE 58, TOGETHER WITH AND AFFECTED BY ASSIGNMENT, RECORDED IN OFFICIAL RECORDS BOOK 1854, PAGE 1826 AND AGREEMENT BETWEEN CITY OF WEST PALM BEACH AND CITY NATIONAL BANK OF MIAMI BEACH, TRUSTEE, RECORDED IN OFFICIAL RECORDS BOOK 1854, PAGE 1838, THAT ASSIGNMENT, RECORDED IN OFFICIAL RECORDS BOOK 8405, PAGE 1104 AND BY DEED RECORDED IN OFFICIAL RECORDS BOOK 1854, PAGE 1803, QUIT CLAIM DEED AND AGREEMENT FOR RESERVATION OF RIGHTS, RECORDED IN OFFICIAL RECORDS BOOK 14742, PAGE 1196, AND PARTIAL RELEASE OF EASEMENTS AND RESERVATIONS OF RIGHTS, RECORDED FEBRUARY 3, 2016, IN OFFICIAL RECORDS BOOK 28084, PAGE 985, ALL OF THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.
- INTERLOCAL AGREEMENT BETWEEN PALM BEACH COUNTY AND THE SEMINOLE IMPROVEMENT DISTRICT, RECORDED APRIL 26, 2006, IN OFFICIAL RECORDS BOOK 20252, PAGE 184, OF THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.
- MATTERS AS CONTAINED ON THAT CERTAIN PLAT OF TOWN CENTER PARKWAY NORTH, ACCORDING TO THE PLAT THEREOF, AS RECORDED IN PLAT BOOK 123, PAGE 106, OF THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.
- RECORDED NOTICE OF ENVIRONMENTAL RESOURCE PERMIT BY SOUTH FLORIDA WATER MANAGEMENT DISTRICT, RECORDED AUGUST 13, 2015, IN OFFICIAL RECORDS BOOK 27737, PAGE 15, OF THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.
- NOTICE OF WESTLAKE COMMUNITY FOUNDATION FEE, RECORDED JANUARY 16, 2018, IN OFFICIAL RECORDS BOOK 29588, PAGE 1066 AND CORRECTIVE WESTLAKE COMMUNITY FOUNDATION FEE, RECORDED JANUARY 24, 2018, IN OFFICIAL RECORDS BOOK 29609, PAGE 1177, BOTH OF THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.
- DECLARATION OF RESTRICTIONS, COVENANTS, AND EASEMENTS FOR WESTLAKE RESIDENCES, RECORDED JANUARY 16, 2018, IN OFFICIAL RECORDS BOOK 29588, PAGE 766, TOGETHER WITH FIRST AMENDMENT TO DECLARATION, RECORDED MAY 1, 2018, IN OFFICIAL RECORDS BOOK 29818, PAGE 284, BOTH OF THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.
- COLLATERAL ASSIGNMENT OF DECLARANT RIGHTS BY AND BETWEEN MINTO PBL, LLC AND WELLS FARGO BANK, NATIONAL ASSOCIATION, RECORDED JANUARY 25, 2018, IN OFFICIAL RECORDS BOOK 29611, PAGE 673, OF THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA. TO THE PERSON(S) EXPRESSLY IDENTIFIED BY NAME IN THE PROPERTY INFORMATION REPORT AS THE RECIPIENT(S) OF THE PROPERTY INFORMATION REPORT.

**SKY COVE SOUTH - PHASE 1B  
BOUNDARY SURVEY**


REVISIONS				Prepared For: MINTO COMMUNITIES, LLC
No.	Date	Description	Dwn.	Last Date of Field Survey: 10/09/20
				<b>SURVEYOR'S CERTIFICATE</b> This certifies that a survey of the hereon described property was made under my supervision and meets the Standards of Practice set forth by the Florida Board of Professional Surveyors & Mappers in Chapter 51-17.050, Florida Administrative Code, pursuant to Section 472.027, Florida Statutes.  <b>Luis J. Ortiz</b> FLORIDA PROFESSIONAL SURVEYOR & MAPPER NO. <b>LS7006</b> Check: GAR   P.C.: DC-9   Field Book: 2020/30w-28 RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER



4152 W. Blue Heron Blvd. Phone: (561) 444-2720  
 Suite 105 www.geopointsurvey.com  
 Riviera Beach, FL 33404 Licensed Business Number LB 7768



LINE DATA TABLE		
NO.	BEARING	LENGTH
L1	S 89°46'44" E	202.29'
L2	S 00°13'16" W	50.00'
L3	S 89°46'44" E	100.03'
L4	N 00°13'16" E	50.00'
L5	S 89°46'44" E	109.40'



- LEGEND**
- P.O.B. ----- POINT OF BEGINNING
  - P.O.C. ----- POINT OF COMMENCEMENT
  - P.B. ----- PLAT BOOK
  - D.B. ----- DEED BOOK
  - PG./PG(s) ----- PAGE(S)
  - NAD ----- NORTH AMERICAN DATUM
  - W.M.T. ----- WATER MANAGEMENT TRACT
  - O.S.T. ----- OPEN SPACE TRACT
  - P.B.C. ----- PALM BEACH COUNTY
  - U.E. ----- UTILITY EASEMENT
  - D.E. ----- DRAINAGE EASEMENT
  - L.M.A.E. ----- LAKE MAINTENANCE ACCESS EASEMENT
  - 7-43-41 ----- SECTION-TOWNSHIP-RANGE
  - R ----- RADIUS
  - L ----- ARC LENGTH
  - D ----- DELTA ANGLE
  - R/W ----- RIGHT-OF-WAY
  - R.P.E. ----- RURAL PARKWAY EASEMENT
  - (R) ----- RADIAL
  - (NR) ----- NON-RADIAL
  - S.I.D. ----- SEMINOLE IMPROVEMENT DISTRICT
  - SIR ● ----- SET 5/8" IRON ROD LB7768 (UNLESS OTHERWISE NOTED)

**SKY COVE SOUTH - PHASE 1B  
BOUNDARY SURVEY**

REVISIONS				Prepared For: MINTO COMMUNITIES, LLC	
No.	Date	Description	Dwn.	Last Date of Field Survey: 10/09/20	

**GeoPoint**  
Surveying, Inc.

4152 W. Blue Heron Blvd. Phone: (561) 444-2720  
Suite 105 www.geopointsurvey.com  
Riviera Beach, FL 33404 Licensed Business Number LB 7768

Drawn: SAB Date: 10-08-2020 Data File: WESTLAKE SKYCOVE SOUTH - PH 1B  
Check: GAR P.C.: DC-8 Field Book: 2020/30w-28  
Section: 12 Twn. 43S Rng. 40E Job #: SKY COVE SOUTH-PH1B\_B8