

CHANGE ORDER

No. 4

Dated: 3/7/2023

OWNER'S Contract No.: 000145 ENGINEER'S Project No.: 215203

Project: **OTIS STREET REHABILITATION**

CONTRACTOR: AMETHYST CONSTRUCTION, INC.

Contract For: Sidewalks & Roadway Contract Date: December 20, 2021

To: AMETHYST CONSTRUCTION, INC.
Contractor

You are directed to make the changes noted below in the subject Contract:

City of West Monroe

Owner

By: Staci Albritton Mitchell - Mayor
Dated: March 7, 2023

Nature of Changes: Replace old culvert and add concrete drive entrance to City property at approx. Sta. 11+00
Pour concrete collar around existing waterline conflict
Build case-in-place catchbasin to accomodate new pipe outfalling directly into the ditch a
approx. Sta. 7+00.

Enclosures: Change Order #4 Detail

These changes result in the following adjustments to the Contract Price and Contract Time

Contract Price Prior to This Change Order: \$ 1,481,027.20

Net (Increase) Resulting from this Change Order: \$ 32,085.74

Current Contract Price Including this Change Order: \$ 1,513,112.94

Contract Time Prior to This Change Order: 104 Days

Net (Add) Resulting from This Change Order: 5 Days

Current Contract Time Including This Change Order: 109 Days

The Above Changes Are Recommended:

S. E. HUEY CO.

Project Engineer

By:

Brad Anzalone, P.E.

Date:

The above Changes Are Approved As Recommended:

City of West Monroe

Owner

By:

Staci Albritton Mitchell - Mayor

Date:

The above Changes Are Accepted:

Amethyst Construction, Inc.

Contractor

By:

Date:

Project: OTIS STREET REHABILITATION			Owner: CITY OF WEST MONROE, LA					
Job #: 215203			Change Order No. 4			Contract Date: December 20, 2021		
Date of Completion:			Amount of Contract:			Contract Days:		
Original: N/A			Current: \$1,481,027.20			Current: 104		
Revised: N/A			Revised: \$1,513,112.94			Revised: 109		
Contract Items			Current:			Change Order No. 4		
Item No.	Item Description	Unit	Quantity	Unit \$	Extension	Quantity	Difference	Extension
202-02-006100	REMOVAL OF CONCRETE WALKS AND DRIVES	SQ. YD.	418	\$30.00	\$12,540.00			\$0.00
203-01-00100	GENERAL EXCAVATION	CU. YD.	15586	\$4.00	\$62,344.00			\$0.00
203-03-00100	EMBANKMENT	CU. YD.	15336	\$4.00	\$61,344.00			\$0.00
203-07-00100	BORROW (VEHICULAR MEASURE)(SELECT SOILS)	CU. YD.	450	\$25.00	\$11,250.00			\$0.00
203-08-00100	GEOTEXTILE FABRIC	SQ. YD.	750	\$5.00	\$3,750.00			\$0.00
303-03-00400	IN-PLACE CEMENT TREATED BASE COURSE, 12" THICK	SQ. YD.	673.5	\$38.00	\$25,593.00			\$0.00
304-01-00100	LIME	TON	24	\$325.00	\$7,637.50			\$0.00
304-05-00100	TYPE E LIME TREATMENT (9% BY VOLUME), 12" THICK	SQ. YD.	325	\$52.00	\$16,900.00			\$0.00
401-02-00100	AGGREGATE SURFACE COURSE (ADUSTED VEHICULAR MEASUREMENT	CU. YD.	105	\$110.00	\$11,550.00			\$0.00
402-01-00100	MAINLINE TRAFFIC MAINTENANCE SURFACING (AGGREGATE)	CU. YD.	250	\$102.00	\$25,500.00			\$0.00
502-01-00100	ASPHALT CONCRETE	TON	1054	\$185.00	\$195,027.00			\$0.00
502-01-00200	ASPHALT CONCRETE, DRIVES, TURNOUTS AND MISC.	TON	43	\$225.00	\$9,562.50			\$0.00
509-01-00100	MILLING ASPHALT PAVEMENT	SQ. YD.	8009	\$7.00	\$56,063.00			\$0.00
509-02-00100	CONTRACTOR RETAINED RECLAIMED ASPHALT CONCRETE PAVEMENT	CU. YD.	-418.0	\$0.01	(\$4.18)			\$0.00
510-01-00200	PAVEMENT PATCHING (12" MINIMUM THICKNESS)	SQ. YD.	250.0	\$112.00	\$28,000.00			\$0.00
701-03-01002	STORM DRAIN PIPE (15" RCP)	LIN. FT.	366	\$92.00	\$33,672.00	398.00	32	\$2,944.00
701-03-01022	STORM DRAIN PIPE (18" RCP)	LIN. FT.	186	\$109.00	\$20,274.00			\$0.00
702-03-00001	CATCH BASIN (REMOVE AND REPLACE FRAME AND COVER)	EACH	1	\$6,000.00	\$6,000.00			\$0.00
702-03-00500	CATCH BASINS (CB-06)	EACH	4	\$9,500.00	\$38,000.00			\$0.00
706-01-00100	CONCRETE WALK (4" THICK)	SQ. YD.	3497.800	\$72.00	\$251,841.60			\$0.00
707-03-00100	COMBINATION CONCRETE CURB AND GUTTER	LIN. FT.	687.0	\$50.00	\$34,350.00			\$0.00
713-01-00100	TEMPORARY SIGNS AND BARRICADES	LUMP SUM	1	\$130,000.00	\$130,000.00			\$0.00
713-02-00500	TEMPORARY PAVEMENT MARKINGS (24" WIDTH)	LIN. FT.	14	\$4.00	\$56.00			\$0.00
713-03-02000	TEMPORARY PAVEMENT MARKINGS (BROKEN LINE) (4" W) (10' L)	MILE	1	\$5,000.00	\$5,000.00			\$0.00
726-01-00100	BEDDING MATERIAL	CU. YD.	121.700	\$115.00	\$13,995.50			\$0.00
727-01-00100	MOBILIZATION	LUMP SUM	1.000	\$135,000.00	\$135,000.00			\$0.00
731-02-00100	REFLECTORIZED RAISED PAVEMENT MARKERS	EACH	166	\$22.00	\$3,652.00			\$0.00
732-01-01080	PLASTIC PAVEMENT STRIPING (24" WIDTH) (THERMOPLASTIC 90 MIL)	LIN. FT.	14	\$40.00	\$560.00			\$0.00
732-02-02000	PLASTIC PAVEMENT STRIPING (SOLID LINE)(4" WIDTH)(THERMOPLASTIC	MILE	1	\$10,000.00	\$12,600.00			\$0.00
732-03-02000	PLASTIC PAVEMENT STRIPING (BROKEN LINE)(4" WIDTH)(THERMOPLAST	MILE	0.63	\$4,000.00	\$2,520.00			\$0.00
739-01-00100	HYDRO-SEEDING	ACRE	2	\$5,000.00	\$10,000.00			\$0.00
740-01-00100	CONSTRUCTION LAYOUT	LUMP SUM	1	\$60,000.00	\$60,000.00			\$0.00
741-11-00200	ADJUSTING WATER VALVE AND METER BOX	EACH	1	\$2,200.00	\$2,200.00			\$0.00
NS-201-00001	TREE AND STUMP REMOVAL (UNDER 36" DIAMETER)	EACH	13	\$1,000.00	\$13,000.00			\$0.00
NS-201-00021	STUMP REMOVAL (UNDER 36" DIAMETER)	EACH	21	\$1,000.00	\$21,000.00			\$0.00
TS-800-00100	WEATHERED STEEL PEDESTRIAN BRIDGE (10' WIDE)	LIN. FT.	1	\$92,000.00	\$92,000.00			\$0.00
706-02-00200*	CONCRETE DRIVE (6" THICK)	SQ. YD.	0	\$142.00	\$0.00	109	109	\$15,478.00
701-03-01062*	STORM DRAIN PIPE (30" RCP)	LIN. FT.	0	\$95.00	\$0.00	40	40	\$3,800.00
202-02-32140*	REMOVAL OF PIPE (STORM DRAIN)	LIN. FT.	0	\$70.00	\$0.00	40	40	\$2,800.00
701-15-00100*	CONCRETE COLLAR	EACH	0	\$1,184.85	\$0.00	2	2	\$2,369.70
CI-000-10GEN*	REIMBURSEMENT FOR PRECAST BOX/CONFLICT	EACH	0	\$2,307.64	\$0.00	1	1	\$2,307.64
CI-000-10GEN*	EXTRA TO POUR BOX AT UTILITY CONFLICT	EACH	0	\$2,386.40	\$0.00	1	1	\$2,386.40
305-01-04040	D BALLAST BACKFILL (Subgrade Layer (12" Thick) (Stone))	CU. YD.	200	\$156.00	\$31,200.00			\$0.00
302-01-00300	CLASS II BASE COURSE (CRUSHED STONE)	CU. YD.	200	\$144.00	\$28,800.00			\$0.00
CI-000-10GEN	GEOGRID TX160 STABILIZING FABRIC	SQ. YD.	673.50	\$9.65	\$6,499.28			\$0.00
CI-107-00600	OCP INSURANCE REIMBURSEMENT	EACH	1	\$1,750.00	\$1,750.00			\$0.00
* - New Item			Project Cost Increase (Decrease): \$32,085.74					
			Contract Amount: Current: \$1,481,027.20 Revised: \$1,513,112.94					