

City of Wheatland - Corp Yard Sinkhole Repair

BID FORM - BK Custom Concrete

ITEM	CONSTRUCTION	QTY	UNITS	UNIT COST	TOTAL
1	MOBILIZATION AND DEMOBILIZATION	1	LS		Phase 1 - Lump Sum
2	TRENCH SHORING AND BRACING	1	LS		Phase 1 - Lump Sum
3	SHORE EXISTING BUILDING FOUNDATIONS	1	LS		Phase 1 - Lump Sum
4	LOCATE EXISTING ABANDONED WELL	1	LS		Phase 2**
5	EXTRACT LOOSE MATERIAL IN VOIDS	1	LS		Phase 1 - Lump Sum
6	SLURRY BACKFILL WELL & VOIDS	30	CY		Phase 1 - Lump Sum
7a	INJECTION GROUT CONC. BLDG. SLAB	15	CY		Phase 2**
or 7b	REMOVE AND REPLACE CONC. BLDG. SLAB	600	SF		Phase 2**
8	REMOVE EXISTING PAVEMENT	1,400	SF		Phase 2**
9	PREPARE SUBGRADE & REGRADE TO DRAIN	1,400	SF		Phase 2**
10	ASPHALT PAVEMENT (4" THICK, 1/2" TYPE A)	34	TON		Phase 2**

TOTAL

Phase 1* **\$29,226.00**

Written Amount: **Twenty nine thousand two hundred twenty six and zero cents**

* Phase 1 items as also indicated on attached BK Custom Concrete Proposal #1117.

** Phase 2 items to be accomplished by negotiated change order.

Submission Date: November 8, 2024

Company Name: BK Custom Concrete

Address: 4164 Markley Road, Yuba City, CA 95993

Phone No.: (530) 635-7046

Email: bksr_9@hotmail.com

CSLB License No(s): 877095

Bidder Signature: 

Proposal

Ca Lic #877095
 DIR# 2023/ 1000029851



4164 Markley Rd
 Yuba City Ca 95993

Name/Address
City of Wheatland Public Works 208 4th Street Wheatland Ca 95692

Date	Proposal No.
11/05/24	1117

Item	Description	Quantity	Cost	Total
04 Concrete	<p>Project: City Yard Sink Hole Location: 208 4th St Wheatland Ca 95692 Prevailing Wage Rates Apply Phase 1 (5 Working Days Only)</p> <ul style="list-style-type: none"> - Remove remaining asphalt to open up the existing sink hole - Remove existing dirt with vacuum excavation that is unstable and falling into sink hole - Secure south east corner of the foundation with high strength grout 4000 psi to stabilize foundation corner prior to excavation - Inspect existing conditions - Sand slurry sink hole after approvals from the City Management Team <p>Projection for Phase 1 completion 5 working days Labor 160 hrs @ \$99.85 = \$15,976.00 Equipment Rate \$900.00 per day x 5 days = \$4500.00 Material - Demo material off haul to dump \$50.00 per trailer load Sand Slurry back fill material 2 sack conc mix estimation 30 yards @ \$125.00 per yard = \$3750.00 High Strength Grout Material estimation \$650.00 Bottle Jacks and cribbing material estimation \$550.00</p>	1	26,826.00	26,826.00
			Total	

Customer Signature: _____

BKCC Signature: _____ Page 1

Proposal



Ca Lic #877095
DIR# 2023/ 1000029851

4164 Markley Rd
Yuba City Ca 95993

Name/Address

City of Wheatland Public Works
208 4th Street
Wheatland Ca
95692

Date	Proposal No.
11/05/24	1117

Item	Description	Quantity	Cost	Total
04 Concrete	Line Pump Service	1	1,400.00	1,400.00
Mobilization	Mobile of equipment and tools to job location	1	1,000.00	1,000.00
	* Time and Materials is based on a 1 week (5 days) period anything above and beyond will be documented and submitted for approvals for a change order in order for BK Concrete to proceed * All underground pipe if damaged will be replaced or fixed by others			
			Total	\$29,226.00

Customer Signature: _____

BKCC Signature: _____