

	Strand Associ	ates, Inc.			
	ALTERNA				
	WHITEWATER				
			PLANNING-LEVEL		
	10/18/20				
ITEM NO.	DESCRIPTION	Quantity	<u>Units</u>	Unit Price (2025)	Total Price
1	Mobilization/Demobilization (2% of Construction Cost)	1	LS	\$54,195.00	\$54,200
2	Clearing and Grubbing	0.58	AC	\$13,800.00	\$8,000
3	Traffic Control	1	LS	\$6,050.00	\$6,050
4	Construction Layout	1	LS	\$6,050.00	\$6,050
5	Stone Tracking Pad	2	EA	\$3,000.00	\$6,000
6	Dust Control	1	LS	\$2,900.00	\$2,900
7	Inlet Protection	4	EA	\$300.00	\$1,200
8	Silt Fence	792	LF	\$4.00	\$3,150
9	Dewatering	1	LS	\$15,000.00	\$15,000
10	Parent Material Excavation and Off-Site Disposal	12,043	CY	\$26.00	\$313,150
11	Excavation w/ On-Site Reuse as Backfill Including Compaction	7,934	CY	\$17.00	\$134,900
12	Stone Backfill (Around and To Top of Unit)	1,283	CY	\$38.50	\$49,400
13	Rock Excavation	1,635	CY	\$25.00	\$40,850
14	Stormtrap Units Incl/ Delivery, Joint Tape, and Joint Rap	1	LS	\$1,470,611.43	\$1,470,600
15	Stormtrap Units Incl/ Delivery, Joint Tape, and Joint Rap (Sales Tax)	1	LS	\$80,883.63	\$80,884
16	Subgrade (6" Thick of 1-1/4" base course)	504	CY	\$38.50	\$19,400
17	Stormtrap Unit Installation	1	LS	\$98,991.30	\$99,000
18	Geomembrane Liner	1	LS	\$73,642.84	\$73,650
19	6-IN Salvaged Topsoil Placement (from project site)	2,190	SY	\$3.50	\$7,650
20	Erosion Control Revegetative Mat	2,190	SY	\$3.00	\$6,550
21	Turf Restoration - Seed and Fertilizer	2,190	SY	\$3.00	\$6,550
22	Trees	10	EA	\$660.00	\$6,600
23	34x53-IN RCP Storm Sewer	308	LF	\$325.00	\$100,100
24	12-IN RCP Storm Sewer	67	LF	\$110.00	\$7,350
25	2'x3' Storm Sewer Inlet	4	EA	\$2,900.00	\$11,600
26	10-FT DIA Storm Sewer Manhole	1	EA	\$22,700.00	\$22,700
27	Base T Storm Sewer Manhole (Connect to Existing Storm Sewer)	1	EA	\$27,497.58	\$27,500
28	JC J-2 Connection	1	EA	\$5,000.00	\$5,000
29	Outlet Control Structure	1	EA	\$10,000.00	\$10,000
30	StormTrap Access Manhole	8	EA	\$2,182.01	\$17,450
31	Asphalt Restoration	1	LS	\$69,500	\$69,500
32	Temporary Access Road	1	LS	\$10,664.99	\$10,650
33 34	Temporary Access Road Removal	831	SY SY	\$4.00 \$9.50	\$3,300
0.	Temporary Access Road Restoration Asphalt Path Removal	831	<u> </u>	<b>\$</b> \$1.55	\$7,900 \$14,650
35	•	509	SY	\$28.79	\$14,650 \$19,300
36 37	Asphalt Path Restoration Curb and Gutter Removal	1 732	LS LF	\$19,300.00 \$5.77	\$19,300 \$4,200
37	Curb and Gutter Restoration	732	LF	\$21.24	\$4,200 \$15,550
38	Pipe Abandonment	1	LS	\$21.24	\$15,550
39	Pipe Removal	134	LF	\$33.00	\$1,000
		.0-		Subtotal Project Cost	
25% Contingency and Technical Services Allowance					
				Construction Cost	\$ 3,454,855
				Geotechnical Investigation	\$ 13,000
Notes:			l	Grand Total	\$ 3,467,855

			erana retai	• •,•••,•••
Notes: 1. This planning level opinion of probable cost is based on limited data and the assumptions, herein.	It should be refined i	n the future with site sp	ecific information.	
······································			WDNR UNPS Grant	\$150,000
		WDNR UNPS O	Grant OSG Monies (if succesful)	\$150,000
			Clean Water Fund Principal Forgiveness (50%)	
			Total Grants	\$2,033,927
		Total Project Cost	(With Grants)	\$1,433,927
	Cost Proration			
	Based on	Without Grants		% of Project Cost
	Watershed Area		With Grants	(With Grants)
City Portion	39.7%	\$1,376,738	\$569,269	16.4%
UW Portion	60.3%	\$2,091,116	\$864,658	24.9%
Grant Portion	<u>0%</u>	<u>\$0</u>	<u>\$2,033,927</u>	58.7%
Tota	100%	\$3,467,855	\$3,467,855	100.0%