


## ABNER CASTRO - ALPHA BUILD



4 CEDAR CT. WHITEWATER WI 53190

ALTHOUGH EVERY EFFORT HAS BEEN MADE IN PREPARING THESE PLANS AND CHECKING THEM FOR ACCURACY, THE CLIENT AND / OR CONTRACTORS MUST CHECK ALL DETAILS AND DIMENSIONS AND BE RESPONSIBLE FOR THE SAME. THE CLIENT AND / OR CONTRACTORS WILL ASSUME ALL RESPONSIBILITY FOR LOCAL CODE COMPLIANCE. THE DESIGNER SHALL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES OR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK.




#### GENERAL MAIN FLOOR TAGS


1 SHELF & POLE PER CONTRACT OR OWNER DIRECTION - SUPPLY BLOCKING AS REQUIRED

SMOKE DETECTORS TO BE PROVIDED AT ALL LEVELS INCLUDING BASEMENT, AND ALL BEDROOMS, DETECTORS TO BE HARDWIRED AND INTERCONNECTED WITH BATTERY BACK-

- (2) LINEN/PANTRY (4) SHELVES, AS WIDE (UP TO 24") AS ALLOWED BY CLOSET DEPTH (VIF)
- (3) KITCHEN, BATH, LAUNDRY CABINERTY LAYOUTS PROVIDED BY SUPPLIER ALL CABINET LAYOUT AND DESIGN TO BE SUPPLIED BY SUPPLIER AND TO BE SITE VERIFIED AFTER FRAMING. SPECIAL BLOCKING LOCATIONS TO BE PROVIDED BY CABINET SUPPLIER.
- 4 SPECIAL BUILT-IN CABINETRY LAYOUTS PROVIDED UNDER SEPERATE COVER OR PROVIDEI BY OWNER PRIOR TO FRAMING. ANY DETAILING PROVIDED BY DESIGNER IS A SUGGESTION ONLY AND MUST BE FINALIZED PRIOR TO ACTUAL CONSTRUCTION.
- \$\text{\left}\$ ALL DOORS BETWEEN GARAGE AREAS AND HOUSE AREAS TO HAVE MIN. 20 MIN. LABEL FOR BOTH DOOR AND FRAME..... THIS INCLUDES DOORS AT BOTTOM OF STAIRS FROM GARAGE TO BASEMENT AREAS.....
- 6) ATTIC ACCESS SCUTTLES TO BE JAMBED AND CASED. ACCESS PANELS ON INTERIOR SPACE TO ATTIC AREAS NOT ACCESSIBLE FROM GARAGE MUST BE WEATHER STRIPPED AND PANEL








MICROLLAM (LVL) DESIGN PROPERTIES:									
DESIGN VALUES SHOWN ARE FOR 100% LOAD DURATION 1 3/4" 2.0E MICROLLAM (LVL)									
ALLOMABLE DESIGN PROPERTIES	DEPTH								
	5 1/2"	7 1/4"	4 1/4°	4 1/2	11 1/4"	11 7/8	14"	16"	18"
MOMENT (FT. LBS.)	2,125	3,555	5,600	5,885	8,070	8,425	12,130	15,555	14,375
SHEAR (LBS.)	1,830	2,410	3,075	3,160	3,740	3,450	4,655	5,320	5,485
MOMENT OF INERTIA (IN4)	24	56	115	125	208	244	400	547	851
MEIGHT (LB5./LIN. FT.)	2.8	3.7	4.7	4.8	5.7	6.1	7.1	8.2	4.2

LATERAL SUPPORT OF BEAM COMPRESSION EDGE IS REQUIRED AT INTERVALS OF 24" O.C. OR CLOSER BEARING LENGTHS ARE BASED ON MICROLLAM LVL'S BEARING STRESS FOR APPLICABLE GRADE AND ORIENTATION

2.0E MICROLLAM LVL ALLOWABLE DESIGN STRESSES SHEAR MODULUS OF ELASTICITY 6 - 125,000 PSI MODULUS OF ELASTICITY E - 2.0 X 10 <sup>6</sup> PSI FLEXURAL STRESS Fb - 2,600 PSI COMPRESSION PERPENDICULAR TO FC 1 - 750 PSI GRAIN PARALLEL TO GLUE LINE COMPRESSION PARALLEL TO GRAIN FC || - 2,5 10 PSI IORIZONTAL SHEAR PERPENDICULAR FV
TO GLUE LINE

(1) FOR 12 INCH DEPTH, FOR OTHERS, MULTIPLY BY (4)
(2) FG\_ SHALL NOT BE INCREASED FOR DURATION OF LOAD.



PF - PORTAL FRAME BRACE CONSTRUCTION

#### NOTES:

- -All Dimensions Are Stud To Stud Or Stud To Centerline Of Opng. Unless Noted
- -All Headers In Load Bearing Walls Not Noted To Be (2) 2x10 HF Select. Struct.
- -All LVL Beams Shown Are RigidLam 2.0E, 3100 Fb Manufactured By Roseburg
- -Bottom Of Window Headers To Be 7'-11 3/8" Above Sub Floor, Unless Noted
- -All Windows & Sliding Pato Doors To Be Andersen 400 Series Woodright Double Hung & Awning Units w/Low-E4 w/Heatlock Coated Glass & Full Screens.
- -Gaurdrails Shall Be Constructed To Prevent The Through Passage Of A Sphere w/A Diameter Of 4 3/8" Or Larger & Shall Be Designed To Withstand A 200 LB. Load Applied In Any Direction.
- -2x6 Walls w/Pocket Door Use Flat 2x4 Studs Vs. Metal Studs To Create Door Pocket
- -Seal Openings (Air Leaks) Around Plumbing Stacks, Exhaust Fan Housing. Electrical Wires, Recessed Lights, Interior Partitions, HVAC Ducts, Attic Scuttle, Chimneys & Any Other Penitrations
- -Headers To Be Sized After Trusses Are Designed

#### ABNER CASTRO - ALPHA BUILD



Lumber and HomeWorks

Scale: AS NOTED Date: 05-02-2024

BY:Andrew Coffell VRH

#### 4 CEDAR CT. WHITEWATER WI 53190

ALTHOUGH EVERY EFFORT HAS BEEN MADE IN PREPARING THESE PLANS AND CHECKING THEM OR ACCURACY. THE CLIENT AND / OR CONTRACTORS MUST CHECK ALL DETAILS AND DIMENSI NACOUNAL, THE CLIENT AND / OR CONTRACTORS WILL ASSUME ALL RESPONSIBILITY FOR LOCAL CODE COMPLIANCE. THE DESIGNER SHALL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES OR SAFETY RECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK


#### GENERAL FOUNDATION NOTES

- BASEMENT WALLS TO BE INSUALTED PER TYPICAL BUILDING SECTION USE PROTECTIVE COVER OVER ANY EXPOSED INSULATING BOARDS
- USE A 2X6 PRESSURE TREATED SILL PLATE WITH SILL SEALER, SECURED WITH 1/2"Ø ANCHOR BOLTS (7" MIN. EMBEDMENT), 72" O.C. AND MIN. 18" FROM CORNERS. (ANCHOR STRAPS MAY BE USED IF APPROVED BY LOCAL INSPECTOR).
- ALL FOUNDATION WALLS SHALL BE POURED CONCRETE PER PLAN TAG WITH POURED CONCRETE FOOTINGS (WITH KEY OR BARS) AS FOLLOWS: 8" WALLS .... 16"x8" / 10" WALL .... 20"x10" / 12" WALLS .... 24"x12"
- ALL WALL/FOOTING HEIGHTS TO BE SITE ADJUSTED BY EXCAVATOR AND CONCRETE WALL CONTRACTOR TO PROVIDE A MINIMUM OF 48" FROST PROTECTION. BRICK LEDGES TO BE STEPPED AS GRADE REQUIRES, VERIFIRD BT GC IN FEILD...
- ALL WOOD IN CONTACT WITH CONCRETE SURFACE SHALL

AT TIME OF WALL POUR. (NAILERS TP BE PLACED MIN. 16" OC).

BE PRESSURE TREATED MATERIAL

- ALL LANDSCAPED RETAINING WALLS AND/OR TREATED WOOD NAILING STRIPS (MIN. 2x IN CONCRETE WALLS SHALL TREATED MATERIAL AND BE SITE VERIFIED BY GC
- ALL STEEL I-BEAMS AND LVL STRUCTURAL MEMBERS TO BE SIZED AND ENGINEERED BY SUPPLIER PRIOR TO INSTALLATION.
  STRUCTURAL ENGINEERING MAY BE OBTAINED UNDER SEPERATE COVER
- ALL TJI JOISTS OR RAFTERS TO BE SIZED AND ENGINEERED PER MANUFACTURER'S REQUIREMENTS. INSTALLATION TO BE VERIFIED BY MANUFACTURER SYSTEM
  REQUIREMENTS AND VERIFIED BY GC AND SUPPLIER PRIOR TO START OF CONSTRUCT



**FOUNDATION PLAN** SCALE: 1/8" = 1'-0"

### ABNER CASTRO - ALPHA BUILD





Lumber and HomeWorks

Scale: AS NOTED Date: 05-02-2024 BY: Andrew Coffell VRH


4 CEDAR CT. WHITEWATER WI 53190

ALTHOUGH EVERY EFFORT HAS BEEN MADE IN PREPARING THESE PLANS AND CHECKING THEM FOR ACCURACY, THE CLIENT AND / OR CONTRACTORS MUST CHECK ALL DETAILS AND DIMENSIONS AND BE RESPONSIBLE FOR THE SAME. THE CLIENT AND / OR CONTRACTORS WILL ASSUME ALL RESPONSIBILITY FOR LOCAL CODE COMPLIANCE. THE DESIGNER SHALL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES OR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK.





PARTY WALL SECTION
Scale: 1/2" = 1'-0"




# TYPICAL WALL SECTION (#1) Scale: 1/2" = 1'-0"

#### ABNER CASTRO - ALPHA BUILD



### 4 CEDAR CT. WHITEWATER WI 53190

ALTHOUGH EVERY EFFORT HAS BEEN MADE IN PREPARING THESE PLANS AND CHECKING THEM FOR ACCURACY, THE CLIENT AND / OR CONTRACTORS MUST CHECK ALL DETAILS AND DIMENSIONS AND BE RESPONSIBLE FOR THE SAME. THE CLIENT AND / OR CONTRACTORS WILL ASSUME ALL RESPONSIBILITY FOR LOCAL CODE COMPLIANCE. THE DESIGNER SHALL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES OR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK.



# ABNER CASTRO - ALPHA BUILD



ALTHOUGH EVERY EFFORT HAS BEEN MADE IN PREPARING THESE PLANS AND CHECKING THEM FOR ACCURACY, THE CLIENT AND / OR CONTRACTORS MUST CHECK ALL DETAILS AND DIMENSIONS AND BE RESPONSIBLE FOR THE SAME. THE CLIENT AND / OR CONTRACTORS WILL ASSUME ALL RESPONSIBILITY FOR LOCAL CODE COMPLIANCE. THE DESIGNER SHALL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, PROCEDURES OR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK.