

Thomas Fence Co. Inc.

5515 Woodman Ave. ♦ P.O. Box 487

Ashtabula, Ohio 44005-0487

(440) 998-4747 Ash. (440) 942-8548 Lake

(814) 835-0707 Erie, PA. (440) 992-2950 Fax

Quotation Page 1 of 1

July 31, 2025

City of Willowick
Mr. Terry McCarthy

Project: Building Department

Scope of Work:

Remove and dispose of 108' of existing 8' high wood board on board fence behind the building department.

Installation of 108' of 8' high all Black chain link fence system with Black Winged slats.

Specifications:

Chain link Fabric:	8' high 9ga. core thermally fused and bonded vinyl coated - 2" mesh - Knuckle/ Knuckle
	All framework will be Powder Coated Black
Terminal posts:	3" O.D. PC. 40, set in 12" x 48" cement footings.
Line posts:	3" O.D. PC. 40, set in 12" x 48" cement footings.
Special post spacing:	Line posts will be spaced no more than 8' apart.
Top rail:	1 5/8" O.D. PC. 40
Middle rail:	1 5/8" O.D. PC. 40
Bottom Tension wire:	7ga. core vinyl coated
Hardware:	All hardware will be vinyl coated

Total Material & Labor\$ 15,000.00

Quote based on the quantities and specifications listed above.

Labor: Non prevailing wage

Project Quoted Tax Exempt

All utilities not marked by OUPS to be located by owner / GC

Layout, staking, grading & clearing by others

Quote is based on standard digging conditions setting posts through dirt; core drilling, rock digging or drilling through asphalt is not included.

HydroVac excavation is not included in this quote and would be an extra charge if needed.

All dirt spoils will be stockpiled on site as directed by owner / GC.

Permits by owner / GC

All pricing is current per. the date of this quotation – pricing is subject to change with market conditions.

Thank You!

Glenn Thomas