

BROADWAY EXCAVATING

27111 Wolf Rd. Bay Village, 44140

December 24, 2020

Repair 7' diameter storm sewer @ 441 Fairway.

Broadway excavating will supply all labor, equipment, material and supervision for:

Item#1: Traffic control and excavation protection (snow fence).

Item#2: Protect existing waterline and storm and sanitary connections.

Item#3: Excavate existing storm sewer to below springline and realign pipe.

Item#4: Pour concrete collars on both ends of pipe class C concrete using anchor bolt into shale walls- vibrated into voids.

Item#5: Vibrate LSM 100 into voids under and over existing 7' storm hookbolts on 1' center length of excavation.

Item#6: Backfill trench with approved material.

Item#7: Replace Storm and sanitary connections exsiting.

Item#8: Replace affected concrete and landscape.

Total cost: \$45,000.00

Terry Fiala President

216-396-9565