#### EXHIBIT A

#### LP22-0001 Wastewater Treatment Plant Master Plan Planning Commission Public Hearing Record Index FINAL (December 13, 2023)

#### PLANNING COMMISSION AND CITY COUNCIL MEETINGS

- December 13, 2023 Planning Commission Public Hearing Resolution LP22-0001 Staff Report and Attachments Presentation Affidavit of Notice of Hearing
- November 6, 2023 City Council Work Session Staff Report and Attachments Presentation Action Minutes
- October 11, 2023 Planning Commission Work Session Staff Report and Attachments Presentation Minutes Excerpt
- October 12, 2022 Planning Commission Public Hearing Cancelled Cancellation Memo Minutes Excerpt
- September 14, 2022 Planning Commission Work Session Staff Report and Attachments Presentation Minutes Excerpt
- August 1, 2022 City Council Work Session Staff Report and Attachments Presentation Action Minutes
- July 13, 2022 Planning Commission Work Session Staff Report and Attachments Presentation Minutes Excerpt

#### PUBLIC ENGAGEMENT

Project Website: https://www.letstalkwilsonville.com/wastewater-treatment-plant-master-plan

Open House - September 28, 2022: <u>https://www.ci.wilsonville.or.us/engineering/page/public-open-house-waste-water-treatment-plant-master-plan</u>

#### LP22-0001 Wastewater Treatment Plant Master Plan Planning Commission Public Hearing Record Index FINAL (December 13, 2023)

#### **COMMENTS/ARTICLES**

Boones Ferry Messenger – September

Spokesman Article for Original Public Hearing notification and cancellation

Emailed Comment 10/2/2022 – Thomas Hooker



## PLANNING COMMISSION WEDNESDAY, DECEMBER 13, 2023

#### PUBLIC HEARING

2. Wastewater Treatment Plant Master Plan (Nacrelli) (30 minutes)

#### PLANNING COMMISSION RESOLUTION NO. LP22-0001

#### A RESOLUTION OF THE CITY OF WILSONVILLE PLANNING COMMISSION RECOMMENDING THE WILSONVILLE CITY COUNCIL ADOPT AN UPDATE TO THE WASTEWATER TREATMENT PLANT MASTER PLAN.

WHEREAS, the City of Wilsonville Wastewater Treatment Plant was last upgraded in 2014, pursuant to Resolution No. 2131; and

WHEREAS, the Capital Improvement Program identified the completion of a Wastewater Treatment Plant Master Plan ("Plan") for FY 2023-24; and

WHEREAS, the Plan provides a detailed framework for expanding treatment process capacity to accommodate future development, comply with environmental regulations, and replace aging assets; and

WHEREAS, the concepts and information contained in the proposed update to the Wastewater Treatment Plant Master Plan were presented at a virtual public meeting on September 28, 2022; and

WHEREAS, the Planning Commission of the City has the authority to review and make recommendations to the City Council regarding the Capital Improvement Program pursuant to Wilsonville Code Sections 2.322 and 4.032; and

WHEREAS, the Planning Commission conducted work sessions on the draft Plan at their regular meetings of July 13 and September 14, 2022 and October 11, 2023; and

WHEREAS, the Planning Commission, after Public Hearing Notices were mailed to property owners within the City limits and a list of interested citizens and agencies, and were posted in three locations throughout the City and on the City website, held a Public Hearing on December 13, 2023, to review the Plan and to gather additional testimony and evidence regarding the proposed Master Plan update in accordance with the public hearing and notice procedures that are set forth in Sections 4.008, 4.010, 4.011 and 4.012 of the Wilsonville Code (WC); and

#### **RESOLUTION NO. LP22-0001**

WHEREAS, the Planning Commission has afforded all interested parties an opportunity to be heard on this subject and has entered all available evidence and testimony into the public record of their proceeding; and

WHEREAS, the Planning Commission has duly considered the subject, including the staff recommendations and all the exhibits and testimony introduced and offered by all interested parties.

NOW, THEREFORE, THE CITY OF WILSONVILLE PLANNING COMMISSION RESOLVES AS FOLLOWS:

- Section 1. The Wilsonville Planning Commission does hereby adopt the Planning Staff Report (attached hereto as Exhibit A) and Attachments, as presented at the December 13, 2023, public hearing, including the conclusionary findings and recommendations contained therein.
- Section 2. The Planning Commission does hereby recommend that the Wilsonville City Council adopt the proposed Wastewater Treatment Plant Master Plan, attached as Exhibit B.
- Section 3. Effective Date. This Resolution is effective upon adoption.

ADOPTED by the Wilsonville Planning Commission at a regular meeting thereof this 13th day of December, 2023, and filed with the Planning Administrative Assistant on this date.

Wilsonville Planning Commission

ATTEST:

Mandi Simmons, Administrative Assistant III

**RESOLUTION NO. LP22-0001** 

SUMMARY OF VOTES:

Ronald Heberlein, Chair	Yes
Jennifer Willard, Vice-Chair	Yes
Nicole Hendrix	<u>Yes</u>
Andrew Karr	<u>Yes</u>
Kamran Mesbah	Ves
Kathryn Neil	<u>Yes</u>

EXHIBITS:

A. Staff Report and Attachments



#### PLANNING COMMISSION

#### STAFF REPORT

Meeting Date: December 13, 2023 Subj			Sub	j <b>ect:</b> Wastewater Tr	eatment Plant Master Plan
		Staff Member: Mike Nacrelli, Senior Civil Engineer			
		Department: Community Development			
Act	ion Required		Advisory Board/Commission Recommendation		
$\boxtimes$	Motion			Approval	
$\boxtimes$	Public Hearing Date: 12/13/2023			Denial	
	Ordinance 1 <sup>st</sup> Reading Date	e:		None Forwarded	
	Ordinance 2 <sup>nd</sup> Reading Date	e:	$\boxtimes$	Not Applicable	
$\boxtimes$	Resolution		Com	nments: N/A	
	Information or Direction				
	Information Only				
	Council Direction				
	Consent Agenda				
Staff Recommendation: A motion to approve a recommendation to the City Council adopting					
the Wastewater Treatment Plant Master Plan					
Recommended Language for Motion: I move to approve Resolution LP22-0001					
	ommending approval of the	Waste	water	<sup>-</sup> Treatment Plant M	aster Plan
Project / Issue Relates To:					
⊠Council Goals/Priorities: □Ado		pted	Master Plan(s):	□Not Applicable	
Strategy 1. Develop an					
Infrastructure resilience plan					
	reprioritize / fund				
reco	ommended projects.				

#### ISSUE BEFORE PLANNING COMMISSION:

The City of Wilsonville is completing a Wastewater Treatment Plant Master Plan to accommodate anticipated development within the City, replace aging assets, and comply with regulatory requirements. The Plan requires a formal adoption process that includes a hearing

before the Planning Commission, a recommendation from the Planning Commission to the City Council, and adoption by the City Council.

#### **EXECUTIVE SUMMARY:**

This new City of Wilsonville (City) Wastewater Treatment Plant (WWTP) Master Plan (the Plan) has been developed to satisfy requirements associated with the State of Oregon Department of Environmental Quality (DEQ) guidance document entitled "Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities." To accommodate future Wilsonville flows and loads, projections were developed based on population projections and referencing WWTP historical data and DEQ wet weather project methodologies. Similarly, to accommodate future regulatory changes.

The City prepared the Plan with the goal of developing a capital plan that identifies improvements required through the planning period (today through 2045) to comply with requirements of the WWTP National Pollutant Discharge Elimination System (NPDES) permit and potential future regulatory requirements, while accommodating growth identified in the City of Wilsonville Comprehensive Plan (October 2018, updated June 2020 - the 2018 Comprehensive Plan). These improvements are designed to provide the best value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development, consistent with goals and policies contained in the 2018 Comprehensive Plan and 2021-2023 City Council Goals.

The City's WWTP was originally built in 1971 and discharges treated effluent to the Willamette River. The WWTP underwent major upgrades in 2014 to expand the average dry weather capacity to four million gallons per day (mgd) to accommodate the City's continued growth. The WWTP processes include headworks screening and grit removal facilities, aeration basins, stabilization basins, secondary clarifiers, biosolids processing, cloth filtration, and disinfection processes. Additionally, the City contracts with Jacobs for operation of the wastewater treatment plant, located at 9275 Southwest Tauchman Road.

This Plan identifies needed capital improvements within the planning period, taking into consideration:

- The age and condition of existing process equipment and structures,
- Growth in demand for sewer service due to increased population and economic development over the planning period,
- Potential changes to water quality regulations impacting process needs in order to meet effluent limitations and discharge prohibitions imposed by the DEQ, and
- Consistency with the 2018 Comprehensive Plan and City Council 2023-2025 Strategy 1.

#### WWTP Condition Assessment

Carollo reviewed prior condition assessments performed by others, conducted geotechnical investigations and performed seismic assessments at the WWTP in the course of Plan development.

In 2019, Jacobs Engineering Group Inc. (Jacobs) and Brown and Caldwell both completed condition assessments at the City's WWTP. A total of 322 major assets (per Jacobs' report), including process and mechanical equipment, motors and drives, control panels, generators, instrumentation, and structures, were examined for a variety of conditions that may signify their need for maintenance or replacement.

#### Seismic Analysis

In 2021, Carollo performed a seismic evaluation and analysis of the City's WWTP as part of the overall plant condition assessment. Because the WWTP was substantially upgraded and expanded in 2014, most of its infrastructure is designed in accordance with the 2010 Oregon Structural Specialty Code (OSSC) and follows modern seismic design and detailing. During Tier 1 evaluations, Carollo identified potential deficiencies and areas for additional investigation. A Tier 1 seismic analysis is an initial evaluation performed to identify any potential deficiencies, whether structural or non-structural, in a building based on the performance of other similar buildings in past earthquakes. Subsequent to the Tier 1 analysis, a more detailed seismic evaluation of five older and potentially seismically vulnerable structures on the WWTP site was conducted. Those structures receiving a more detailed evaluation included the following:

- Operations Building
- Process Gallery
- Workshop
- Aeration Basins and Stabilization Basins
- Sludge Storage Basins and Biofilter

The five potentially vulnerable structures were compared against an S-4 Limited Safety structural performance level and N-B Position Retention non-structural performance level for an M9.0 Cascadia Seismic Zone (CSZ) earthquake. The M9.0 CSZ is reflective of a catastrophic natural disaster event that has an estimated 35 percent likelihood of occurring within the next 50 years. Following the Tier 1 evaluation, Carollo began Tier 2 evaluations for a select number of identified deficiencies. Although none of the structures showed significant irregularities, the team did identify seismic deficiencies. The recommended seismic retrofits are included in the CIP for the Plan.

Prior to the 2021 seismic evaluation, Carollo's subconsultant, Northwest Geotech, Inc. (NGI), completed a seismic response and geologic hazards assessment of the City's WWTP. Through past and present site investigations and engineering analyses, NGI determined that the native soils beneath the site's granular pit backfill have low risk of liquefaction and its slopes do not pose undue risk. NGI concluded that the WWTP's primary site hazard is the differential settlement that may be caused by soil piping (development of subsurface air-filled voids), which raises the risk of sinkholes forming beneath structures and pipelines. Soil piping usually develops in unsaturated soils when a water source percolates into the ground. While the site is mostly paved and stormwater is being collected, there may be areas where infiltration is occurring next to structures or below pipelines. Recommended actions from NGI to mitigate the risk of soil piping are presented in the Plan.

#### Wastewater Flow and Load Projections

The Plan evaluates the historical and projected wastewater flows and loads generated in the City of Wilsonville's service area. The load projections include total suspended solids (TSS), biochemical oxygen demand (BOD5), ammonia (NH3), and total phosphorous (TP) loads.

Service area, residential population, industrial contribution, and rainfall records were all considered in the flow and load projection analyses.

#### **Capacity Analysis**

Summaries of plant process area capacity assessments and conclusions are presented in the Plan. These assessments focus on the need for improvements or upgrades to existing facilities to address capacity deficiencies identified in the course of Master Plan evaluations.

#### **Regulatory Considerations and Strategy**

Several possible regulatory actions by the Oregon DEQ could drive investments in future improvements at the City's WWTP. The plant discharges to the Willamette River and existing and future effluent limitations contained in the NPDES permit dictate, in large part, the necessary treatment processes and configuration at the WWTP necessary to maintain compliance. The existing permit limits for the Wilsonville WWTP are effective September 1, 2020 through July 30, 2025.

#### Alternative Development and Evaluation

The Plan presents the methodology and findings of a process improvements alternatives evaluation. The plant's treatment process needs were defined by comparing the plant's existing condition, capacity and reliability, with the projected flows, loads, and regulatory constraints for the recommended alternatives. Where capacity deficiencies were predicted, at least two alternatives were analyzed for each corresponding unit process.

Project Description	Timeframe	Cost*		
Dewatering Performance Optimization	2025	\$150,000		
Fiber Optic Conduit Addition	2025	\$60,000		
UV System Improvement	2026	\$1,705,000		
Seismic Improvements	2026	\$1,082,000		
Geotechnical Foundation Mitigation	2026	\$2,000,000		
New Aeration Basin and Blower	2025 – 2027	\$10,222,000		
Replace Secondary Clarifier Mechanisms	2026 - 2027	\$1,775,000		
Membrane Bioreactor (MBR) Phase 1 (includes new blower, fine screens, electrical and hydraulic upgrades)	2028 – 2031	\$69,727,000		
New Solids Dryer	2031 – 2033	\$17,130,000		
Thickening and Dewatering Improvements	2031 – 2033	\$3,701,000		
New Cooling Tower	2035 – 2036	\$642,000		
MBR Phase 2 (includes new blower)	2037 – 2039	\$2,330,000		
UV Equipment Replacement and Outfall Upsizing	2039 – 2040	\$2,571,000		
UV Equipment Replacement and Outfall Upsizing	2039 – 2040	\$1,244,000		
MBR Phase 3 (includes 2 new blowers)	2042 - 2044	\$8,117,000		
Total \$122,456,00				
*Costs are shown in 2023 dollars and include 25% for engineering, legal, and administration.				

The most significant impact to the required level of capital investment is the need for membrane bioreactor (MBR) facilities. These are state-of-the-art, compact facilities that provide a high level of treatment. Due to the limited amount of space available at the existing WWTP site, MBR facilities are the only feasible means of providing the necessary treatment to accommodate build out of the Wilsonville urban reserve areas.

#### **EXPECTED RESULTS**:

The Plan includes a list of recommended capital improvements, along with an anticipated schedule for completion and preliminary cost estimates. The total estimated amount of capital investment over the planning period is approximately \$122 million, of which \$17 million is anticipated in the next 5 years. The recommended capital improvements will provide the basis for an analysis of sewer rates and system development charges (SDCs) that are necessary to adequately fund the upgrades needed to meet the projected growth.

#### TIMELINE:

A public hearing before City Council for the Plan adoption is anticipated in January 4, 2024, with a second reading on January 18, 2024.

#### **CURRENT YEAR BUDGET IMPACTS:**

The amended FY24 Budget for CIP #2104, Wastewater Treatment Plant Master Plan, includes \$130,000 in sewer operations and system development charge funds. The remaining budget is sufficient to complete the remaining work to update and adopt the Plan.

#### COMMUNITY INVOLVEMENT PROCESS:

A virtual town hall meeting to present the findings of the Plan and solicit public input was held in September 2022 and posted on the City's online calendar and Let's Talk Wilsonville page, where a project overview and periodic updates to the Executive Summary have also been posted. In addition, draft versions of the Executive Summary have been sent to the ten largest industrial customers for review and comment. The public hearings listed above will provide further opportunity for public input. The forthcoming Sewer System Rate Study and SDC Update will also include a public engagement process with outreach to utility customers and the development community.

#### POTENTIAL IMPACTS or BENEFIT TO THE COMMUNITY:

A technically and financially sound plan for providing reliable wastewater treatment, capacity to accommodate future development, and compliance with environmental regulations.

#### ALTERNATIVES:

The project team considered and evaluated numerous technologies and alternatives to provide the needed wastewater treatment plant capacity to meet future demands and recommend a capital improvement program that implements the needed improvements in a way that is efficient and cost effective.

#### ATTACHMENTS:

- 1. Wastewater Treatment Plant Master Plan (dated December 2023)
- 2. Wastewater Treatment Plant Master Plan Appendices (dated December 2023)
- 3. Conclusionary Findings
- 4. Master Plan Record (electronic only)

WWTP Master Plan attached separately

### The Wastewater Treatment Plant Master Plan (LP22-0001) Appendices can be found at this link:

https://www.ci.wilsonville.or.us/commdev/page/wastewater-treatment-plant-master-plan

#### **CONCLUSIONARY FINDINGS**

The updated Wastewater Treatment Plant Master Plan has been found to be consistent with the applicable criteria as follows.

#### COMPREHENSIVE PLAN COMPLIANCE

#### Standards for Approval of Plan Amendments

In order to grant a Plan amendment, the City Council shall after considering the recommendation of the Development Review Board (quasi-judicial) or Planning Commission (legislative), find that:

#### a. Conformance with Other Portions of the Comprehensive Plan

CP1. <u>**Review Criteria**</u>: "The proposed amendment is in conformance with those portions of the Plan that are not being considered for amendment."

**Finding:** These criteria are satisfied.

**Explanation of Finding:** The proposed updated Wastewater Treatment Plant Master Plan has been found to be in conformance with the Comprehensive Plan. See Findings CP2 through CP30 below.

#### b. Amendment is in the Public Interest

CP2. <u>**Review Criterion**</u>: "The granting of the amendment is in the public interest." **Finding:** This criterion is satisfied.

**Explanation of Finding:** Development Code Subsection 4.198 (.01) A. implements this standard. It is in the public interest to periodically update the master plans for critical public facilities such as the wastewater treatment plant to ensure the system provides for adequate service for current and future residents and businesses to ensure proper treatment of wastewater.

#### c. Public Interest and Timing of Amendment

CP3. **<u>Review Criterion</u>**: "The public interest is best served by granting the amendment at this time."

**Finding:** This criterion is satisfied.

**Explanation of Finding:** Facility master plans such as the wastewater treatment plant must be updated periodically to provide updated current condition information and use updated data to forecast future needs. The last update to the Wastewater Treatment Plant Master Plan was in 2004, so the public interest is best served by updating the master plan as soon as possible making the current timing appropriate.

#### d. Adequately Addressing Specific Factors

CP4. <u>**Review Criteria**</u>: "The following factors have been adequately addressed in the proposed amendment: the suitability of the various areas for particular land uses and improvements; the land uses and improvements in the area; trends in land improvement; density of development; property values; the needs of economic enterprises in the future development of the area; transportation access; natural resources; and the public need for healthful, safe and aesthetic surroundings and conditions."

Finding: These criteria are satisfied.

#### **Explanation of Finding:**

Suitability of the Various Areas for Particular Land Uses and Improvements: The plan only considers serving areas otherwise acknowledged as future growth areas. The plan includes analysis of the current location and how to best expand within the limited footprint.

Land Uses and Improvements in the Area: The updated Wastewater Treatment Plant Master Plan considers the current land uses throughout the city as well as potential land uses in future growth areas.

*Trends in Land Improvement:* The amended Wastewater Treatment Plant Master Plan supports the trends identified in other master plans and studies.

*Density of Development:* The updated Wastewater Treatment Plant Master Plan considers planned densities throughout the City and growth areas over the planning horizon.

*Property Values:* Planning for an adequate wastewater treatment plant helps enable a functional system long term which supports sanitation. Lack of proper sanitation and ability to properly dispose of wastewater would negatively affect property values.

The Needs of Economic Enterprises in the Future Development of the Area: Planning for an adequate wastewater treatment plant helps support economic enterprise in areas planned for business growth by planning adequate capacity and service.

*Transportation Access:* No transportation access is impacted by the plan.

*Natural Resources:* The updated Wastewater Treatment Plant Master Plan doesn't specifically address how facility siting will affect natural resources. However, the improvements will be within a confined previously disturbed area and the City has regulations in place to look at conservation of resources during the design and final siting of future improvements.

Public Need for Healthful, Safe and Aesthetic Surroundings and Conditions: Functional and sanitary treatment of wastewater, which is the aim of the updated Wastewater Treatment Plant Master Plan, supports healthful, safe, and aesthetic surroundings by

preventing unsanitary or environmentally detrimental disposal or treatment of wastewater.

#### e. Conflict with Metro Requirements

CP5. <u>Review Criteria</u>: "Proposed changes or amendments to the Comprehensive Plan do not result in conflicts with applicable Metro requirements." <u>Finding</u>: These criteria are satisfied. <u>Explanation of Finding</u>: No conflicts with Metro requirements have been identified.

#### <u>Citizen Involvement</u>

Goal 1.1: To encourage and provide means for interested parties to be involved in land use planning processes, on individual cases and City-wide programs and policies.

#### Policy 1.1.1: Wide Range of Public Involvement

CP6. <u>Review Criterion</u>: "The City of Wilsonville shall provide opportunities for a wide range of public involvement in City planning programs and processes." **Finding:** This criterion is satisfied.

**Explanation of Finding:** A number of different media and venues have been used to encourage public involvement. Wastewater treatment tends to be a subject in which the community does not express a lot of interest as long as the system is functioning well. While a reasonable effort has been made to notify and solicit community involvement, limited interest has been expressed. Information was published in the Boones Ferry Messenger, a community newsletter mailed to every address within Wilsonville's 97070 zip code, the Planning Commission held work sessions, and project staff made information about the project available on the City's website. Required public noticing for for the Planning Commission and upcoming City Council public hearings has occurred.

#### Implementation Measure 1.1.1.a. Early Public Involvement

CP7. <u>**Review Criterion**</u>: "Provide for early public involvement to address neighborhood or community concerns regarding Comprehensive Plan and Development Code changes. Whenever practical to do so, City staff will provide information for public review while it is still in "draft" form, thereby allowing for community involvement before decisions have been made."

#### Finding: This criterion is satisfied.

**Explanation of Finding:** The City solicited feedback from the Planning Commission and public early in the planning process while the plan was still in draft form. Any feedback has been considered in preparation of the plan.

#### Goal 1.2: For Wilsonville to have an interested, informed, and involved citizenry.

#### Policy 1.2.1: User Friendly Information

CP8. <u>**Review Criterion**</u>: "The City of Wilsonville shall provide user-friendly information to assist the public in participating in the City planning programs and processes." <u>**Finding**</u>: This criterion is satisfied.

**Explanation of Finding:** The City has produced user-friendly notices for the project, as well as provided other information, and opportunities, both in person and online, to examine the materials related to the updated Wastewater Treatment Plant Master Plan.

### Implementation Measures 1.2.1.a.-c. Clarification, Publicity, and Procedures for Public Involvement

CP9. <u>**Review Criteria**</u>: These measures address the City's responsibility to help clarify the public participation process, publicize ways to participate, and establish procedures to allow reasonable access to information.

**Finding:** These criteria are satisfied.

**Explanation of Finding:** The City has produced user-friendly notices for the project, as well as provided other information, and opportunities, both in person and online, to examine the materials related to the updated Wastewater Treatment Plant Master Plan.

### Policy 1.3.1. Implementation Measures 1.3.1.b. Clarification, Publicity, and Procedures for Public Involvement

CP10. <u>Review Criteria</u>: "The City of Wilsonville shall coordinate with other agencies and organizations involved with Wilsonville's planning programs and policies." "Where appropriate, the City shall continue to coordinate its planning activities with affected public agencies and private utilities. Draft documents will be distributed to such agencies and utilities and their comments shall be considered and kept on file by the City." <u>Finding</u>: These criteria are satisfied.

**Explanation of Finding:** The appropriate agencies have been notified through the DLCD notice and/or the Public Hearing Notice. Any comments will be entered into the public hearing record and be considered.

#### Urban Growth Management

Goal 2.1: To allow for urban growth while maintaining community livability, consistent with the economics of development, City administration, and the provision of public facilities and services.

### Implementation Measure 2.1.1.d. Establish and Maintain Revenue Sources for Public Services and Facilities

CP11. <u>**Review Criterion**</u>: "Establish and maintain revenue sources to support the City's policies for urbanization and maintain needed public services and facilities."

**Finding:** This criterion is satisfied.

**Explanation of Finding:** While the scope of the Wastewater Treatment Plant Master Plan includes prioritizing short-term and long-term projects for the Capital Improvement Program and developing budget level cost estimates, the update does not evaluate funding tools. The City is examining and will continue to examine revenue sources to support the CIP.

#### Implementation Measure 2.1.1.e. Concurrency of Facilities and New Development

CP12. **<u>Review Criterion</u>**: "Allow new development to proceed concurrently with the availability of adequate public services and facilities as specified in Public Facilities and Services Section (Section C) of the Comprehensive Plan."

**Finding:** This criterion is satisfied.

**Explanation of Finding:** The City's current policies supporting concurrency of public services and facilities with new development are not altered by the proposed update to the Wastewater Treatment Plant Master Plan.

#### Policy 2.2.1. Plan for Urbanization

CP13. <u>**Review Criterion**</u>: "The City of Wilsonville shall plan for the eventual urbanization of land within the local planning area, beginning with land within the Urban Growth Boundary." <u>Finding</u>: This criterion is satisfied.

**Explanation of Finding:** By updating the plan for wastewater treatment infrastructure, including ensuring adequate capacity and service to land within the Urban Growth Boundary and Urban Reserves around the City, the City is supporting the effort to plan for the eventual urbanization of these areas.

#### Implementation Measure 2.2.1.b. Fair Share to Increase Development Capacity

CP14. <u>**Review Criterion:**</u> "The City of Wilsonville, to the best of its ability based on infrastructure provided at the local, regional, and state levels, shall do its fair share to increase the development capacity of land within the Metro UGB."

Finding: This criterion is satisfied.

**Explanation of Finding:** By updating the plan for wastewater treatment infrastructure, including ensuring adequate capacity and service for planned densities, the City is supporting the effort to provide for its fair share of development within the UGB.

#### Implementation Measure 2.2.1.g. Urban Services to Not be Extended Outside City Limits

- CP15. <u>**Review Criterion**</u>: "Urban sanitary sewer and water service shall not be extended outside the City limits, with the following exceptions:
  - 1. Where an immediate demonstrable threat to the public health exists, as a direct result of the lack of the service in question;
  - 2. Where a Governmental agency is providing a vital service to the City; or

Where it is reasonable to assume that the subject area will be annexed to the City within a reasonable period of time."

**Finding:** This criterion is satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan does not allow for or encourage provision of City services outside City limits.

#### **Public Facilities and Services**

Goal 3.1 To assure that good quality public facilities and services are available with adequate, but not excessive, capacity to meet community needs, while also assuring that growth does not exceed the community's commitment to provide adequate facilities and services.

#### Policy 3.1.1. The City to Provide Public Facilities

CP16. <u>Review Criterion</u>: "The City of Wilsonville shall provide public facilities to enhance the health, safety, educational, and recreational aspects of urban living." <u>Finding</u>: This criterion is satisfied.

**Explanation of Finding:** By updating the plan for wastewater treatment infrastructure, including ensuring adequate capacity for land within the Urban Growth Boundary and Urban Reserves around the City, the City is supporting the effort to continue to provide for all aspects of urban living affected by wastewater treatment.

#### Implementation Measure 3.1.1.a. City to Prepare and Implement Facility/Services Master Plans

CP17. <u>Review Criterion</u>: "The City will continue to prepare and implement master plans for facilities/services, as sub-elements of the City's Comprehensive Plan. Facilities/services will be designed and constructed to help implement the City's Comprehensive Plan." <u>Finding</u>: This criterion is satisfied.

**Explanation of Finding:** The City is continuing the practice to prepare and implement facility/services master plans as sub-elements of the Comprehensive Plan by updating the 19-year-old Wastewater Treatment Plant Master Plan.

#### Implementation Measure 3.1.1.d. City to Review Development Densities and Facilities/Services Capacity

CP18. <u>Review Criterion</u>: "The City shall periodically review and, where necessary, update its development densities indicated in the land use element of the Plan, based on the capacity of existing or planned services and/or facilities." **Finding:** This criterion is satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan incorporates the most up to date growth forecast information to plan enough capacity for the expected growth; it has not identified any areas where planned development densities need to be adjusted based on the capacity to serve with the waste water treatment plant.

#### Policy 3.1.2. Concurrency

CP19. <u>Review Criterion</u>: "The City of Wilsonville shall provide, or coordinate the provision of, facilities and services concurrent with need (created by new development, redevelopment, or upgrades of aging infrastructure)." Finding: This criterion is satisfied.

**Explanation of Finding:** By updating the Wastewater Treatment Plant Master Plan the City is coordinating its efforts over the planning horizon to provide wastewater treatment facilities and services concurrent with need, whether it involves new development, redevelopment, or upgrading aging infrastructure.

#### Implementation Measure 3.1.2.a. Urban Development only in Serviceable Areas

CP20. <u>**Review Criterion:**</u> "Urban development will be allowed only in areas where necessary facilities and services can be provided."

Finding: This criterion is satisfied.

**Explanation of Finding:** In addition to analyzing the condition of existing infrastructure the updated Wastewater Treatment Plant Master Plan identifies deficiencies and needed improvements to serve areas expected to develop. The City will continue to follow concurrency policies for public facilities and development and thus allow development only in areas were wastewater treatment services can be provided.

#### Policy 3.1.3. Payment for and Benefits from Facilities and Services

CP21. <u>**Review Criterion**</u>: "The City of Wilsonville shall take steps to assure that the parties causing a need for expanded facilities and services or those benefiting from such facilities and services, pay for them."

**Finding:** This criterion is satisfied.

**Explanation of Finding:** The City's current practices to require parties causing a need for expanded facilities pay for them are not changed by the scope of the updated Wastewater Treatment Plant Master Plan.

#### Implementation Measure 3.1.3.a. Developers and SDC's

CP22. <u>Review Criterion</u>: "Developers will continue to be required to pay for demands placed on public facilities/services that are directly related to their developments. The City may establish and collect systems development charges (SDCs) for any or all public facilities/services, as allowed by law. An individual exception to this standard may be justified, or SDC credits given, when a proposed development is found to result in public benefits that warrant public investment to support the development."

Finding: This criterion is satisfied.

**Explanation of Finding:** The City's current SDC practices are not affected by the updated Wastewater Treatment Plant Master Plan.

#### Implementation Measure 3.1.3.b. Capital Improvement Program

CP23. <u>**Review Criterion**</u>: "The City will continue to prepare and implement a rolling five- year Capital Improvement Program, with annual funding decisions made as part of the municipal budget process."

**Finding:** This criterion is satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan is part of the City's continuing effort to prepare and implement a rolling five-year Capital Improvement Program by prioritizing short-term and long-term wastewater treatment plant projects for the CIP.

#### Implementation Measure 3.1.3.c. Pay-back Agreements

CP24. <u>**Review Criterion**</u>: "The City shall continue to employ pay-back agreements, development agreements, and other creative solutions for facilities that are over-sized or extended from off-site at the expense of only some of the benefited properties." **Finding:** This criterion is satisfied.

Finding: This criterion is satisfied.

**Explanation of Finding:** The City's policies towards and use of pay-back agreements, development agreements, and other creative infrastructure financing solutions are not affected by the updated Wastewater Treatment Plant Master Plan.

#### Policy 3.1.4. City Operations of Sanitary System to Standards

CP25. <u>**Review Criterion**</u>: "The City of Wilsonville shall continue to operate and maintain the wastewater treatment plant and system in conformance with federal, state, and regional water quality standards."

**Finding:** This criterion is satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan will continue to allow the wastewater system to operate to applicable standards.

### Implementation Measure 3.1.4.a. City to Maintain Sewer Service Monitoring and Expansion Program

CP26. <u>Review Criterion</u>: "The City shall continue to maintain a sewer service capacity monitoring and expansion program to assure that adequate treatment and trunk main capacity is available to serve continued development, consistent with the City's urban growth policies and the concurrency standards noted above." Finding: This criterion is satisfied.

**Explanation of Finding:** By updating the plan for wastewater treatment infrastructure, including ensuring adequate capacity and service to land within the Urban Growth Boundary and Urban Reserves around the City, the City is supporting this implementation measure.

#### Implementation Measures 3.1.4.b. Sanitary Sewer Capacity

CP27. <u>**Review Criteria:**</u> "The City shall continue to manage growth consistent with the capacity of sanitary sewer facilities."

**Finding:** These criteria are satisfied.

**Explanation of Finding:** An updated Wastewater Treatment Plant Master Plan will enable the City to better manage growth consistent with the capacity of the wastewater treatment plant by identifying needed upgrades to current infrastructure as well as infrastructure needed for growth in different planned growth areas.

#### Implementation Measure 3.1.4.e. All Urban Development Served by Sanitary Sewer

CP28. <u>**Review Criterion**</u>: "The City shall continue to require all urban level development to be served by the City's sanitary sewer system."

**Finding:** This criterion is satisfied.

**Explanation of Finding:** By updating the plan for wastewater treatment infrastructure, including ensuring adequate capacity for land within the Urban Growth Boundary and Urban Reserves around the City, the City is supporting the ability to provide sanitary sewer service to all urban level development. The updated Wastewater Treatment Plant Master Plan does not affect the City's policy of requiring sanitary sewer system service as part of urban level development approval.

#### Implementation Measure 3.1.4.f. Cost of Individual Services and Line Extensions

CP29. <u>Review Criterion</u>: "The cost of all line extensions and individual services shall be the responsibility of the developer and/or property owners(s) seeking service. When a major line is to be extended, the City may authorize and administer formation of a Local Improvement District (LID). All line extensions shall conform to the City Sanitary Sewer Collection System Master Plan, urbanization policies, and Public Works Standards." <u>Finding</u>: This criterion is satisfied.

**Explanation of Finding:** The City's current practices regarding LID's and costs for services are not affected by the updated Wastewater Treatment Plant Master Plan.

#### Parks/Recreation/Open Space, Environmental Resources and Community Design

### Policies 3.1.11., 4.1.5. and Implementation Measures 3.1.11.a. ,4.1.5.d.-g.,aa. . Conservation of Natural, Scenic, and Historic Areas

CP30. <u>**Review Criteria**</u>: These policies and implementation measures require and encourage conservation of natural resources, as well as scenic and historic areas. **Finding:** These criteria are satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan doesn't specifically address how facility siting will affect natural resources. However, the improvements will be within a confined previously disturbed area and the City has

regulations in place to look at conservation of resources during the design and final siting of future improvements.

#### COMPLIANCE WITH PLANNING AND LAND DEVELOPMENT ORDINANCE

#### Section 4.003 Consistency with Plans and Laws

PL1. **Review Criterion:** "Actions initiated under this Code shall be consistent with the Comprehensive Plan and with applicable State and Federal laws and regulations as these plans, laws and regulations now or hereafter provide."

**<u>Finding</u>**: This criterion is satisfied.

**Explanation of Finding:** Consistency with the Comprehensive Plan and applicable state laws has been reviewed and summarized in this report.

#### Section 4.008 General Application Procedures

PL2. **Review Criterion:** "The general application procedures listed in Section 4.008 through 4.024 apply to all land use and development applications governed by Chapter 4 of the Wilsonville Code. These include applications for all of the following types of land use or development approvals:

H. Changes to the text of the Comprehensive Plan, including adoption of new Plan elements or sub-elements, pursuant to Section 4.198;"

**Finding:** This criterion is satisfied.

**Explanation of Finding:** Adoption of the updated Wastewater Treatment Plant Master Plan is being reviewed pursuant to Section 4.198.

#### Subsection 4.009 (.02) Who Can Initiate Application

PL3. <u>Review Criterion</u>: "Applications involving large areas of the community or proposed amendments to the text of this Chapter or the Comprehensive Plan may be initiated by any property owner, business proprietor, or resident of the City, as well as the City Council, Planning Commission, or Development Review Board acting by motion." <u>Finding:</u> This criterion is satisfied.

**Explanation of Finding:** The application has been initiated by the City as part of its responsibility to periodically update facility master plans.

#### Subsection 4.032 (.01) B. Authority of Planning Commission

PL4. <u>Review Criterion</u>: This Section states that the Planning Commission has authority to make recommendations to the City Council on "legislative changes to, or adoption of new elements or sub-elements of the Comprehensive Plan." <u>Finding</u>: This criterion is satisfied.

**Explanation of Finding:** The proposed legislative change is being considered by the Planning Commission as a recommendation to the City Council. The issue before the Planning Commission is a legislative review of an amended sub-element of the Comprehensive Plan.

#### Subsection 4.033 (.01) B. Authority of City Council

PL5. <u>Review Criterion</u>: This Section states that the City Council has final decision-making authority on "applications for amendments to, or adoption of new elements or subelements to the maps or text of the Comprehensive Plan, as authorized in Section 4.198." <u>Finding</u>: This criterion is satisfied.

**Explanation of Finding:** Final action will be taken by the City Council following a recommendation from the Planning Commission.

#### Subsection 4.198 (.01) A. Comprehensive Plan Changes: Public Need

PL6. **<u>Review Criterion</u>**: "That the proposed amendment meets a public need that has been identified;"

Finding: This criterion is satisfied.

**Explanation of Finding:** It is in the public interest to periodically update the master plans for critical public facilities such as the wastewater treatment plant to ensure the system provides for adequate service for current and future residents and businesses to ensure proper sanitation.

### Subsection 4.198 (.01) B. Comprehensive Plan Changes: Meets Public Needs As Well As Other Options

PL7. <u>Review Criterion</u>: "That the proposed amendment meets the identified public need at least as well as any other amendment or change that could reasonably be made;" <u>Finding</u>: This criterion is satisfied.

**Explanation of Finding:** As a sub-element of the Comprehensive Plan the Wastewater Treatment Plant Master Plan aims to provide for the public need of adequate wastewater treatment service. An updated Wastewater Treatment Plant Master Plan better meets the public need than the current plan by using updated information about the condition of existing infrastructure and growth projections.

#### Subsection 4.198 (.01) C. Comprehensive Plan Changes: Statewide Planning Goals

PL8. <u>Review Criterion</u>: "That the proposed amendment supports applicable Statewide Planning Goals or a Goal exception has been found to be appropriate; and;" <u>Finding</u>: This criterion is satisfied.

**Explanation of Finding:** Please see compliance with Statewide Planning Goals section below.

### Subsection 4.198 (.01) D. Comprehensive Plan Changes: Conflict with Other Portions of the Comprehensive Plan

PL9. <u>Review Criterion</u>: "That the proposed change will not result in conflicts with any portion of the Comprehensive Plan that is not being amended."
 <u>Finding</u>: This criterion is satisfied.
 <u>Explanation of Finding</u>: No conflicts between the updated Wastewater Treatment Plant Master Plan and other portions of the Comprehensive Plan have been identified.

#### COMPLIANCE WITH OREGON STATEWIDE PLANNING GOALS

#### Statewide Planning Goals

#### Goal 1 Citizen Involvement

OR1. <u>Review Criterion</u>: "To develop a citizen involvement program that insures the opportunity for citizens to be involved in all phases of the planning process." <u>Finding</u>: This criterion is satisfied.

**Explanation of Finding:** The citizen involvement process defined in Wilsonville's Comprehensive Plan has been acknowledged to be in conformance with Goal 1. Findings CP6 through CP10 demonstrate compliance with the citizen involvement component of the Comprehensive Plan and thus Goal 1.

#### Goal 2 Land Use Planning

OR2. **<u>Review Criterion</u>**: "To establish a land use planning process and policy framework as a basis for all decision and actions related to use of land and to assure an adequate factual base for such decisions and actions."

**Finding:** This criterion is satisfied.

**Explanation of Finding:** The City is currently in compliance with Goal 2 because it has an acknowledged Comprehensive Plan and regulations implementing the plan. The Wastewater Treatment Plant Master Plan is a sub-element supporting this plan. A Wastewater Treatment Plant Master Plan will continue to be a sub-element of the Comprehensive Plan and the scope of the update will not change conformance with this goal, but rather provide updated information to better support land use planning in Wilsonville.

#### Goal 5 Natural Resources, Scenic and Historic Areas, and Open Spaces

OR3. **<u>Review Criterion</u>**: "To protect natural resources and conserve scenic and historic areas and open spaces."

Finding: This criterion is satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan doesn't specifically address how facility siting will affect natural resources. However, the

improvements will be within a confined previously disturbed area and the City has regulations in place to look at conservation of resources during the design and final siting of future improvements.

#### Goal 6 Air, Water and Land Resource Quality

OR4. **<u>Review Criteria</u>:** "To maintain and improve the quality of the air, water and land resources of the state."

**Finding:** These criteria are satisfied.

**Explanation of Finding:** The proposed updated Wastewater Treatment Plant Master Plan provides for sanitary disposal of wastewater to prevent the wastewater from polluting and degrading water and land resources. It supports the planning guideline of this rule to only designate residential use where approvable sewage disposal alternatives have been clearly identified.

#### Goal 7 Areas Prone to Natural Disasters and Hazards

OR5. <u>Review Criteria</u>: "To protect life and property from natural disasters and hazards." <u>Finding</u>: These criteria are satisfied. <u>Explanation of Finding</u>: The wastewater Treatment Plant has been evaluated for risks associated with natural disasters and hazards; see Chapter 2.

#### **Goal 11 Public Facilities and Services**

OR6. <u>Review Criteria</u>: "To plan and develop a timely, orderly and efficient arrangement of public facilities and services to serve as a framework for urban and rural development." <u>Finding</u>: These criteria are satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan is among the utility plans that are sub-elements of the City's Comprehensive Plan. Using updated information on the condition of existing infrastructure as well as updated growth forecasts will better enable the timely, orderly and efficient arrangement of wastewater treatment facilities and services.

#### Oregon Administrative Rules

#### **Division 660 Public Facilities Planning**

#### OAR 660-11-0010 The Public Facility Plan

OR7. <u>**Review Criteria**</u>: This OAR identifies what a Public Facility Plan, such as the updated Wastewater Collection System Master Plan, must contain.

Finding: These criteria are satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan inventories and assesses Wilsonville's wastewater treatment plant in support of current

and planned land uses; and it includes a list of projects and prioritized projects for shortterm and long-term improvements, budget-level cost estimates of projects. The master plan also identifies the City as the service provider in City limits and in areas expected to be annexed into the City in the future. A discussion of the City's funding mechanisms is included in the Comprehensive Plan, but is not affected by this update.

#### OAR 660-11-0015 Responsibility for Public Facility Plan Preparation

OR8. **<u>Review Criteria</u>**: This OAR identifies who is responsible for preparing public facility plans.

**Finding:** These criteria are satisfied.

**Explanation of Finding:** The City of Wilsonville has the responsibility to prepare facility plans for public facilities including the wastewater treatment plant. An existing facility plan, which is a sub-element of the City of Wilsonville's Comprehensive Plan, is being updated to ensure an up-to-date facility plan.

#### OAR 660-11-0020 Public Facility Inventory and Determination of Future Facility Projects

OR9. <u>**Review Criteria**</u>: This OAR identifies components of public facility inventories. <u>Finding</u>: These criteria are satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan includes an inventory of the City's wastewater treatment plant including all the required components listed in this OAR: information on capacity and size, assessment of conditions, identification of projects supportive of the City's Comprehensive Plan land use designations, and acknowledgment of future flexibility based on impact studies, facility design, and further master planning efforts.

#### OAR 660-11-0025 Timing of Required Public Facilities

OR10. <u>Review Criteria</u>: This OAR requires public facility plans include a general estimate of the timing for planned public facility projects.
 <u>Finding</u>: These criteria are satisfied.
 <u>Explanation of Finding</u>: The updated Wastewater Treatment Plant Master Plan includes information on short-term and long-term projects. See Chapter 7.

#### OAR 660-11-0030 Location of Public Facility Projects

OR11. <u>Review Criteria</u>: This OAR requires public facility plans include a general location of projects

Finding: These criteria are satisfied.

**Explanation of Finding:** The updated Wastewater Treatment Plant Master Plan includes information on project location.

#### OAR 660-11-0035 Determination of Rough Cost Estimates

Planning Commission Staff Report LP21-0001 Updated Wastewater Treatment Plant Master Plan Planning Commission Meeting - December 13, 2023 Wastewater Treatment Plant Master Plan OR12. **<u>Review Criteria</u>**: This OAR requires public facility plans include rough cost estimates for projects.

Finding: These criteria are satisfied.

**Explanation of Finding:** The scope of the updated Wastewater Treatment Plant Master Plan includes budget level cost estimates for identified projects.

#### OAR 660-11-0045 Adoption and Amendment Procedures for Public Facility Plans

OR13. <u>Review Criteria</u>: This OAR identifies public facility plans as supporting documents to the comprehensive plan and identifies related items to be in the comprehensive plan. <u>Finding</u>: These criteria are satisfied.

**Explanation of Finding:** The Wastewater Treatment Plant Master Plan is a sub-element of the City of Wilsonville's Comprehensive Plan and includes a list of projects, a map of projects, and policies on urban growth and the provision public facilities. The updated Master Plan is being considered a land use decision with the appropriate noticing and hearing processes being followed.

#### LP22-0001 Wastewater Treatment Plant Master Plan Planning Commission Public Hearing Record Index DRAFT (December 13, 2023)

#### PLANNING COMMISSION AND CITY COUNCIL MEETINGS

December 13, 2023 - Planning Commission Public Hearing Resolution LP22-0001 (included above, adoption pending) Staff Report and Attachments (included above, adoption pending) Presentation (not included at this time) Affidavit of Notice of Hearing

November 6, 2023 - City Council Work Session Staff Report and Attachments Presentation Action Minutes

October 11, 2023 - Planning Commission Work Session Staff Report and Attachments Presentation Minutes Excerpt

October 12, 2022 - Planning Commission Public Hearing - Cancelled Cancellation Memo Minutes Excerpt

- September 14, 2022 Planning Commission Work Session Staff Report and Attachments Presentation Minutes Excerpt
- August 1, 2022 City Council Work Session Staff Report and Attachments Presentation Action Minutes
- July 13, 2022 Planning Commission Work Session Staff Report and Attachments Presentation Minutes Excerpt

#### PUBLIC ENGAGEMENT

Project Website: https://www.letstalkwilsonville.com/wastewater-treatment-plant-master-plan

Open House - September 28, 2022: <u>https://www.ci.wilsonville.or.us/engineering/page/public-open-house-waste-water-treatment-plant-master-plan</u>

#### LP22-0001 Wastewater Treatment Plant Master Plan Planning Commission Public Hearing Record Index DRAFT (December 13, 2023)

#### **COMMENTS/ARTICLES**

Boones Ferry Messenger – September

Spokesman Article for Original Public Hearing notification and cancellation

Emailed Comment 10/2/2022 – Thomas Hooker

The Wastewater Treatment Plant Master Plan (LP22-0001) Record can be found on the December 13, 2023 Planning Commission meeting page, in the "Agenda Packet" (https://www.ci.wilsonville.or.us/bcpc/page/planning-commission-72) City of Wilsonville Wastewater Treatment Plant Master Plan

Planning Commission December 13, 2023





# **Project Overview and Update**

- Accommodating Expected Build-Out by 2045
  - Growth projections consistent with recent planning efforts
  - Increased industrial discharges to permitted limits
- Capacity Assessment Complete
  - Includes hydraulic modeling of WWTP
- Equipment Replacement and Seismic Retrofits
- Costs and Schedule for Updated CIP




# **Capital Planning and Expected Growth - 2045**

- Buildout of Service Area through 2045
  - Adjusted population growth rate, consistent with recent planning efforts
  - Modified service area boundary, per Basalt Creek Concept Plan


Buildout Population Projections (High 2.9%)

2020	2030	2040	2045
25,915	34,491	45,904	50,388



# **Buildout Service Area - 2045**

Land Use	Acreage
Commercial	224
Industrial	2,383.2
Public	482.9
Residential	2,278.3
Town Center	136.1
Village	367.4



# **Facility Capacity Assessment**

- Flows & Loads Updated to reflect Buildout of Service Area
- Projected 2045 flows and loads exceed design criteria (~2X current)

Item	2022	Rated Capacity	Projected 2045
Average Dry Weather Flow, mgd	2.06	4.00	4.17
Average Annual Flow, mgd	2.39	4.48	4.77
Maximum Month Wet Weather Flow, mgd	4.00	6.68	7.76
Max Month BOD₅, ppd	11,456	12,900	22,301
Max Month TSS, ppd	9,504	12,500	18,116







Existing Vicinity Map

# **Selection of MBR Process**



Alternative	Advantages	Challenges
Membranes (Selected)	<ul> <li>Space-efficient</li> <li>High-quality effluent</li> <li>Provides capacity for reliable full nitrification</li> <li>No need to expand tertiary filtration</li> </ul>	<ul> <li>Expensive (&gt;2x cost of 4<sup>th</sup> AB)</li> <li>Requires Fine Screening</li> <li>High O&amp;M Costs (Power, Chemicals, etc.)</li> <li>Highest aeration rate</li> <li>Redundancy requirements</li> </ul>
BioMag®	<ul> <li>Space-efficient</li> <li>High-quality effluent</li> <li>Potentially no need to expand tertiary filtration</li> <li>Utilizes secondary clarifier capacity (no stranded assets)</li> </ul>	<ul> <li>Requires Magnetite Recovery Facility</li> <li>Increased maintenance requirement from the magnetite</li> <li>Reports of solids smoldering, may require inert gas system</li> <li>Will not provide sufficient capacity under projected 2045 F&amp;L</li> </ul>
IFAS	<ul> <li>Space-efficient</li> <li>Utilizes secondary clarifier capacity (no stranded assets)</li> </ul>	<ul> <li>Will not provide sufficient capacity under projected 2045 F&amp;L</li> <li>Significant basin modifications needed</li> </ul>

# **Selected Capacity Upgrades**


- Secondary Process
  - Add new aeration basin & additional blower
  - Phased implementation of MBR technology (includes hydraulic and electrical upgrades, new building, new fine screens, and additional blowers)
- Effluent Cooling
  - Add new cooling tower
- Outfall Piping
  - Increase hydraulic capacity for UV disinfection



### Asset Replacement and Seismic Resilience

- Secondary Process
  - Replace secondary clarifier mechanisms
- Solids Thickening and Dewatering
  - Replace GBTs and centrifuge units
- UV System
  - Replace 1997 unit in the near term
  - Replace 2014 unit near the end of the planning period
- Solids Dryer
  - Add redundant unit (requires building expansion)
- Seismic Resilience
  - Structural retrofits to Administration Building, Process Gallery, and Maintenance Workshop

### **Recommended Plan**




- 3 New Aeration Basin 2 Additional Aeration Blowers **New Fine Screens** (9) New Emergency Generator 10 New MBR Facility 11 New Cooling Tower 12 **Replace Gravity Belt Thickeners** 13 Replace backup UV system Replace Solids Dryer & (1)Centrifuges Replace Clarifier 1 & 2 **5 6** mechanisms 4 8 17 Seismic retrofits of buildings
  - 18 New fiber optic connection

Solids process study

# **Capacity Trigger Plot**






# **Project Cost**

DESCRIPTION	ESTIMATED TIMEFRAME	AUGUST 2023 PROJECT COST
Dewatering Performance Optimization	2025	\$150,000
Fiber Optic Cable Addition	2025	\$60,000
Backup UV System Replacement	2026	\$1,705,000
Seismic Improvements	2026	\$1,082,000
Geotechnical Foundation Mitigation	2026	\$2,000,000
New Aeration Basin + Blower + Retaining Wall	2025 – 2027	\$10,222,000
Replace Secondary Clarifier Mechanisms	2026 – 2027	\$1,775,000
MBR Phase 1 + 2 Blowers + Fine Screens + Electrical Upgrades	2028 – 2031	\$69,727,000
Solids Dryer Addition	2031 – 2033	\$17,130,000
Existing Centrifuge and GBT Replacement	2031 – 2033	\$3,701,000
Additional Cooling Tower	2035 – 2036	\$642,000
MBR Phase 2 + 2 Blowers	2037 – 2039	\$2,330,000
UV Equipment Replacement	2039 – 2040	\$2,571,000
Outfall Improvements	2039 – 2040	\$1,244,000
MBR Phase 3 + 2 Blowers	2042 – 2044	\$8,117,000
TOTAL		\$122,456,000

## **Estimated Cash Flow**






Dewatering Performance Optimization (Allowance)
 New Secondary Clarifier Mechanisms
 Backup UV System Improvement
 Existing Centrifuge and GBT Replacement
 MBR Phase 3 + 2 Blower
 Seismic Improvements
 Outfall Improvements

Solids Dryer Improvement
 MBR Phase 1 + 2 Blowers + Fine Screens + Electrical Upgrades
 MBR Phase 2 + 2 Blowers
 Cooling Tower
 Fiber Optic Cable Addition
 New Aeration Basin + Blower + Retaining Wall
 Geotechnical Foundation Mitigation

## **Next Steps**



- City Council Public Hearing 1st Reading 1/4/24
- City Council 2nd Reading 1/18/24
- Sewer System Rate Study and SDC Update 2024





#### **AFFIDAVIT OF MAILING AND POSTING NOTICE OF** PUBLIC HEARING IN THE CITY OF WILSONVILLE

STATE OF OREGON	)	
COUNTIES OF CLACKAMAS AND WASHINGTON	) )	
CITY OF WILSONVILLE	)	

I, Mandi Simmons, do hereby certify that I am Administrative Assistant for the City of Wilsonville, Counties of Clackamas and Washington, State of Oregon, that the attached copy of Notice of Public Hearing is a true copy of the originals of the following that I did cause to be mailed/displayed copies of said public hearing in the exact form hereto attached:

- Single-paged notice was emailed on November 22, 2023 to the attached list of affected agencies .
- Single-paged notice was emailed on November 22, 2023 to the attached list of interested parties
- Single-paged notice was sent to the Wilsonville Spokesman for publication in the November 30. 2023 newspaper issue
- The content of the notice was posted on November 22, 2023 on the City's website .
- Single-paged notice was posted at physical locations listed below on November 22, 2023
  - City Hall, 29799 SW Town Center Loop, East, Wilsonville OR 97070
  - Wilsonville Community Center, 7965 SW Wilsonville Road, Wilsonville, OR 97070 0
  - 0 Library, 8200 SW Wilsonville Road, Wilsonville OR 97070

Witness my hand this	Uthday of December 2023	
	Mo M Simmong Administration Assistant	

Mana Simmons, Administrative Assistant


Acknowledged before me this  $\frac{4 + \lambda}{2}$  day of December 2023, in Clackamas County, Oregon

Yam Z. C.J. Signature of Oregon Notary

Tamara E. Callaway Printed Notary Name

NOTARY PUBLIC

My Commission Expires <u>6/7/25</u>



#### NOTICE OF LEGISLATIVE PUBLIC HEARING BEFORE THE PLANNING COMMISSION AND CITY COUNCIL WASTEWATER TREATMENT PLANT (WWTP) MASTER PLAN LP22-0001

**OREGON STATE LAW ORS 227.186**. The City has not determined how or if this particular proposal will reduce or otherwise impact either the value or use of properties within Wilsonville. Any changes to permitted land uses may reduce or increase property values, depending on various factors. A written notice has been mailed to potentially impacted property owners as required.

#### PLANNING COMMISSION

On Wednesday, December 13, 2023, beginning at 6 pm, the Planning Commission will hold a public hearing on the Wastewater Treatment Plant Master Plan, and will consider whether to recommend to City Council adoption of the Plan.

You will not receive another mailed notice unless you: submit a request in writing or by phone, or submit testimony or sign-in at the hearing.

#### **CITY COUNCIL**

On **Thursday, January 4, 2024 beginning at 7 pm,** the City Council will hold a public hearing regarding **the Wastewater Treatment Plant Master Plan** after which it may make the final decision.

The hearings will take place at **Wilsonville City Hall**, 29799 SW Town Center Loop East. A complete copy of the project record, including staff report, findings, and recommendations, will be available online and at City Hall for viewing 7 days prior to each public hearing.

#### SUMMARY OF PROPOSAL

The City of Wilsonville is updating its Wastewater Treatment Plant Master Plan. The improvements detailed in this Plan are designed to provide optimal value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development.

The City's Wastewater Treatment Plant, along I-5 between the river and Old Town, was originally built in 1971. A major 2014 upgrade expanded the capacity to accommodate population growth. This Plan, which satisfies requirements established by the State of Oregon Department of Environmental Quality (DEQ), considers:

- The age and condition of existing process equipment and structures
- Upgrades to accommodate population growth and new economic development over the planning period (through 2045). Projections are based on land use, historical data, and DEQ wet weather flow methodologies.
- Potential changes to water quality regulations established by the DEQ
- City of Wilsonville Wastewater Collection System Master Plan (2014), and
- Consistency with the 2018 Comprehensive Plan and City Council 2021-2023 Goals 5, 6 and 7

For more details, visit https://www.letstalkwilsonville.com/wastewater-treatment-plant-master-plan

**HOW TO COMMENT:** Oral or written testimony may be presented at the public hearings. Written comment on the proposal is welcome prior to the public hearings. To have your written comments or testimony distributed to the Planning Commission before the meeting, it must be received by 2 pm on December 5, 2023. **Direct written comments to Mandi Simmons, Administrative Assistant** 29799 SW Town Center Loop East, Wilsonville, Oregon, 97070 | msimmons@ci.wilsonville.or.us | (503) 682-4960

Note: Assistive Listening Devices (ALD) are available for persons with impaired hearing and can be scheduled for this meeting. The City will also endeavor to provide qualified sign language interpreters and/or bilingual interpreters, without cost, if requested at least 48 hours prior to the meeting. To obtain such services, please call Mandi Simmons, Administrative Assistant at (503) 682-4960.

Pat McGough West Linn/Wilsonville School District 3J 2755 SW Borland Road Tualatin, OR 97062

Attn: Development Review ODOT Region 1 123 NW Flanders Street Portland, OR 97209

Dr. Kathy Ludwig West Linn/Wilsonville School District 3J 22210 SW Stafford Road Tualatin, OR 97062

Land Use Contact, Planning Department Metro 600 NE Grand Ave Portland, OR 97232

City Planner City of Canby P.O. Box 930 Canby, OR 97013

John Lilly Department of State Lands 775 Summer Street, NE Salem, OR 97301

Clackamas County Planning Director 150 Beavercreek Road Oregon City, OR 97045

Planning Director City of Sherwood 22560 SW Pine Street Sherwood, OR 97140

Tualatin Valley Fire and Rescue South Division 8445 SW Elligsen Road Wilsonville, OR 97070 Andy Back Wash. County Long Range Planning 155 N. First Avenue Hillsboro, OR 97124

Ben Baldwin Tri-Met Project Planning Dept 4012 SE 17th Avenue Portland, OR 97202

Tracy Wilder, Department of Corrections Facilities Services 3601 State Street Salem, Oregon 97301

Nina Carlson NW Natural Gas 250 SW Taylor St. Portland, OR 97204

Diane Taniguchi-Dennis Clean Water Services 2550 SW Hillsboro Hwy. Hillsboro, OR 97123

Roseann Johnson, Assistant Director of Government Affairs Home Builders Associations 15555 SW Bangy Road, Suite 301 Lake Oswego, OR 97035

Oregon Dept of Environ Quality 700 NE Multnomah Street, Suite 600 Portland, OR 97232

James Clark BPA, Realty Department 2715 Tepper Lane Keizer, OR 97013 Steve Koper City of Tualatin 18880 SW Martinazzi Avenue Tualatin, OR 97062

Bill Ferber, Region Manager Oregon Water Resources Department 725 Summer Street, NE Salem, OR 97301

Steve Hursh, Service & Design Supervisor Portland General Electric 2213 SW 153<sup>rd</sup> Drive Beaverton, OR 97006

John Olivares, Operations Manager Republic Services of Clackamas & Washington Counties 10295 SW Ridder Road Wilsonville, OR 97070

Department of Corrections 2575 Center Street NE Salem, OR 97310

Sherwood School Dist Admin Office 23295 SW Main Street Sherwood, OR 97140

Tualatin Valley Water District 1850 SW 170th Ave. Beaverton, OR 97005

Tualatin Valley Fire and Rescue 29875 SW Kinsman Road Wilsonville, OR 97070 Elizabeth Kenney 12451 Orchard Hill Rd Lake Oswego, OR 97035

### Pamplin Media Group

### -Ad Proof-

This is the proof of your ad, scheduled to run on the dates indicated below. Please proofread carefully, and if changes are needed, please contact Sarah Penn prior to deadline at or spenn@pamplinmedia.com.

Date: 11/22/23 Account #: 108863	Start:	308944 11/29/23 11/30/23
Reference #: LP22-0001 WWTP MASTER PLAN Company Name: WILSONVILLE, CITY OF Contact: Address: 29799 SW TOWN CENTER LOOP E WILSONVILLE	Total Cost: Ad Size: Column Width: Column Height:	12.069 1
<b>Telephone:</b> (503) 570-1510 <b>Fax:</b> (503) 682-1015	Ad Class: Phone # Email:	1202 spenn@pamplinmedia.com

#### Run Dates:

Wilsonville Spokesman 11/30/23

#### NOTICE OF LEGISLATIVE PUBLIC HEARING **BEFORE THE** PLANNING COMMISSION AND CITY COUNCIL:

#### WASTEWATER TREATMENT PLANT (WWTP) **MASTER PLAN LP22-0001**

OREGON STATE LAW ORS 227.186. The City has not determined how or if this particular proposal will reduce or otherwise impact either the value or use of properties within Wilsonville. Any changes to permitted land uses may reduce or increase property values, depending on various factors. A written notice has been mailed to potentially impacted property owners as required.

PLANNING COMMISSION: On Wednesday, Dec. 13, 2023, beginning at 6 pm, the Planning Commission will hold a public hearing on the Wastewater Treatment Plant Master Plan, and will consider whether to recommend to City Council adoption of the Plan.

You will not receive another mailed notice unless you: submit a request in writing or by phone, or submit testimony or sign-in at the hearing

#### CITY COUNCIL:

On Thursday, Jan. 4, 2024 beginning at 7 pm, the City Coun-cil will hold a public hearing regarding the Wastewater Treat-ment Plant Master Plan after which it may make the final decision

The hearings will take place at Wilsonville City Hall, 29799 SW Town Center Loop East. A complete copy of the project record, including staff report, findings, and recommendations, will be available online and at City Hall for viewing 7 days prior to each public hearing.

#### SUMMARY OF PROPOSAL:

The City of Wilsonville is updating its Wastewater Treatment Plant Master Plan. The improvements detailed in this Plan are designed to provide optimal value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development.

The City's Wastewater Treatment Plant, along I-5 between the river and Old Town, was originally built in 1971. A major 2014 upgrade expanded the capacity to accommodate population growth.

This Plan, which satisfies requirements established by the State of Oregon Department of Environmental Quality (DEQ), considers:

- · The age and condition of existing process equipment and structures
- · Growth to accommodate population growth and new economic development over the planning period (through 2045). Projections are based on projections, historical data and DEQ wet weather project methodologies.
- · Potential changes to water quality regulations established by the DEO
- · City of Wilsonville Wastewater Collection System Master Plan (2014), and
- Consistency with the 2018 Comprehensive Plan and City Council 2021-2023 Goals 5, 6 and 7

For more details, visit https://www.letstalkwilsonville.com/ wastewater-treatment-plant-master-plan.

#### HOW TO COMMENT:

Oral or written testimony may be presented at the public hear-ings. Written comment on the proposal is welcome prior to the public hearings. To have your written comments or testimony distributed to the Planning Commission before the meeting, it must be received by 2 pm on Dec. 5, 2023. Direct written comments to Mandi Simmons, Administrative Assistant 29799 SW Town Center Loop East, Wilsonville, Oregon, 97070 | msimmons@ci.wilsonville.or.us | (503) 682-4960

Note: Assistive Listening Devices (ALD) are available for persons with impaired hearing and can be scheduled for this meeting. The City will endeavor to provide qualified sign lan-guage interpreters and/or bilingual interpreters, without cost, if requested at least 48 hours prior to the meeting. To obtain such services, please call Mandi Simmons, Administrative As-sistant at (503) 682-4960. Publish November 30, 2023 WS308944



### CITY COUNCIL MONDAY, NOVEMBER 6, 2023

#### WORK SESSION

Wastewater Treatment Plant Master Plan (Nacrelli)



### **CITY COUNCIL MEETING**

#### STAFF REPORT

Meeting Date: November 6, 202	3 <b>Subject:</b> Wastewater Treatment Plant Master Plan Update
	Staff Member: Mike Nacrelli, Senior Civil Engineer
	Department: Community Development
Action Required	Advisory Board/Commission Recommendation
☐ Motion	Approval
Public Hearing Date:	🔲 Denial
Ordinance 1 <sup>st</sup> Reading Date	: 🔲 None Forwarded
Ordinance 2 <sup>nd</sup> Reading Date	e: 🛛 Not Applicable
Resolution	Comments: N/A
Information or Direction	
Information Only	
Council Direction	
🔲 Consent Agenda	
Staff Recommendation: Review	v Wastewater Treatment Plant Master Plan updates and
provide feedback on the recomn	nended capital improvement plan.
Recommended Language for Mo	otion: N/A
Project / Issue Relates To:	
	□Adopted Master Plan(s): □Not Applicable
Strategy 1. Develop an	
Infrastructure resilience plan	
and reprioritize/ fund	
recommended projects.	

#### **ISSUE BEFORE COUNCIL:**

The project team will provide an update on the additional analysis included in the Wastewater Treatment Plant (WWTP) Master Plan and the proposed changes made since the previous Council discussion on August 1, 2022.

#### **EXECUTIVE SUMMARY:**

The City of Wilsonville (City) Wastewater Treatment Plant (WWTP) Master Plan (the Plan) has been developed to satisfy requirements associated with the State of Oregon Department of Environmental Quality (DEQ) guidance document entitled "Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities." To accommodate future flows and loads, projections were developed based on population projections and referencing WWTP historical data and DEQ wet weather project methodologies. Similarly, to accommodate future water quality regulations, the Plan is adaptive and considers potential future regulatory changes.

The City prepared the Plan with the goal of developing a capital plan that identifies improvements required through the planning period (today through 2045) to comply with requirements of the WWTP National Pollutant Discharge Elimination System (NPDES) permit and potential future regulatory requirements, while accommodating growth identified in the City of Wilsonville Comprehensive Plan (October 2018, updated June 2020). These improvements are designed to provide the best value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development, consistent with goals and policies contained in the Comprehensive Plan and 2023-2025 City Council Goals.

The City's WWTP was originally built in 1971 and discharges treated effluent to the Willamette River. The WWTP underwent major upgrades in 2014 to expand the average dry weather capacity to four million gallons per day (mgd) to accommodate the City's continued growth. The WWTP processes include headworks screening and grit removal facilities, aeration basins, stabilization basins, secondary clarifiers, biosolids processing, cloth filtration, and disinfection processes. Additionally, the City contracts with Jacobs for operation of the wastewater treatment plant, located at 9275 Southwest Tauchman Road.

This Plan identifies needed capital improvements within the planning period, taking into consideration:

- The age and condition of existing process equipment and structures,
- Growth in demand for sewer service due to increased population and economic development over the planning period,
- Potential changes to water quality regulations impacting process needs in order to meet effluent limitations and discharge prohibitions imposed by the Oregon Department of Environmental Quality (DEQ), and
- Consistency with the 2018 Comprehensive Plan and City Council 2023-2025 Strategy 1.

#### **Plan Updates**

Since the previous Council Work Session on August 1, 2022 growth projections have been updated to an assumed 2.9% annual population increase, consistent with recent planning documents adopted by the City, including the Wastewater Collection System Master Plan (November 2014), the Willamette River Water Treatment Plan Master Plan Update (March 2018), and the Basalt Creek Concept Plan (August 2018). In addition, the wastewater flow and load projections for biochemical oxygen demand (BOD) and total suspended solids (TSS) have been

further updated to account for increases in industrial discharges, as allowed under existing permits. The project team also performed a more in depth seismic and resiliency analysis of the wastewater treatment plant facilities to address the City Council 2023-2025 goal to develop an infrastructure resilience plan and reprioritize/ fund recommended projects. These changes result in a higher level of capital investment over the planning period than previously reported, as reflected in the table below.

Project Description	Timeframe	Cost*
Dewatering Performance Optimization	2025	\$150,000
Fiber Optic Conduit Addition	2025	\$60,000
UV System Improvement	2026	\$1,705,000
Seismic Improvements	2026	\$1,082,000
New Aeration Basin and Blower	2025 – 2027	\$10,222,000
Replace Secondary Clarifier Mechanisms	2026 - 2027	\$1,775,000
Membrane Bioreactor (MBR) Phase 1 (includes new blower,	2028 – 2030	\$69,727,000
fine screens, electrical and hydraulic upgrades)	2024 2022	647 420 000
New Solids Dryer	2031 – 2033	\$17,130,000
Thickening and Dewatering Improvements	2031 – 2033	\$3,701,000
New Cooling Tower	2037 – 2038	\$642,000
MBR Phase 2 (includes new blower)	2037 – 2038	\$2,330,000
UV Equipment Replacement	2039 – 2040	\$2,571,000
Outfall Upsizing	2039 – 2040	\$1,244,000
MBR Phase 3 (includes 2 new blowers)	2042 – 2043	\$8,117,000
Total		\$120,456,000
*Costs are shown in 2023 dollars and include 25% for engineer	ing, legal, and a	dministration.

The most significant impact to the required level of capital investment is the need for membrane bioreactor (MBR) facilities. These are state-of-the-art, compact facilities that provide a high level of treatment. Due to the limited amount of space available at the existing WWTP site, MBR facilities are the most feasible means of providing the necessary treatment to accommodate build out of the Wilsonville urban reserve areas.

#### **EXPECTED RESULTS:**

The Plan includes a list of recommended capital improvements, along with an anticipated schedule for completion and preliminary cost estimates. The total estimated amount of capital investment over the planning period is approximately \$120 million, of which \$15 million is anticipated in the next five (5) years. The recommended capital improvements will provide the basis for an analysis of sewer rates and system development charges (SDCs) that are necessary to adequately fund the upgrades needed to meet the projected growth.

#### TIMELINE:

The project team will incorporate feedback received by both the Planning Commission (October 11, 2023 Work Session) and the City Council (November 6, 2023 Work Session) into the Plan.

Currently, a public hearing for the Plan adoption recommendation by the Planning Commission is scheduled for December 13, 2023. A public hearing before City Council for the Plan adoption is anticipated in January 2024.

#### **CURRENT YEAR BUDGET IMPACTS:**

The amended fiscal year 2023 -2024 Budget for capital improvement project (CIP) #2104, Wastewater Treatment Plant Master Plan, includes \$130,000 in sewer operations and system development charge funds. The remaining budget is sufficient to complete the remaining work to update and adopt the Plan.

#### COMMUNITY INVOLVEMENT PROCESS:

A virtual town hall meeting to present the findings of the Plan and solicit public input was held in September 2022 and posted on the City's online calendar and Let's Talk Wilsonville page, where a project overview and periodic updates to the Executive Summary have also been posted. In addition, draft versions of the Executive Summary have been sent to the ten (10) largest industrial customers for review and comment. The public hearings listed above will provide further opportunity for public input. The forthcoming Sewer System Rate Study and SDC Update will also include a public engagement process with outreach to utility customers and the development community.

#### POTENTIAL IMPACTS OR BENEFIT TO THE COMMUNITY:

A technically and financially sound plan for providing reliable wastewater treatment, capacity to accommodate future development, and compliance with environmental regulations.

#### ALTERNATIVES:

The project team considered and evaluated numerous technologies and alternatives to provide the needed wastewater treatment plant capacity to meet future demands and recommend a capital improvement program that implements the needed improvements in a way that is efficient and cost effective.

#### **CITY MANAGER COMMENT:**

N/A

#### ATTACHMENT:

1. Wastewater Treatment Plant Master Plan Draft Executive Summary (dated October 2023)

#### EXHIBIT A

### **EXECUTIVE SUMMARY**

This new City of Wilsonville (City) Wastewater Treatment Plant (WWTP) Master Plan (the Plan) has been developed to satisfy requirements associated with the State of Oregon Department of Environmental Quality (DEQ) guidance document entitled "Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities." To accommodate future flows and loads, projections were developed based on population projections and referencing WWTP historical data and DEQ wet weather projection methodologies. Similarly, to accommodate future regulatory changes.

The City prepared the Plan with the goal of developing a capital plan that identifies improvements required through the planning period (today through 2045) to comply with requirements of the WWTP National Pollutant Discharge Elimination System (NPDES) permit and potential future regulatory requirements, while accommodating growth identified in the City of Wilsonville Comprehensive Plan (October 2018, updated June 2020 - the 2018 Comprehensive Plan). These improvements are designed to provide the best value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development, consistent with goals and policies contained in the 2018 Comprehensive Plan and 2021-2023 City Council Goals.

The City's WWTP was originally built in the early 1970's and discharges treated effluent to the Willamette River. The WWTP underwent major upgrades in 2014 to expand the average dry weather capacity to four million gallons per day (mgd) to accommodate the City's continued growth. The WWTP processes include headworks screening and grit removal facilities, aeration basins, stabilization basins, secondary clarifiers, biosolids processing, cloth filtration, and disinfection processes. Additionally, the City contracts with Jacobs for operation of the WWTP, located at 9275 Southwest Tauchman Road.

This Plan identifies improvements taking into consideration:

- The age and condition of existing process equipment and structures,
- Growth in demand for sewer service due to increased population and economic development over the planning period,
- Potential changes to water quality regulations impacting process needs in order to meet effluent limitations and discharge prohibitions imposed by DEQ,
- City of Wilsonville Wastewater Collection System Master Plan (2014, MSA), and
- Consistency with the 2018 Comprehensive Plan and City Council 2023-2025 Strategy 1.



#### **ES.1** Planning Area Characteristics


Chapter 1 summarizes the City's wastewater service area characteristics relevant to assessing WWTP facility needs. The planning area considered by this Plan is consistent with the City's 2014 Collection System Master Plan and 2018 Comprehensive Plan including the urban growth boundary (UGB). The Basalt Creek Concept Plan, adopted in 2018, resulted in a modification of the future boundary between the cities of Tualatin and Wilsonville relative to the 2014 Wastewater Collection System Master Plan (CSMP). This decision is reflected in Figure ES.1, which shows the Study Area Boundary as analyzed in the 2014 CSMP, with the portion likely to annex to Tualatin now shown outside the current Study Area Boundary.

The northern portion of the City of Wilsonville is located within Washington County, and the majority of the City lies in the southwestern part of Clackamas County.

The City sits within the jurisdictional boundaries of Metro, the regional government for the Portland metropolitan area. By state law, Metro is responsible for establishing the Portland metropolitan area's UGB, which includes Wilsonville. Land uses and densities inside the UGB require urban services such as police and fire protection, roads, schools, and water and sewer systems. A figure of the City's existing land use is presented in Chapter 1. Also presented in

Chapter 1 are the City's physical characteristics, water resources, and population and employment information, which are all significant factors in planning for wastewater conveyance and treatment facilities.





#### EXECUTIVE SUMMARY | WASTEWATER TREATMENT PLANT MASTER PLAN | CITY OF WILSONVILLE

Figure ES.1 Planning Area

123 10:51 AMpw:\\IO-PW-INT.Carollo.local:Carollo\Documents\Client\OR\Wilsonville\11962A00\GIS\wilsonville\_11962A00.APRX

The Portland State University Population Research Center (PSU PRC) publishes annual estimates of populations for the previous year for cities in Oregon while Metro develops population projections for the future within the Portland metropolitan area, including Wilsonville. The PSU PRC estimated the City's population as 27,414 in 2022.

The historical per capita flow and loads presented in this master plan are based on the PSU PRC certified population estimates while future flow and load projections are based on the CSMP estimates to maintain consistency with prior water and sewer enterprise planning (with the slight modification to exclude the portion of the Basalt Creek Planning Area (BCPA) mentioned above). Figure ES.2 details the current population along with the historical population and growth expected for the City using the CSMP projections. As is shown in Figure ES.2, the WSMP (2003) assumption of a 2.9 percent growth rate lines up well with the PSU PRC and US census data for the years 2010 through 2022. Current and future population are described in greater detail in Chapter 3.




Figure ES.2 Historical Population and Expected Growth for the City of Wilsonville

#### ES.2 WWTP Condition Assessment

Carollo Engineers, Inc. (Carollo) reviewed prior condition assessments performed by others, conducted geotechnical investigations and performed seismic assessments at the WWTP in the course of Plan development.



In 2019, Jacobs Engineering Group Inc. (Jacobs) and Brown and Caldwell both completed condition assessments at the City's WWTP. A total of 322 major assets (per Jacobs' report), including process and mechanical equipment, motors and drives, control panels, generators, instrumentation, and structures, were examined for a variety of conditions that may signify their need for maintenance or replacement. Chapter 2 presents a summary of critical assets that require short term rehabilitation or replacement, as well as a list of assets that are less critical to operations, or have minor condition issues, but may be included in a short-term improvements project or a task order for Jacobs operations personnel. Table ES.1 displays the condition driven rehabilitation or replacement projects from Chapter 2 that were included in the recommended Capital Improvement Plan (CIP) in Chapter 7. The City undertook an updated assessment of WWTP condition in the summer of 2023. The 2023 assessment did not identify additional issues requiring significant capital outlays compared to the 2019 assessments.

#### Table ES.1 CIP Condition Driven Replacement Projects

Asset	Description
Trojan UV 4000 System	While only used as a backup to the Suez UV system, the Trojan system's HMI has errors that prevent it from showing the status of the lamps in module 3. Since it is used infrequently, the system's condition is largely unknown. After review of the 2019 condition assessment reports and discussion with the City and Jacobs staff, it was concluded that the UV 4000 unit must be replaced.
Secondary Clarifiers No. 1 and No. 2	Ovivo completed a field review of the plant's secondary clarifiers No. 1 and No. 2 in April 2022. Although both units were operational, repairs were identified to improve the operation of the clarifiers. The recommended repairs include drive controls for both units, new skimmers for both units, squeegees for both tanks rake arms, EDI chains, one motor and reducer assembly, one skimmer arm assembly, and new secondary clarifier mechanisms.

#### Notes:

Abbreviations: EDI - electronic data interchange; HMI - human-machine interface; No. - number; UV - ultraviolet.

#### **ES.3** Seismic Analysis

In 2021, Carollo performed a seismic evaluation and analysis of the City's WWTP as part of the overall plant condition assessment. Because the WWTP was substantially upgraded and expanded in 2014, most of its infrastructure is designed in accordance with the 2010 Oregon Structural Specialty Code (OSSC) and follows modern seismic design and detailing. During Tier 1 evaluations, Carollo identified potential deficiencies and areas for additional investigation. A Tier 1 seismic analysis is an initial evaluation performed to identify any potential deficiencies, whether structural or non-structural, in a building based on the performance of other similar buildings in past earthquakes. Subsequent to the Tier 1 analysis, a more detailed seismic evaluation of five older and potentially seismically vulnerable structures on the WWTP site was conducted. Those structures receiving a more detailed evaluation included the following:

- Operations Building.
- Process Gallery.
- Workshop.
- Aeration Basins and Stabilization Basins.
- Sludge Storage Basins and Biofilter.



The five potentially vulnerable structures were compared against an S-4 Limited Safety structural performance level and N-B Position Retention non-structural performance level for an M9.0 Cascadia Seismic Zone (CSZ) earthquake. The M9.0 CSZ is reflective of a catastrophic natural disaster event that has an estimated 35 percent likelihood of occurring within the next 50 years. Following the Tier 1 evaluation, Carollo began Tier 2 evaluations for a select number of identified deficiencies. Although none of the structures showed significant irregularities, the team did identify seismic deficiencies. The recommended seismic retrofits are included in the CIP for this Plan.

Prior to the 2021 seismic evaluation, Carollo's subconsultant, Northwest Geotech, Inc. (NGI), completed a seismic response and geologic hazards assessment of the City's WWTP. Through past and present site investigations and engineering analyses, NGI determined that the native soils beneath the site's granular pit backfill have low risk of liquefaction and its slopes do not pose undue risk. NGI concluded that the WWTP's primary site hazard is the differential settlement that may be caused by soil piping (development of subsurface air-filled voids), which raises the risk of sinkholes forming beneath structures and pipelines. Soil piping usually develops in unsaturated soils when a water source percolates into the ground. While the site is mostly paved and stormwater is being collected, there may be areas where infiltration is occurring next to structures or below pipelines. In spring 2023, NGI performed a visual crack survey and mapped existing cracks at accessible structure floor and foundation stem wall locations. In addition, NGI completed a 50-foot boring utilizing a sonic drilling technique to assist in determining grouting conditions, prior maximum excavation depths, and fill materials present in the vicinity of secondary clarifier 3.Recommended actions from NGI to mitigate the risk of soil piping and considerations for new structure foundations are presented in Chapter 2.

#### ES.4 Wastewater Flow and Load Projections

Chapter 3 of the Plan evaluates the historical and projected wastewater flows and loads generated in the City of Wilsonville's service area. The load projections include total suspended solids (TSS), biochemical oxygen demand (BOD<sub>5</sub>), ammonia (NH<sub>3</sub>), and total phosphorous (TP) loads.

Service area, residential population, industrial contribution, and rainfall records were all considered in the flow and load projection analyses. Facility planning involves estimating rates of growth in wastewater generation within the service area which are unlikely to align precisely with the actual growth observed. During the planning period, City staff will need to assess service area growth at regular intervals and revisit the analysis presented in this Plan.

The City previously estimated population for build-out of their service area. These estimates were taken from the City's Collection System Master Plan (2014, MSA) and as assumed in that document, projected the UGB reaches build-out in 2045. Figure ES.2 details the historical population and growth expected for the City. In addition, the City service area boundary upon which 2045 UGB build-out projections were based on the 2014 CSMP, has been altered slightly to account for a portion of the Basalt Creek Planning Area (BCPA) which is now expected to annex to the City of Tualatin and therefore will not receive wastewater service from the City of Wilsonville. Figure ES.2 illustrates the 2014 UGB build-out population projections from the CSMP compared to those based on the modified service area boundary.



The flow and load projections presented in Chapter 3 are based on the Collection System Master Plan projections (with the slight modification to exclude the portion of the BCPA mentioned above).

A determination will need to be made whether projected flows and loads (which drive assessments of unit process capacity) are aligned with calendar projections presented in this plan and consider if conclusions presented regarding capacity and timing of recommended improvements remain valid. If not, adjustments to the plan will need to be undertaken to ensure sufficient capacity remains available to serve anticipated growth. As actual future wastewater generation rates may also be slightly different than the unit factors considered in this Plan, operations staff at the plant will need to be familiar with the flow and load triggers for planning and design of logical increments of treatment capacity presented in this plan. If growth rates are higher, the schedule for improvements in this plan will need to align with calendar dates presented herein. If growth occurs more slowly, the City will be able to phase WWTP improvements on a less aggressive schedule.



Analysis of flow projections were completed through two different methods: (1) analysis of historical plant records and (2) DEQ Guidelines for Making Wet-Weather and Peak Flow Projections for Sewage Treatment in Western Oregon, which is referred to as the DEQ methodology in this Plan. Since there is no DEQ methodology for load analysis, all projections were developed based on historical plant records. Figure ES.3 summarizes the measured and projected maximum month, peak day and peak hour flows. The projections for the remaining flow elements can be found in Chapter 3. As is shown in Figure ES.3, the peak hour flow is projected to exceed the peak hour flow of 16 mgd listed on the 2014 Improvements Drawings close to the year 2040. The projected 2045 peak hour flow is based on a 10-year (rather than a 5-year) design storm and does not account for storage or flow attenuation in the collection system. In 2023 the City undertook a hydraulic analysis of the WWTP concluding that certain elements will be deficient as the service area develops. This is discussed in greater detail in Chapter 4. This has important implications for facility improvement costs recommended in this Master Plan, which are based on estimates and projections of flows and loads which may not align with the timelines presented in this Master Plan. As such it is recommended the City perform additional evaluation of the WWTP and collection system, along with monitoring actual flows, to further evaluate whether future flow equalization can be achieved and whether recommended improvements at the WWTP will all be triggered within the planning period.




Figure ES.3 Flow Projection Summary



Load projections were calculated for influent TSS, BOD<sub>5</sub>, NH<sub>3</sub>, and TP. Figure ES.4 summarizes the measured and projected influent maximum month BOD and TSS loads. The projections for the remaining load elements can be found in Chapter 3.




Figure ES.4 Load Projection Summary

The projected flows and loads developed in Chapter 3 were compared against the rated capacity for each of the WWTP's unit processes to determine whether expansion would be required within the planning period. The findings of this capacity analysis are discussed in the next section.

#### ES.5 Capacity Analysis

Summaries of plant process area capacity assessments and conclusions are presented in this Plan. These assessments focus on the need for improvements or upgrades to existing facilities to address capacity deficiencies identified in the course of Master Plan evaluations. A site plan of the City's existing WWTP is presented in Figure ES.5.

Chapter 4 identifies existing capacity ratings and deficiencies for the liquid and solids stream treatment processes at the City's WWTP. Analyses are based on operational practices in place at the time and existing effluent limits established by the WWTP's NPDES permit. Biological process modeling was performed using BioWin version 6.2 to predict plant performance under current and future flow and loading conditions to assess when unit process capacities may be exceeded within the planning period (present through 2045).

A summary of the capacity assessment completed using growth projections described in Section ES.1 is detailed below in Table ES.2. Chapter 4 presents the methodology and findings in greater detail.



Plot Date: 6/28/2022 9:15:35

30' 60' SCALE: 1" = 60'

#### LEGEND:

- 1 DEWATERING & DRYING BUILDING
- 2 PROCESS GALLERY
- 3 SECONDARY CLARIFIER NO. 1
- 4 SECONDARY CLARIFIER NO. 2
- 5 UV DISINFECTION SYSTEM
- 6 WORKSHOP
- 7 SECONDARY PROCESS FACILITY
- 8 STABILIZATION BASIN
- 9 SLUDGE STORAGE BASINS AND BIOFILTERS 12 - SECONDARY CLARIFIER NO. 3
- 10 HEADWORKS
- 11 DISK FILTERS
- 12 COOLING TOWERS
- 13 W3 REUSE PUMP STATION
- 14 OPERATIONS BUILDING
- 15 SITE ENTRANCE

Figure ES.5 EXISTING WILSONVILLE WWTP CITY OF WILSONVILLE



Item A.

#### Table ES.2 Unit Process Capacity Assessment

Unit Process	Capacity Assessment
reliminary Treatment	
Screening	There is sufficient hydraulic capacity with both mechanical screens operational to accommodate a PHF of 17.6 mgd. Hydraulic modeling co influent screening can pass the projected PHF.
Grit Removal	The 2012 WWTP Improvement documents indicate a design capacity of 16 mgd for the vortex grit basin. However, Hydraulic modeling co removal system can pass a PHF of 17.6 mgd. At this flow rate the anticipated performance would be poor.
Secondary Treatment	
Secondary Treatment	Based on maximum week MLSS predicted from BioWin modeling at peak day flow with all clarifiers in service (and assuming a 5-day SRT), piping is expected to be necessary to convey flow from the headworks to the secondary process and to return activated sludge within the s
Aeration Blowers	The air demands of the secondary treatment process are projected to exceed the firm capacity of the aeration blowers under peak condition
Fertiary Treatment and Disinfection	
Disk Filters	The existing disk filter capacity is expected to be exceeded by 2032 with one unit out of service or in backwash mode based on effluent lim this time the City expects to relax these contract limitations rather than invest in additional capacity.
Secondary Effluent Cooling Towers	The projected peak day flow during the months of June through September is expected to exceed the capacity of the colling tower by the
UV Disinfection	The existing UV channels do not have adequate capacity to disinfect the 2045 PHF with all units in service. However, the firm capacity of tl 2045 with one channel out of service. The City currently has an older UV unit in place as an emergency backup to the primary system. That planning period. By the year 2040, the UV channels are expected to exceed their hydraulic capacity.
Outfall	Even with the Willamette River at its 100-year flood elevation, it is expected that the outfall pipeline can accommodate approximately 19 submergence upstream. Since this flow is well above the hydraulic capacity of the rest of the plant, no expansion will be needed until after conditions certain process and effluent piping, including piping just upstream of the Willamette River outfall and diffuser system, may be h mgd recycle scenario the headworks screens and grit removal systems are expected to be unsubmerged. However, upsized outfall piping l convey flow from the headworks to the secondary process under these conditions
Solids Handling	
Gravity Belt Thickener	Assuming continuous operation, the capacity analysis results indicate adequate capacity for thickening the current and projected maximu aging and the City plans replacement during the planning period.
TWAS Storage	The TWAS storage volume is sufficient to accommodate the expected maximum week solids loads for two days (assuming TWAS is thicke
Dewatering Centrifuges	The rated capacity of the current centrifuges is sufficient to process the maximum week load with one unit out of service though 2042 assu per the criteria detailed in Chapter 4. <sup>(2)</sup> These units will reach the end of useful life during the planning period and the City plans replaceme
Biosolids Dryer and Solids Disposal	The capacity of the biosolids dryer is adequate for handling the current and projected max week solids loads (in year 2045) on the basis of from 20 percent TS to 92 percent TS and the dryer is operated for 24 hour per day for 7 days per week. <sup>(3)</sup> This unit is aging, has had recent planning period.

(1) The existing outfall was recently modified and equipped with five parallel diffuser pipes equipped with duckbill check valves to improve the mixing zone characteristics in the Willamette River.

(2) The centrifuges have exhibited inconsistent performance. The City recently refurbished these units and expects they will provide sufficient capacity through 2045.

(3) The existing solids dryer has sufficient capacity through 2045 but has exhibited inconsistent performance. See Alternative 2B, Chapter 6.

Abbreviations: DBO - Design-Build-Operate; gpd/sf - gallons per day per square foot; MLSS - mixed liquor suspended solids, SPA - State Point Analysis; SRT - solids residence time; TS - total solids; TWAS - thickened waste activated sludge.



conducted by Jacobs in 2023 indicates that hydraulically the

conducted by Jacobs in 2023 indicates that hydraulically, the grit

T), there is only sufficient capacity through 2027. Upsized process ne secondary process under future flow conditions litions by 2027.

imitations included in the City's DBO Contract with Jacobs. At

he year 2036.

f the UV system is sufficient to treat the PDDWF through the year hat backup unit is aging and the City plans replacement during the

L9 mgd before the UV channel effluent weirs are at risk of ter 2045.<sup>(1)</sup> Jacobs found that under projected 2045 PHF he hydraulically deficient. At PHF 17.6 mgd and assuming a 0.8 hg between MH-B and MH-D2 is expected to be necessary to

num week WAS loads with one unit out of service. These units are

kened to 4 percent).

ssuming operating times of 24 hours per day for 7 days per week, ment accordingly.

of its design evaporation rate, assuming dewatered cake is dried nt performance issues and the City plans replacement during the

Item A.

Item A.

Table ES.3 further summarizes the capacity assessment by listing each unit process, associated design parameters and year of possible capacity exceedance.

Unit Process	Design Parameter	Redundancy Criteria	Year of Capacity Exceedance
Influent Screening	PHF	Bypass channel with manual bar rack in service and one mechanical screen out of service	>2045
Grit Chamber	PHF	All units in service	>2045(1)
Secondary Treatment	MW MLSS Inventory at PDF	All units in service	2027
Secondary Effluent Cooling Towers	June 1 - Sept 30 PDF	All units in service	2036
Disk Filters	MWDWF	One unit in backwash	2032 <sup>(2)</sup>
UV Disinfection Channels	PHF	All units in service	2040 <sup>(1)</sup>
Outfall	PHF	-	>2045
Gravity Belt Thickening	MW Load	One unit out of service	2042
Dewatering Centrifuges	MW Load	One unit out of service	>2045 <sup>(3)</sup>
Biosolids Dryer	MW Load	All units in service	>2045 <sup>(3)</sup>

Notes:

(1) The plant hydraulic modeling done as a part of the 2012 WWTP Improvements Project only evaluated plant flows as high as 16 mgd. The projected peak hour flows presented in Chapter 3 exceed this flow by the year 2045. There are some unit processes including the grit removal system, secondary clarification and UV disinfection that have a peak hydraulic capacity of 16 mgd. The hydraulic analysis conducted by Jacobs in 2023 found that under projected 2045 PHF conditions certain process and effluent piping may be hydraulically deficient. At PHF 17.6 mgd and assuming a 0.8 mgd recycle scenario the headworks screens and grit removal systems are expected to be unsubmerged. However, upsized piping is expected to be necessary to convey flow from the headworks to the secondary process under these conditions.

- (2) Existing Disk Filters are predicted to exceed reliable capacity (one unit out of service) in 2028 based on vendor provided design criteria. This conclusion assumes limitations for effluent total suspended solids contained in the WWTP DBO contract, which are far more stringent than the City's NPDES permit. At this time the City expects to relax these contract limitations rather than invest in additional capacity. Following startup of secondary treatment membrane bioreactors in 2030, the tertiary filters will be required less to meet the effluent requirements of the NPDES permit. It is anticipated the City will maintain these facilities to allow flexibility in operation to account for servicing and membrane facility downtime.
- (3) As noted previously, the existing centrifuges and biosolids dryer appear to have sufficient capacity through the planning year 2045, however condition and age are likely to require replacement during the planning period. It is recommended the City reassess available replacement technologies prior to replacement and consider loading appropriate to the planning horizon of any new units selected.

Abbreviations: MW - maximum week



#### ES.6 Regulatory Considerations and Strategy

It is the responsibility of the Oregon DEQ to establish and enforce water quality standards that ensure the Willamette River's beneficial uses are preserved. Discharges from wastewater treatment plants are regulated through the (NPDES. All discharges of treated wastewater to a receiving stream must comply with the conditions of an NPDES permit. The Wilsonville WWTP discharges to the Willamette River at River Mile 38.5 just upstream of the Interstate 5 bridge. The existing permit limits for the Wilsonville WWTP are shown in Table ES.4. This permit became effective on September 1, 2020 and expires July 30, 2025.

Parameter		e Effluent itrations	Monthly Average,	Weekly Average,	Daily Maximum,
	Monthly	Weekly	(ppd)	(ppd)	(lbs)
May 1 - October 31			,		
CBOD <sub>5</sub>	10 mg/L	15 mg/L	190	280	380
TSS	10 mg/L	15 mg/L	190	280	380
November 1 - April 30					
BOD₅	30 mg/L	45 mg/L	560	840	1100
TSS	30 mg/L	45 mg/L	560	840	1100
Other Parameters Limitation	ıs				
F. coli Bacteria	•	Shall not excee geometric mea	-	sms per 100	ml monthly
E. COILBACTENA	•	No single sam 100 ml.	ple shall exce	ed 406 orga	nisms per
рН	•	Instantaneous of 6.0 and a da		•	nimum
BOD <sub>5</sub> Removal Efficiency	•	Shall not be le	ss than 85% r	nonthly ave	rage
TSS Removal Efficiency	•	Shall not be le	ss than 85% r	nonthly ave	rage
ETL June 1 through Septe	ember 30	Option A: 39 m			ng average
	•	Option B: Calc	ulate the dail	y E I L limit	

Table ES.4	Current	Effluent	Permit	Limits
------------	---------	----------	--------	--------

Notes:

Abbreviations: CBOD<sub>5</sub> - five-day carbonaceous biochemical oxygen demand; ETL - excess thermal load; kcal/day - kilocalories per day; lbs - pounds, mg/L - milligrams per liter; ml - milliliter.

The WWTP has been compliant with NPDES permit limits, generally. However due to construction issues that required that aeration basins be offline, equipment failure and issues with solids processing, the WWTP did violate their NPDES permit over eight months between 2015 and 2020 (December 2015, February 2017, April 2017, January 2018, August 2018, May 2020, June 2020 and July 2020). Most of these violations were due to the daily effluent TSS load exceeding the maximum daily load limit in the NPDES permit. It is anticipated that once the issues with solids processing are addressed, the City's current treatment process will be able to meet permit limits.

Chapter 5 details potential regulatory issues the City will need to take into consideration in coming years. Several possible regulatory actions by the Oregon DEQ could drive investments in



future improvements at the City's WWTP. The plant discharges to the Willamette River and existing and future effluent limitations contained in the NPDES permit dictate, in large part, the necessary treatment processes and configuration at the WWTP necessary to maintain compliance.

Future treatment upgrades may be required when DEQ establishes total maximum daily loads (TMDL) for the lower Willamette River. Dissolved oxygen and nutrient limits, such as phosphorus limitations, are possible. The dissolved oxygen in the lower part of the river does not always meet water quality standards, and indications of excessive nutrients, such as chlorophylla, aquatic weeds, and harmful algal blooms, are present in the lower Willamette River. DEQ has begun its triennial review of Oregon's water quality criteria. The review could result in more stringent or new discharge requirements, but this process will take several years. For planning purposes, providing plant footprint to accommodate future treatment to remover phosphorus and address dry weather seasonal limits on dissolved oxygen should be anticipated. In addition, the City should continue to engage with DEQ regarding any proposed receiving water temperature regulatory actions.

#### ES.7 Alternative Development and Evaluation

Chapter 6 presents the methodology and findings of a process improvements alternatives evaluation. The plant's treatment process needs were defined by comparing the plant's existing condition, capacity and reliability, with the projected flows, loads, and regulatory constraints for the recommended alternatives. Where capacity deficiencies were predicted, at least two alternatives were analyzed for each corresponding unit process. Process modifications associated with each alternative were modeled in BioWin to evaluate the overall impact on plant operations.

As identified in Chapter 4, the secondary treatment process is expected to require additional capacity during the planning horizon (2045). Chapter 6 details two alternatives to address these capacity limitations. The two alternatives considered to increase secondary capacity are:

- 1. Expansion of the existing conventional activated sludge process; and
- 2. Intensification of the existing treatment process using membrane bioreactor (MBR) technology.

Due to the higher capital and operating costs of intensification, construction of a new conventional aeration basin is recommended as the first phase to increase secondary capacity. As flows and loads increase, or regulatory requirements become more stringent, it is expected to become necessary to intensify treatment. It is recommended the City revisit this evaluation as the need for 1) additional capacity to accommodate growth nears or 2) more stringent effluent limitations are considered. This offers the opportunity to take advantage of potential advances in technology as well as confirming the predicted time frame of capacity exceedance. A new aeration basin project is included in the Capital Improvement Plan in Chapter 7. As loads continue to increase, this plan includes the gradual conversion of the existing conventional activated sludge process to a membrane bioreactor process.

The existing aeration blower system firm capacity is expected to be deficient by 2027. An additional aeration blower (with approximately double the capacity of the current blowers) would provide for the first phase of capacity expansion. As loads continue to increase, the plan includes the gradual upsizing of the existing blowers.



The projected peak day flow between June through September is expected to exceed the capacity of the existing cooling tower. Since the existing cooling tower system was designed to be expanded with the addition of one more tower, the plan assumes the expansion of the existing cooling tower process by the year 2036 to meet the projected summer peak day flows.

Additional tertiary filtration capacity is predicted to be needed by 2032 to provide full treatment of the MWDWF with one disc filter out of service or in backwash mode. As the City has selected an intensification technology utilizing membranes, this is likely to eliminate tertiary filtration capacity concerns as the membranes replace the filtration process for TSS removal in plant effluent.

While the capacity assessment findings presented in Chapter 4 determined existing gravity belt thickeners and dewatering centrifuges have sufficient capacity assuming continuous operation, the remaining equipment service life may require replacement within the planning horizon. The centrifuges, installed in 2014, were recently refurbished, but by 2045, will have been in service for over 30 years. In addition, the gravity belt thickeners (GBT) which thicken the sludge prior to delivery to the centrifuges for dewatering, have been in service even longer. The City should plan for their replacement within the planning horizon and consider whether a capacity increase is needed at the time of replacement based on projections of solids production and processing needs. Additionally, the secondary process was modified in 2020 and has experienced extended periods where mixed liquor concentrations have been elevated above typical ranges for conventional activated sludge or extended aeration processes. Due to the complications with secondary process operation and performance issues with the centrifuges, it is recommended the City study the secondary treatment and dewatering processes to confirm that the assumptions and conclusions regarding centrifuge capacity in Chapter 4 may be relied upon. A dewatering performance optimization study is recommended so the City can collect and analyze secondary treatment and solids processing performance data. For budgeting purposes, an opinion of probable cost for replacing the existing centrifuges is presented in Chapter 7. Timing of that equipment replacement will depend on performance of the existing units, future loading assumptions, and observed condition.

The existing solids dryer has experienced operational issues in recent years, including a fire that caused extensive damage to the equipment in April 2019 and a leaking rotary joint and damaged seal in 2021. As of February 25, 2022, the dryer has been repaired and is operating. Because of the City's commitment to solids drying as the preferred process to achieve Class A biosolids, the alternatives evaluation presented in this Plan for future dryer replacement was conducted with a focus on thermal drying options only.

Chapter 6 details an analysis of the following alternatives to improve the drying system:

- 1. Alternative 1 Continue operating the existing biochemical reactor (BCR) paddle dryer and defer replacement.
- 2. Alternative 2 Modify the existing Dewatering and Drying Building to accommodate a different solids dryer technology or a redundant dryer.
- 3. Alternative 3 Construct a new dryer building with a different solids dryer technology.

While it is anticipated the existing dryer has useful life through at least 2026 (current DBO contract expiration), by 2031 the dryer will have been in operation for over 15 years. It is recommended the planning and design of upgrades to provide reliable dryer capacity begin in 2031, or sooner if further operational concerns arise. The City has indicated a preference for a



Item A.

variation of Alternative 2 which involves expanding the existing Dewatering and Drying Building to accommodate a second solids paddle dryer. This alternative provides backup capacity to allow the City to continue delivering Class A solids during periods of downtime if a mechanical failure occurs or to accommodate regular maintenance of one dryer train. As mentioned previously, this Plan recommends the City complete a study of the secondary sludge quality, performance of that process, chemical addition types and locations, and solids handling process performance overall prior to making a final selection of the preferred dryer alternative from the alternatives detailed in Chapter 6. For purposes of capital planning, this Plan assumes the City will implement Alternative 2b (modification of Dewatering and Drying Building to accommodate a second paddle dryer) with a study and confirmation of this selection beginning in 2031.

Lastly, the City wants to establish a direct connection between the City's fiber optics network and the WWTP. This addition consists of routing two new conduits (one spare) and fiber optic cabling from the WWTP's Operations Building to the site entrance, where the conduits will be tied into the City's fiber optics network. Chapter 6 details one potential routing from the Operations Building to the site entrance that would minimize impact to existing yard utilities. The fiber optic cable addition is included in Chapter 7 and the City's 5-year CIP.

Table ES.5 below summarizes the alternatives evaluated in Chapter 6 including recommendations for future WWTP improvements.

Unit Process	Alternatives Considered	Selected Alternative
Secondary Treatment	<ul> <li>Expansion of the existing conventional activated sludge process.</li> <li>Intensification of the existing treatment process.</li> </ul>	<ul> <li>Expansion of the existing conventional activated sludge process through the addition of another aeration basin. Further phased expansion of capacity through addition of membrane bioreactor (MBR) and fine screening facilities.</li> </ul>
Solids Dryer	<ul> <li>Continue operating the existing BCR paddle dryer and defer replacements.</li> <li>Modify the existing Dewatering and Drying Building to accommodate a different solids dryer technology or a redundant dryer.</li> <li>Construct a new dryer building with a different solids dryer technology.</li> </ul>	<ul> <li>Modify the existing Dewatering and Drying Building to accommodate a different solids dryer technology or a redundant dryer by expanding the Dewatering and Drying Building to accommodate a second solids paddle dryer.</li> </ul>

#### Table ES.5 Summary of Alternatives

#### **ES.8** Recommended Alternative

Figure ES.6 presents a WWTP site plan identifying locations of recommended improvements resulting from condition and capacity assessments, including evaluation of alternatives, as described.

Summaries of opinions of probable costs and anticipated phasing for the improvements recommended for inclusion in the City's WWTP CIP are provided in Table ES.6.

The expected cash flow for the planning period was determined for the recommended improvements summarized in Table ES.6. The cash flow through 2045 includes an escalation rate of three percent, and the estimated peak expenditure for any fiscal year is



Item A.

approximately \$55,434,000 in fiscal year 2030. The projected CIP expenditures are presented in Figure ES.7. Capital costs estimated in the Plan will be considered as the City assesses the need to adjust sewer enterprise rates and charges in coming months. It will be important to distinguish capacity and condition (repair and replacement) driven improvements in assigning costs to existing rate payers and future users.

Plant Area	Project <sup>(1)</sup>	Opinion of Probable Cost <sup>(2)</sup>	Approximate Year Online
Solids Handling	Dewatering Performance Optimization	\$150,000	2025
Communications/IT	Fiber Optic Cable Addition	\$60,000	2025
UV System	Backup UV System Improvement	\$1,705,000	2026
Support Buildings	Seismic Improvements	\$1,082,000	2026
Secondary Treatment	New Conventional Aeration Basin and Blower	\$10,222,000	2027 <sup>(3)</sup>
Secondary Treatment	New Secondary Clarifier Mechanisms	\$1,775,000	2027
Secondary Treatment	New MBR, Blowers and Fine Screens (Phase 1)	\$69,727,000	2031
Solids Handling	Solids Dryer Improvement	\$17,130,000 <sup>(7)</sup>	2033
Solids Handling	Existing Centrifuge and GBT Replacement	\$3,701,000 <sup>(4,6)</sup>	2033 <sup>(5)</sup>
Cooling Towers	New Effluent Cooling Tower	\$642,000	2036
Secondary Treatment	Additional MBR and Blower Capacity (Phase 2)	\$2,330,000	2039
UV System	UV Equipment Replacement	\$2,571,000	2040
Outfall	Outfall Improvements	\$1,244,000	2040
Secondary Treatment	Additional MBR and Blower Capacity (Phase 3)	\$8,117,000	2044
TOTAL		\$120,456,000	

Table ES.6 WWTP CIP - Recommended Alternative Opinion of Probable Cost and Phasing	Table ES.6	WWTP CIP	- Recommended /	Alternative O	pinion of Probable	Cost and Phasing
--	------------	----------	-----------------	---------------	--------------------	------------------

#### Notes:

White rows indicate projects that are in the City's 5-year CIP and blue rows indicate projects that are outside the 5-year CIP window.

(1) Details of each project can be found in Chapter 2 or Chapter 6 of this Master Plan.

- (2) The estimated opinion of probable costs include the construction costs plus ELA (or soft costs). Details on the estimated project costs can be found in Chapter 2 or Chapter 6 of the plan, with the exception of costs for the backup UV system and centrifuges which are presented earlier in Chapter 7. All costs presented are based on an August 2023 ENR index of 13473.
- (3) As identified in Chapter 4, the secondary treatment process at the Wilsonville WWTP is expected to require additional capacity by the year 2027. Since design and construction of a new aeration basin may take longer than the year 2027, the City will likely need to operate at SRTs lower than 5 days during the maximum week condition if growth occurs as predicted in Chapter 3.
- (4) For budgeting purposes, the Option B centrifuge cost from Table H-2 in Appendix H is used for the project cost summary and the CIP.

(5) Replacement timing dependent upon satisfactory equipment performance.

- (6) The centrifuges installed with the City's 2014 upgrade project have exhibited inconsistent performance in recent months. The City recently refurbished these units and expects they will provide sufficient capacity through 2042. However, by that time, the units will have been in service for over 30 years. It is recommended the City plan for replacement of these units during the planning horizon of this Master Plan. Assuming replacement occurs in the mid-2030's the City should reassess capacity needs of those units beyond the 2045 horizon, consistent with the expected service life of the new equipment.
- (7) The existing solids dryer has sufficient capacity through 2045. As with the dewatering centrifuges, the dryer equipment will soon have been in operation for a decade. It is recommended the City plan for replacement of the dryer during the planning horizon of this Master Plan. The City plans to replace the existing dryer with a new piece of equipment using similar technology and potentially rehabilitate the existing unit to serve as a backup. See Alternative 2B, Chapter 6.



The years in which key processes are projected to exceed capacity are presented in Figure ES.8. The green line illustrates projected MM BOD triggers for existing and proposed new secondary treatment facilities. Projected PHF is shown in blue indicating capacity exceedance of the cooling tower and certain elements of plant hydraulics. Prior to the year of projected exceedance, planning, design, and construction activities will be required to allow upgrades to be commissioned to prevent capacity exceedances. It is important to note that the timing of improvements should be driven by the rate of growth in influent flow and load. Dates indicated in Figure ES.8 and elsewhere in this document should be considered best, conservative estimates based on projections presented herein and professional judgment.







Figure ES.6 Proposed WWTP Improvements Site Plan

#### *Carollo*



New Secondary Clarifier Mechanisms

EXECUTIVE SUMMARY | WASTEWATER TREATMENT PLANT MASTER PLAN | CITY OF WILSONVILLE


Figure ES.7 Projected 20-Year CIP Expenditures

Solids Dryer Improvement

MBR Phase 1 + 2 Blowers + Fine Screens + Electrical Upgrades



Item A.




ES-24 | OCTOBER 2023 | FINAL



City of Wilsonville Wastewater Treatment Plant Master Plan

### City Council Work Session November 6, 2023







## **Project Overview and Update**


- Work Completed Since Last Work Session
  - Updated population growth projections and service area boundary
  - Increased existing industrial discharges to maximum allowed by permit limits
  - Expanded seismic resilience analysis
  - Hydraulic modeling of WWTP
  - Updated capital project list and schedule

## **Capital Planning and Expected Growth - 2045**

- Buildout of Service Area
  through 2045
  - Adjusted population growth rate, consistent with recent planning efforts
  - Modified service area boundary, per Basalt Creek Concept Plan

Buildout Population Projections (High 2.9%)

2020	2030	2045	2050
25,915	35,163	46,798	50,388




# **Facility Capacity Assessment**

- Flows & Loads Updated to reflect Buildout of Service Area
- Projected 2045 flows and loads exceed design criteria (~2X current)

Item	2022	Rated Capacity	Projected 2045
Average Dry Weather Flow, mgd	2.06	4.00	4.17
Average Annual Flow, mgd	2.39	4.48	4.77
Maximum Month Wet Weather Flow, mgd	4.00	6.68	7.76
Max Month BOD₅, ppd	11,456	12,900	22,301
Max Month TSS, ppd	9,504	12,500	18,116








Existing Vicinity Map

# **Selection of MBR Process**



Alternative	Advantages	Challenges
Membranes (Selected)	<ul> <li>Space-efficient</li> <li>High-quality effluent</li> <li>Provides capacity for reliable full nitrification</li> <li>No need to expand tertiary filtration</li> </ul>	<ul> <li>Expensive (&gt;2x cost of 4<sup>th</sup> AB)</li> <li>Requires Fine Screening</li> <li>High O&amp;M Costs (Power, Chemicals, etc.)</li> <li>Highest aeration rate</li> <li>Redundancy requirements</li> </ul>
BioMag <sup>®</sup>	<ul> <li>Space-efficient</li> <li>High-quality effluent</li> <li>Potentially no need to expand tertiary filtration</li> <li>Utilizes secondary clarifier capacity (no stranded assets)</li> </ul>	<ul> <li>Requires Magnetite Recovery Facility</li> <li>Increased maintenance requirement from the magnetite</li> <li>Reports of solids smoldering, may require inert gas system</li> <li>Will not provide sufficient capacity under projected 2045 F&amp;L</li> </ul>
IFAS	<ul> <li>Space-efficient</li> <li>Utilizes secondary clarifier capacity (no stranded assets)</li> </ul>	<ul> <li>Will not provide sufficient capacity under projected 2045 F&amp;L</li> <li>Significant basin modifications needed</li> </ul>


# **Recommended Plan**



# **Project Cost**

DESCRIPTION	ESTIMATED TIMEFRAME	AUGUST 2023 PROJECT COST
Dewatering Performance Optimization	2025	\$150,000
Fiber Optic Cable Addition	2025	\$60,000
Backup UV System Replacement	2026	\$1,705,000
Seismic Improvements	2026	\$1,082,000
New Aeration Basin + Blower + Retaining Wall	2025 – 2027	\$10,222,000
Replace Secondary Clarifier Mechanisms	2026 – 2027	\$1,775,000
MBR Phase 1 + 2 Blowers + Fine Screens + Electrical Upgrades	2028 – 2030	\$69,727,000
Solids Dryer Addition	2031 – 2033	\$17,130,000
Thickening + Dewatering	2031 – 2033	\$3,701,000
Additional Cooling Tower	2034 – 2035	\$642,000
MBR Phase 2 + 2 Blowers	2037 – 2038	\$2,330,000
UV Equipment Replacement	2039 – 2040	\$2,571,000
Outfall Improvements	2039 – 2040	\$1,244,000
MBR Phase 3 + 2 Blowers	2042 – 2043	\$8,117,000
TOTAL		\$120,456,000

# **Capacity Trigger Plot**





# **Next Steps**

- Planning Commission Public Hearing 12/13/23
- City Council Public Hearing 1st Reading 1/4/24
- City Council 2nd Reading 1/18/24
- Sewer System Rate Study and SDC Update 2024



# **Questions?**

#### City Council Meeting Action Minutes November 6, 2023

COUNCILORS PRESENT Mayor Fitzgerald	Erika Valentine, Arts & Culture Program Coordinator Jeanna Troha, Assistant City Manager
Council President Akervall – Arrived 7:00 p.m.	Kerry Rappold, Natural Resources Manager
Councilor Linville	Kimberly Veliz, City Recorder
Councilor Berry	Kris Ammerman, Parks and Recreation Director
Councilor Dunwell – Arrived 5:07 p.m.	Mark Ottenad, Public/Government Affairs Director
	Mike Nacrelli, Civil Engineer
STAFF PRESENT	Stephanie Davidson, Assistant City Attorney
Bryan Cosgrove, City Manager	Zach Weigel, City Engineer
Amanda Guile-Hinman, City Attorney	Zack Morse, Parks Maintenance Specialist
Dan Pauly, Planning Manager	Zoe Mombert, Assistant to the City Manager
Delora Kerber, Public Works Director	
Dustin Schull, Parks Supervisor	

AGENDA ITEM	ACTIONS		
WORK SESSION	<b>START:</b> 5:06 p.m.		
A. Wastewater Treatment Plant Master Plan Update	Staff shared analysis that informs an updated draft of the Wastewater Treatment Plant Master Plan.		
B. Stormwater Master Plan Update – Executive Summary and Capital Improvement Project	Staff presented an executive summary of the draft Stormwater Master Plan, a 20-year plan detailing the City's work plan and identifying capital needs to effectively maintain, restore and enhance local watersheds and to meet engineering, environmental and land use needs.		
C. Frog Pond East and South Development Code	Staff sought the Council's feedback to inform development code amendments drafted for the Frog Pond East and South Master Plan.		
D. Boones Ferry Park Projects Update	Staff provided a combined presentation on Resolution Nos. 3088 and 3089, both of which provide upgrades to Boones Ferry Park.		
REGULAR MEETING			
<u>Mayor's Business</u> A. Upcoming Meetings	Upcoming meetings were announced by the Mayor as well as the regional meetings she attended on behalf of the City.		

B.	Proclamation	The Mayor read a proclamation declaring November 2023 as National American Indian Heritage month.					
Comm	unications						
	None.						
Conse	nt Agenda	The Consent Agenda was adopted 5-0.					
Α.	Resolution No. 3088						
	A Resolution Of The City Of Wilsonville Approving A						
	Construction Contract With Romtec, Inc. For The						
	Boones Ferry Restroom Construction Project.						
В.	Resolution No. 3089						
	A Resolution Of The City Of Wilsonville Approving A						
	Construction Contract With Buell Recreation LLC For						
	The Boones Ferry Playground Project.						
	-						
C.	Resolution No. 3090						
	A Resolution Of The City Of Wilsonville Authorizing						
	The City Manager To Execute A Master Services						
	Agreement With OpenGov, Inc. For Asset						
	Management Software Services.						
D.	Resolution No. 3092						
	A Resolution Of The City Of Wilsonville Authorizing						
	The City Manager To Execute A Professional Services						
	Agreement With Century West Engineering For						
	Engineering Consulting Services For The 2024 Street						
	Maintenance Project (Capital Improvement Project						
	No. 4014, 4118, 4725).						
Ε.	Resolution No. 3093						
	A Resolution Of The City Of Wilsonville Accepting The						
	Jurisdictional Surrender For A Portion Of SW Stafford						
	Road And SW Frog Pond Lane By Clackamas County						
	Pursuant To Oregon Revised Statute 373.270.						
F.	Minutes of the October 16, 2023 City Council						
	Meeting.						
	Baselution No. 2001	Decolution No. 2001 uses a douted 5.0					
A.	Resolution No. 3081	Resolution No. 3081 was adopted 5-0.					
	A Resolution Of The City Of Wilsonville Approving The						
	City Of Wilsonville Public Art Policy And Guidelines.						

<ul> <li>B. <u>Resolution No. 3083</u></li> <li>A Resolution Of The City Of Wilsonville Adopting The Arts, Culture, And Heritage Commission (ACHC) FY 2023/24 Five-Year Action Plan And Annual One-Year Implementation Plan.</li> </ul>	Resolution No. 3083 was adopted 5-0.
C. <u>Resolution No. 3091</u> A Resolution Of The City Of Wilsonville Adopting The Findings And Recommendations Of The "Solid Waste Collection Rate Report, October 2023" And Modifying The Current Republic Services Rate Schedule For Collection And Disposal Of Solid Waste, Recyclables, Organic Materials And Other Materials, Effective January 1, 2024.	Resolution No. 3091 was tabled until the December 4, 2023 City Council meeting.
<u>Continuing Business</u> A. None.	
<ul> <li><u>Public Hearing</u></li> <li>A. <u>Ordinance No. 883</u></li> <li>An Ordinance Of The City Of Wilsonville Adopting A Franchise Agreement For Solid Waste Management And Collection Within The City And Repealing Ordinance No. 814.</li> </ul>	After a public hearing was conducted, Ordinance No. 883 was adopted on first and second reading by a vote of 5-0.
<u>City Manager's Business</u>	The City Manager shared staff would arrange a training for Council to prepare them for their trip to Kitakata, Japan.
Legal Business	The City Attorney, who is also a running coach at the Coffee Creek Correctional Facility, shared some feedback from adults in custody who participate in the running program.
ADJOURN	10:10 p.m.



### PLANNING COMMISSION WEDNESDAY, OCTOBER 11, 2023

#### WORK SESSION

4. Wastewater Treatment Plant Master Plan (Nacrelli) (15 minutes)



## PLANNING COMMISSION WORK SESSION STAFF REPORT

Me	Meeting Date: October 11, 2023Subject: Wastewater Treatment Plant Master Plan			eatment Plant Master Plan	
		Staff Member: Mike Nacrelli, Senior Civil Engineer			
			Department: Community Development		
Act	ion Required		Adv	isory Board/Commi	ssion Recommendation
	Motion			Approval	
	Public Hearing Date:			Denial	
	Ordinance 1 <sup>st</sup> Reading Dat	e: 🗌 None Forwarded			
	Ordinance 2 <sup>nd</sup> Reading Dat	te: 🛛 Not Applicable			
	Resolution	Comments: N/A			
$\boxtimes$	Information or Direction				
	Information Only				
	Council Direction				
	Consent Agenda				
Staff Recommendation: Provide requested input regarding recommended capital			ommended capital		
improvement plan.					
Recommended Language for Motion: N/A					
Project / Issue Relates To:					
⊠C	⊠Council Goals/Priorities: □Ado		pted	Master Plan(s):	□Not Applicable
Alig	n Infrastructure Plans	ifrastructure Plans			
with	n Sustainable Financing				
Sou	rces				

#### ISSUE BEFORE PLANNING COMMISSION:

Provide feedback and input on components of the Wastewater Treatment Plant (WWTP) Master Plan.

Wastewater Treatment Plant Master Plan Work Session Staff Report Planning Commission Meeting - October 11, 2023 Wastewater Treatment Plant Master Plan

#### **EXECUTIVE SUMMARY**:

This new City of Wilsonville (City) Wastewater Treatment Plant (WWTP) Master Plan (the Plan) has been developed to satisfy requirements associated with the State of Oregon Department of Environmental Quality (DEQ) guidance document entitled "Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities." To accommodate future flows and loads, projections were developed based on population projections and referencing WWTP historical data and DEQ wet weather project methodologies. Similarly, to accommodate future water quality regulations, the Plan is adaptive and considers potential future regulatory changes.

The City prepared the Plan with the goal of developing a capital plan that identifies improvements required through the planning period (today through 2045) to comply with requirements of the WWTP National Pollutant Discharge Elimination System (NPDES) permit and potential future regulatory requirements, while accommodating growth identified in the City of Wilsonville Comprehensive Plan (October 2018, updated June 2020 - the 2018 Comprehensive Plan). These improvements are designed to provide the best value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development, consistent with goals and policies contained in the 2018 Comprehensive Plan and 2021-2023 City Council Goals.

The City's WWTP was originally built in 1971 and discharges treated effluent to the Willamette River. The WWTP underwent major upgrades in 2014 to expand the average dry weather capacity to four million gallons per day (mgd) to accommodate the City's continued growth. The WWTP processes include headworks screening and grit removal facilities, aeration basins, stabilization basins, secondary clarifiers, biosolids processing, cloth filtration, and disinfection processes. Additionally, the City contracts with Jacobs for operation of the wastewater treatment plant, located at 9275 Southwest Tauchman Road.

This Plan identifies improvements taking into consideration:

- The age and condition of existing process equipment and structures,
- Growth in demand for sewer service due to increased population and economic development over the planning period,
- Potential changes to water quality regulations impacting process needs in order to meet effluent limitations and discharge prohibitions imposed by the Oregon Department of Environmental Quality (DEQ), and
- Consistency with the 2018 Comprehensive Plan and City Council 2021-2023 Goals 5, 6, & 7.

#### Updated Growth Projection and Capital Improvement Plan

At the previous work session (9/14/2022), the team presented the capital improvement plan based on an assumed 2.9% annual population increase, consistent with recent planning documents adopted by the City, including the Wastewater Collection System Master Plan (CSMP, November 2014) and the Willamette River Water Treatment Plan Master Plan Update (March 2018). The flow and load projections have been further updated to account for increases in industrial discharges, as allowed under existing permits. This change results in a higher level of capital investment over the planning period, mainly due to hydraulic upgrades, as reflected in the table below.

Project Description	Timeframe	Cost*	
Dewatering Performance Optimization	2025	\$150,000	
Fiber Optic Conduit Addition	2025	\$60,000	
UV System Improvement	2026	\$1,705,000	
Seismic Improvements	2026	\$1,082,000	
New Aeration Basin and Blower	2025 – 2027	\$10,179,000	
Replace Secondary Clarifier Mechanisms	2026 - 2027	\$1,775,000	
Membrane Bioreactor (MBR) Phase 1 (includes new blower, fine screens,	2028 – 2030	\$69,637,000	
electrical and hydraulic upgrades)			
New Solids Dryer	2031 – 2033	\$17,130,000	
Thickening and Dewatering Improvements	2031 – 2033	\$3,701,000	
New Cooling Tower	2037 – 2038	\$642,000	
MBR Phase 2 (includes new blower)	2037 – 2038	\$2,242,000	
UV Equipment Replacement and Outfall Upsizing	2039 – 2040	\$2,571,000	
UV Equipment Replacement and Outfall Upsizing	2039 – 2040	\$1,244,000	
MBR Phase 3 (includes 2 new blowers)	2042 – 2043	\$8,030,000	
Total \$120,148,00			
*Costs are shown in 2023 dollars and include 25% for engineering, legal, and administration.			

As shown in the table above, the most significant impact to the required level of capital investment is the need for membrane bioreactor (MBR) facilities. These are state-of-the-art, compact facilities that provide a high level of treatment. The adjusted growth projection results in an approximate doubling of the City population over the planning period. Due to the limited amount of space available at the existing WWTP site, MBR facilities are the only feasible means of providing the necessary treatment to accommodate such a substantial rate of growth.

#### Question for the Planning Commission:

What input does the Planning Commission have on the updated capital improvements list for the Wastewater Treatment Plant Master Plan?

#### EXPECTED RESULTS:

The Plan includes a list of recommended capital improvements, along with an anticipated schedule for completion and preliminary cost estimates. These improvements will provide the basis for an analysis of sewer rates and system development charges (SDCs) that will be necessary to provide adequate funding to implement to required upgrades.

#### TIMELINE:

This is the third in a series of presentations to the Planning Commission and City Council. Completed and planned meetings are as follows:

• Planning Commission Work Session 7/13/22 (completed)

- City Council Work Session 8/1/22 (completed)
- Planning Commission Work Session 9/14/22 (completed)
- Planning Commission Work Session 10/11/23 (current)
- City Council Work Session 11/6/23
- Planning Commission Public Hearing 12/13/23
- City Council Public Hearing 1st Reading 1/4/24
- City Council 2nd Reading 1/18/24

#### CURRENT YEAR BUDGET IMPACTS:

The remaining contract balance for finalizing the Plan will be expended this fiscal year. An additional \$92,450 has been budgeted in FY 23/24 for the Sewer System Rate Study and SDC Update, using a combination of Sewer Operating funds and SDCs.

#### COMMUNITY INVOLVEMENT PROCESS:

The public hearings listed above will provide opportunity for public input. In addition, the Sewer System Rate Study and SDC Update will include a robust public engagement process.

#### POTENTIAL IMPACTS or BENEFIT TO THE COMMUNITY:

A technically and financially sound plan for providing reliable wastewater treatment, capacity to accommodate future development, and compliance with environmental regulations.

#### ALTERNATIVES:

The Plan is based on a projected population growth rate that is somewhat aggressive but is consistent with other recently adopted planning documents and with historical growth data. The capital project schedule can be adjusted as appropriate if actual growth rates differ significantly from the projected growth included in the Plan. In addition, some of the recommended hydraulic upgrades might avoided, depending on the results of more detailed analysis of storage and attenuation in the wastewater collection system, when the next CSMP update is completed.

#### ATTACHMENTS:

N/A

City of Wilsonville Wastewater Treatment Plant Master Plan

Planning Commission Work Session October 11, 2023



### WILSONVILLE OREGON



## Introduction

**Presenters:** 

## Mike Nacrelli, PE, Senior Civil Engineer

## Dave Price, PE, Carollo Engineers



## **Status Update**

- Accommodating Expected Build-Out by 2045
  - Increased industrial discharges to permitted limits
- Capacity Assessment Complete


   Includes hydraulic modeling of WWTP
- Costs and Schedule for Updated CIP
- Update of Master Plan



## **Capital Planning and Expected Growth - 2045**


- Current Service Area needs
  - 20+ years through 2045
    - Population and associated economic development

2020	2030	2030 2045	
25,915	35,163	46,798	50,388



## **Buildout Service Area - 2045**

Land Use	Acreage
Commercial	224
Industrial	2,383.2
Public	482.9
Residential	2,278.3
Town Center	136.1
Village	367.4



# **Facility Capacity Assessment**

- Flows & Loads Updated to reflect Buildout of Service Area
- Projected 2045 flows and loads exceed design criteria (~2X current)

Item	2022	Rated Capacity	Projected 2045
Average Dry Weather Flow, mgd	2.06	4.00	4.17
Average Annual Flow, mgd	2.39	4.48	4.77
Maximum Month Wet Weather Flow, mgd	4.00	6.68	7.76
Max Month BOD₅, ppd	11,456	12,900	22,301
Max Month TSS, ppd	9,504	12,500	18,116



## **Unit Process Capacity Summary**


Unit Process	Capacity Limit	Redundancy Criteria	Possible Year of Capacity Exceedance	Identified Alternatives
Secondary Treatment	MW MLSS inventory @ PDF	All units in service	2027	New Aeration Basin
Additional Secondary Treatment	MM MLSS inventory @ PDF	One train out of service	2031, 2039, 2044	Membrane Bioreactor
Effluent Cooling Towers	6 MGD (May 1 – October 31)	All units in service	2039	<ul> <li>Additional Cooling Tower</li> </ul>
UV Effluent/Outfall	16 MGD	All units in service	2041	<ul> <li>Upsizing outfall piping of MH-B to future MH-E</li> </ul>

# **Alternatives Evaluation**



- Consider alternatives for process units identified as capacity deficient
- Secondary Process
  - Add new Aeration Basin & additional blower
  - Phase MBR technology (includes hydraulic upgrades)
- Solids Thickening and Dewatering
  - Replace GBTs and Centrifuge units during the planning period expected useful life
- UV System and Outfall Piping
  - Replace aging equipment and upgrade hydraulic capacity
- Prior conclusions plan to replace based on condition/age during planning period:
  - Backup UV system
  - Solids dryer
  - Dewatering Centrifuges
  - Thickening GBTs

### **Recommended Plan**



New Aeration Basin
Additional Aeration Blowers
New Fine Screens
New Emergency Generator
New MBR Facility
New Cooling Tower
Replace backup UV system
Plan to replace Solids Dryer & Centrifuges

- 5 6 Replace Clarifier 1 & 2 mechanisms
- 4 8 17 Seismic retrofits of buildings
  - 18 New fiber optic connection

Solids process study

# **Proposed Project Phasing Schedule**




# **Project Cost**

DESCRIPTION	ESTIMATED TIMEFRAME	AUGUST 2023 PROJECT COST
Dewatering Performance Optimization	2025	\$150,000
Fiber Optic Cable Addition	2025	\$60,000
Backup UV System Improvement	2026	\$1,705,000
Seismic Improvements	2026	\$1,082,000
New Aeration Basin + Blower + Retaining Wall	2025 – 2027	\$10,179,000
New Secondary Clarifier Mechanisms	2026 – 2027	\$1,775,000
MBR Phase 1 + 2 Blowers + Fine Screens + Electrical Upgrades	2028 – 2030	\$69,637,000
Solids Dryer Improvement	2031 – 2033	\$17,130,000
Thickening + Dewatering	2031 – 2033	\$3,701,000
Cooling Tower	2037 – 2038	\$642,000
MBR Phase 2 + 2 Blower	2037 – 2038	\$2,242,000
UV Equipment Replacement	2039 – 2040	\$2,571,000
Outfall Improvements	2039 – 2040	\$1,244,000
MBR Phase 3 + 2 Blower	2042 – 2043	\$8,030,000
TOTAL		\$120,148,000

## **Estimated Cash Flow**





- New Aeration Basin + Blower + Retaining Wall
- Fiber Optic Cable Addition
- Cooling Tower
- MBR Phase 2 + 2 Blowers
- MBR Phase 1 + 2 Blowers + Fine Screens + Electrical Upgrades
- Solids Dryer Improvement

- Seismic Improvements
  - ■MBR Phase 3 + 2 Blower
- Thickening + Dewatering
- Backup UV System Improvement
- New Secondary Clarifier Mechanisms

## **Next Steps**



- City Council Work Session 11/6/23
- Planning Commission Public Hearing 12/13/23
- City Council Public Hearing 1st Reading 1/4/24
- City Council 2nd Reading 1/18/24
- Sewer System Rate Study and SDC Update 2024



- Ms. Weiland added that LID and vegetated stormwater facilities provided truly good pollutant removal in accordance with effectiveness information that was well documented. Different processes were used, and vegetation enhances uptake. Through these facilities, retention and infiltration of stormwater was encouraged, which was another means to remove pollutants before they discharged via overland flow or pipe flow into receiving water, so the types of facilities proposed were intentionally in alignment with the City's design standards and MS4 permit requirements.
- 4. Wastewater Treatment Plant Master Plan (Nacrelli)

Mike Nacrelli, Senior Civil Engineer, and Dave Price, Senior Civil Engineer, Carollo Engineers, presented on the update Wastewater Treatment Plant Master Plan via PowerPoint, reviewing key components of the Master Plan which would accommodate expected demand for build out by 2045. Highlights included details regarding the completed facility capacity assessment, costs and a schedule for the updated Capital Improvements Program (CIP), an alternatives evaluation and a breakdown of costs by project, estimated cash flow, and the next steps for advancing the Master Plan for adoption.

and the additional changes since the last work session with the Commission.

Discussion and feedback from the Planning Commission was as follows with responses by Staff to Commissioner questions as noted:

- In September 2022, the estimate was \$75 million which moved to \$120 million in the span of a year with the increased industrial discharges.
  - Mr. Nacrelli noted an oversight in the presentation, stating the \$75 million had not included the engineering portion, it was only construction. The actual cost should have been in the \$90,000s.
- If the project were not space constrained, what would the project cost and overall plan look like? Would clarifiers be added instead of adding a membrane bioreactor (MBR)? Considering the huge sum of money involved, maybe it would be cheaper overall to acquire some additional land south of the existing facility to add more equipment, rather than this huge increase for the MBR. The river was south of the facility, but there were a lot of trees that could be cut down.
  - Mr. Nacrelli responded Staff could cost out what a conventional expansion would take and how much land would be required; however, the direction provided was that there was no room to grow.
  - Ms. Guile-Hinman understand the facility was all surrounded by Boones Ferry Park, and there were deed restrictions that did not allow the City to use it for anything other than a recreational use.
  - Mr. Nacrelli clarified the land on the east side had a large grade adjacent to where the new aeration basin would go in the northeast corner.
  - Mr. Price added a significant retaining wall would have to be built there in order to put in the additional aeration basin, so the area was already tight due to the slopes.
  - At a high level, it would be good to double check that there is no physical space to put in a conventional facility, because this was a huge sum of money, especially with the \$60 million outlay in 2030. It would be good to make sure the City was looking at all the options out there.

- Mr. Nacrelli stated they could run the numbers and understand how much space would be needed, but he was pretty satisfied with the property footprint; perhaps he could come up with a map that extended beyond the area.
- If deed restrictions prevented the City for adding land, no additional analysis was needed, but if there was space or an opportunity to be creative, then be creative about a more conventional plant. If not, then just let the Commission know.
  - Mr. Price added access was also required on the site for trucks with trailers, so there was limitations with travel ways and the plan did not show the slopes on three sides of the site. Based on the team's analysis, there were not too many square feet on the site that were not already being used. When the facility was upgraded in 2011/2012, one notion was that beyond the three existing aeration basins and clarifiers that the next step was to put some [inaudible] but he believed that project predated the collection system at the time, so it did not evaluate the full indications of what that might be. He wanted to make sure the Commission considered the conventional options as well as the expectations coming out of the Master Plan update and whether things could be [inaudible] or reduced. A scenario that would reduce the cost of Phase 1, but would be at least \$10 million to eliminate the need for some of those future projects, which would be something to think about, because in that scenario the City would be running kind of a combined conventional/membrane plant. The two distinct clarifiers would not go away until Phase 3. The project team was trying to preserve the City's conventional facility for as long as possible, but it would cost to maintain the existing facilities and give you less energy for chemicals to operate that facility than a more complicated, high intensity system line an MBR.
- Mr. Nacrelli suggested they could add property lines and contours to the site plan. (Slide 9) Regarding an increase in industrial discharge, what was the current industrial discharge versus what was in the plan versus what is the maximum? And where was the City in that window, right at the maximum of what was theoretically possible from the permits in this plan, or some amount lower than that? That information would be helpful to have for the next go around.
  - Mr. Nacrelli believed they could provide those numbers, which would be in the Master Plan attached to the Staff report. He confirmed the assumption was that all the City's permanent industries would be discharging the maximum amount, which they were not currently doing, so that was a pretty significant impact, especially since they were higher dischargers. The lows were just as important to evaluate capacity. Those numbers would be incorporated into the slides.
- Incorporating the risks of not implementing the recommended plan in the master plan was suggested. Communities along the Willamette were having wastewater failures and having boil orders for water. Articulate the consequences of not doing this to our river environment would be great.
  - Mr. Nacrelli responded a chapter in the regulatory constraints essentially stated that once you start exceeding your limits, you get financial [inaudible], and the City could get to a point where a moratorium would have to be issued until the issues were fixed.
  - Mr. Price added that typically with improvement at this scale, community outreach would be incorporated into the more detailed planning and design steps to help educate people about rates and charges and to make sure the message got out there about why these improvements were needed.

- With only two funding sources noted, rates and SDCs, at the current rates and expected SDCs, what was the City's shortfall and how would that shortfall be made up?
  - Mr. Nacrelli responded [inaudible] not part of the Master Plan's scope, noting the rate study would delve into those details.
  - Mr. Price added also need to consider the condition-related verses capacity-related improvements.
- Mr. Nacrelli confirmed the rate study would be completed after City Council adopted the Master Plan.
  - A comment was made that the City was creating the Master Plan without knowing how to pay for it, which was not how budgeting worked in real life.
- Zach Weigel, City Engineer, added further context on how the master planning worked. The City was going to grow to a certain population, and these projects were needed for the treatment plant to meet the population demand. When master planning, the needs were identified, then a rate study determined the impact on fees and development costs.
- Mr. Weigel confirmed a certain portion of development fees went toward wastewater, and each CIP project would be split on base with a portion that serves new development and serves existing customers, and that portion of new growth gets figured into the SDC cost.
- SDCs affect affordability.
- The Commission discussed growth rates when the housing report came out, and the City's actual growth numbers were outpacing Metro's projections. Which numbers were used in the Master Plan engineering?
  - Mr. Weigel stated the project team used the same numbers from the collection system master plan, which was an aggressive growth rate that was trending with what the City has been seeing over the last 10 years on average. It was hard to know what was going to happen. Was it going to slow down? Was Metro going to put limits on the City to meet certain housing projections? Staff believed the aggressive growth rate was the right measure to use for this Master Plan.
  - Mr. Nacrelli noted the Master Plan numbers were compared with Metro's Transportation Analysis projections, and they were very close.
  - Mr. Weigel confirmed there was really no way to avoid MBR. There were ways to avoid additional chambers of MBR that Staff would be tracking over time, but that was typical with a master plan; the needs were identified, population growth, flow, and needs were tracked over time, and the projects were implemented when they were needed. And then, every 10 years or so, the Master Plan is updated when a deeper dive is taken into the data to make sure the City was following those projections and then updating the Master Plan as needed.

Chair Heberlein called for a brief recess and reconvened the meeting at 8:45 pm.

#### INFORMATIONAL

5. 2023 Transportation Performance Monitoring Report (Pepper)

Amy Pepper, Development Engineering Manager, presented a report card on the City's performance of the City's Transportation System Plan (TSP), its policies, programs, and projects, and how the City's projects had measured up to Goals 1 through 7 of the TSP, along with recommended actions to lead to desired outcomes. A full update of the report was included in the packet.



### PLANNING COMMISSION WEDNESDAY, OCTOBER 12, 2022

#### PUBLIC HEARING

2. Wastewater Treatment Plant Master Plan (Nacrelli) (No staff presentation) - CANCELLED



#### MEMO Engineering Division

RE:	Cancellation of October 12, 2022 Public Hearing for the Wastewater Treatment Plant Master Plan
FROM:	Mike Nacrelli, PE Senior Civil Engineer
TO:	Planning Commission
DATE:	October 5, 2022

The Wastewater Treatment Plant (WWTP) Master Plan has used a study area boundary consistent with recently completed master planning documents, including the 2012 Water System Master Plan, the 2014 Wastewater Collection System Master Plan, and the 2017 Water Treatment Plant Master Plan. However, the 2018 Basalt Creek Concept Plan has altered the future service area that will send flows to the WWTP, requiring further analysis of the projected wastewater flows and loads and the planned capital improvements to provide the needed treatment capacity. In order to allow adequate time to complete this additional analysis, I request that the public hearing for the WWTP Master Plan currently scheduled with the Planning Commission for October 12, 2022 be cancelled and rescheduled for February 8, 2023.

Respectfully,

Michael Macrell

Project Manager

CITY OF WILSONVILLE • COMMUNITY DEVELOPMENT DEPT.

29799 SW Town Center Loop East Planning Commission Meeting - October 12, 2022 Wastewater Treatment Plant Master Plan www.ci.wilsonville.or.us info@ci.wilsonville.or.us

Commissioner Mesbah asked if **Mr. Nacrelli** meant a certain quality of effluent since anything produces effluent; perhaps, "high quality effluent" should be used.

**Mr. Nacrelli** agreed something might be missing there, but without hearing the recording, the quality of effluent was the only thing that made sense.

**Amanda Guile-Hinman, City Attorney**, advised postponing the consideration of the minutes to allow time to check the audio recording.

Chair Heberlein stated consideration of the September 14, 2022 Planning Commission Minutes would be delayed to the next Planning Commission meeting to clarify the language on Page 9.

#### LEGISLATIVE HEARING

2. Wastewater Treatment Plant Master Plan (Nacrelli) (No staff presentation) - CANCELLED

Chair Heberlein noted tonight's public hearing had been cancelled and would be rescheduled to a later date.

**Miranda Bateschell, Planning Director**, asked that anyone present for the hearing add their contact information to the sign in sheet to receive notification about the new public hearing date. She also offered to provide the project manager's business card.

#### WORK SESSION

3. Transit Master Plan (Lewis)

**Kelsey Lewis, SMART Grants and Programs Manager**, introduced the City consultant who would present information about the public engagement conducted on the Master Plan over the summer.

**Brenda Martin, Consultant, Envirolssues**, presented via PowerPoint a summary of the engagement conducted as part of the SMART Transit Master Plan Update. She highlighted the purpose of the Master Plan Update and described the outreach methods used to gather public input from various stakeholders and diverse groups of citizens, including underrepresented communities. She also reviewed the key findings from the data collected from surveys and the stakeholder's workshop which identified ridership patterns and included requests for transit time and frequency changes, as well as additions to SMART's service routes, which included connections to other destinations in the region.

Questions from the Commission were as follows with responses as noted:

- Why was there such a low turnout for the in-person stakeholder workshop where only 18 people attended after more than 100 invites were sent out?
  - **Ms. Martin** noted the project team made about 150 calls and sent emails, but she believed that ultimately, it was just the day and time, coupled with not being able to invite the right people to come from certain organizations due to changes in employment. The team did share the survey with most of those invitees, so the team did collect some feedback from those organizations. She believed having one time and place for attendance was difficult for some people.



### PLANNING COMMISSION WEDNESDAY, SEPTEMBER 14, 2022

#### WORK SESSION

3. Wastewater Treatment Plant Master Plan (Nacrelli) (30 minutes)



### PLANNING COMMISSION WORK SESSION STAFF REPORT

Meeting Date: September 14, 202	Subject: Wastewater Treatment Plant Master Plan		
	Staff Member: Mike Nacrelli, Senior Civil Engineer		
	Department: Community Development		
Action Required	Advisory Board/Commission Recommendation		
□ Motion	□ Approval		
□ Public Hearing Date:	□ Denial		
$\Box$ Ordinance 1 <sup>st</sup> Reading Date:	□ None Forwarded		
$\Box$ Ordinance 2 <sup>nd</sup> Reading Date:	☑ Not Applicable		
□ Resolution	Comments: N/A		
☑ Information or Direction			
□ Information Only			
□ Council Direction			
□ Consent Agenda			
Staff Recommendation: Provid	e requested input regarding recommended capital		
improvement plan.			
Recommended Language for	Motion: N/A		
Project / Issue Relates To:			
	Adopted Master Plan(s):		
Align infrastructure plans with sustainable financing resources.			

#### **ISSUE BEFORE PLANNING COMMISSION:**

Provide feedback and input on components of the Wastewater Treatment Plant (WWTP) Master Plan.

#### **EXECUTIVE SUMMARY:**

This new City of Wilsonville (City) Wastewater Treatment Plant (WWTP) Master Plan (the Plan) has been developed to satisfy requirements associated with the State of Oregon Department of Environmental Quality (DEQ) guidance document entitled "Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities." To accommodate future flows and loads, projections were developed based on population projections and referencing WWTP historical data and DEQ wet weather project methodologies. Similarly, to accommodate future water quality regulations, the Plan is adaptive and considers potential future regulatory changes.

The City prepared the Plan with the goal of developing a capital plan that identifies improvements required through the planning period (today through 2045) to comply with requirements of the WWTP National Pollutant Discharge Elimination System (NPDES) permit and potential future regulatory requirements, while accommodating growth identified in the City of Wilsonville Comprehensive Plan (October 2018, updated June 2020 - the 2018 Comprehensive Plan). These improvements are designed to provide the best value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development, consistent with goals and policies contained in the 2018 Comprehensive Plan and 2021-2023 City Council Goals.

The City's WWTP was originally built in 1971 and discharges treated effluent to the Willamette River. The WWTP underwent major upgrades in 2014 to expand the average dry weather capacity to four million gallons per day (mgd) to accommodate the City's continued growth. The WWTP processes include headworks screening and grit removal facilities, aeration basins, stabilization basins, secondary clarifiers, biosolids processing, cloth filtration, and disinfection processes. Additionally, the City contracts with Jacobs for operation of the wastewater treatment plant, located at 9275 Southwest Tauchman Road.

This Plan identifies improvements taking into consideration:

- The age and condition of existing process equipment and structures,
- Growth in demand for sewer service due to increased population and economic development over the planning period,
- Potential changes to water quality regulations impacting process needs in order to meet effluent limitations and discharge prohibitions imposed by the Oregon Department of Environmental Quality (DEQ), and
- Consistency with the 2018 Comprehensive Plan and City Council 2021-2023 Goals 5, 6 and 7.

#### Updated Growth Projection and Capital Improvement Plan

The previous (7/13/2022) work session included a capital improvement plan based on population growth projections over the planning period obtained from Metro. The growth projections have since been updated to an assumed 2.9% annual population increase, consistent with recent planning documents adopted by the City, including the Wastewater Collection System Master Plan (November 2014) and the Willamette River Water Treatment Plan Master Plan Update (March 2018). This change results in a considerably higher level of capital investment over the planning period, as reflected in the table below.

Timeframe	Cost*
2023	\$155,724
2023	\$1,370,369
2023	\$45,679
2024	\$841,323
2025	\$6,928,208
2026	\$1,382,827
2028 - 2029	\$31,811,200
2031 - 2032	\$13,371,479
2033 - 2034	\$6,211,200
2035	\$2,854,359
2036 - 2037	\$452,138
2038	\$4,742,400
2040 - 2041	\$5,142,400
	\$75,309,306
	$\begin{array}{r} 2023\\ 2023\\ 2023\\ 2024\\ 2025\\ 2026\\ 2028 - 2029\\ \hline \\ 2031 - 2032\\ 2033 - 2034\\ 2035\\ 2036 - 2037\\ 2038\\ \hline \end{array}$

As shown in the table above, the most significant impact to the required level of capital investment is the need for membrane bioreactor (MBR) facilities. These are state-of-the-art, compact facilities that provide a high level of treatment. The adjusted growth projection results in an approximate doubling of the City population over the planning period. Due to the limited amount of space available at the existing WWTP site, MBR facilities are the only feasible means of providing the necessary treatment to accommodate such a substantial rate of growth.

#### **EXPECTED RESULTS:**

The Plan includes a list of recommended capital improvements, along with an anticipated schedule for completion and preliminary cost estimates. These improvements will provide the basis for an analysis of sewer rates and system development charges (SDCs) that will be necessary to provide adequate funding to implement to required upgrades.

#### TIMELINE:

This is the third in a series of presentations to the Planning Commission and City Council. Completed and planned meetings are as follows:

- Planning Commission Work Session 7/13 (completed)
- City Council Work Session 8/1 (completed)
- Planning Commission Work Session 9/14
- Planning Commission Public Hearing 10/12
- City Council Work Session 11/7
- City Council Public Hearing 1st Reading 11/21
- City Council 2nd Reading 12/5

#### **CURRENT YEAR BUDGET IMPACTS:**

The remaining contract balance for finalizing the Plan will carry over into FY 22/23. An additional \$92,450 has been budgeted in FY 22/23 for the Sewer System Rate Study and SDC Update, using a combination of Sewer Operating funds and SDCs.

#### COMMUNITY INVOLVEMENT PROCESS:

The public hearings listed above will provide opportunity for public input. In addition, the Sewer System Rate Study and SDC Update will include a robust public engagement process.

#### POTENTIAL IMPACTS or BENEFIT TO THE COMMUNITY:

A technically and financially sound plan for providing reliable wastewater treatment, capacity to accommodate future development, and compliance with environmental regulations.

#### ALTERNATIVES:

The Plan is based on a projected population growth rate that is somewhat aggressive but is consistent with other recently adopted planning documents and with historical growth data. The capital project schedule can be adjusted as appropriate if actual growth rates differ significantly from the projected growth included in the Plan.

#### ATTACHMENTS:

N/A

**City of Wilsonville** Wastewater Treatment **Plant Master Plan** 

### **Planning Commission Work** Session September 14, 2022



WILSONVILLE OREGON

### Introduction

**Presenters:** 

### Mike Nacrelli, PE, Senior Civil Engineer

### Dave Price, PE, Carollo Engineers



### **Status Update**

- July 13 Work Session Comments
- Accommodating Expected Build-out UGB Growth
- Capacity Assessment Complete
- Costs and Schedule for Updated CIP Drafted
- Update of Master Plan Chapters in Progress
- September 28 Open House



# **Facility Capacity Assessment**

- Flows & Loads Updated to reflect Build-out of USB
- Existing WWTP design (2014 expansion) ADWF 4 mgd
- Projected 2045 flows and loads exceed design criteria (~2X current)

Item	Existing	Projected 2045
Average Dry Weather Flow, mgd	1.93	4.16
Average Annual Flow, mgd	2.23	4.77
Maximum Month Wet Weather Flow, mgd	3.78	7.92
Average Annual BOD <sup>®</sup> , ppd	7,534	16,333
Average Annual TSS, ppd	6,484	13,789

## **Unit Process Capacity Summary**


Unit Process	Design Parameter	Redundancy Criteria	Possible Year of Capacity Exceedance	Identified Alternatives
Secondary Treatment	MM MLSS inventory @ PDF	All units in service	2026	<ul> <li>New Aeration Basin</li> <li>New Secondary Clarifier</li> </ul>
Aeration Blowers	Peak BOD Load	Largest unit out of service	2026	Additional Blower
Additional Secondary Treatment	MM MLSS inventory @ PDF	One train out of service	2031, 2034, 2038, 2042	Membrane Bioreactor
Effluent Cooling Towers	6 MGD (May 1 – October 31)	All units in service	2037	<ul> <li>Additional Cooling Tower</li> </ul>

# **Alternatives Evaluation**



- Consider alternatives for process units identified as capacity deficient
- Secondary Process
  - Add new Aeration Basin & additional blower 2026
  - Phase MBR technology starting later
- Solids Thickening and Dewatering
  - Replace GBTs and Centrifuge units during the planning period
     expected useful life
- Prior conclusions plan to replace based on condition/age during planning period:
  - Backup UV system
  - Solids dryer
  - Dewatering Centrifuges
  - Thickening GBTs

## **Recommended Plan**




 New Aeration Basin
 Additional Aeration Blowers
 New Fine Screens
 New Emergency Generator
 New MBR Facility
 New Cooling Tower
 Replace backup UV system
 Plan to replace Solids Dryer & Centrifuges

- 5 6 Replace Clarifier 1 & 2 mechanisms
- 4 8 17 Seismic retrofits of buildings
  - 18 New fiber optic connection

Solids process study

# **Proposed Project Phasing Schedule**




# Project Costs (2022 Dollars)

DESCRIPTION	TIMEFRAME	ESTIMATED COST	TOTAL WITH 25% E, L, & A
Dewatering Performance Optimization	2023	\$ 155,724	\$ 155,724
Trojan 4000 UV System Improvement	2023	\$ 1,370,369	\$ 1,712,961
Fiber Optic Conduit Addition	2023	\$ 45,679	\$ 57,099
Seismic Improvements	2024	\$ 841,323	\$ 1,051,654
New Aeration Basin + Blower + Retaining Wall	2025	\$ 6,928,208	\$ 8,660,260
Replace Secondary Clarifier Mechanisms	2025 – 2026	\$ 1,382,827	\$ 1,728,534
MBR Phase 1 + 1 Blower + Fine Screens + Electrical Upgrades	2028 – 2030	\$ 31,811,200	\$ 39,764,000
New Solids Dryer	2031 – 2033	\$ 13,371,479	\$ 16,714,349
MBR Phase 2 + 1 Blower	2033 – 2034	\$ 6,211,200	\$ 7,764,000
Thickening + Dewatering	2035	\$ 2,854,359	\$ 3,567,948
New Cooling Tower	2037	\$ 452,138	\$ 565,173
MBR Phase 3 + 2 Blowers	2037 – 2038	\$ 4,742,400	\$ 5,928,000
MBR Phase 4 + 2 Blowers	2040 – 2041	\$ 5,142,400	\$ 6,428,000
TOTAL		\$ 75,309,306	\$ 94,097,702

## **Draft Cash Flow**





## **Next Steps**

- Virtual Public Open House (9/28)
- Planning Commission Public Hearing 10/12
- DEQ review and approval of Plan
- City Council Work Session 11/7
- City Council Public Hearing 1<sup>st</sup> Reading 11/21
- City Council 2<sup>nd</sup> Reading 12/5
- Sewer System Rate Study and SDC Update FY23






### **Reference Slides**

### **Capital Planning and Expected Growth - 2045**

- Current Service Area needs
   20+ years through 2045
  - Population and associated economic development

2015	2020	2030	2045
22,870	25,915	29,756	30,566




# **Condition Assessment**

- Prioritize 2019 findings of consultant assessments
  - Secondary clarifiers
  - UV system
- Geotechnical and seismic evaluations
  - Older buildings found to present moderate risk
  - Identified mitigations to address seismic concerns
    - Operations Building
    - Process Gallery
    - Workshop



## **Alternatives Evaluation**

- Solids Dryer driven by performance, not capacity
  - Further study, placeholder to expand dewatering and drying building, add new paddle dryer, refurbish existing dryer (backup)
  - Largest potential investment in Master Plan



# **Asset Condition Assessment**



- 2014 project facilities and equipment in service > 30 years by 2045
- Solids facilities
  - Performance issues
    - Solids Dryer fire (2019), component failures (2021), uneven performance
    - Solids Dewatering Centrifuges uneven performance (2020/21)
- Secondary clarifiers Pre-date 2014 upgrades, near term mechanism replacements, clarifiers no. 1 and 2
- UV Disinfection backup unit pre-dates 2014 upgrades, near term replacement

# **Potential Regulatory Drivers**

- DEQ Total Maximum Daily Load (TMDL) Lower Willamette River
- Dissolved oxygen & nutrients
  - Nutrients can contribute to low oxygen conditions
  - Anticipate and accommodate future phosphorous, possibly nitrogen limits
- Pay attention to Willamette River temperature concerns



- **Mr. Green** replied some probability or possibility of growth happening was anticipated if there was an expansion of the airport area, resulting in the development area potentially expanding outward as well.
  - He clarified these were not necessarily trying to anticipate specific events happening that would lead to development in those areas. It was saying development in the area around the airport, such as an industrial development located one parcel away from the through the fence, might occur due to its proximity to the airport.

**Ms. Bateschell** clarified the project team had a work session with the City Council on Monday to review the draft policies and get Council's input. The collective input received would refine what came before the Commission in November.

3. Wastewater Treatment Plant Master Plan (Nacrelli)

**Mike Nacrelli, Senior Civil Engineer** updated on the progress of the Wastewater Treatment Master Plan (WWTP) process via PowerPoint noting the growth projections presented to the Commission in July were based on lower growth projections from Metro. Following discussions with the Planning Commission and internal with management, the project team [we] went back and looked at the higher growth curve, which was just under 3 percent annually, and reran the numbers for the modeling of the flows and loads at the plant, as well as the impact on plant capacity and the capital investment required to handle that level of growth, which resulted in substantial changes. (Slide 3) An updated project phasing schedule and cost estimates were created for the projects and all the other portions of the Master Plan document impacted by these changes were being updated as well. An online public open house would begin September 28<sup>th</sup> for any members of the general public who wanted to provide input.

**Dave Price, Carollo Engineers**, continued the PowerPoint presentation on the WWTP Master Plan process, reviewing the updates made to the Facility Capacity Assessment and Unit Process Capacity Summary, given the higher growth projections from Metro; the Alternatives Evaluation and Recommended Plan for the required improvement projects, including new capacity upgrades, as well as the now more accelerated Project Phasing Schedule. With the higher growth scenario, the Project Costs had increased to more than three times the approximately \$31 million reported in July. The Draft Cash Flow chart provided a visual representation of the Project Costs along the timeline. (Slide 10)

Discussion and feedback from the Planning Commission was as follows with responses to Commissioner questions as noted:

- Looking at the Draft Cash Flow, the membrane bioreactor (MBR) was the biggest outlay of cash in years. Was the City doing any pro-planning of the funds that would be needed for that?
  - **Mr. Nacrelli** replied that upon completion of this plan and part of next steps, the City planned to do a rate and SDC study within this current budget year to look at the details of how to fund the improvements through a combination of rate adjustments and SDCs, and maybe other mechanisms available.
- Assuming some monies were already in reserve, at what point would the rate and SDC changes need to happen for the monies to be there for the 2028, 2029, 2030 MBR expenditures?

- **Mr. Nacrelli** replied the timing was one of the question the study would have to be able to answer. He suspected rate and SDC increases would be phased in over time, but that would have to be fleshed out in that study, accommodating the growth expected and how those rates would have to be adjusted as growth occurs in order to provide the necessary funding. Once the study and public involvement process were completed, and the fee increases adopted, the new rates would probably have to start right away to make those adjustments.
- How would rate changes for future expansion be explained to existing customers?
  - **Mr. Nacrelli** stated that was ultimately a Council decision. He agreed the majority of the investment was driven by capacity needs; however, some components involved replacing old equipment, so it was not entirely growth driven. He anticipated the impact on SDCs would be far greater than the impact on rates.
- **Mr. Nacrelli** confirmed the improvements would be triggered by threshold population growth; as growth reached a certain place, a new unit gets triggered which provides some flexibility, so the project costs/schedule were not cast in concrete
- Regarding the cost of growth, this was an interesting exercise because in simulating a doubling of the size and the cost tripled, which slows growth because some of the growth occurs because it was competitive price wise. People come to Wilsonville because it was cheaper than Tualatin, for example, and the city has a growth spurt. Growth slows as costs catch up. The schedule was not cast in concrete, growth triggers the decisions for these units to come in.
  - Mr. Nacrelli displayed the Capital Planning and Expected Growth 2045, explaining the numbers in the table on the left were for the orange curve, but the numbers presented in the PowerPoint were based on the purple curve, which was the same growth rate Mr. Price mentioned was used in the 2014 Collection System Master Plan, as well as the Water Treatment Plant Master Plan, and possibly several other planning documents. (Slide 14)
- **Commissioner Mesbah** noted in a previous life, he would be reviewing the Master Plan. A community's Comprehensive Plan was a wish that did not necessarily come true. A cost-effective analysis was needed of some of this projection, growth, and units, especially since by taking this population growth curve, the City had managed to say the only option was the MBR treatment, which was a more expensive treatment, which he understood was to meet higher water quality standards. It was taking away a lot of choices that the City may do well to consider. Maybe the City decides it does not want to double in size—ever—to avoid dealing with higher water quality impacts on city water. These were necessary to explain to rate payers in a comprehensive and understandable way why the City was planning what it was planning. Questions like, "Am I paying for someone else's growth?" were divisive and not helpful to a sense of community. This was a community service, and it should be approached as a benefit for all and the environment that was receiving the City's treated waste.
- In terms of the current analysis for flow rates and the details in some of the earlier slides, what baseline population numbers were used as the starting point, 2021 or 2015?
  - Mr. Price explained typically 5 to 6 years' worth of data were used, adding this could be considered a 2021 number. When looking at existing data, they often analyzed the flow meter and data being collected from operators at the plant, then they projected out using unit factors and numbers that were conservative to a certain extent, making sure it provided for some flexibility in terms of how the facility was being planned. If the numbers being used were too conservative, and growth did not occur as that particular projection envisioned, then the Plan needed to adjust to that.

- The projected flows made sense, but did the City really expect to be at that 2045 population level to drive all the necessary infrastructure requirements that had been defined. (Slide 14) In July, the projection seemed low and now, was it too high? Was there a middle ground that was a more realistic growth scenario or, if that were to come to pass, would the system's design be done differently from a planning perspective if 45,000 people were expected rather than 52,000.
  - **Mr. Price** responded not necessarily, given the space available at the existing treatment plant site. The City would likely wind up with the same recommendation.
  - **Mr. Nacrelli** noted it might push the timeline further into the future, but to serve the ultimate build out, whether that happened in 2045 or later, there was no more space to do something different.
  - Mr. Price agreed, adding they had looked at other options to provide capacity and other processes to intensify secondary treatment, and the conclusion was that the MBR was the direction the City should go no matter the timeline. This was a plan the team believed would provide a very robust facility that the City could feel confident would meet its requirements on the water quality side, while also being flexible to the degree to which it could be made flexible; some additional variations could be added should different criteria or scenarios apply over the next 23 years. At this time, the July and this current proposal bracketed the range of options.
  - **Mr. Nacrelli** stated the Rate and SDC Study would certainly look at how the funding would be impacted by changes in growth. If growth slowed way down for some reason and the projected flows were not achieved, then the City would likely push some of these projects out. To serve the ultimate population within the UGB around Wilsonville with the limited existing site, what would be built would not change, just possibly when things were built.
  - **Mr. Price** noted none of the scenarios accounted for any significant changes on the regulatory side. There were processes in place, underway, or pending to potentially look at other pollutants that might be regulated. This particular plan provided a very firm basis upon which to build, which was why the aeriation basin was proposed first as opposed to going right to the membranes. Having that additional volume and capacity in the plant would provide flexibility for the City in the future in being able to address potential future regulatory concerns.
    - He noted that when the membrane facility was in place, the filters and the two secondary clarifiers that are not demolished would effectively become redundant facilities because the MBR would produce <u>effluent that</u> would not be necessary to run through clarifiers and filters because of the process of the liquid separation that occurs with the membrane.
    - The membrane facility was chosen due to the site constraints at the treatment plant, but when the facilities are in place, some space would be freed up providing the City with some flexibility in the future should additional regulatory issues arise in addition to the growth.
- **Commissioner Mesbah** said he wanted to clarify his earlier comments. The proposed plan was based on population that was currently baked into the City's plans and would eventually happen, so the projects would be necessary. As long as this plan was based on need and the projects were pushed out if the population growth did not happen, it was a sound plan. The City still needed to explain it very clearly, so it did not create an impression that this was cost for newcomers versus cost for what was not done before, etc. He was unsure whether the fiscal impacts of growth were looked at ahead of planning. Since it was a separate process, it did not get considered when the City adopted new areas to grow into. He suggested doing this kind of thinking before adding areas would be helpful in the overall process.

- **Commissioner Karr** believed the original concern with following the orange line was the fact that the Commission knew of future developments that were going to exceed the orange line. If those developments come to fruition, the orange line was not usable, and that becomes the problem of, "It's an essential service and it has to be in place". Even though there was a timeline, it sounded like the project list would not change, only the timing of the project list and representative costs. He proposed amending the chart on Page 3 to state, "*potential* timeframe based on expected growth" to provide a clearer picture. Since the expenditures for these projects depended upon seeing the anticipated growth, the timeframe should be a little more 'squishy'. (Slide 9)
  - **Mr. Nacrelli** confirmed that whether build out was reached around 2045 or 10 years later, the facilities would still be needed, but perhaps not as soon. (Slide 9)
  - **Chair Heberlein** suggested adding "estimated timeframe" as well as "estimated costs" to clarify there was no hard date.
  - **Mr. Nacrelli** stated that even with the orange population curve, the aeration basin would be done fairly soon.
  - He clarified the first few projects before the aeration basin were not substantial and that the funding for those first few was available, adding the projects were not necessarily even growth projects. (Slide 9)
- The new aeration basin was more growth driven that current population, replace secondary clarifier mechanisms was maintenance, but all the "new" projects were growth-driven. The majority of the estimated cost was growth related and if the timeline was not certain, it would be better to state an estimated timeframe instead of a timeframe which leads people to think a project was certain to happen at that point.
  - **Mr. Nacrelli** agreed that could be presented better and they would make it clear in the document.
- Rather than 'squishy' the project team was encouraged to use 'commensurate to population threshold numbers' and hopefully, the team could show at least a range population levels that would trigger an action, so that it gave some guidance to decision makers.
  - Mr. Price agreed including an assumed population column would be helpful.
  - **Mr. Nacrelli** reminded there was a significant element of industrial use in the projections, so population could be a guide, but it was not 100 percent.
- **Commissioner Gallagher** said she fully supported taking care of infrastructure, but she reacted to the projection of growth. Did the City really plan on doubling the population of Wilsonville? Is that what was wanted? Was that what this was all about or was that what the City was concerned about?
  - **Mr. Nacrelli** displayed the City Land use Designations Map, noting most of the service area was mostly already within the city limits. If the available land developed as planned, the projects in the Master Plan was what would be needed, unless there were Zoning or Comprehensive Plan changes.
- The Commissioners discussed where 50,000 people would come from, noting Frog Pond would be 6,000 people. If the study area was based on this Land Use Map boundary, then the population estimates should be based on that boundary as well. Either the boundary or the population estimate was off, as well as what the density would permit.
  - **Mr. Nacrelli** clarified these numbers were consistent with the planning done for the sewer system, as well as the water treatment plant currently under expansion. The numbers were not really a departure from other projections the City had been using to plan for infrastructure.

- As long as it was timebound, or population or use based, then it was okay. This was the plan for infrastructure when Wilsonville needed it, regardless of what the boundary said.
- If the team low balled it and blew the water quality standards because the City was now discharging raw **sewage** or polluted wastewater, it would penalize the City, and potentially put a total stop to any new growth, etc. until it was addressed. The City did not want to be in that position, which was why planning was done ahead of time.

The Planning Commission took a brief recess, reconvening at 7:48 pm

4. Frog Pond East and South Master Plan (Pauly)

**Dan Pauly, Planning Manager,** stated this was the Commission's eighth work session on the Frog Pond East and South Master Plan. He introduced the project team and began the PowerPoint presentation, noting tonight's discussion would be around infrastructure, continued discussion on Housing Variety Policy, next steps, and what the finish line looked like at this point.

- He explained the preliminary work done during the 2015 Frog Pond Area Plan provided a foundation for the list of needed infrastructure projects as well as the cost estimates to develop a program for funding them.
- A sensitivity test for a hypothetical higher residential unit count was included in the water and sewer memorandum, and not in the current draft of the transportation memo. During the State administrative rule making for implementation of House Bill 2001, a variety of options was provided that jurisdictions could take, one of which was to plan for 20 units per net acre. How much more expensive would infrastructure be if 20 units per acre were planned versus what the City anticipated would be built during the initial buildout.

Jenna Bogert, Transportation Engineer Consultant, DKS Associates, continued the PowerPoint, highlighting the transportation analysis process and the housing unit and job counts used in the traffic model to identify failing intersections and needed improvements, including for bike and pedestrian facilities. She noted the traffic operations, identified deficiencies, and proposed improvements within the subject area, and described four main intersection improvements, which included roundabouts. (Slide 7) She reviewed the pros and cons of single lane roundabouts, as well as proposed pedestrian and bicycle treatments to address gaps and deficiencies, and the proposed street cross sections on Stafford and Advance Rds.

- **Mr. Pauly** noted the Stafford Rd/65th Avenue intersection was a high-priority project for the County to fix. The team's scenario assumed that those improvements were built within the 2040 baseline being considered. (Slide 6)
- **Ms. Bogert** added City Staff had been informing the County of the changes and plans for the Frog Pond Area throughout the master planning process.

Commissioner comments regarding the transportation infrastructure was as follows with responses to questions by the project team as noted:

- With the Advance Road and 60<sup>th</sup> roundabout so close to the school and park, what advanced safety precautions beyond the crosswalks would be taken because school children would be crossing there?
  - **Mr. Pauly** replied the project team talked directly with the School District this week on how to plan it. The District likes the roundabout for bus and traffic circulation, having buses go out that



# CITY COUNCIL MONDAY, AUGUST 1, 2022

# WORK SESSION

Wastewater Treatment Plant Master Plan (Nacrelli)



# CITY COUNCIL MEETING

# STAFF REPORT

Meeting Date: August 1, 2022		Subject: Wastewater Treatment Plant Master Plan					
		Staff Member: Mike Nacrelli, Senior Civil Engineer					
			Dep	Department: Community Development			
Act	ion Required		Adv	isory Board/Commi	ission Recommendation		
	Motion			Approval			
	Public Hearing Date:			Denial			
	Ordinance 1 <sup>st</sup> Reading Date	:		None Forwarded			
	Ordinance 2 <sup>nd</sup> Reading Date	e:	$\boxtimes$	Not Applicable			
	Resolution		Com	Comments: N/A			
☑ Information or Direction							
Information Only							
Council Direction							
Consent Agenda							
<b>Staff Recommendation:</b> Provide input (WWTP) Master Plan.			t on	components of the	Wastewater Treatment Plant		
<b>Recommended Language for Motion:</b> N/A							
Project / Issue Relates To:							
⊠Council Goals/Priorities: □Add			pted	Master Plan(s):	□Not Applicable		
Align infrastructure plans							
with sustainable financing							
resources.							

# **ISSUE BEFORE COUNCIL:**

Provide feedback and input on components of the Wastewater Treatment Plant (WWTP) Master Plan.

# **EXECUTIVE SUMMARY:**

This new City of Wilsonville (City) Wastewater Treatment Plant (WWTP) Master Plan (the Plan) has been developed to satisfy requirements associated with the State of Oregon Department of Environmental Quality (DEQ) guidance document entitled "Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities." To accommodate future flows and loads, projections were developed based on population projections and referencing WWTP historical data and DEQ wet weather project methodologies. Similarly, to accommodate future water quality regulations, the Plan is adaptive and considers potential future regulatory changes.

The City prepared the Plan with the goal of developing a capital plan that identifies improvements required through the planning period (today through 2045) to comply with requirements of the WWTP National Pollutant Discharge Elimination System (NPDES) permit and potential future regulatory requirements, while accommodating growth identified in the City of Wilsonville Comprehensive Plan (October 2018, updated June 2020). These improvements are designed to provide the best value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development, consistent with goals and policies contained in the Comprehensive Plan and 2021-2023 City Council Goals.

The City's WWTP was originally built in 1971 and discharges treated effluent to the Willamette River. The WWTP underwent major upgrades in 2014 to expand the average dry weather capacity to four million gallons per day (mgd) to accommodate the City's continued growth. The WWTP processes include headworks screening and grit removal facilities, aeration basins, stabilization basins, secondary clarifiers, biosolids processing, cloth filtration, and disinfection processes. Additionally, the City contracts with Jacobs for operation of the wastewater treatment plant, located at 9275 Southwest Tauchman Road.

This Plan identifies improvements taking into consideration:

- The age and condition of existing process equipment and structures,
- Growth in demand for sewer service due to increased population and economic development over the planning period,
- Potential changes to water quality regulations impacting process needs in order to meet effluent limitations and discharge prohibitions imposed by the Oregon Department of Environmental Quality (DEQ), and
- Consistency with the 2018 Comprehensive Plan and City Council 2021-2023 Goals 5, 6 and 7.

# WWTP Condition Assessment

Carollo reviewed prior condition assessments performed by others, conducted geotechnical investigations and performed seismic assessments at the WWTP in the course of Plan development.

In 2019, Jacobs Engineering Group Inc. (Jacobs) and Brown and Caldwell both completed condition assessments at the City's WWTP. A total of 322 major assets (per Jacobs' report), including process and mechanical equipment, motors and drives, control panels, generators, instrumentation, and structures, were examined for a variety of conditions that may signify their need for maintenance or replacement.

# Seismic Analysis

In 2021, Carollo performed a seismic evaluation and analysis of the City's WWTP as part of the overall plant condition assessment. Because the WWTP was substantially upgraded and expanded in 2014, most of its infrastructure is designed in accordance with the 2010 Oregon Structural Specialty Code (OSSC) and follows modern seismic design and detailing. During Tier 1 evaluations, Carollo identified potential deficiencies and areas for additional investigation. A Tier 1 seismic analysis is an initial evaluation performed to identify any potential deficiencies, whether structural or non-structural, in a building based on the performance of other similar buildings in past earthquakes. Subsequent to the Tier 1 analysis, a more detailed seismic evaluation of five older and potentially seismically vulnerable structures on the WWTP site was conducted. Those structures receiving a more detailed evaluation included the following:

- Operations Building
- Process Gallery
- Workshop
- Aeration Basins and Stabilization Basins
- Sludge Storage Basins and Biofilter

The five potentially vulnerable structures were for an M9.0 Cascadia Seismic Zone (CSZ) earthquake. The M9.0 CSZ is reflective of a catastrophic natural disaster event that has an estimated 35 percent likelihood of occurring within the next 50 years. Following the Tier 1 evaluation, Carollo began Tier 2 evaluations for a select number of identified deficiencies. Although none of the structures showed significant irregularities, the team did identify seismic deficiencies. The recommended seismic retrofits are included in the CIP for the Plan.

Prior to the 2021 seismic evaluation, Carollo's subconsultant, Northwest Geotech, Inc. (NGI), completed a seismic response and geologic hazards assessment of the City's WWTP. Through past and present site investigations and engineering analyses, NGI determined that the native soils beneath the site's granular pit backfill have low risk of liquefaction and its slopes do not pose undue risk. NGI concluded that the WWTP's primary site hazard is the differential settlement that may be caused by soil piping (development of subsurface air-filled voids), which raises the risk of sinkholes forming beneath structures and pipelines. Soil piping usually develops in unsaturated soils when a water source percolates into the ground. While the site is mostly paved and stormwater is being collected, there may be areas where infiltration is occurring next to structures or below pipelines. Recommended actions from NGI to mitigate the risk of soil piping are presented in the Plan.

# Wastewater Flow and Load Projections

The Plan evaluates the historical and projected wastewater flows and loads generated in the City of Wilsonville's service area. The load projections include total suspended solids (TSS), biochemical oxygen demand (BOD5), ammonia (NH3), and total phosphorous (TP) loads.

Service area, residential population, industrial contribution, and rainfall records were all considered in the flow and load projection analyses.

## **Capacity Analysis**

Summaries of plant process area capacity assessments and conclusions are presented in the Plan. These assessments focus on the need for improvements or upgrades to existing facilities to address capacity deficiencies identified in the course of Master Plan evaluations.

# **Regulatory Considerations and Strategy**

Several possible regulatory actions by the Oregon DEQ could drive investments in future improvements at the City's WWTP. The plant discharges to the Willamette River and existing and future effluent limitations contained in the NPDES permit dictate, in large part, the necessary treatment processes and configuration at the WWTP necessary to maintain compliance. The existing permit limits for the Wilsonville WWTP are effective September 1, 2020 through July 30, 2025.

### Alternative Development and Evaluation

The Plan presents the methodology and findings of a process improvements alternatives evaluation. The plant's treatment process needs were defined by comparing the plant's existing condition, capacity and reliability, with the projected flows, loads, and regulatory constraints for the recommended alternatives. Where capacity deficiencies were predicted, at least two alternatives were analyzed for each corresponding unit process.

# **EXPECTED RESULTS:**

The Plan includes a list of recommended capital improvements, along with an anticipated schedule for completion and preliminary cost estimates. The total estimated amount of capital investment over the planning period is approximately \$31 million, of which \$4.5 million is anticipated in the next 5 years. The recommended capital improvements will provide the basis for an analysis of sewer rates and system development charges (SDCs) that will be necessary to ensure adequate funding to implement to required upgrades.

### TIMELINE:

This is the second in a series of presentations to the Planning Commission and City Council. Completed and subsequent planned meetings are as follows:

- Planning Commission Work Session July 13 (completed)
- City Council Work Session August 1 (current)
- Planning Commission Public Hearing September 14
- City Council Public Hearing 1st Reading October 3
- City Council 2nd Reading October 17

### Wastewater Treatment Plant Master Plan Staff Report

C:\Users\MeetingsOfficeUser\AppData\Local\Temp\tmp2C93.tmp

# **CURRENT YEAR BUDGET IMPACTS:**

The remaining contract balance for finalizing the Plan will carry over into FY 22/23. An additional \$92,450 has been budgeted in FY 22/23 for the Sewer System Rate Study and System Development Charge (SDC) Update, using a combination of Sewer Operating funds and SDCs.

# COMMUNITY INVOLVEMENT PROCESS:

A virtual town hall meeting to present the findings of the Plan and solicit public input will be scheduled in August and posted on the City's online calendar. The public hearings listed above will provide additional opportunity for public input. The forthcoming Sewer System Rate Study and SDC Update will also include a robust public engagement process.

## POTENTIAL IMPACTS OR BENEFIT TO THE COMMUNITY:

A technically and financially sound plan for providing reliable wastewater treatment, capacity to accommodate future development, and compliance with environmental regulations.

# ALTERNATIVES:

The Plan includes alternatives for several of the recommended improvements. The selected alternatives were determined to be the most economically viable. Some of the more capital intensive alternatives can be revisited if necessary due to changing regulatory requirements.

# **CITY MANAGER COMMENT:**

N/A

# ATTACHMENT:

1. Draft Wastewater Treatment Plant Executive Summary (dated July 2022)





City of Wilsonville Wastewater Treatment Plant Master Plan

# **EXECUTIVE SUMMARY**

DRAFT | July 2022





City of Wilsonville Wastewater Treatment Plant Master Plan

# **EXECUTIVE SUMMARY**

DRAFT | July 2022

# Contents

# **Executive Summary**

ES.1 Planning Area Characteristics	ES-2
ES.2 WWTP Condition Assessment	ES-6
ES.3 Seismic Analysis	ES-6
ES.4 Wastewater Flow and Load Projections	ES-7
ES.5 Capacity Analysis	ES-9
ES.6 Regulatory Considerations and Strategy	ES-15
ES.7 Alternative Development and Evaluation	ES-17
ES.8 Recommended Alternative	ES-20

# Tables

Table ES.1	CIP Condition Driven Replacement Projects	ES-6
Table ES.2	Unit Process Capacity Assessment	ES-13
Table ES.3	Unit Process Capacity Year Summary	ES-15
Table ES.4	Current Effluent Permit Limits	ES-16
Table ES.5	Summary of Alternatives	ES-19
Table ES.6	WWTP CIP - Recommended Alternative Opinion of Probable Cost and Phasing	ES-20

# Figures

Figure ES.1	Planning Area	ES-3
Figure ES.2	Historical Population and Expected Growth for the City of Wilsonville	ES-5
Figure ES.3	Flow Projection Summary	ES-8
Figure ES.4	Load Projection Summary	ES-9
Figure ES.5	Existing Wilsonville WWTP	ES-11
Figure ES.6	Proposed WWTP Improvements Site Plan	ES-21
Figure ES.7	Projected 20-Year CIP Expenditures	ES-23



# Abbreviations

AA	average annual
AAF	average annual flow
ABF	average base flow
ADWF	average dry-weather flow
AWWF	average wet weather flow
BCR	biochemical reactor
BOD <sub>5</sub>	biochemical oxygen demand
Carollo	Carollo Engineers, Inc.
CIP	Capital Improvement Plan
City	the City of Wilsonville
CBOD <sub>5</sub>	five-day carbonaceous biochemical oxygen demand
CSZ	Cascadia Seismic Zone
DBO	Design-Build-Operate
DEQ	Department of Environmental Quality
DMR	Discharge Monitoring Reports
ETL	excess thermal load
gpd/sf	gallons per day per square foot
HMI	human-machine interface
Jacobs	Jacobs Engineering Group Inc.
kcal/day	kilocalories per day
lbs	pounds
MBR	membrane bioreactor
mg/L	milligrams per liter
mgd	million gallons per day
MGI	Northwest Geotech, Inc.
ml	milliliter
MLSS	mixed liquor suspended solids
MM	maximum month
MMDWF	maximum month dry weather flow
MMWWF	maximum month wet weather flow
MW	maximum week
MWDWF	maximum month dry weather flow
MWWWF	maximum week wet weather flow
NH₃	ammonia
No.	number
NPDES	National Pollutant Discharge Elimination System
OSSC	Oregon Structural Specialty Code



PD	peak day
PDDWF	peak day dry weather flow
PDWWF	peak day wet weather flow
PHF	peak hour flow
ppd	pounds per day
PSU PRC	Portland State University Population Research Center
R/C	residential/commercial
SPA	State Point Analysis
SRT	solids residence time
the Plan	Master Plan
TMDL	total maximum daily loads
TP	total phosphorous
TS	total solids
TSS	total suspended solids
TWAS	thickened waste activated sludge
UGB	urban growth boundary
UV	ultraviolet
WWTP	wastewater treatment plant



# **EXECUTIVE SUMMARY**

This new City of Wilsonville (City) Wastewater Treatment Plant (WWTP) Master Plan (the Plan) has been developed to satisfy requirements associated with the State of Oregon Department of Environmental Quality (DEQ) guidance document entitled "Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities." To accommodate future flows and loads, projections were developed based on population projections and referencing WWTP historical data and DEQ wet weather project methodologies. Similarly, to accommodate future water quality regulations, the Plan is adaptive and considers potential future regulatory changes.

The City prepared the Plan with the goal of developing a capital plan that identifies improvements required through the planning period (today through 2045) to comply with requirements of the WWTP National Pollutant Discharge Elimination System (NPDES) permit and potential future regulatory requirements, while accommodating growth identified in the City of Wilsonville Comprehensive Plan (October 2018, updated June 2020 - the 2018 Comprehensive Plan). These improvements are designed to provide the best value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development, consistent with goals and policies contained in the 2018 Comprehensive Plan and 2021-2023 City Council Goals.

The City's WWTP was originally built in 1971 and discharges treated effluent to the Willamette River. The WWTP underwent major upgrades in 2014 to expand the average dry weather capacity to four million gallons per day (mgd) to accommodate the City's continued growth. The WWTP processes include headworks screening and grit removal facilities, aeration basins, stabilization basins, secondary clarifiers, biosolids processing, cloth filtration, and disinfection processes. Additionally, the City contracts with Jacobs for operation of the wastewater treatment plant, located at 9275 Southwest Tauchman Road.

This Plan identifies improvements taking into consideration:

- The age and condition of existing process equipment and structures,
- Growth in demand for sewer service due to increased population and economic development over the planning period,
- Potential changes to water quality regulations impacting process needs in order to meet effluent limitations and discharge prohibitions imposed by the Oregon Department of Environmental Quality (DEQ),
- City of Wilsonville Wastewater Collection System Master Plan (2014, MSA), and



- Consistency with the 2018 Comprehensive Plan and City Council 2021-2023 Goals 5, 6 and 7:
  - Goal 5: Align infrastructure plans with sustainable financing sources.
  - Goal 6: Engage the community to support emergency preparedness and resiliency.
  - Goal 7: Protect Wilsonville's environment and increase access to sustainable lifestyle choices.

# **ES.1** Planning Area Characteristics

Chapter 1 summarizes the City's wastewater service area characteristics relevant to assessing WWTP facility needs. The planning area considered by this Plan is consistent with the City's 2014 Collection System Master Plan and 2018 Comprehensive Plan including the urban growth boundary (UGB), which is currently the limit of City sewer service as shown in Figure ES 1.

The northern portion of the City of Wilsonville is located within Washington County, and the majority of the City lies in the southwestern part of Clackamas County.

The City sits within the jurisdictional boundaries of Metro, the regional government for the Portland metropolitan area. By state law, Metro is responsible for establishing the Portland metropolitan area's UGB, which includes Wilsonville. Land uses and densities inside the UGB require urban services such as police and fire protection, roads, schools, and water and sewer systems. A figure of the City's existing land use is presented in Chapter 1. Also presented in Chapter 1 are the City's physical characteristics, water resources, and population and employment information, which are all significant factors in planning for wastewater conveyance and treatment facilities.



#### EGONS 87TH C 86TH AVE ARAPAHO RO 115TH AVE MDUSTRIAL TO8TH HT801 NIE SIUSLAW LN 5 J OPHLKE LN COQUILLEDR MARTINAZZI CT JULINA DR COQUILLE CT ---- County Line AVE ALSEA DR P × TALAWA DR ONZE 87 ROM TER MAKAY Streets 5 HR DR HI 75TH AVE COLUMBIA DR PRIKARA DR 1.OOP City of Wilsonville Boundary 70TH AVE 5 4 ALA BACH ST COLUM 109TH DR TH NE 106TH A AVE Urban Growth Boundary CREEK SILVIN B LUM NORSEHALL KOLLER ST BACH CT 56 TAYLORS 13AR, INAZZI Urban Reserve Areas 0 GRAM ST LUSTER CT MANDAN DR TER 12ATH ANE NELSON ST Waterbodies MARILYN ST ONEIDA ST COTTONWOOD ST В CHI Z PALOUSE LN MCCAMPANT DR MIAMI A DOGWOOD ST ERIO PL ENOPL 96TH DR STONO DR Jd H. NORWOOD RD BROWN ST RO COWILI 1000 CLEAR ST ⊐ Feet AVE Ч HELENIUS ST 0 1,200 2,400 HELEINICE ST BOONES FERRY RD Data Sources: ESRI, City of Wilsonville Disclaimer: Features shown in this TONQUIN PL figure are for planning purposes and represent approximate locations. FROBASE RD Engineering and/or survey accuracy BASALT CREEK PKWY GREENHILL LN is not implied. SUN OUARRYNE STAFFOE MORGAN RO AHALIN RD HELEN PIONEER CT EASTGATE DR KNOLLWOOD CT ELLIGSEN RD LIGSEN WAY COMMERCE CIR BURNS DF JACK BURNS BLVD ROBEF YLLE P RIDDER R BURNS WAY Washington County WAY CENTER HOMESTEADER RD **Clackamas** County 5 00 AVE BRIAR PATCH LN 95TH WIEDEMANN RD PRINTER PAGE CAN FREEMAN DR TOOZE RD AVE NIKE DR MERDON COLOR CONNECTION NOOD KAHLE RD ARKINAY HILLMAN CT MALLOY WAY AVE WESTFALL RD BURY LOC BOECKMAN RD BAY LN FALLEN ADVANCE RD OSLO ST NE DR IBON HORSE ST BERLIN ALS LOOP H ASH MERTON ST VALECT FERNOR RD ONSLOOP MAXINELN AVE ß BOBERG DODA DAYBREAK ST MEADOWS RD FERRY CAS 53RD ND SERENITY HELENE ST MONT BLANC ST CREST BOONES AVE CIR KINSMAN RD KRUSE RD BARBER ST MEADOWS PKWY COSTA COUNTRY LN LISBON ST VLAHOS OR I CENTER O MCDONALD DR WIMBLEDO Ξ MADRID LOOP -00p CASTING OT ST BRUCK EVERGREEN AVE GRASS CT SEELY PARKWOOD LN RACQUET CT TAMI NNOY NCELOT LN AVE COURTSIDE DR 6 C TENNIS CT GCAT WA 02 GAYLORD LN CITIZENS DR ALE DE MATZEN DR ILSONVILLE RD BELLRD MONTI ROBBYST MAIN ST :LORES ST DR MONTGOMERY OREPAC AVE Ξ TRIAL WAY JESSICA ST HOLLYLN ROSE BAILEY ST ORC Z HARD DR 5TH ST 200 RUT 2 WHANNS FERRY RD 2 4TH ST AVE PARKVIEW DR NUTTING

90TH

NEY LN CHERRY LN

P0,

# EXECUTIVE SUMMARY | WASTEWATER TREATMENT PLANT MASTER PLAN | CITY OF WILSONVILLE

ROBBINS RD

Legend

5-1205 RAMP



MAIN

E LAKESIDE DR 4

OLD

/15/2022 12:18 PMpw:\\IO-PW-INT.Carollo.local:Carollo\Documents\Client\OR\Wilsonville\11962Aoo\GIS\wilsonville\_11962Aoo.APRX

OXMPI OCREEK

RD

PRESTWICLC MOREY

N

ITEL ST

MORGAN LN

BAKER RD


BAKER RD

WAY

SUSQUEHANNA DR

The Portland State University Population Research Center (PSU PRC) publishes annual estimates of populations for the previous year for cities in Oregon while Metro develops population projections for the future within the Portland metropolitan area, including Wilsonville. The PSU PRC estimated the City's population as 27,186 in 2021. Metro estimates the City's population to reach 30,566 people by 2045.

For establishing a per capita basis for flow and load projections for the Plan, certified PSU PRC historical population estimates were used for 2015 through 2019. Metro's future population forecasts were used for 2020 through 2045. Figure ES.2 shows the historical population and future growth predicted for the City. Figure ES.2 also identifies growth projections developed to allow the City to assess capital requirements possibly resulting from more aggressive growth than projected by Metro. Analysis of possible growth scenarios is described in greater detail in Chapter 4.







# ES.2 WWTP Condition Assessment

Carollo Engineers, Inc. (Carollo) reviewed prior condition assessments performed by others, conducted geotechnical investigations and performed seismic assessments at the WWTP in the course of Plan development.

In 2019, Jacobs Engineering Group Inc. (Jacobs) and Brown and Caldwell both completed condition assessments at the City's WWTP. A total of 322 major assets (per Jacobs' report), including process and mechanical equipment, motors and drives, control panels, generators, instrumentation, and structures, were examined for a variety of conditions that may signify their need for maintenance or replacement. Chapter 2 presents a summary of critical assets that require short term rehabilitation or replacement, as well as a list of assets that are less critical to operations, or have minor condition issues, but may be included in a short-term improvements project or a task order for Jacobs operations personnel. Table ES.1 displays the condition driven rehabilitation or replacement projects from Chapter 2 that were included in the recommended Capital Improvement Plan (CIP) in Chapter 7.

## Table ES.1 CIP Condition Driven Replacement Projects

Asset	Description
Trojan UV 4000 System	While only used as a backup to the Ozonia UV system, the Trojan system's HMI has errors that prevent it from showing the status of the lamps in module 3. Since it is used infrequently, the system's condition is largely unknown. After review of the 2019 condition assessment reports and discussion with the City and Jacobs staff, it was concluded that the UV 4000 unit must be replaced.
Secondary Clarifiers No. 1 and No. 2	Ovivo completed a field review of the plant's secondary clarifiers No. 1 and No. 2 in April 2022. Although both units were operational, repairs were identified to improve the operation of the clarifiers. The recommended repairs include drive controls for both units, new skimmers for both units, squeegees for both tanks rake arms, EDI chains, one motor and reducer assembly, one skimmer arm assembly, and new secondary clarifier mechanisms. <sup>(1)</sup>

Notes:

(1) The detailed Ovivo Field Service Report is included in Appendix X.

Abbreviations: HMI - human-machine interface; No. - number; UV - ultraviolet.

# **ES.3** Seismic Analysis

In 2021, Carollo performed a seismic evaluation and analysis of the City's WWTP as part of the overall plant condition assessment. Because the WWTP was substantially upgraded and expanded in 2014, most of its infrastructure is designed in accordance with the 2010 Oregon Structural Specialty Code (OSSC) and follows modern seismic design and detailing. During Tier 1 evaluations, Carollo identified potential deficiencies and areas for additional investigation. A Tier 1 seismic analysis is an initial evaluation performed to identify any potential deficiencies, whether structural or non-structural, in a building based on the performance of other similar buildings in past earthquakes. Subsequent to the Tier 1 analysis, a more detailed seismic



evaluation of five older and potentially seismically vulnerable structures on the WWTP site was conducted. Those structures receiving a more detailed evaluation included the following:

- Operations Building.
- Process Gallery.
- Workshop.
- Aeration Basins and Stabilization Basins.
- Sludge Storage Basins and Biofilter.

The five potentially vulnerable structures were compared against an S-4 Limited Safety structural performance level and N-B Position Retention non-structural performance level for an M9.0 Cascadia Seismic Zone (CSZ) earthquake. The M9.0 CSZ is reflective of a catastrophic natural disaster event that has an estimated 35 percent likelihood of occurring within the next 50 years. Following the Tier 1 evaluation, Carollo began Tier 2 evaluations for a select number of identified deficiencies. Although none of the structures showed significant irregularities, the team did identify seismic deficiencies. The recommended seismic retrofits are included in the CIP for this Plan.

Prior to the 2021 seismic evaluation, Carollo's subconsultant, Northwest Geotech, Inc. (NGI), completed a seismic response and geologic hazards assessment of the City's WWTP. Through past and present site investigations and engineering analyses, NGI determined that the native soils beneath the site's granular pit backfill have low risk of liquefaction and its slopes do not pose undue risk. NGI concluded that the WWTP's primary site hazard is the differential settlement that may be caused by soil piping (development of subsurface air-filled voids), which raises the risk of sinkholes forming beneath structures and pipelines. Soil piping usually develops in unsaturated soils when a water source percolates into the ground. While the site is mostly paved and stormwater is being collected, there may be areas where infiltration is occurring next to structures or below pipelines. Recommended actions from NGI to mitigate the risk of soil piping are presented in Chapter 2.


# ES.4 Wastewater Flow and Load Projections

Chapter 3 of the Plan evaluates the historical and projected wastewater flows and loads generated in the City of Wilsonville's service area. The load projections include total suspended solids (TSS), biochemical oxygen demand (BOD<sub>5</sub>), ammonia (NH<sub>3</sub>), and total phosphorous (TP) loads.

Service area, residential population, industrial contribution, and rainfall records were all considered in the flow and load projection analyses. Facility planning involves estimating rates of growth in wastewater generation within the service area which are unlikely to align precisely with the actual growth observed. During the planning period, City staff will need to assess service area growth at regular intervals and revisit the analysis presented in this Plan. A determination will need to be made whether projected flows and loads (which drive assessments of unit process capacity) are aligned with calendar projections presented in this plan and consider if conclusions presented regarding capacity and timing of recommended improvements remain valid. If not, adjustments to the plan will need to be undertaken to ensure sufficient capacity remains available to serve anticipated growth.



Analysis of flow projections were completed through two different methods: (1) analysis of historical plant records and (2) DEQ Guidelines for Making Wet-Weather and Peak Flow Projections for Sewage Treatment in Western Oregon, which is referred to as the DEQ methodology in this Plan. Since there is no DEQ methodology for load analysis, all projections were developed based on historical plant records. Figure ES.3 summarizes the measured and projected maximum month, peak day and peak hour flows. The projections for the remaining flow elements can be found in Chapter 3.



#### Figure ES.3 Flow Projection Summary

Load projections were calculated for influent TSS, BOD<sub>5</sub>, NH<sub>3</sub>, and TP. Figure ES.4 summarizes the measured and projected influent maximum month BOD and TSS loads. The projections for the remaining load elements can be found in Chapter 3.






Figure ES.4 Load Projection Summary

The projected flows and loads developed in Chapter 3 were compared against the rated capacity for each of the WWTP's unit processes to determine whether expansion would be required within the planning period. The findings of this capacity analysis are discussed in the next section.

# **ES.5 Capacity Analysis**

Summaries of plant process area capacity assessments and conclusions are presented in this Plan. These assessments focus on the need for improvements or upgrades to existing facilities to address capacity deficiencies identified in the course of Master Plan evaluations. A site plan of the City's existing WWTP is presented in Figure ES.5.

Chapter 4 identifies existing capacity ratings and deficiencies for the liquid and solids stream treatment processes at the City's WWTP. Analyses are based on operational practices in place at the time and existing effluent limits established by the WWTP's National Pollutant Discharge Elimination System (NPDES) permit. Biological process modeling was performed using BioWin version 6.2 to predict plant performance under current and future flow and loading conditions to assess when unit process capacities may be exceeded within the planning period (present through 2045).

A summary of the capacity assessment completed and presented in Chapter 4 is detailed below in Table ES.2.





Plot Date: 6/28/2022 9:15:35

30' 60' SCALE: 1" = 60'

# LEGEND:

- 1 DEWATERING & DRYING BUILDING
- 2 PROCESS GALLERY
- 3 SECONDARY CLARIFIER NO. 1
- 4 SECONDARY CLARIFIER NO. 2
- 5 UV DISINFECTION SYSTEM
- 6 WORKSHOP
- 7 SECONDARY PROCESS FACILITY
- 8 STABILIZATION BASIN
- 9 SLUDGE STORAGE BASINS AND BIOFILTERS 12 - SECONDARY CLARIFIER NO. 3
- 10 HEADWORKS
- 11 DISK FILTERS
- 12 COOLING TOWERS
- 13 W3 REUSE PUMP STATION
- 14 OPERATIONS BUILDING
- 15 SITE ENTRANCE

Figure ES.5 EXISTING WILSONVILLE WWTP CITY OF WILSONVILLE



#### Table ES.2 Unit Process Capacity Assessment

Unit Process	Capacity Assessment
Preliminary Treatment	
Screening	There is sufficient hydraulic capacity for both mechanical screens to accommodate the projected 2045 PHF.
Grit Removal	Capacity is adequate for providing full treatment of the projected 2045 PHF.
Secondary Treatment	
Secondary Treatment	Based on maximum week MLSS predicted from BioWin modeling at peak day flow with all clarifiers in service (and assuming a 5-day SRT),
Secondary Clarifiers	The secondary clarifiers are expected to stay under the maximum hydraulic loading criteria for the entirety of the planning period.
Aeration Blowers	The air demands of the secondary treatment process are projected to exceed the firm capacity of the aeration blowers under peak condition
Tertiary Treatment and Disinfection	
Disk Filters	The existing disk filter capacity is expected to be exceeded by 2037 with one unit out of service or in backwash mode based on effluent limi time the City expects to relax these contract limitations rather than invest in additional capacity.
Secondary Effluent Cooling Towers	It is not expected that the total hydraulic capacity of the cooling towers will be exceeded by 2045.
UV Disinfection	The existing UV channels are adequately sized to fully disinfect the 2045 PHF with all units in service, as well as the PDDWF with one chanr place as an emergency backup to the primary system. That backup unit is aging and the City plans replacement during the planning period
Outfall	Even with the Willamette River at its 100-year flood elevation, it is expected that the outfall pipeline can accommodate approximately 19 r submergence upstream. Since this flow is well above the hydraulic capacity of the rest of the plant, no expansion will be needed until after
Solids Handling	
Gravity Belt Thickener	The capacity analysis resultsindicate adequate for thickening the current and projected maximum week WAS loads with one unit out of ser
TWAS Storage	The TWAS storage volume is sufficient to accommodate the expected maximum week solids loads for three days (assuming TWAS is thick
Dewatering Centrifuges	The rated capacity of the current centrifuges is sufficient to process the maximum week load with one unit out of service though 2045 assu per the criteria detailed in Chapter 4. <sup>(2)</sup>
Biosolids Dryer and Solids Disposal	The capacity of the biosolids dryer is adequate for handling the current and projected max week solids loads (in year 2045) on the basis of i from 20 percent TS to 92 percent TS and the dryer is operated for 24 hour per day for 5 days per week. <sup>(3)</sup>
i .	

Notes:

(1) The existing outfall was recently modified and equipped with five parallel diffuser pipes equipped with duckbill check valves to improve the mixing zone characteristics in the Willamette River.

(2) The centrifuges have exhibited inconsistent performance in recent months. The City recently refurbished these units and expects they will provide sufficient capacity through 2045.

(3) The existing solids dryer has sufficient capacity through 2045 but has exhibited inconsistent performance. See Alternative 2B, Chapter 6.

Abbreviations: DBO - Design-Build-Operate; gpd/sf - gallons per day per square foot; MLSS - mixed liquor suspended solids, SPA - State Point Analysis; SRT - solids residence time; TS - total solids; TWAS - thickened waste activated sludge.



Γ), there is only sufficient capacity through 2038.

tions by 2035.

mitations included in the City's DBO Contract with Jacobs. At this

nnel out of service. The City currently has an older UV unit in od.

9 mgd before the UV channel effluent weirs are at risk of er 2045.<sup>(1)</sup>

service.

ckened to 4 percent).

suming operating times of 24 hours per day for 5 days per week,

f its design evaporation rate, assuming dewatered cake is dried

Table ES.3 further summarizes the capacity assessment by listing each unit process, associated design parameters and year of possible capacity exceedance.

Unit Process	Design Parameter	Redundancy Criteria <sup>(3)</sup>	Year of Capacity Exceedance
Influent Screening	PHF	One mechanical screen out of service	>2045
Grit Chamber	PHF	All units in service	>2045
Secondary Treatment	MW MLSS inventory at PDF	All units in service	2038
Aeration Blowers	Peak BOD Load	Largest unit out of service	2035
Secondary Effluent Cooling Towers	June 1 - Sept 30 PDF	All units in service	>2045
Disk Filters	MWDWF	One unit in backwash	<b>2037</b> <sup>(1)</sup>
UV Disinfection Channels	PHF	All units in service	>2045
Outfall	PHF	-	>2045
Gravity Belt Thickening	MW Load	One unit out of service	>2045
TWAS Storage	MW Load	All units in service	>2045
Dewatering Centrifuges	MW Load	One unit out of service	>2045 <sup>(2)</sup>
Biosolids Dryer	MW Load	All units in service	>2045 <sup>(2)</sup>

Notes:

Unit processes in white are projected to run out of capacity before year 2045.

(1) Existing Disk Filters are predicted to exceed reliable capacity (one unit out of service) in 2037 based on vendor provided design criteria. This conclusion assumes limitations for effluent total suspended solids contained in the WWTP DBO contract, which are far more stringent than the City's NPDES permit.

(2) As noted previously, the existing centrifuges and biosolids dryer appear to have sufficient capacity through the planning year 2045, however condition and age are likely to require replacement during the planning period. It is recommended the City reassess available replacement technologies prior to replacement and consider loading appropriate to the planning horizon of any new units selected.

(3) Reference Appendix D - Reliability requirements, Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities, OR DEQ, 2018, Revised July 2019

### ES.6 Regulatory Considerations and Strategy

It is the responsibility of the Oregon Department of Environmental Quality (DEQ) to establish and enforce water quality standards that ensure the Willamette River's beneficial uses are preserved. Discharges from wastewater treatment plants are regulated through the National Pollutant Discharge Elimination System (NPDES). All discharges of treated wastewater to a receiving stream must comply with the conditions of an NPDES permit. The Wilsonville WWTP discharges to the Willamette River at River Mile 38.5 just upstream of the Interstate 5 bridge. The existing permit limits for the Wilsonville WWTP are shown in Table ES.4. This permit became effective on September 1, 2020 and expires July 30, 2025.



Parameter	Average Effluent Concentrations		Monthly Average,	Weekly Average,	Daily Maximum,	
	Monthly		Weekly	(ppd)	(ppd)	(lbs)
May 1 - October 31						
CBOD <sub>5</sub>	10 mg/L		15 mg/L	190	280	380
TSS	10 mg/L		15 mg/L	190	280	380
November 1 - April 30						
BOD <sub>5</sub>	30 mg/L		45 mg/L	560	840	1100
TSS 30 mg/L			45 mg/L	560	840	1100
Other Parameters Limitation						
E. coli Bacteria			Shall not exceed 126 organisms per 100 ml monthly geometric mean. No single sample shall exceed 406 organisms per 100 ml.			
рН			Instantaneous limit between a daily minimum of 6.0 and a daily maximum of 9.0			
BOD₅ Removal Efficiency			Shall not be less than 85% monthly average			
TSS Removal Efficiency			Shall not be less than 85% monthly average			
ETL June 1 through September 30			Option A: 39 million kcal/day 7-day rolling average Option B: Calculate the daily ETL limit			

#### Table ES.4 Current Effluent Permit Limits

#### Notes:

Abbreviations: CBOD<sub>5</sub> - five-day carbonaceous biochemical oxygen demand; ETL - excess thermal load; kcal/day - kilocalories per day; lbs - pounds, mg/L - milligrams per liter; ml - milliliter.

The WWTP has been compliant with NPDES permit limits, generally. However due to construction issues that required that aeration basins be offline, equipment failure and issues with solids processing, the WWTP did violate their NPDES permit over eight months between 2015 and 2020 (December 2015, February 2017, April 2017, January 2018, August 2018, May 2020, June 2020 and July 2020). Most of these violations were due to the daily effluent TSS load exceeding the maximum daily load limit in the NPDES permit. It is anticipated that once the issues with solids processing are addressed, the City's current treatment process will be able to meet permit limits.

Chapter 5 details potential regulatory issues the City will need to take into consideration in coming years. Several possible regulatory actions by the Oregon DEQ could drive investments in future improvements at the City's WWTP. The plant discharges to the Willamette River and existing and future effluent limitations contained in the NPDES permit dictate, in large part, the necessary treatment processes and configuration at the WWTP necessary to maintain compliance.

Future treatment upgrades may be required when DEQ establishes total maximum daily loads (TMDL) for the lower Willamette River. Dissolved oxygen and nutrient limits, such as phosphorus limitations, are possible. The dissolved oxygen in the lower part of the river does not always meet water quality standards, and indications of excessive nutrients, such as chlorophylla, aquatic weeds, and harmful algal blooms, are present in the lower Willamette River. DEQ has begun its triennial review of Oregon's water quality criteria. The review could result in more stringent or new discharge requirements, but this process will take several years. For planning purposes, providing plant footprint to accommodate future treatment to remover phosphorus and address dry weather seasonal limits on dissolved oxygen should be anticipated. In addition, the City should continue to engage with DEQ regarding any proposed receiving water temperature regulatory actions.

# ES.7 Alternative Development and Evaluation

Chapter 6 presents the methodology and findings of a process improvements alternatives evaluation. The plant's treatment process needs were defined by comparing the plant's existing condition, capacity and reliability, with the projected flows, loads, and regulatory constraints for the recommended alternatives. Where capacity deficiencies were predicted, at least two alternatives were analyzed for each corresponding unit process. Process modifications associated with each alternative were modeled in BioWin using a calibrated model to evaluate the overall impact on plant operations.

As identified in Chapter 4, the secondary treatment process is expected to require additional capacity during the planning horizon (2045). Chapter 6 details two alternatives to address these capacity limitations. The two alternatives considered to increase secondary capacity are:

- 1. Expansion of the existing conventional activated sludge process; and
- 2. Intensification of the existing treatment process using membrane bioreactor (MBR) technology.

Due to the higher capital and operating costs of intensification, construction of a new conventional aeration basin is recommended to increase secondary capacity. As flows and loads increase, or regulatory requirements become more stringent, it may be necessary to intensify treatment. It is recommended the City revisit this evaluation as the need for 1) additional capacity to accommodate growth nears or 2) more stringent effluent limitations are considered. This offers the opportunity to take advantage of potential advances in technology as well as confirming the predicted time frame of capacity exceedance. A new aeration basin project is included in the Capital Improvement Plan in Chapter 7.

The existing aeration blower system firm capacity is expected to be deficient by 2035. An additional aeration blower (same size and design air flow rate as the existing high-speed turbo blowers) would ensure there is sufficient blower capacity through the end of the planning period to meet current permit requirements. There is adequate space to add a fourth turbo blower to the same discharge header pipe as the existing turbo blowers. Additionally, intensification of the secondary treatment process would further increase the aeration demands because operating at a higher MLSS reduces oxygen transfer efficiency in the aeration basins. If intensification is reconsidered and selected for the planning period, or if nutrient limits are imposed within the planning period that requires intensification or operation at a higher MLSS, the blower air demands should be revisited.



Additional tertiary filtration capacity is predicted to be needed before 2045 to provide full treatment of the MWDWF with one disc filter out of service or in backwash mode. After discussions with the City, two alternatives were identified to increase capacity:

- 1. Increase filtration capacity, and
- 2. Modify the requirement in the WWTP DBO contract to relax effluent limitations which are currently more stringent than those contained in the City's NPDES permit.

The City's WWTP NPDES permit currently requires effluent to contain less than 10 mg/L TSS during the dry season (see Table ES.8). However, the DBO firm's contract with the City requires an effluent TSS of less than five mg/L, or half of the WWTP's permitted effluent quality. At this time, the City has decided to study the performance of the existing tertiary filters over time and expects to relax effluent TSS requirements in the DBO contract unless actual water quality impacts (exceedances of permit limitations) are realized. The City will also consider the option of new technologies for filtration, noting that if the City selected an intensification technology utilizing membranes, this may potentially eliminate tertiary filtration capacity concerns.

While the capacity assessment findings presented in Chapter 4 determined existing solids dewatering centrifuges have sufficient capacity, the remaining equipment service life may require replacement within the planning horizon. The centrifuges, installed in 2014, were recently refurbished, but by 2045, will have been in service for over 30 years. The City should plan for their replacement within the planning horizon and consider whether a capacity increase is needed at the time of replacement based on projections of solids production and processing needs. Additionally, the secondary process was modified in 2020 and has experienced extended periods where mixed liquor concentrations have been elevated above typical ranges for conventional activated sludge or extended aeration processes. Due to the complications with secondary process operation and performance issues with the centrifuges, it is recommended the City study the secondary treatment and dewatering processes to confirm that the assumptions and conclusions regarding centrifuge capacity in Chapter 4 may be relied upon. A dewatering performance optimization study is recommended so the City can collect and analyze secondary treatment and solids processing performance data. For budgeting purposes, an opinion of probable cost for replacing the existing centrifuges is provided in Chapter 7. Timing of that equipment replacement will depend on performance of the existing units, future loading assumptions, and observed condition.

The existing solids dryer has experienced operational issues in recent years, including a fire that caused extensive damage to the equipment in April 2019 and a leaking rotary joint and damaged seal in 2021. As of February 25, 2022, the dryer has been repaired and is operating. Because of the City's commitment to solids drying as the preferred process to achieve Class A biosolids, the alternatives evaluation presented in this Plan for future dryer replacement was conducted with a focus on thermal drying options only.

Chapter 6 details an analysis of the following alternatives to improve the drying system:

- 1. Alternative 1 Continue operating the existing biochemical reactor (BCR) paddle dryer and defer replacement.
- 2. Alternative 2 Modify the existing Dewatering and Drying Building to accommodate a different solids dryer technology or a redundant dryer.
- 3. Alternative 3 Construct a new dryer building with a different solids dryer technology.



While it is anticipated the existing dryer has useful life through at least 2026 (current DBO contract expiration), by 2031 the dryer will have been in operation for over 15 years. It is recommended the planning and design of upgrades to provide reliable dryer capacity begin in 2029, or sooner if further operational concerns arise. The City has indicated a preference for a variation of Alternative 2 which involves expanding the existing Dewatering and Drying Building to accommodate a second solids paddle dryer. This alternative provides backup capacity to allow the City to continue delivering Class A solids during periods of downtime if a mechanical failure occurs or to accommodate regular maintenance of one dryer train. As mentioned previously, this Plan recommends the City complete a study of the secondary sludge quality, performance of that process, chemical addition types and locations, and solids handling process performance overall prior to making a final selection of the preferred dryer alternative from the alternatives detailed in Chapter 6. For purposes of capital planning, this Plan assumes the City will implement Alternative 2b (modification of Dewatering and Drying Building to accommodate a second paddle dryer) with a study and confirmation of this selection beginning in 2029.

Lastly, the City wants to establish a direct connection between the City's fiber optics network and the WWTP. This addition consists of routing two new conduits (one spare) and fiber optic cabling from the WWTP's Operations Building to the site entrance, where the conduits will be tied into the City's fiber optics network. Chapter 6 details one potential routing from the Operations Building to the site entrance that would minimize impact to existing yard utilities. The fiber optic cable addition is included in Chapter 7 and the City's 5-year CIP.

Table ES.5 below summarizes the alternatives evaluated in Chapter 6 including recommendations for future WWTP improvements.

Unit Process	Alternatives Considered	Selected Alternative
Secondary Treatment	<ul> <li>Expansion of the existing conventional activated sludge process.</li> <li>Intensification of the existing treatment process.</li> </ul>	• Expansion of the existing conventional activated sludge process through the addition of another aeration basin.
Tertiary Treatment	<ul> <li>Increase filtration capacity.</li> <li>Eliminate the requirement on the DBO firm to meet effluent limits more stringent than the NPDES permit.</li> </ul>	• Eliminate the requirement on the DBO firm to meet effluent limits more stringent than the NPDES permit.
Solids Dryer	<ul> <li>Continue operating the existing BCR paddle dryer and defer replacements.</li> <li>Modify the existing Dewatering and Drying Building to accommodate a different solids dryer technology or a redundant dryer.</li> <li>Construct a new dryer building with a different solids dryer technology.</li> </ul>	• Modify the existing Dewatering and Drying Building to accommodate a different solids dryer technology or a redundant dryer by expanding the Dewatering and Drying Building to accommodate a second solids paddle dryer.

#### Table ES.5 Summary of Alternatives



#### ES.8 Recommended Alternative

Figure ES.6 presents a WWTP site plan identifying locations of recommended improvements resulting from condition and capacity assessments, including evaluation of alternatives, as described.

Summaries of opinions of probable costs and anticipated phasing for the improvements recommended for inclusion in the City's WWTP CIP are provided in Table ES.6.

The expected cash flow for the planning period was determined for the recommended improvements summarized in Table ES.6. The cash flow through 2045 includes an escalation rate of three percent, and the estimated peak expenditure for any fiscal year is approximately \$13,906,000 in fiscal year 2031. The projected CIP expenditures are presented in Figure ES.7.

Table ES.6 WWTP CIP - Recommended Alternative Opinion of Probable Cost and Phasing	Table ES.6	WWTP CIP -	Recommended	Alternative O	pinion of	Probable	Cost and Phasing
--	------------	------------	-------------	---------------	-----------	----------	------------------

Plant Area	Project <sup>(1)</sup>	Opinion of Probable Cost	Approximate Year Online
Solids Handling	Dewatering Performance Optimization	\$150,000	2023
Communications/IT	Fiber Optic Cable Addition	\$55,000	2023
UV System	Trojan 4000 UV System Improvement	\$1,650,000	2024
Support Buildings	Seismic Improvements	\$1,015,000	2024
Secondary Treatment	New Secondary Clarifier Mechanisms	\$1,665,000	2026
Solids Handling	Solids Dryer Improvement	\$16,100,000 <sup>(6)</sup>	2031
Solids Handling	Existing Centrifuge Replacement	\$2,200,000 <sup>(3,5)</sup>	2033(4)
Secondary Treatment	New Aeration Blower	\$394,000	2035
Secondary Treatment	New Conventional Aeration Basin	\$7,895,000	2038
	TOTAL	\$31,124,000	

Notes:


White rows indicate projects that are in the City's 5-year CIP and blue rows indicate projects that are outside the 5-year CIP window.

(1) Details of each project can be found in Chapter 2 or Chapter 6 of this Master Plan.

- (2) The estimated opinion of probable costs include the construction costs plus Engineering, legal and administration fees (ELA, or soft costs). Details on the estimated project costs can be found in Chapter 2 or Chapter 6 of the plan, with the exception of costs for the backup UV system and centrifuges which are presented earlier in Chapter 7.
- (3) For budgeting purposes, the Option B centrifuge cost from Table 7.4 is used for the project cost summary and the CIP
   (4) Replacement timing dependent upon satisfactory equipment performance
- (5) The centrifuges installed with the City's 2014 upgrade project have exhibited inconsistent performance in recent months. The City recently refurbished these units and expects they will provide sufficient capacity through 2045. However, by that time, the units will have been in service for over 30 years. It is recommended the City plan for replacement of these units during the planning horizon of this Master Plan. Assuming replacement occurs in the mid-2030's the City should reassess capacity needs of those units beyond the 2045 horizon, consistent with the expected service life of the new equipment.
- (6) The existing solids dryer has sufficient capacity through 2045. As with the dewatering centrifuges, the dryer equipment will soon have been in operation for a decade. It is recommended the City plan for replacement of the dryer during the planning horizon of this Master Plan. The City plans to replace the existing dryer with a new piece of equipment using similar technology and potentially rehabilitate the existing unit to serve as a backup. See Alternative 2B, Chapter 6.

Capital costs estimated in the Plan will be considered as the City assesses the need to adjust sewer enterprise rates and charges in coming months. It will be important to distinguish capacity and condition (repair and replacement) driven improvements in assigning costs to existing rate payers and future users.





30' 60'

SCALE: 1" = 60'



#### LEGEND:

#### CONDITION OR ADDITION PROJECTS

- 1 DEWATERING & DRYING BUILDING
- 1A EXISTING CENTRIFUGE REPLACEMENT
- 1B SOLIDS DRYER IMPROVEMENT
- 3 SECONDARY CLARIFIER NO. 1 REPLACE
- 4 SECONDARY CLARIFIER NO. 2 REPLACE
- 5 STANDBY UV SYSTEM REPLACEMENT
- 16 FIBER OPTIC CABLE ADDITION

#### CAPACITY PROJECTS

- 17 NEW AERATION BLOWER
- 18 NEW AERATION BASIN NO. 3, ACCESS **IMPROVEMENTS & GRADING**


#### SEISMIC RETROFIT PROJECTS

- 2 PROCESS GALLERY
- 14 OPERATIONS BUILDING
- 7 SECONDARY PROCESS FACILITY
- 8 STABILIZATION BASIN
- 9 SLUDGE STORAGE BASINS AND **BIOFILTERS 12 - SECONDARY** CLARIFIER NO. 3
- 12 COOLING TOWERS
- 13 W3 REUSE PUMP STATION

Figure ES.6 **PROPOSED WILSONVILLE WWTP IMPROVEMENTS** CITY OF WILSONVILLE



Item B.



EXECUTIVE SUMMARY | WASTEWATER TREATMENT PLANT MASTER PLAN | CITY OF WILSONVILLE



39

City of Wilsonville Wastewater Treatment Plant Master Plan

City Council Work Session August 1, 2022





### Introduction

**Presenters:** 

Mike Nacrelli, PE, Senior Civil Engineer

Dave Price, PE, Carollo Engineers



### **Master Plan Drivers**

- City Capital Planning
- Accommodating Expected Growth
- Addressing Asset Condition and Replacement needs
- Assessing Potential Regulatory Drivers



## **Facility Capacity Assessment**

- Flows & Loads Drive core process needs
- Existing WWTP design (2014 expansion) ADWF 4 mgd

Item	Existing	Projected 2045
Average Dry Weather Flow, mgd	1.94	2.68 (~38% > existing)
Average Annual Flow, mgd	2.24	3.03 (~35% > existing)
Maximum Month Wet Weather Flow, mgd	3.78	4.90 (~30% > existing)
Average Annual BOD <sup>5</sup> , ppd	7,470	10,613 (~40% > existing)
Average Annual TSS, ppd	6,427	8,714 (~35% > existing)



## **Asset Condition Assessment**

- Process Condition/Age Drivers
  - 2014 project facilities and equipment in service > 30 years by 2045
  - Solids facilities
    - Performance issues
      - Solids Dryer fire (2019), component failures (2021), uneven performance
      - Solids Dewatering Centrifuges uneven performance (2020/21)
  - Secondary clarifiers Pre-date 2014 upgrades, near term mechanism replacements, clarifiers no. 1 and 2
  - UV Disinfection backup unit pre-dates 2014 upgrades, near term replacement



# **Potential Regulatory Drivers**

- DEQ Total Maximum Daily Load (TMDL) Lower Willamette River
- Dissolved oxygen & nutrients
  - Nutrients can contribute to low oxygen conditions
  - Anticipate and accommodate future phosphorous, possibly nitrogen limits
- Pay attention to Willamette River temperature concerns



## **Unit Process Capacity Summary**


Unit Process	Design Parameter	Redundancy Criteria	Possible Year of Capacity Exceedance	Identified Alternatives
Secondary Treatment	MW MLSS inventory @ PDF	All units in service	2038	<ul> <li>New Aeration Basin</li> <li>New Secondary Clarifier</li> </ul>
Aeration Blowers	Peak BOD Load	Largest unit out of service	2035	Additional Blower
Disk Filters	MWDWF	One unit in backwash	2037	<ul><li>Third Disc Filter</li><li>Relax DBO limits</li></ul>
				<ul> <li>Emergency Biosolids Management Plan</li> </ul>
Biosolids Dryer	MW Load	All units in service	>2045	<ul> <li>Redundant Dryer, similar technology</li> </ul>
				Different Dryer     technology

# **Alternatives Evaluation**

- Consider alternatives for process units identified as capacity deficient
- Secondary Process
  - Add new Aeration Basin
  - Add new blower
- Tertiary Disk Filters
  - Relax DBO effluent TSS limits
- Solids Dryer driven by performance, not necessarily capacity
  - Further study, placeholder to expand dewatering and drying building, add new paddle dryer, refurbish existing dryer (backup)



### **Recommended Plan**




- 3 New Aeration Basin
- 2 Additional Aeration Blower
- Replace backup UV system
- Plan to replace Solids Dryer & Centrifuges
- 6 Replace Clarifier 1 & 2 mechanisms
- 4 8 Seismic retrofits of buildings
  - 18 New fiber optic connection

Solids process study

### **Proposed Project Phasing Schedule**



## **Draft Cash Flow**





# **Next Steps**

- DEQ review and approval of Plan
- Virtual Public Open House (8/24)
- Planning Commission Work Session 9/14
- Planning Commission Public Hearing 10/12
- City Council Public Hearing 1<sup>st</sup> Reading 11/7
- City Council 2<sup>nd</sup> Reading 11/21
- Sewer System Rate Study and SDC Update FY23




## **Questions?**

## **Reference Slides**

### **Capital Planning and Expected Growth - 2045**

- Current Service Area needs
   20+ years through 2045
  - Population and associated economic development

2015	2020	2030	2045
22,870	25,915	29,756	30,566




# **Condition Assessment**

- Prioritize 2019 findings of consultant assessments
  - Secondary clarifiers
  - UV system
- Geotechnical and seismic evaluations
  - Older buildings found to present moderate risk
  - Identified mitigations to address seismic concerns
    - Operations Building
    - Process Gallery
    - Workshop



### **Alternatives Evaluation**

- Solids Dryer driven by performance, not capacity
  - Further study, placeholder to expand dewatering and drying building, add new paddle dryer, refurbish existing dryer (backup)
  - Largest potential investment in Master Plan



### City Council Meeting Action Minutes August 1, 2022

City Council members present included:	Jeanna Troha, Assistant City Manager
Mayor Fitzgerald	Delora Kerber, Public Works Director
Council President Akervall	Martin Montalvo, Public Works Ops. Manager
Councilor Lehan	Mark Ottenad, Public/Government Affairs Director
Councilor West	Mike Nacrelli, Civil Engineer
Councilor Linville	Cindy Luxhoj, Associate Planner
	Zach Weigel, City Engineer
Staff present included:	Martin Montalvo, Public Works Ops. Manager
Amanda Guile-Hinman, City Attorney	Zoe Mombert, Assistant to the City Manager
Kimberly Veliz, City Recorder	Ryan Adams, Assistant City Attorney

	AGENDA ITEM	ACTIONS
WORK	SESSION	<b>START:</b> 5:05 p.m.
A.	Public Works Complex Construction Contract	Council was informed of Resolution No. 2988, which authorizes the City Manager to execute a construction contract with Emerick Construction Company for construction of the Public Works Complex Project.
В.	Waste Water Treatment Plant Master Plan	Staff shared tenets of a draft Wastewater Treatment Master Plan that accommodates the City's projected 20-year growth, addresses seismic resiliency and identifies assets to be upgraded and/or replaced.
C.	2023 League of Oregon Cities Legislative Priorities Ballot	The City's lobbyist sought the Council's direction to finalize the legislative priorities to be listed on the League of Oregon Cities' (LOC) legislative priority ballot.
REGUL	AR MEETING	
<u>Mayor</u>	's Business	
A.	July 30, 2022 Curtailment Event	Staff explained the water pump failure at the Willamette River Water Treatment Plant (WRWTP) and the subsequent Water Curtailment Notice for the cities of Wilsonville and Sherwood.
В.	Upcoming Meetings	Upcoming meetings were announced by the Mayor as well as the regional meetings she attended on behalf of the City.

<u>Communications</u> A. Tourism Promotion Committee Marketing	City Council heard highlights about the City's current promotional activities displayed on ExploreWilsonville.com, which are designed to attract visitors for overnight lodging.
<ul> <li><u>Consent Agenda</u></li> <li>A. <u>Resolution No. 2988</u> Authorizing the City Manager to execute a construction contract with Emerick Construction Company for construction of the Public Works Complex Project (Capital Improvement Project #8113).</li> <li>B. <u>Resolution No. 2991</u> A Resolution Of The City Of Wilsonville Authorizing The City Manager To Execute The Second Amendment To Construction Contract With Moore Excavation, Inc. For The 5th Street / Kinsman Road Extension Project.</li> <li>C. Minutes of the July 18, 2022 City Council Meeting.</li> </ul>	The Consent Agenda was approved 5-0.
<u>New Business</u> A. None.	
<u>Continuing Business</u> A. None.	
Public HearingA.Ordinance No. 865An Ordinance Of The City Of Wilsonville Approving AZoneMapAmendmentFromThe FutureDevelopment Agricultural – Holding (FDA-H) Zone ToThe Planned Development Industrial (PDI) Zone OnApproximately0.55AcreLocatedAt 28505SWBoonesFerry Road; The Land Is More ParticularlyDescribed As Tax Lot 800, Section 14A, Township 3South, Range1West, WillametteMeridian,Clackamas County, Oregon. Davidsons Boones FerryIndustrial LLC, Owner/Applicant.	After a public hearing was conducted, Ordinance No. 865 was approved on first reading by a vote of 5-0.
<u>City Manager's Business</u>	No report.
Legal Business	No report.

URBAN RENEWAL AGENCY	
<ul> <li><u>URA Consent Agenda</u> <ul> <li>A. <u>URA Resolution No. 327</u></li> <li>A Resolution Of The City Of Wilsonville Urban Renewal Agency Authorizing The City Manager To Execute The Second Amendment To Construction Contract With Moore Excavation, Inc. For The 5th Street / Kinsman Road Extension Project.</li> <li>B. Minutes of the June 20, 2022 Urban Renewal Agency Meeting.</li> </ul> </li> </ul>	The URA Consent Agenda was approved 5-0.
<u>New Business</u> A. None.	
URA Public Hearing A. None.	
EXECUTIVE SESSION	Pursuant to ORS 192.660(2)(h) Legal Counsel/Litigation
ADJOURN	9:01 p.m.



### PLANNING COMMISSION WEDNESDAY, JULY 13, 2022

#### WORK SESSION

2. Wastewater Treatment Plant Master Plan (Nacrelli) (45 minutes)



### PLANNING COMMISSION WORK SESSION STAFF REPORT

Meeting Date: July 13, 2022	Subject: Wastewater Treatment Plant Master Plan
	Staff Member: Mike Nacrelli, Senior Civil Engineer
	Department: Community Development
Action Required	Advisory Board/Commission Recommendation
□ Motion	□ Approval
□ Public Hearing Date:	Denial
$\Box$ Ordinance 1 <sup>st</sup> Reading Dat	$\Box$ None Forwarded
$\Box$ Ordinance 2 <sup>nd</sup> Reading Dat	e: $\bowtie$ Not Applicable
□ Resolution	Comments: N/A
☑ Information or Direction	
□ Information Only	
□ Council Direction	
□ Consent Agenda	
Staff Recommendation: Pro	vide requested input regarding recommended capital
improvement plan.	
Recommended Language f	or Motion: N/A
Project / Issue Relates To:	
⊠Council Goals/Priorities:	□ Adopted Master Plan(s): □Not Applicable
Align infrastructure plans with sustainable financing resources.	

#### ISSUE BEFORE PLANNING COMMISSION:

Provide feedback and input on components of the Wastewater Treatment Plant (WWTP) Master Plan.

#### **EXECUTIVE SUMMARY:**

This new City of Wilsonville (City) Wastewater Treatment Plant (WWTP) Master Plan (the Plan) has been developed to satisfy requirements associated with the State of Oregon Department of Environmental Quality (DEQ) guidance document entitled "Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities." To accommodate future flows and loads, projections were developed based on population projections and referencing WWTP historical data and DEQ wet weather project methodologies. Similarly, to accommodate future water quality regulations, the Plan is adaptive and considers potential future regulatory changes.

The City prepared the Plan with the goal of developing a capital plan that identifies improvements required through the planning period (today through 2045) to comply with requirements of the WWTP National Pollutant Discharge Elimination System (NPDES) permit and potential future regulatory requirements, while accommodating growth identified in the City of Wilsonville Comprehensive Plan (October 2018, updated June 2020 - the 2018 Comprehensive Plan). These improvements are designed to provide the best value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development, consistent with goals and policies contained in the 2018 Comprehensive Plan and 2021-2023 City Council Goals.

The City's WWTP was originally built in 1971 and discharges treated effluent to the Willamette River. The WWTP underwent major upgrades in 2014 to expand the average dry weather capacity to four million gallons per day (mgd) to accommodate the City's continued growth. The WWTP processes include headworks screening and grit removal facilities, aeration basins, stabilization basins, secondary clarifiers, biosolids processing, cloth filtration, and disinfection processes. Additionally, the City contracts with Jacobs for operation of the wastewater treatment plant, located at 9275 Southwest Tauchman Road.

This Plan identifies improvements taking into consideration:

- The age and condition of existing process equipment and structures,
- Growth in demand for sewer service due to increased population and economic development over the planning period,
- Potential changes to water quality regulations impacting process needs in order to meet effluent limitations and discharge prohibitions imposed by the Oregon Department of Environmental Quality (DEQ), and
- Consistency with the 2018 Comprehensive Plan and City Council 2021-2023 Goals 5, 6 and 7.

#### WWTP Condition Assessment

Carollo reviewed prior condition assessments performed by others, conducted geotechnical investigations and performed seismic assessments at the WWTP in the course of Plan development.

In 2019, Jacobs Engineering Group Inc. (Jacobs) and Brown and Caldwell both completed condition assessments at the City's WWTP. A total of 322 major assets (per Jacobs' report), including process and mechanical equipment, motors and drives, control panels, generators,

instrumentation, and structures, were examined for a variety of conditions that may signify their need for maintenance or replacement.

#### Seismic Analysis

In 2021, Carollo performed a seismic evaluation and analysis of the City's WWTP as part of the overall plant condition assessment. Because the WWTP was substantially upgraded and expanded in 2014, most of its infrastructure is designed in accordance with the 2010 Oregon Structural Specialty Code (OSSC) and follows modern seismic design and detailing. During Tier 1 evaluations, Carollo identified potential deficiencies and areas for additional investigation. A Tier 1 seismic analysis is an initial evaluation performed to identify any potential deficiencies, whether structural or non-structural, in a building based on the performance of other similar buildings in past earthquakes. Subsequent to the Tier 1 analysis, a more detailed seismic evaluation of five older and potentially seismically vulnerable structures on the WWTP site was conducted. Those structures receiving a more detailed evaluation included the following:

- Operations Building
- Process Gallery
- Workshop
- Aeration Basins and Stabilization Basins
- Sludge Storage Basins and Biofilter

The five potentially vulnerable structures were compared against an S-4 Limited Safety structural performance level and N-B Position Retention non-structural performance level for an M9.0 Cascadia Seismic Zone (CSZ) earthquake. The M9.0 CSZ is reflective of a catastrophic natural disaster event that has an estimated 35 percent likelihood of occurring within the next 50 years. Following the Tier 1 evaluation, Carollo began Tier 2 evaluations for a select number of identified deficiencies. Although none of the structures showed significant irregularities, the team did identify seismic deficiencies. The recommended seismic retrofits are included in the CIP for the Plan.

Prior to the 2021 seismic evaluation, Carollo's subconsultant, Northwest Geotech, Inc. (NGI), completed a seismic response and geologic hazards assessment of the City's WWTP. Through past and present site investigations and engineering analyses, NGI determined that the native soils beneath the site's granular pit backfill have low risk of liquefaction and its slopes do not pose undue risk. NGI concluded that the WWTP's primary site hazard is the differential settlement that may be caused by soil piping (development of subsurface air-filled voids), which raises the risk of sinkholes forming beneath structures and pipelines. Soil piping usually develops in unsaturated soils when a water source percolates into the ground. While the site is mostly paved and stormwater is being collected, there may be areas where infiltration is occurring next to structures or below pipelines. Recommended actions from NGI to mitigate the risk of soil piping are presented in the Plan.

#### Wastewater Flow and Load Projections

The Plan evaluates the historical and projected wastewater flows and loads generated in the City of Wilsonville's service area. The load projections include total suspended solids (TSS), biochemical oxygen demand (BOD5), ammonia (NH3), and total phosphorous (TP) loads.

Service area, residential population, industrial contribution, and rainfall records were all considered in the flow and load projection analyses.

#### Capacity Analysis

Summaries of plant process area capacity assessments and conclusions are presented in the Plan. These assessments focus on the need for improvements or upgrades to existing facilities to address capacity deficiencies identified in the course of Master Plan evaluations.

#### **Regulatory Considerations and Strategy**

Several possible regulatory actions by the Oregon DEQ could drive investments in future improvements at the City's WWTP. The plant discharges to the Willamette River and existing and future effluent limitations contained in the NPDES permit dictate, in large part, the necessary treatment processes and configuration at the WWTP necessary to maintain compliance. The existing permit limits for the Wilsonville WWTP are effective September 1, 2020 through July 30, 2025.

#### Alternative Development and Evaluation

The Plan presents the methodology and findings of a process improvements alternatives evaluation. The plant's treatment process needs were defined by comparing the plant's existing condition, capacity and reliability, with the projected flows, loads, and regulatory constraints for the recommended alternatives. Where capacity deficiencies were predicted, at least two alternatives were analyzed for each corresponding unit process.

#### **EXPECTED RESULTS**:

The Plan includes a list of recommended capital improvements, along with an anticipated schedule for completion and preliminary cost estimates. These improvements will provide the basis for an analysis of sewer rates and system development charges (SDCs) that will be necessary to adequate funding to implement to required upgrades.

#### TIMELINE:

This is the first in a series of presentations to the Planning Commission and City Council. Subsequent planned meetings are as follows:

- City Council Work Session 8/1
- Planning Commission Public Hearing 9/14
- City Council Public Hearing 1st Reading 10/3
- City Council 2nd Reading 10/17

#### CURRENT YEAR BUDGET IMPACTS:

The remaining contract balance for finalizing the Plan will carry over into FY 22/23. An additional \$92,450 has been budgeted in FY 22/23 for the Sewer System Rate Study and SDC Update, using a combination of Sewer Operating funds and SDCs.

#### COMMUNITY INVOLVEMENT PROCESS:

The public hearings listed above will provide opportunity for public input. In addition, the Sewer System Rate Study and SDC Update will include a robust public engagement process.

#### POTENTIAL IMPACTS or BENEFIT TO THE COMMUNITY:

A technically and financially sound plan for providing reliable wastewater treatment, capacity to accommodate future development, and compliance with environmental regulations.

#### **ALTERNATIVES:**

The Plan includes alternatives for several of the recommended improvements. The selected alternatives were determined to be the most economically viable. Some of the more capital intensive alternatives can be revisited if necessary due to changing regulatory requirements.

#### **ATTACHMENTS:**

Attachment 1 Draft Wastewater Treatment Plant Executive Summary (dated June 2022)





City of Wilsonville Wastewater Treatment Plant Master Plan

### **EXECUTIVE SUMMARY**

DRAFT | June 2022



Attachment 1



### City of Wilsonville Wastewater Treatment Plant Master Plan

### **EXECUTIVE SUMMARY**

DRAFT | June 2022

Attachment 1

### Contents

### **Executive Summary**

ES.1 Planning Area Characteristics	ES-6
ES.2 WWTP Condition Assessment	ES-10
ES.3 Seismic Analysis	ES-10
ES.4 Wastewater Flow and Load Projections	ES-11
ES.5 Capacity Analysis	ES-13
ES.6 Regulatory Considerations and Strategy	ES-19
ES.7 Alternative Development and Evaluation	ES-20
ES.8 Recommended Alternative	ES-24

### Tables

Table ES.1	CIP Condition Driven Replacement Projects	ES-10
Table ES.2	Existing (2020) Flow Summary	ES-12
Table ES.3	2045 Flow Projections	ES-12
Table ES.4	Load Projections	ES-13
Table ES.5	Unit Process Capacity Assessment	ES-17
Table ES.6	Unit Process Capacity Year Summary	ES-19
Table ES.7	Current Effluent Permit Limits	ES-20
Table ES.8	Secondary Alternatives Opinion of Probable Cost Comparison	ES-21
Table ES.9	Summary of Alternatives	ES-23
Table ES.10	WWTP Recommended Alternative Opinion of Probable Cost and Phasing	ES-24

### Figures

Figure ES.1	Planning Area	ES-7
Figure ES.2	Historical Population and Expected Growth for the City of Wilsonville	ES-9
Figure ES.3	Existing Wilsonville WWTP	ES-15
Figure ES.4	Proposed WWTP Improvements Site Plan	ES-25
Figure ES.5	Projected 20-Year CIP Expenditures	ES-27

*<i><i>carollo* 



### Abbreviations

AA	average annual
AAF	average annual flow
ABF	Average base flow
ADWF	average dry-weather flow
AWWF	average wet weather flow
BCR	biochemical reactor
BOD₅	biochemical oxygen demand
CIP	Capital Improvement Plan
City	the City of Wilsonville
CBOD₅	five-day carbonaceous biochemical oxygen demand
CSZ	Cascadia Seismic Zone
DBO	Design-Build-Operate
DEQ	Department of Environmental Quality
DMR	Discharge Monitoring Reports
ETL	excess thermal load
gpd/sf	gallons per day per square foot
НМІ	human-machine interface
Jacobs	Jacobs Engineering Group Inc.
kcal/day	kilocalories per day
lbs	pounds
MBR	membrane bioreactor
mg/L	milligrams per liter
mgd	million gallons per day
MGI	Northwest Geotech, Inc.
ml	milliliter
MLSS	mixed liquor suspended solids
MM	maximum month
MMDWF	maximum month dry weather flow
MMWWF	maximum month wet weather flow
MW	maximum week
MWDWF	maximum month dry weather flow
MWWWF	maximum week wet weather flow
NH₃	ammonia
No.	number
NPDES	National Pollutant Discharge Elimination System
OSSC	Oregon Structural Specialty Code
PD	peak day



#### CITY OF WILSONVILLE | WASTEWATER TREATMENT PLANT MASTER PLAN | EXECUTIVE SUMMARY

PDDWF	peak day dry weather flow
PDWWF	peak day wet weather flow
PHF	peak hour flow
ppd	pounds per day
PSU PRC	Portland State University Population Research Center
R/C	residential/commercial
SPA	State Point Analysis
SRT	solids residence time
the Plan	Master Plan
TMDL	total maximum daily loads
ТР	total phosphorous
TS	total solids
TSS	total suspended solids
TWAS	thickened waste activated sludge
UGB	urban growth boundary
UV	ultraviolet
WWTP	wastewater treatment plant



### **EXECUTIVE SUMMARY**

This new City of Wilsonville (City) Wastewater Treatment Plant (WWTP) Master Plan (the Plan) has been developed to satisfy requirements associated with the State of Oregon Department of Environmental Quality (DEQ) guidance document entitled "Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities." To accommodate future flows and loads, projections were developed based on population projections and referencing WWTP historical data and DEQ wet weather project methodologies. Similarly, to accommodate future water quality regulations, the Plan is adaptive and considers potential future regulatory changes.

The City prepared the Plan with the goal of developing a capital plan that identifies improvements required through the planning period (today through 2045) to comply with requirements of the WWTP National Pollutant Discharge Elimination System (NPDES) permit and potential future regulatory requirements, while accommodating growth identified in the City of Wilsonville Comprehensive Plan (October 2018, updated June 2020 - the 2018 Comprehensive Plan). These improvements are designed to provide the best value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development, consistent with goals and policies contained in the 2018 Comprehensive Plan and 2021-2023 City Council Goals.

The City's WWTP was originally built in 1971 and discharges treated effluent to the Willamette River. The WWTP underwent major upgrades in 2014 to expand the average dry weather capacity to four million gallons per day (mgd) to accommodate the City's continued growth. The WWTP processes include headworks screening and grit removal facilities, aeration basins, stabilization basins, secondary clarifiers, biosolids processing, cloth filtration, and disinfection processes. Additionally, the City contracts with Jacobs for operation of the wastewater treatment plant, located at 9275 Southwest Tauchman Road.

This Plan identifies improvements taking into consideration:

- The age and condition of existing process equipment and structures,
- Growth in demand for sewer service due to increased population and economic development over the planning period,
- Potential changes to water quality regulations impacting process needs in order to meet effluent limitations and discharge prohibitions imposed by the Oregon Department of Environmental Quality (DEQ), and
- Consistency with the 2018 Comprehensive Plan and City Council 2021-2023 Goals 5, 6 and 7.



#### **ES.1** Planning Area Characteristics

Chapter 1 summarizes the City's wastewater service area characteristics relevant to assessing WWTP facility needs. The planning area considered by this Plan is consistent with the City's 2014 Collection System Master Plan and 2018 Comprehensive Plan including the urban growth boundary (UGB), which is currently the limit of City sewer service as shown in Figure ES 1.



#### EXECUTIVE SUMMARY | WASTEWATER TREATMENT PLANT MASTER PLAN | CITY OF WILSONVILLE




Figure ES.1 Planning Area

Mpw:\\IO-PW-INT.Carollo.local:Carollo\Documents\Client\OR\W elaPlanning Commission Meeting - July 13, 2022

Wastewater Treatment Plant Master Plan

ES-8 | JUNE 2022 | DRAFT



Planning Commission Meeting - July 13, 2022 Wastewater Treatment Plant Master Plan The northern portion of the City of Wilsonville is located within Washington County, and the majority of the City lies in the southwestern part of Clackamas County.

The City sits within the jurisdictional boundaries of Metro, the regional government for the Portland metropolitan area. By state law, Metro is responsible for establishing the Portland metropolitan area's UGB, which includes Wilsonville. Land uses and densities inside the UGB require urban services such as police and fire protection, roads, schools, and water and sewer systems. A figure of the City's existing land use is presented in Chapter 1. Also presented in Chapter 1 are the City's physical characteristics, water resources, and population and employment information, which are all significant factors in planning for wastewater conveyance and treatment facilities.

The Portland State University Population Research Center (PSU PRC) publishes annual estimates of populations for the previous year for cities in Oregon while Metro develops population projections for the future within the Portland metropolitan area, including Wilsonville. The PSU PRC estimated the City's population as 25,625 in 2019. Metro estimates the City's population to reach 30,566 people by 2045.

For establishing a per capita basis for flow and load projections for the Plan, certified PSU PRC historical population estimates were used for 2015 through 2019. Metro's future population forecasts were used for 2020 through 2045. Figure ES.2 shows the historical population and future growth predicted for the City.




Figure ES.2 Historical Population and Expected Growth for the City of Wilsonville



### ES.2 WWTP Condition Assessment

Carollo reviewed prior condition assessments performed by others, conducted geotechnical investigations and performed seismic assessments at the WWTP in the course of Plan development.

In 2019, Jacobs Engineering Group Inc. (Jacobs) and Brown and Caldwell both completed condition assessments at the City's WWTP. A total of 322 major assets (per Jacobs' report), including process and mechanical equipment, motors and drives, control panels, generators, instrumentation, and structures, were examined for a variety of conditions that may signify their need for maintenance or replacement. Chapter 2 presents a summary of critical assets that require short term rehabilitation or replacement, as well as a list of assets that are less critical to operations, or have minor condition issues, but may be included in a short-term improvements project or a task order for Jacobs operations personnel. Table ES.1 displays the condition driven rehabilitation or replacement projects from Chapter 2 that were included in the recommended Capital Improvement Plan (CIP) in Chapter 7.

#### Table ES.1 CIP Condition Driven Replacement Projects

Asset	Description		
Trojan UV 4000 System	While only used as a backup to the Ozonia UV system, the Trojan system's HMI has errors that prevent it from showing the status of the lamps in module 3. Since it is used infrequently, the system's condition is largely unknown. After review of the 2019 condition assessment reports and discussion with the City and Jacobs staff, it was concluded that the UV 4000 unit must be replaced.		
Secondary Clarifiers No. 1 and No. 2	Ovivo completed a field review of the plant's secondary clarifiers No. 1 and No. 2 in April 2022. Although both units were operational, repairs were identified to improve the operation of the clarifiers. The recommended repairs include drive controls for both units, new skimmers for both units, squeegees for both tanks rake arms, EDI chains, one motor and reducer assembly, one skimmer arm assembly, and new secondary clarifier mechanisms. <sup>(1)</sup>		

Notes:

(1) The detailed Ovivo Field Service Report is included in Appendix X.

Abbreviations: HMI - human-machine interface; No. - number; UV - ultraviolet.

#### ES.3 Seismic Analysis

In 2021, Carollo performed a seismic evaluation and analysis of the City's WWTP as part of the overall plant condition assessment. Because the WWTP was substantially upgraded and expanded in 2014, most of its infrastructure is designed in accordance with the 2010 Oregon Structural Specialty Code (OSSC) and follows modern seismic design and detailing. During Tier 1 evaluations, Carollo identified potential deficiencies and areas for additional investigation. A Tier 1 seismic analysis is an initial evaluation performed to identify any potential deficiencies, whether structural or non-structural, in a building based on the performance of other similar buildings in past earthquakes. Subsequent to the Tier 1 analysis, a more detailed seismic



evaluation of five older and potentially seismically vulnerable structures on the WWTP site was conducted. Those structures receiving a more detailed evaluation included the following:

- Operations Building.
- Process Gallery.
- Workshop.
- Aeration Basins and Stabilization Basins.
- Sludge Storage Basins and Biofilter.

The five potentially vulnerable structures were compared against an S-4 Limited Safety structural performance level and N-B Position Retention non-structural performance level for an M9.0 Cascadia Seismic Zone (CSZ) earthquake. The M9.0 CSZ is reflective of a catastrophic natural disaster event that has an estimated 35 percent likelihood of occurring within the next 50 years. Following the Tier 1 evaluation, Carollo began Tier 2 evaluations for a select number of identified deficiencies. Although none of the structures showed significant irregularities, the team did identify seismic deficiencies. The recommended seismic retrofits are included in the CIP for this Plan.

Prior to the 2021 seismic evaluation, Carollo's subconsultant, Northwest Geotech, Inc. (NGI), completed a seismic response and geologic hazards assessment of the City's WWTP. Through past and present site investigations and engineering analyses, NGI determined that the native soils beneath the site's granular pit backfill have low risk of liquefaction and its slopes do not pose undue risk. NGI concluded that the WWTP's primary site hazard is the differential settlement that may be caused by soil piping (development of subsurface air-filled voids), which raises the risk of sinkholes forming beneath structures and pipelines. Soil piping usually develops in unsaturated soils when a water source percolates into the ground. While the site is mostly paved and stormwater is being collected, there may be areas where infiltration is occurring next to structures or below pipelines. Recommended actions from NGI to mitigate the risk of soil piping are presented in Chapter 2.

#### ES.4 Wastewater Flow and Load Projections

Chapter 3 of the Plan evaluates the historical and projected wastewater flows and loads generated in the City of Wilsonville's service area. The load projections include total suspended solids (TSS), biochemical oxygen demand (BOD<sub>5</sub>), ammonia (NH<sub>3</sub>), and total phosphorous (TP) loads.

Service area, residential population, industrial contribution, and rainfall records were all considered in the flow and load projection analyses.

Analysis of flow projections were completed through two different methods: (1) analysis of historical plant records and (2) DEQ Guidelines for Making Wet-Weather and Peak Flow Projections for Sewage Treatment in Western Oregon, which is referred to as the DEQ methodology in this Plan. Since there is no DEQ methodology for load analysis, all projections were developed based on historical plant records. Tables ES.2 and ES.3 below detail the existing and year 2045 flows that serve as the basis for the flow projections.



ltem	Selected Flow (mgd)	Industrial Flow (mgd)	R/C Flow (mgd)	R/C Peaking Factor
ABF	1.88	0.17	1.71	1.00
AAF	2.24	0.17	2.07	1.21
ADWF	1.94	0.17	1.77	1.03
AWWF	2.54	0.17	2.37	1.38
MMDWF	2.52	0.19	2.33	1.36
MMWWF	3.78	0.19	3.59	2.09
MWDWF	2.94	0.19	2.75	1.61
MWWWF	4.54	0.19	4.35	2.54
PDDWF	3.63	0.19	3.44	2.01
PDWWF	5.59	0.19	5.41	3.16
PHF	8.80	0.19	8.61	5.02

#### Table ES.2 Existing (2020) Flow Summary

Notes:

Abbreviations: AAF - average annual flow; ABF - average base flow; ADWF - average dry-weather flow; AWWF - average wet weather flow; MMDWF - maximum month dry weather flow; MMDWF - maximum month dry weather flow; MMWWF - maximum month wet weather flow; MWWWF - maximum week wet weather flow; PDDWF - peak day dry weather flow; PDWWF - peak day wet weather flow; PHF - peak hour flow; R/C - residential/commercial.

#### Table ES.3 2045 Flow Projections

ltem	Existing R/C Flow (mgd)	R/C Peaking Factor	2045 R/C Flow	2045 Industrial Flow (mgd)	Projected 2045 WWTP Flow (mgd)
ABF	1.71	1.00	2.02	0.6	2.62
AAF	2.07	1.21	2.43	0.6	3.03
ADWF	1.77	1.03	2.08	0.6	2.68
AWWF	2.37	1.38	2.79	0.6	3.39
MMDWF	2.33	1.36	2.75	0.7	3.42
MMWWF	3.59	2.09	4.23	0.7	4.90
MWDWF	2.75	1.61	3.24	0.7	3.92
MWWWF	4.35	2.54	5.12	0.7	5.80
PDDWF	3.44	2.01	4.05	0.7	4.72
PDWWF	5.41	3.16	6.38	0.7	7.05
PHF	8.61	5.02	10.15	0.7	10.82

Load projections were calculated for influent TSS, BOD<sub>5</sub>, NH<sub>3</sub>, and TP as detailed below in Table ES.4.

Load Parameters	2045 R/C (ppd)	2045 Industrial (ppd)	2045 WWTP (ppd)
BOD₅			
AA BOD5	8,000	2,613	10,613
MM BOD <sub>5</sub>	11,437	2,978	14,415
MW BOD5	14,307	2,978	17,285
PD BOD <sub>5</sub>	21,656	2,978	24,634
TSS			
AA TSS	7,097	1,617	8,714
MM TSS	9,535	1,844	11,379
MW TSS	12,478	1,844	14,322
PD TSS	16,295	1,844	18,139
NH₃			
AA NH₃	695	171	866
MM NH <sub>3</sub>	800	171	971
MW NH <sub>3</sub>	1,035	171	1,205
PD NH <sub>3</sub>	1,443	171	1,614
Total Phosphorus (TP)			
AA TP	222	73	295
MM TP	318	83	400
MW TP	397	83	480
PD TP	601	83	684

Notes:

Abbreviations: AA - average annual; MM - maximum month; MW - maximum week; PD - peak day; ppd - pounds per day.

#### ES.5 Capacity Analysis

Summaries of plant process area capacity assessments and conclusions are presented in this Plan. These assessments focus on the need for improvements or upgrades to existing facilities to address capacity deficiencies identified in the course of Master Plan evaluations. A site plan of the City's existing WWTP is presented in Figure ES.3.

Chapter 4 identifies existing capacity ratings and deficiencies for the liquid and solids stream treatment processes at the City's WWTP. Analyses are based on operational practices in place at the time and existing effluent limits established by the WWTP's National Pollutant Discharge Elimination System (NPDES) permit. Biological process modeling was performed using BioWin version 6.2 to predict plant performance under current and future flow and loading conditions to assess when unit process capacities may be exceeded within the planning period (present through 2045).

A summary of the capacity assessment completed and presented in Chapter 4 is detailed below in Table ES.5.







F

30' 60'

SCALE: 1" = 60'

120



#### LEGEND:

- 1 DEWATERING & DRYING BUILDING
- 4 PROCESS GALLERY
- 5 SECONDARY CLARIFIER NO. 1
- 6 SECONDARY CLARIFIER NO. 2
- 7 UV DISINFECTION SYSTEM
- 8 WORKSHOP
- 9 SECONDARY PROCESS FACILITY
- 10 STABILIZATION BASIN
- 11 SLUDGE STORAGE BASINS AND BIOFILTERS
- 12 SECONDARY CLARIFIER NO. 3
- 13 HEADWORKS
- 14 DISK FILTERS
- 15 COOLING TOWERS
- 16 W3 REUSE PUMP STATION
- 17 OPERATIONS BUILDING 19 - SITE ENTRANCE

Figure ES.3 EXISTING WILSONVILLE WWTP CITY OF WILSONVILLE





#### Table ES.5 Unit Process Capacity Assessment

Unit Process	Capacity Assessment
Preliminary Treatment	
Screening	There is sufficient hydraulic capacity for both mechanical screens to accommodate the projected 2045 PHF. However, if one screen is out o loss in screening capacity.
Grit Removal	Capacity is adequate for providing full treatment of the projected 2045 PHF.
Secondary Treatment	
Secondary Treatment	Based on maximum week MLSS predicted from BioWin modeling at peak day flow with all clarifiers in service (and assuming a 5-day SRT), 2038. SPA also indicates that there is sufficient capacity using the predicted average annual MLSS concentrations and the peak day dry we planning period.
Secondary Clarifiers	The secondary clarifiers are expected to stay under the maximum hydraulic loading criteria of 920 gpd/sf on peak day flow events with all u one unit out of service, for the entirety of the planning period.
Aeration Blowers	The air demands of the secondary treatment process are projected to exceed the firm capacity of the aeration blowers under peak condition
Tertiary Treatment and Disinfection	
Disk Filters	The existing disk filter capacity is expected to be exceeded by 2037 with one unit out of service or in backwash mode based on effluent lim time the City expects to relax these contract limitations rather than invest in additional capacity. There is sufficient time for the City to recarding capacity to the filtration process.
Secondary Effluent Cooling Towers	It is not expected that the total hydraulic capacity of the cooling towers will be exceeded by 2045.
UV Disinfection	The existing UV channels are adequately sized to fully disinfect the 2045 PHF with all units in service, as well as the PDDWF with one chan place as an emergency backup to the primary system. That backup unit is aging and the City plans replacement during the planning period
Outfall	Even with the Willamette River at its 100-year flood elevation, it is expected that the outfall pipeline can accommodate approximately 19 r submergence upstream. Since this flow is well above the hydraulic capacity of the rest of the plant, no expansion will be needed until after
Solids Handling	
Gravity Belt Thickener	The capacity analysis results show that the assumed operating times of 24 hours per day, 5 days per week are adequate for thickening the out of service.
TWAS Storage	The TWAS storage volume is sufficient to accommodate the expected maximum week solids loads for three days (assuming TWAS is thick taken out of service, there is insufficient storage volume for three days of storage under average annual solids loading conditions.
Dewatering Centrifuges	The rated capacity of the current centrifuges is sufficient to process the maximum week load with one unit out of service though 2045 assuper the criteria detailed in Chapter 4. <sup>(2)</sup>
Biosolids Dryer and Solids Disposal	The capacity of the biosolids dryer is adequate for handling the current and projected max week solids loads (in year 2045) on the basis of i from 20 percent TS to 92 percent TS and the dryer is operated for 24 hour per day for 5 days per week. <sup>(3)</sup>

(1) The existing outfall was recently modified and equipped with five parallel diffuser pipes equipped with duckbill check valves to improve the mixing zone characteristics in the Willamette River.

(2) The centrifuges installed with the City's 2014 upgrade project have exhibited inconsistent performance in recent months. The City recently refurbished these units and expects they will provide sufficient capacity through 2045. However, by that time, the units will have been in service for over 30 years. It is recommended the City plan for replacement of these units during the planning horizon of this Master Plan. Assuming replacement occurs in the mid-2030's the City should reassess capacity needs of those units beyond the 2045 horizon, consistent with the expected service life of the new equipment. (3) The existing solids dryer has sufficient capacity through 2045. As with the dewatering centrifuges, the dryer equipment will soon have been in operation for a decade. It is recommended the City plan for replacement of the dryer during the planning horizon of this Master Plan. The City plans to replace the

existing dryer with a new piece of equipment using similar technology and potentially rehabilitate the existing unit to serve as a backup. See Alternative 2B, Chapter 6.

Abbreviations: DBO - Design-Build-Operate; gpd/sf - gallons per day per square foot; MLSS - mixed liquor suspended solids, SPA - State Point Analysis; SRT - solids residence time; TS - total solids; TWAS - thickened waste activated sludge.

EXECUTIVE SUMMARY | WASTEWATER TREATMENT PLANT MASTER PLAN | CITY OF WILSONVILLE

ut of service, the manual bar rack must be used to make up the

T), a SPA predicts that there is only sufficient capacity through weather flows with a clarifier out of service for the duration of the

all units in service, as well as on max month dry weather flows with

tions by 2035.

mitations included in the City's DBO Contract with Jacobs. At this econsider this approach prior to 2037 and evaluate options for

annel out of service. The City currently has an older UV unit in od.

19 mgd before the UV channel effluent weirs are at risk of ter 2045.<sup>(1)</sup>

ne current and projected maximum week WAS loads with one unit

ickened to 4 percent). However, if one of the two storage tanks is

ssuming operating times of 24 hours per day for 5 days per week,

of its design evaporation rate, assuming dewatered cake is dried



Table ES.6 further summarizes the capacity assessment by listing each unit process, associated design parameters and year of possible capacity exceedance.

Table ES.6	Unit Process	Capacity	Year Summary
------------	--------------	----------	--------------

Unit Process	Design Parameter	Redundancy Criteria <sup>(3)</sup>	Year of Capacity Exceedance
Influent Screening	PHF	One mechanical screen out of service	>2045
Grit Chamber	PHF	All units in service	>2045
Secondary Treatment	MW MLSS inventory at PDF	All units in service	2038
Aeration Blowers	Peak BOD Load	Largest unit out of service	2035
Secondary Effluent Cooling Towers	June 1 - Sept 30 PDF	All units in service	>2045
Disk Filters	MWDWF	One unit in backwash	<b>2037</b> <sup>(1)</sup>
UV Disinfection Channels	PHF	All units in service	>2045
Outfall	PHF	-	>2045
Gravity Belt Thickening	MW Load	One unit out of service	>2045
TWAS Storage	MW Load	All units in service	>2045
Dewatering Centrifuges	MW Load	One unit out of service	>2045 <sup>(2)</sup>
Biosolids Dryer	MW Load	All units in service	>2045 <sup>(2)</sup>

Notes:

Unit processes in white are projected to run out of capacity before year 2045.

(1) Existing Disk Filters are predicted to exceed reliable capacity (one unit out of service) in 2037 based on vendor provided design criteria. This conclusion assumes limitations for effluent total suspended solids contained in the WWTP DBO contract, which are far more stringent than the City's NPDES permit.

(2) As noted previously, the existing centrifuges and biosolids dryer appear to have sufficient capacity through the planning year 2045, however condition and age are likely to require replacement during the planning period. It is recommended the City reassess available replacement technologies prior to replacement and consider loading appropriate to the planning horizon of any new units selected.

(3) Reference Appendix D - Reliability requirements, Preparing Wastewater Planning Documents and Environmental Reports for Public Utilities, OR DEQ, 2018, Revised July 2019

#### ES.6 Regulatory Considerations and Strategy

Chapter 5 details potential regulatory issues the City will need to take into consideration in coming years. Several possible regulatory actions by the Oregon DEQ could drive investments in future improvements at the City's WWTP. The plant discharges to the Willamette River and existing and future effluent limitations contained in the NPDES permit dictate, in large part, the necessary treatment processes and configuration at the WWTP necessary to maintain compliance. The existing permit limits for the Wilsonville WWTP are effective September 1, 2020 through July 30, 2025, and summarized below in Table ES.7



Parameter	Average Effluent Concentrations		Monthly Average,	Weekly Average,	Daily Maximum,	
	Monthly		Weekly	(ppd)	(ppd)	(lbs)
May 1 - October 31						
CBOD₅	10 mg/L		15 mg/L	190	280	380
TSS	10 mg/L		15 mg/L	190	280	380
November 1 - April 30						
BOD <sub>5</sub>	30 mg/L		45 mg/L	560	840	1100
TSS	30 mg/L		45 mg/L	560	840	1100
Other Parameters Limitations						
E. coli Bacteria		•	Shall not excee geometric mea No single samp 100 ml.	in.	·	
рН •		•	Instantaneous limit between a daily minimum of 6.0 and a daily maximum of 9.0			
BOD₅ Removal Efficiency •		•	Shall not be less than 85% monthly average			
TSS Removal Efficiency •		•	Shall not be less than 85% monthly average			
ETL June 1 through September 30		•	Option A: 39 million kcal/day 7-day rolling average Option B: Calculate the daily ETL limit			

#### Table ES.7 Current Effluent Permit Limits

#### Notes:

Abbreviations: CBOD<sub>5</sub> - five-day carbonaceous biochemical oxygen demand; ETL - excess thermal load; kcal/day - kilocalories per day; lbs - pounds, mg/L - milligrams per liter; ml - milliliter.

Future treatment upgrades may be required when DEQ establishes total maximum daily loads (TMDL) for the lower Willamette River. Dissolved oxygen and nutrient limits, such as phosphorus limitations, are possible. The dissolved oxygen in the lower part of the river does not always meet water quality standards, and indications of excessive nutrients, such as chlorophylla, aquatic weeds, and harmful algal blooms, are present in the lower Willamette River. DEQ has begun its triennial review of Oregon's water quality criteria. The review could result in more stringent or new discharge requirements, but this process will take several years. For planning purposes, providing plant footprint to accommodate future treatment to remover phosphorus and address dry weather seasonal limits on dissolved oxygen should be anticipated. In addition, the City should continue to engage with DEQ regarding any proposed receiving water temperature regulatory actions.

#### ES.7 Alternative Development and Evaluation

Chapter 6 presents the methodology and findings of a process improvements alternatives evaluation. The plant's treatment process needs were defined by comparing the plant's existing condition, capacity and reliability, with the projected flows, loads, and regulatory constraints for the recommended alternatives. Where capacity deficiencies were predicted, at least two alternatives were analyzed for each corresponding unit process. Process modifications associated with each alternative were modeled in BioWin using a calibrated model to evaluate the overall impact on plant operations.



As identified in Chapter 4, the secondary treatment process is expected to require additional capacity during the planning horizon (2045). Chapter 6 details two alternatives to address these capacity limitations. The two alternatives considered to increase secondary capacity are:

- 1. Expansion of the existing conventional activated sludge process; and
- 2. Intensification of the existing treatment process using membrane bioreactor (MBR) technology.

Due to the higher capital and operating costs of intensification, construction of a new conventional aeration basin is recommended to increase secondary capacity. As flows and loads increase, or regulatory requirements become more stringent, it may be necessary to intensify treatment. It is recommended the City revisit this evaluation as the need for 1) additional capacity to accommodate growth nears or 2) more stringent effluent limitations are considered. This offers the opportunity to take advantage of potential advances in technology as well as confirming the predicted time frame of capacity exceedance. Table ES.8 below illustrates the differences in cost between the two alternatives. A new aeration basin project is included in the Capital Improvement Plan in Chapter 7.

Description	New Aeration Basin	MBR
Site Work	\$1,273,000	\$62,000
Fine Screens		\$1,268,000
Aeration Basin	\$1,739,000	
MBR Tank		\$3,564,000
Electrical, Instrumentation, and Control	\$522,000	\$1,469,000
Total Direct Cost	\$3,534,000	\$6,363,000
Total Estimated Construction Cost <sup>(1)</sup>	\$5,812,000	\$10,465,000
Total Estimated Project Cost <sup>(2)</sup>	\$7,265,000	\$13,081,000

#### Table ES.8 Secondary Alternatives Opinion of Probable Cost Comparison

Notes:

(1) Assumes 30% Contingency, 10% General Conditions, and 15% Contractor Overhead and Profit.

(2) Assumes 25% Engineering, Legal, and Administrative Fees and ENR Construction Cost Index = 12683 (February 2022).

The existing aeration blower system firm capacity is expected to be deficient by 2035. An additional aeration blower (same size and design air flow rate as the existing high-speed turbo blowers) would ensure there is sufficient blower capacity through the end of the planning period to meet current permit requirements. There is adequate space to add a fourth turbo blower to the same discharge header pipe as the existing turbo blowers. Additionally, intensification of the secondary treatment process would further increase the aeration demands because operating at a higher MLSS reduces oxygen transfer efficiency in the aeration basins. If intensification is reconsidered and selected for the planning period, or if nutrient limits are imposed within the planning period that requires intensification or operation at a higher MLSS, the blower air demands should be revisited.



Additional tertiary filtration capacity is predicted to be needed before 2045 to provide full treatment of the MWDWF with one disc filter out of service or in backwash mode. After discussions with the City, two alternatives were identified to increase capacity:

- 1. Increase filtration capacity, and
- 2. Modify the requirement in the WWTP DBO contract to relax effluent limitations which are currently more stringent than those contained in the City's NPDES permit.

The City's WWTP NPDES permit currently requires effluent to contain less than 10 mg/L TSS during the dry season (see Table ES.8). However, the DBO firm's contract with the City requires an effluent TSS of less than five mg/L, or half of the WWTP's permitted effluent quality. At this time, the City has decided to study the performance of the existing tertiary filters over time and expects to relax effluent TSS requirements in the DBO contract unless actual water quality impacts (exceedances of permit limitations) are realized. The City will also consider the option of new technologies for filtration, noting that if the City selected an intensification technology utilizing membranes, this may potentially eliminate tertiary filtration capacity concerns.

While the capacity assessment findings presented in Chapter 4 determined existing solids dewatering centrifuges have sufficient capacity, the remaining equipment service life may require replacement within the planning horizon. The centrifuges, installed in 2014, were recently refurbished, but by 2045, will have been in service for over 30 years. The City should plan for their replacement within the planning horizon and consider whether a capacity increase is needed at the time of replacement based on projections of solids production and processing needs. Additionally, the secondary process was modified in 2020 and has experienced extended periods where mixed liquor concentrations have been elevated above typical ranges for conventional activated sludge or extended aeration processes. Due to the complications with secondary process operation and performance issues with the centrifuges, it is recommended the City study the secondary treatment and dewatering processes to confirm that the assumptions and conclusions regarding centrifuge capacity in Chapter 4 may be relied upon. A dewatering performance optimization study is recommended so the City can collect and analyze secondary treatment and solids processing performance data. For budgeting purposes, an opinion of probable cost for replacing the existing centrifuges is provided in Chapter 7. Timing of that equipment replacement will depend on performance of the existing units, future loading assumptions, and observed condition.

The existing solids dryer has experienced operational issues in recent years, including a fire that caused extensive damage to the equipment in April 2019 and a leaking rotary joint and damaged seal in 2021. As of February 25, 2022, the dryer has been repaired and is operating. Because of the City's commitment to solids drying as the preferred process to achieve Class A biosolids, the alternatives evaluation presented in this Plan for future dryer replacement was conducted with a focus on thermal drying options only.

Chapter 6 details an analysis of the following alternatives to improve the drying system:

- 1. Alternative 1 Continue operating the existing biochemical reactor (BCR) paddle dryer and defer replacement.
- 2. Alternative 2 Modify the existing Dewatering and Drying Building to accommodate a different solids dryer technology or a redundant dryer.
- 3. Alternative 3 Construct a new dryer building with a different solids dryer technology.



While it is anticipated the existing dryer has useful life through at least 2026 (current DBO contract expiration), by 2031 the dryer will have been in operation for over 15 years. It is recommended the planning and design of upgrades to provide reliable dryer capacity begin in 2029, or sooner if further operational concerns arise. The City has indicated a preference for a variation of Alternative 2 which involves expanding the existing Dewatering and Drying Building to accommodate a second solids paddle dryer. This alternative provides backup capacity to allow the City to continue delivering Class A solids during periods of downtime if a mechanical failure occurs or to accommodate regular maintenance of one dryer train. As mentioned previously, this Plan recommends the City complete a study of the secondary sludge quality, performance of that process, chemical addition types and locations, and solids handling process performance overall prior to making a final selection of the preferred dryer alternative from the alternatives detailed in Chapter 6. For purposes of capital planning, this Plan assumes the City will implement Alternative 2b (modification of Dewatering and Drying Building to accommodate a second paddle dryer) with a study and confirmation of this selection beginning in 2029.

Lastly, the City wants to establish a direct connection between the City's fiber optics network and the WWTP. This addition consists of routing two new conduits (one spare) and fiber optic cabling from the WWTP's Operations Building to the site entrance, where the conduits will be tied into the City's fiber optics network. Chapter 6 details one potential routing from the Operations Building to the site entrance that would minimize impact to existing yard utilities. The fiber optic cable addition is included in Chapter 7 and the City's 5-year CIP.

Table ES.9 below summarizes the alternatives evaluated in Chapter 6 including recommendations for future WWTP improvements.

Unit Process	Alternatives Considered	Selected Alternative
Secondary Treatment	<ul> <li>Expansion of the existing conventional activated sludge process.</li> <li>Intensification of the existing treatment process.</li> </ul>	• Expansion of the existing conventional activated sludge process through the addition of another aeration basin.
Tertiary Treatment	<ul> <li>Increase filtration capacity.</li> <li>Eliminate the requirement on the DBO firm to meet effluent limits more stringent than the NPDES permit.</li> </ul>	• Eliminate the requirement on the DBO firm to meet effluent limits more stringent than the NPDES permit.
Solids Dryer	<ul> <li>Continue operating the existing BCR paddle dryer and defer replacements.</li> <li>Modify the existing Dewatering and Drying Building to accommodate a different solids dryer technology or a redundant dryer.</li> <li>Construct a new dryer building with a different solids dryer technology.</li> </ul>	• Modify the existing Dewatering and Drying Building to accommodate a different solids dryer technology or a redundant dryer by expanding the Dewatering and Drying Building to accommodate a second solids paddle dryer.

#### Table ES.9 Summary of Alternatives



#### ES.8 Recommended Alternative

Figure ES.4 presents a WWTP site plan identifying locations of recommended improvements resulting from condition and capacity assessments, including evaluation of alternatives, as described.

Summaries of opinions of probable costs and anticipated phasing for the improvements recommended for inclusion in the City's WWTP CIP are provided in Table ES.10.

The expected cash flow for the planning period was determined for the recommended improvements summarized in Table ES.10. The cash flow through 2045 includes an escalation rate of three percent, and the peak expenditure is approximately \$13,906,000 in fiscal year 2031. The projected CIP expenditures are presented in Figure ES.5.

Table ES.10	WWTP Recommended	<b>Alternative Opinion</b>	of Probable Cost and Phasing

Plant Area	Project <sup>(1)</sup>	Opinion of Probable Cost	Approximate Year Online
Solids Handling	Dewatering Performance Optimization	\$150,000	2023
Communications/IT	Fiber Optic Cable Addition	\$55,000	2023
UV System	Trojan 4000 UV System Improvement	\$1,650,000	2024
Support Buildings	Seismic Improvements	\$1,015,000	2024
Secondary Treatment	New Secondary Clarifier Mechanisms	\$1,665,000	2026
Solids Handling	Solids Dryer Improvement	\$16,100,000 <sup>(6)</sup>	2031
Solids Handling	Existing Centrifuge Replacement	\$2,200,000 <sup>(3,5)</sup>	2033 <sup>(4)</sup>
Secondary Treatment	New Aeration Blower	\$394,000	2035
Secondary Treatment	New Conventional Aeration Basin	\$7,895,000	2038
	TOTAL	\$31,124,000	


Notes:

White rows indicate projects that are in the City's 5-year CIP and blue rows indicate projects that are outside the 5-year CIP window.

(1) Details of each project can be found in Chapter 2 or Chapter 6 of this Master Plan.

- (2) The estimated opinion of probable costs include the construction costs plus Engineering, legal and administration fees (ELA, or soft costs). Details on the estimated project costs can be found in Chapter 2 or Chapter 6 of the plan, with the exception of costs for the backup UV system and centrifuges which are presented earlier in Chapter 7.
- (3) For budgeting purposes, the Option B centrifuge cost from Table 7.4 is used for the project cost summary and the CIP
   (4) Replacement timing dependent upon satisfactory equipment performance
- (5) The centrifuges installed with the City's 2014 upgrade project have exhibited inconsistent performance in recent months. The City recently refurbished these units and expects they will provide sufficient capacity through 2045. However, by that time, the units will have been in service for over 30 years. It is recommended the City plan for replacement of these units during the planning horizon of this Master Plan. Assuming replacement occurs in the mid-2030's the City should reassess capacity needs of those units beyond the 2045 horizon, consistent with the expected service life of the new equipment.
- (6) The existing solids dryer has sufficient capacity through 2045. As with the dewatering centrifuges, the dryer equipment will soon have been in operation for a decade. It is recommended the City plan for replacement of the dryer during the planning horizon of this Master Plan. The City plans to replace the existing dryer with a new piece of equipment using similar technology and potentially rehabilitate the existing unit to serve as a backup. See Alternative 2B, Chapter 6.





30' 60'

SCALE: 1" = 60'

120





#### LEGEND:

- CONDITION OR ADDITION PROJECTS
- 1 DEWATERING & DRYING BUILDING
- 1A EXISTING CENTRIFUGE REPLACEMENT
- 1B SOLIDS DRYER IMPROVEMENT
- 5 SECONDARY CLARIFIER NO. 1 REPLACE MECHANISMS
- 6 SECONDARY CLARIFIER NO. 2 REPLACE MECHANISMS
- 7 STANDBY UV SYSTEM REPLACEMENT
- 18 FIBER OPTIC CABLE ADDITION
- CAPACITY PROJECTS
- 2 NEW AERATION BLOWER
- 3 NEW AERATION BASIN NO. 3, ACCESS IMPROVEMENTS & GRADING
- SEISMIC RETROFIT PROJECTS
- 4 PROCESS GALLERY
- 8 WORKSHOP
- 17 OPERATIONS BUILDING
- OTHER FACILITIES
- 9 SECONDARY PROCESS FACILITY
- 10 STABILIZATION BASIN 11 - SLUDGE STORAGE BASINS AND BIOFILTERS
- 12 SECONDARY CLARIFIER NO. 3

- 13 HEADWORKS
- 14 DISK FILTERS
- 15 COOLING TOWERS
- 16 W3 REUSE PUMP STATION
- 19 SITE ENTRANCE

Figure ES.4 PROPOSED WILSONVILLE WWTP IMPROVEMENTS CITY OF WILSONVILLE










Figure ES.5 Projected 20-Year CIP Expenditures



ES-28 | JUNE 2022 | DRAFT



City of Wilsonville Wastewater Treatment Plant Master Plan

Planning Commission





# **Master Plan Drivers**


- City Capital Planning
- Accommodating Expected Growth
- Addressing Asset Condition and Replacement needs
- Assessing Potential Regulatory Drivers



## **Capital Planning and Expected Growth - 2045**

- Current Service Area needs 20+ years through 2045
  - Population and associated economic development

2015	2020	2030	2045
22,870	25,945	29,756	30,566



# **Facility Capacity Assessment**



- Flows & Loads Drive core process needs
- Existing WWTP design (2014 expansion) ADWF 4 mgd

Item	Existing	Projected 2045
Average Dry Weather Flow, mgd	1.94	2.68 (~38% > existing)
Average Annual Flow, mgd	2.24	3.03 (~35% > existing)
Maximum Month Wet Weather Flow, mgd	3.78	4.90 (~30% > existing)
Average Annual BOD <sup>,</sup> , ppd	7,470	10,613 (~40% > existing)
Average Annual TSS, ppd	6,427	8,714 (~35% > existing)

# **Asset Condition Assessment**



- Process Condition/Age Drivers
  - 2014 project facilities and equipment in service > 30 years by 2045
  - Solids facilities
    - Performance issues
      - Solids Dryer fire (2019), component failures (2021), uneven performance
      - Solids Dewatering Centrifuges uneven performance (2020/21)
  - Secondary clarifiers Pre-date 2014 upgrades, near term mechanism replacements, clarifiers no. 1 and 2
  - UV Disinfection backup unit pre-dates 2014 upgrades, near term replacement

# **Potential Regulatory Drivers**

- DEQ Total Maximum Daily Load (TMDL) Lower Willamette River
- Dissolved oxygen & nutrients
  - Nutrients can contribute to low oxygen conditions
  - Anticipate and accommodate future phosphorous, possibly nitrogen limits
- Pay attention to Willamette River temperature concerns



# **Condition and Capacity Assessments**

# **Condition Assessment**

- Prioritize 2019 findings of consultant assessments
  - Secondary clarifiers
  - UV system
- Geotechnical and seismic evaluations
  - Older buildings found to present moderate risk
  - Identified mitigations to address seismic concerns
    - Operations Building
    - Process Gallery
    - Workshop



# **Unit Process Capacity Summary**

Unit Process	Design Parameter	Redundancy Criteria	Possible Year of Capacity Exceedance	Identified Alternatives
Secondary Treatment	MW MLSS inventory @ PDF	All units in service	2038	<ul> <li>New Aeration Basin</li> <li>New Secondary Clarifier</li> </ul>
Aeration Blowers	Peak BOD Load	Largest unit out of service	2035	Additional Blower
Disk Filters	MWDWF	One unit in backwash	2037	<ul><li>Third Disc Filter</li><li>Relax DBO limits</li></ul>
Biosolids Dryer	MW Load	All units in service	>2045	<ul> <li>Emergency Biosolids Management Plan</li> </ul>
				<ul> <li>Redundant Dryer, similar technology</li> </ul>
				Different Dryer     technology

# **ALTERNATIVES EVALUATION**


# **Alternatives Evaluation**



- Consider alternatives for process units identified
   as capacity deficient
- Secondary Process
  - Add new Aeration Basin
  - Add new blower
- Tertiary Disk Filters
  - Relax DBO effluent TSS limits
- Solids Dryer driven by performance, not necessarily capacity
- Process Gallery
  - Further study, placeholder to expand dewatering and drying building, add new paddle dryer, refurbish existing dryer (backup)


# **Alternatives Evaluation**

- Solids Dryer driven by performance, not capacity
  - Further study, placeholder to expand dewatering and drying building, add new paddle dryer, refurbish existing dryer (backup)
  - Largest potential investment in Master Plan



# **Recommended Plan**

# **Recommended Plan**



3 New Aeration Basin

- 2 Additional Aeration Blower
- Replace backup UV system
- Plan to replace Solids
   Dryer & Centrifuges
- 6 Replace Clarifier 1 & 2 mechanisms
- 4 8 Seismic retrofits of buildings
  - 10 New fiber optic connection


Solids process study

# **Proposed Project Phasing Schedule**



# **Draft Cash Flow**





# **Next Steps**

- DEQ review and approval of Plan
- City Council Work Session 8/1
- Planning Commission Public Hearing 9/14
- City Council Public Hearing 1<sup>st</sup> Reading 10/3
- City Council 2<sup>nd</sup> Reading 10/17





Draft PC Minutes were reviewed and approved as corrected at the September 14, 2022 PC Meeting. Corrections are bold and underlined. Commissioner Gallagher moved to approve the July 13, 2022 minutes as corrected. Commissioner Karr seconded the motion, which passed unanimously.

## PLANNING COMMISSION MEETING MINUTES July 13, 2022 at 6:00 PM City Hall Council Chambers & Remote Video Conferencing

## CALL TO ORDER - ROLL CALL

A regular meeting of the Wilsonville Planning Commission was held at City Hall beginning at 6:00 p.m. on Wednesday, July 13, 2022. Chair Heberlein called the meeting to order at 6:01 p.m., followed by roll call. Those present:

Planning Commission:	Ron Heberlein, Jennifer Willard, Aaron Woods, Andrew Karr, and Kamran Mes	
	Olive Gallagher arrived after roll call. Breanne Tusinski was absent.	

City Staff: Daniel Pauly, Ryan Adams, Mike Nacrelli, and Mandi Simmons.

## PLEDGE OF ALLEGIANCE

The Pledge of Allegiance was recited.

## **CITIZEN'S INPUT**

This is an opportunity for visitors to address the Planning Commission on items not on the agenda. There was none.

## **ADMINISTRATIVE MATTERS**

1. Consideration of the June 8, 2022 Planning Commission Minutes

The June 8, 2022 Planning Commission Minutes were accepted as presented.

## WORK SESSION

2. Wastewater Treatment Plant Master Plan (Nacrelli)

Mike Nacrelli, Senior Civil Engineer, noted the Wastewater Treatment Plant Master Plan was the first since the last major upgrade to the Master Plan in 2012 and would look at the plant capacity, condition of the equipment, the regulatory landscape, and any issues that needed to be incorporated into a capital plan.

Dave Price, Project Manager & Vice President, Carollo Engineers, briefly highlighted his professional background. He presented the Wastewater Treatment Plant (WWTP) Master Plan via PowerPoint, noting Carollo based its planning around the City's Comprehensive Plan and the growth expected in the community through 2045 to ensure the treatment plant had capacity to treat in compliance with the NPDS permit to discharge to the Willamette River. Also reviewed were potential regulatory drivers, the WWTP condition and process capacity assessments, alternatives evaluation for addressing capacity deficiencies, as well as the recommended plan for new projects and infrastructure to provide additional capacity, the proposed phasing schedule, projected yearly cashflow, and next steps, which included the Master Plan's adoption anticipated in mid-October.

Discussion and feedback from the Planning Commission was as follows with responses to Commissioner questions as noted:

- Had the upcoming projects in 2023 and 2024 been estimated in the City's budget to provide the needed funding? (Slides 15 and 16)
  - Mr. Nacrelli replied the larger dollar amount projects, the UV System Improvement and Secondary Clarifier Mechanisms, were both in the Five-Year Plan of the recently adopted budget. The Seismic Improvements project could be accommodated in the City's Wastewater Capital Budget, and Staff would look into adding it to the Five-Year Plan in the next budget cycle. The Fiber Optic Cable Addition, at less than \$60,000, was a relatively small project. The Dewatering Performance Optimization project did <u>not</u> yet have a dollar amount and Staff would work with Jacobs Engineering Group Inc., the City's contract operator, to get that figure. The City might provide some funding through that operations contract, but the project would not have a major impact on the City's cash flow.
    - He confirmed a good amount of the near term proposed projects were in the Five-Year Plan, though a few things still needed to be addressed.
- What was the financing plan for 2031? Would funds come from CIP and is there adequate annual Capital Improvement Project (CIP) funding for the 2031 projects? (Slide 16)
  - Mr. Nacrelli noted the 2031 Solids Dryer Improvements project was the next big project. As
    mentioned in the Staff report, the current fiscal year budget identified a wastewater rate study and
    SDC analysis would be done in. The final Master Plan document would be used to see what the
    numbers and schedule meant for the monthly rates and the system development charges (SDCs) and
    how they might need to be adjusted. After the public hearings, over the next year, figuring out the
    finance plan would be the next step in implementation.
- Mr. Price clarified that grouting any soil voids around the existing piping was not part of the Seismic Improvements project but recommended in the geotechnical report and Northwest Geotech's study.
   When Northwest Geotech did its site work, no active erosion or piping was occurring; however, the City would need to pay attention to those requirements when doing the new improvements for the aeration basin, or if something was identified that appeared could be an issue, such as a hole showing up suddenly after some rain events. He did not know of anything to be worried about regarding the soils currently.
- Were there many complaints over odor and should the City do any projects to address odor?
  - Mr. Nacrelli responded he had not heard much about odor complaints from the operators at the site or from Delora Kerber, Public Works Director, who manages the contract.
  - Mr. Price added odor-control facilities were tied to the dryer and the solids building. He was not a solids processing expert, but there were risks when the process was interrupted and solids were not making it through the dewatering process to the dryer on a continual basis, which would occur because something broke or something else interrupted the normal flow. Under normal operations, the assumption was that the existing units were functioning as they were intended to control odor.
  - Mr. Nacrelli added he had not noticed any odor during his many times visiting the site.
- Mr. Nacrelli clarified the process for solids did not include a digester with gas harvesting, noting the digesters were eliminated with the last upgrade.
  - Mr. Price added there was no digestion, dewatered raw solids went from the centrifuge units right into the dryer unit, and that process was intended to function on a continual basis.
- Regarding plans for generating gas in the future, which was typical when dealing with solids, Mr. Nacrelli noted producing heat and electricity from harvested methane had been a big part of his previous job at

the City of Gresham, but it would be prohibitive for the City of Wilsonville to try and go back to using anaerobic digestion after eliminating the digesters.

- Mr. Price clarified that the percentage increases on Slide 4 were 2045 projections for an increase in the potential need for capacity based upon Staff's analysis using Metro numbers.
  - On how the percentage projections compared to the population increase percentage, Mr. Price replied the projected population of 30,000 in 2045 (Slide 3) was less than those represented in the table. (Slide 4) Often, conservative numbers were used when evaluating specific elements, like the loads or flows, for future growth and what would be produced. To ensure, Carollo was being conservative for planning purposes, the best-case scenario was not used. Every home built would not necessarily have the number of residents assumed by the Comprehensive Plan.
- The project assumed the same per capita load and flow generation seen today for 2045. The population increase would be around 18 percent, but the analysis showed increases of more than twice that in all categories. What infiltration inflow analysis information was available?
  - Mr. Price replied evaluations for treatment facilities looked at the actual flows received at the plant. Depending on the circumstance, the client's desires, and the needs of the community, the analysis might look at the collection system model to see the maximum amount of flow it could deliver. Typically, the flow numbers were generated based upon an evaluation using rolling averages, often a maximum month flow based upon a rolling 30-day average was used; not what the average was in one month compared to some time period, often it was the previous five years. The analysis did not necessarily utilize the same kinds of assumptions used in a collection system plan in part because with a treatment plant, no matter how tight the site was, the assumption was that more capacity could be built, expanded, or intensified. However, once pipe was put in the ground, it was difficult to make it any larger so often the collection system plan made very conservative assumptions, especially for peak flows it needed to convey to the plant to prevent wastewater protrusion from manholes.
- Did the City have a handle on clear water intrusion in the system?
  - Mr. Nacrelli replied the Wastewater Collection System Master Plan would have definitely looked at water intrusion and the Master Plan had a CIP to replace a lot of older pipes. He had been involved in several projects in Charbonneau, an older area where the age of the infrastructure had been a particular issue. The City was definitely addressing intrusion and the best way to do it was to either line or replace old pipes.
  - Commissioner Mesbah responded he had hoped to hear the City had a handle on any potential large inflow areas; not old pipes, but broken lines, especially in low areas with shallow ground water and he assumed some gravity lines were located where such water intrusion could occur, letting in water that was not efficient to treat. Was a conservation plan to reduce the loads in the future part of the WWTP Master Plan, assuming people would **not** be as wasteful as they were today?
    - Mr. Nacrelli noted the increases in BOD and TSS were a bit higher than the flows, which probably reflected that the influent was often trending stronger because less clean water, or rainwater, was coming into the system. The City was treating the same amount of solids, but the hydraulic impact was not as severe as it would have been in past years. (Slide 4) He agreed more efficient pipe materials, fixtures, and plumbing contributed to less water being treated.
      - A program to encourage more conservation would be more to do with the water distribution and plumbing side of things and was not part of this project's scope. However, the City was interested in conservation and pursuing it.
    - Mr. Price added one thing that came up with many of the planning studies he had done over the last 18 to 20 years was the idea that flows were very important, and they are however, as Mr.

Nacrelli had indicated, wastewater management tried to control the flow as well as ensure a process that could handle and treat the organic loads coming in, all of which included contaminants. In his experience, water conservation efforts did not always benefit wastewater treatment plants. For example, efforts in northern California, where constituents were regulated to a much lower level than DEQ, had resulted in the unintended consequence of water coming into the plants with a much higher concentration of pollutants. Water conservation was important, but it needed to be looked at carefully and watched at the wastewater plant, which was why the loads were looked at closely in the analysis which was often more important in some ways.

- Mr. Nacrelli noted the flows and loads increase was greater than the population increase and asked if that was because non-residential sources were also included.
  - Mr. Price confirmed the numbers did reflect non-residential sources, which included the prison and other industrial/commercial users within the service area, which were not reflected in the population numbers. Following Commissioner Mesbah's comments, he did want to take a hard look at the flows and loads analysis along with evolving land uses to make sure everything was in line.
- Industrial uses, like a brewery with higher loads to the treatment plant might exist in the city that the Commission was unaware of. Was the growth projection lowballed or would the City experience higher growth?
  - Mr. Nacrelli replied Metro's numbers were definitely on the low end, which was why they looked more closely at the medium projections indicated by the green line. (Slide 3, Green line)
- Historically, Metro numbers had been low, but the other aspect was that the City did have some say in how fast it grew. Some of the costs shown in the Draft Cash Flow chart were the costs of growth. (Slide 16) Perhaps those things should be thought about in addition to the expansion of load systems, etc. There were costs associated with choosing to grow which the City needed to be strategic about. The plan was conservative and seemed to have room to cover more than Metro's projections. Layering conservatism in the planning process should be avoided. Conservatism in facilities planning sometimes resulted in overbuilding unnecessarily that went unused long term.
  - Mr. Price replied that was a concern of his as well. Process engineers were conservative because no
    one wanted to under plan. The community should pay close attention to who was responsible for
    paying for which element of the need. Unfortunately, some elements might not be driven by capacity,
    but performance. There was an element of capacity embedded even in that large dryer unit that
    somebody would benefit from other than the existing users.
  - Mr. Nacrelli added because the City did not appear to have a capacity issue in the near-term, it could track what growth actually looks like over the next five years and then adjust accordingly, as the Master Plan would be adaptive. The City had not updated the Plan in 10 years, but he expected the City would not go longer than five years before assessing growth and making adjustments to the Master Plan as necessary.
- It would be helpful for the report to include a full built-out analysis. As the City built out areas it was
  adding, would it have adequate capacity, or would capacity go unused by the time the equipment needed
  to be replaced because it was not useful anymore; without having really used it? That would be a waste
  of taxpayer or ratepayer money. A full build-out analysis with timelines would provide some idea of
  whether the growth of the facility was being tracked in lockstep with the expected built-out of the areas
  added to the urban area.
  - Mr. Price noted the flows and loads had been projected out to the projection curves. Early in the analysis of the plant, Carollo Engineering, in conjunction with City Staff, decided not to necessarily

plan around the built-out numbers for the reasons pointed out. Including the build-out numbers would result in a more intense treatment plant site at the facility to account for the population nearly doubling, as shown by the projection on the higher rate curve. (Slide 3)

- Mr. Nacrelli clarified build-out was unrelated to the rate of growth. The current city boundaries and reserve areas would max out and fill up at some point according to how the areas were zoned. There was a number associated with build-out, though not it was not necessarily tied to a time frame but to land use.
- Build-out could be tied to a time frame because the Planning Department had some idea of how fast the neighborhoods would develop. For example, 1680 units were planned for Town Center, 1750 units were planned in Frog Pond East and South. At 2.5 people per unit, 8500 residents would be living in developments the City knew were likely to be built between 2022 and 2035. Coffee Creek and Basalt Creek would likely be built out within a 20-year time period. While those were industrial uses, the City knew it would happen during the subject growth period.
- The expected growth chart should reflect the planning the City knew was already in progress. The city's population would increase from 27,000 to 37,000 just with the known development in Frog Pond East and South and Town Center, and that did not include Frog Pond West. The standard curve should include known development and another curve should address potential additional growth.
  - Additionally, the City should be explicit in its conservatism. Right now, the plan showed a 12 percent population growth from 2021 to 2045, but a 30 percent increase in load. The discrepancy between those two numbers should be explicit, especially as it the Master Plan progressed toward Council. The plan needed to be explicit in why the load increase was twice as much as the population growth, which was a big deal.
  - Mr. Nacrelli clarified Jacobs Engineering had taken over CH2MHill, the company that had the design/build/operate contract for the treatment plant, so Jacobs was now the City's contract operator for the treatment plant.
- As different population projections were done, Staff and the consultants were asked to use the same time frame for gathering historical data and for the future projection. For example, show 30 years' worth of previous data and then project 30 years into the future. A projection using 5 years of data to project 25 years in the future was not statistically defensible. The prior five years of growth could have been a growth spurt that was being extended 30 years into the future, which was not accurate. Growth, especially in a small city like Wilsonville, was choppy, so it should be averaged out to determine the long-term trends.
  - 3. Frog Pond East and South Master Plan (Pauly)

Dan Pauly, Planning Manager, noted this was the Commission's sixth work session on the Frog Pond East and South Master Plan. He presented the Master Plan, including updates in response to the Commission's feedback via PowerPoint, reviewing the housing related design concepts and describing the similarities and differences between the three housing design types, displaying examples of each type using photographs from Villebois and Frog Pond West. He noted three housing design types were not set in stone, but the presentation addressed questions from Council and would be helpful for the Commission. Understanding the three housing types would be important in developing policy.

Joe Dills, MIG APG continued the PowerPoint presentation, summarizing the feedback and preferences discussed by the Planning Commission last month, noting the aspiration to create and connect special destinations within the neighborhoods was still part of the physical planning. (Slide 29) He described the

The Boones Ferry Messenger

Monthly newsletter of the City of Wilsonville

September 2022

## Open House Scheduled for Public Review of Waste Water Treatment Master Plan

The City of Wilsonville is conducting a virtual public open house to present the draft Wastewater Treatment Plant Master Plan, and to respond to questions and comments from community stakeholders.

The improvements detailed in this draft Plan are designed to provide optimal value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting

Waste Water Treatment Plant Master Plan Open House *Wed, Sept. 28, 7 pm* Zoom Virtual Meeting economic development, consistent with goals and policies contained in the 2018 Com-

prehensive Plan and 2021-2023 City Council Goals.

The plan accounts for the age and condition of existing process equipment and structures as well as projected residential and commercial growth and potential regulatory changes.

To learn more about this project, review the draft Plan or attend the open house, visit letstalkwilsonville.com/wastewater-treatment-plant-master-plan or contact Mike Nacrelli, Senior Civil Engineer, at mnacrelli@ci.wilsonville.or.us.

## Pamplin Media Group

## -Ad Proof-

This is the proof of your ad, scheduled to run on the dates indicated below. Please proofread carefully, and if changes are needed, please contact Sarah Penn prior to deadline at or spenn@pamplinmedia.com.

<b>Date:</b> 09/20/22	0		258403 09/28/22
Account #: 108863	-		
		Stop:	09/29/22
Reference #: LP22-00	01 Wastewater Treatment		
Plant Master Plan		Total Cost:	\$206.38
Company Name: WILSON	IVILLE, CITY OF	Ad Size:	12.069
Contact:		Column Width:	1
Address: 29799 S WILSON	W TOWN CENTER LOOP E	Column Height:	12.069
		Ad Class:	1202
<b>Telephone:</b> (503) 57	70-1510	Phone #	
<i>Fax:</i> (503) 68	2-1015	Email:	spenn@pamplinmedia.com

## Run Dates:

Wilsonville Spokesman 09/29/22

#### NOTICE OF LEGISLATIVE PUBLIC HEARING BEFORE THE CITY OF WILSONVILLE PLANNING COMMISSION AND CITY COUNCIL:

### WASTEWATER TREATMENT PLANT (WWTP) MASTER PLAN LP22-0001

OREGON STATE LAW ORS 227.186. The City has not determined how or if this particular proposal will reduce or otherwise impact either the value or use of properties within Wilsonville. Any changes to permitted land uses may reduce or increase property values, depending on various factors. A written notice has been mailed to potentially impacted property owners as required.

PLANNING COMMISSION: On Wednesday, Oct. 12, 2022, beginning at 6 pm, the Planning Commission will hold a public hearing on the Wastewater Treatment Plant Master Plan, and will consider whether to recommend to City Council adoption of the Plan.

You will not receive another mailed notice unless you: submit a request in writing or by phone, or submit testimony or sign-in at the hearing

CITY COUNCIL: On Monday, Nov. 21, 2022 beginning at 7 pm, the City Council will hold a public hearing regarding the Wastewater Treatment Plant Master Plan after which it may make the final decision.

The hearings will take place at Wilsonville City Hall, 29799 SW Town Center Loop East. A complete copy of the project record, including staff report, findings, and recommendations, will be available online and at City Hall for viewing 7 days prior to each public hearing.

### SUMMARY OF PROPOSAL:

The City of Wilsonville is updating its Wastewater Treatment Plant Master Plan. The improvements detailed in this Plan are designed to provide optimal value to the City's ratepayers by maximizing the use of existing infrastructure and improving system operation while continuing to protect water quality and human health and supporting economic development.

The City's Wastewater Treatment Plant, along I-5 between the river and Old Town, was originally built in 1971. A major 2014 upgrade expanded the capacity to accommodate population growth.

This Plan, which satisfies requirements established by the State of Oregon Department of Environmental Quality (DEQ), considers:

- · The age and condition of existing process equipment and structures
- · Growth to accommodate population growth and new economic development over the planning period (through 2045). Projections are based on projections, historical data and DEQ wet weather project methodologies.
- · Potential changes to water quality regulations established by the DEO
- · City of Wilsonville Wastewater Collection System Master Plan (2014), and
- Consistency with the 2018 Comprehensive Plan and City Council 2021-2023 Goals 5, 6 and 7

For more details, visit https://www.letstalkwilsonville.com/ wastewater-treatment-plant-master-plan

### HOW TO COMMENT:

Oral or written testimony may be presented at the public hear-ings. Written comment on the proposal is welcome prior to the public hearings. To have your written comments or testimony distributed to the Planning Commission before the meeting, it must be received by 2 pm on Oct. 4, 2022. Direct written com-ments to Mandi Simmons, Administrative Assistant 29799 SW Town Center Loop East, Wilsonville, Oregon, 97070 | msim-mons@ci.wilsonville.or.us | (503) 682-4960

Note: Assistive Listening Devices (ALD) are available for persons with impaired hearing and can be scheduled for this meeting. The City will also endeavor to provide qualified sign language interpreters and/or bilingual interpreters, without cost, if requested at least 48 hours prior to the meeting. To obtain such services, please call Mandi Simmons, Adminis-trative Assistant at (503) 682-4960. Publish September 29, 2022 WS258403

## Pamplin Media Group

## -Ad Proof-

This is the proof of your ad, scheduled to run on the dates indicated below. Please proofread carefully, and if changes are needed, please contact Sarah Penn prior to deadline at or spenn@pamplinmedia.com.

<b>Date:</b> 10/05/2	22		260775 10/12/22
Account #: 108863	3	Stop:	10/13/22
	0001 Wastewater Treatment		
Plant Master Plan		Total Cost:	\$33.02
Company Name: WILSC	ONVILLE, CITY OF	Ad Size:	1.931
Contact:		Column Width:	1
	SW TOWN CENTER LOOP E	Column Height:	1.931
		Ad Class:	1202
<b>Telephone:</b> (503) 5	570-1510	Phone #	
<b>Fax:</b> (503) 6	582-1015	Email:	spenn@pamplinmedia.com

## Run Dates:

Wilsonville Spokesman 10/13/22

## NOTICE OF CANCELLATION OF THE LEGISLATIVE PUBLIC HEARING BEFORE THE CITY OF WILSONVILLE PLANNING COMMISSION AND CITY COUNCIL:

The public hearing before the Planning Commission for the **Wastewater Treatment Plant Master Plan (LP22-0001)** scheduled for Wednesday, Oct. 12, 2022 at 6pm has been cancelled. We are sorry for the short notification.

The public hearing before the City Council for the Wastewater Treatment Plant Master Plan scheduled for Monday, Nov. 21, 2022 at 7pm has also been cancelled. Publish October 12, 2022 WS258403

## Simmons, Mandi

From:	Thomas Hooker <thomas.hooker@gmail.com></thomas.hooker@gmail.com>
Sent:	Sunday, October 2, 2022 4:57 PM
To:	Simmons, Mandi
Subject:	Wastewater Treatment Plant Master Plan Comment / Request
Follow Up Flag:	Follow up
Flag Status:	Completed

[This email originated outside of the City of Wilsonville]

Mandi,

Thanks you for allowing me to comment on the proposed WWTP. I am a resident of Wilsonville, having live here for 30+ years. I am generally in agreement with the plan and its goals. Owning and RV and watching our community grow over the years, I have often thought a city of our size should have a waste dump for residents with RV's. Our process now is go to Tigard or other areas to dump our RV's, adding addition travel time in high traffic areas. I would like to request that an RV Dump be added to the WWTP Master Plan to support our residents with RV's.

Using Tigard as an example, it could be a highly functional perk for our residents as well as generating money to support the cost through Automated Dump Fees (TYP. \$5.00 per Dump or \$250.00 annual fee).

Tigard Link:

https://cleanwaterservices.org/community-home/resources/dispose/rv-waste/

Thank you for your time.

Thomas Hooker Park at Merryfield Roland Ct. thomas.hooker@gmail.com