Harvest Rain MAIL:1450 Hwy 290 W. Unit #91 Dripping Springs, TX 78620 US 512.645.2955 accounting@harvestrain.com



## ADDRESS

City of Woodcreek 41 Champions Circle Woodcreek, TX 78676



## ESTIMATE # 4287 DATE 07/03/2024 EXPIRATION DATE 08/03/2024

PRODUCT	DESCRIPTION	QTY	RATE	AMOUNT	
Gutters with screens	6" Seamless, Aluminum Ogee gutters Color: (TBD); Step-lock guter screens on gazebo.	1	720.00	720.00	
Rainwater Components	Painted PVC downspout (1) (Color TBD); Collection pipe; Pressure pipe with stub out for irrigation connections (by others); Fittings; Tank connections; First flush; Overflow systems. (1) hose bib on a T at the pump location on the post of the northeast corner of the gazebo.	1	1,555.00	1,555.00	
Pump Components (Irrigation)	Grundfos Scala 2 (3/4 HP) variable speed on demand centrifugal pump. (115V/20amp); Weather protected poly pump enclosure Color: (TBD). * Assumes access to dedicated electrical circuit (115v20amp) within 5' of proposed pump location. *	1	1,725.00	1,725.00	
Trenching and Labor	Includes labor to complete install, hand trenching to protect existing landscape, backfill, and flagging trenches.	1	2,000.00	2,000.00	
Texas Metal Tank- // 1000 Gallons // Galvanized	Dimensions: (5'D x 7'H), 20-Gauge G-90 galvanized steel, FDA approved epoxy liner, Warranty: 1yr. Includes base prep and tank pad installation per manufacturer standards. * Assumes no greater than 6" change in elevation at proposed tank location. *	1	3,995.00	3,995.00	
Exclusions	<ul> <li>The following are NOT included in our scope of work:</li> <li>Providing dedicated 115v/20amp electrical circuit for pump power supply.</li> <li>Permits, RPZ Backflow Prevention Device and Installation, Inspections. (If required.)</li> <li>Final connections to irrigation system(s).</li> <li>Water Delivery.</li> <li>Spoils Removal.</li> </ul>	1	0.00	0.00	
	** See Alternate Tank Options On Next Page. **				

PRODUCT	DESCRIPTION		QTY	RATE	AMOUNT
	** See Alternate Tank Options	Below: **			
Texas Metal Tank- // 830 Gallons // Galvanized	Dimensions: (5'D x 5'8"H), 20-Gauge G-90 galvanized steel, FDA approved epoxy liner, Warranty: 1yr. Includes base prep and tank pad installation per manufacturer standards. * Assumes no greater than 6" change in elevation at proposed tank location. *		0	2,995.00	0.00
Texas Metal Tank- // 1200 Gallons // Galvanized	Dimensions: (6'D x 5'8"H), 20- galvanized steel, FDA approve Warranty: 1yr. Includes base p installation per manufacturer s * Assumes no greater than 6" o proposed tank location. *	0	3,995.00	0.00	
** OPTION 3: GAZEBO ** * Assumes tank is installed within 2 * Proposed collection from approx. 120 gallons, approx. 4,000 gallons/	200sf, potential collection on 1" of rain =	SUBTOTAL TAX TOTAL		\$9,	9,995.00 0.00 <b>,995.00</b>

Accepted By

Accepted Date