



ProLine Striping Inc.

1115 Iowa Ave.
Muscatine, IA 52761 US
563-260-7711
prolinestriping@gmail.com
prolineiowa.com

Estimate

ADDRESS
Street Striping 2022

ESTIMATE 1615
DATE 12/20/2021

DESCRIPTION	QTY	RATE	AMOUNT
-------------	-----	------	--------

ReStripe Roadway per Plan Including:	194,426	0.105	20,414.73
--------------------------------------	---------	-------	-----------

Waterborne Latex Paint UC-3587
 (194,426 LF) 4" WHITE Edge Line, Lane Line, 4" YELLOW Centerline, No Passing, Edge Line and Island Hashing.
 This is with some changes:
 NO striping on West Burlington Ave,
 NO striping on Mt Pleasant from Gear to overpass,
 NO striping on Broadway north of Agency only south of Agency and then west on Division to S Gear,
 NO striping on Huston.

Waterblasted Prep for above- NONE Requested per bid docs.
 (0 LF) Short Term Pavement Marking -- \$
 (0 LF) Reflectorized Tape
 (0) Arrows/Legends
 (0) Arrows removed
 (0 LF) Paint Removal/Scarifier -- \$
 (1) Mobilizations included.

NOTE: This is a total package bid, not line item. To be completed by end of Summer 2022. This includes no traffic coning per competitive bid from other contractors. The paint is fast dry 5 min dry time.

Included: Paint is Latex IA State DOT, Reflectorized with Iowa Contractor Beads.

This bid is based on current product availability and supply chain.

SUBTOTAL	20,414.73
TAX	
TOTAL	\$20,414.73

Accepted By

Accepted Date