

Wylie WWTP Demolition OPCC Options

	DEMO OPTIONS		OPCC			
1	Demolition of Aeration Basin	\$	543,144			
2	Demo All Structures (2' below ground)	\$	864,979			
2A	Additional Cost for Full Removal	\$	329,918			
3	Demo All Structures (2' below ground) and WW Interceptor	\$	1,208,952			
4	Demo All Structures (2' below ground) and WW Interceptor/Decel Lane	\$	1,355,363			
5	Demo All Structures (2' below ground) and WW Interceptor/Access Drive	\$	1,392,487			
Demolit	emolition of Wylie WWTP					

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

- 1 FNI OPCC classified as an AACE Class 4 Estimate with accuracy range or -20 to + 30.
- 2 FNI OPCC does not include costs associated with engineering fees, permits, surveying, etc.



nnovative approaches Practical results Outstanding service

OPINION OF PROBABLE CONSTRUCTION COST

PROJECT NAME	Wylie WWTP Demolition	DATE	9/8/2021
CLIENT	NTMWD	GROUP	1153
% SUBMITTAL	Conceptual	PM	Clayton Barnard

ESTIMATED BY	QC CHECKED BY	FNI PROJECT NUMBER
		WLE20563

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE		TOTAL
Demoli	tion of Wylie WWTP - Option 1 Demo Containment Structures				1	
	Demolition of Aeration Basin					
1	Remove Existing Mechanical Equipment	1	LS	\$ 15,000.00	\$	15,000
2	Demo Concrete Structural Walls to 2' Below Grade	6531	SF	\$ 4.00	\$	26,124
3	Fill Structure with Fill	6485	CY	\$ 25.00	\$	162,125
	Demolition of Waste Sludge Holding Basin					
4	Remove Existing Mechanical Equipment	1	LS	\$ 5,000.00	\$	5,000
5	Demo Concrete Structural Walls to 2' Below Grade	571	SF	\$ 7.50	\$	4,283
6	Fill Structure with Fill	1075	CY	\$ 25.00	\$	26,875
	Demolition of Secondary Clarifier					
7	Remove Existing Mechanical Equipment	1	LS	\$ 10,000.00	\$	10,000
8	Demo Concrete Structural Walls to 2' Below Grade	1885	SF	\$ 7.50	\$	14,138
9	Fill Structure with Fill	3686	CY	\$ 25.00	\$	92,150
	Demolition of Chlorine Contact Chamber/Headworks					
10	Remove Existing Mechanical Equipment	1	LS	\$ 7,500.00	\$	7,500
11	Demo Concrete Structural Walls to 2' Below Grade	800	SF	\$ 4.00	\$	3,200
12	Fill Structure with Fill	592	CY	\$ 25.00	\$	14,800
		SUBTOTAL			\$	381,194
		CONTINGENC	Υ	15%	\$	57,179
		SUBTOTAL			\$	438,373
		MOBILIZATIO	N	5%	\$	21,919
		SUBTOTAL			\$	460,292
		OH&P		18%	\$	82,853

PROJECT TOTAL (2021 COSTS)	\$ 543,144

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

- 1 FNI OPCC classified as an AACE Class 4 Estimate with accuracy range or -20 to + 30.
- 2 FNI OPCC does not include costs associated with engineering fees, permits, surveying, etc.



nnovative approaches Practical results Outstanding service

PROJECT NAME	Wylie WWTP Demolition	DATE	9/8/2021
CLIENT	NTMWD	GROUP	1153
% SUBMITTAL	Conceptual	PM Clayton Barn	

ESTIMATED BY	QC CHECKED BY	FNI PROJECT NUMBER
		WLE20563

ITEM	DESCRIPTION	QUANTITY	UNIT		JNIT PRICE		TOTAL
) 1i4	ing of White WINTD Option 2/21 Delays Copyrid						
emoii	cion of Wylie WWTP - Option 2 (2' Below Ground)			1			
	Demolition of Aeration Basin	1	1.6	<u>,</u>	45,000,00	<u> </u>	45.000
1	Remove Existing Mechanical Equipment Demo Concrete Structural Walls to 2' Below Grade	1	LS	\$	15,000.00	\$	15,000
2		6531	SF	\$	4.00	\$	26,124
3	Fill Structure with Fill	6485	CY	\$	25.00	\$	162,125
	Demolition of Waste Sludge Holding Basin						
4	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
5	Demo Concrete Structural Walls to 2' Below Grade	571	SF	\$	7.50	\$	4,283
6	Fill Structure with Fill	1075	CY	\$	25.00	\$	26,875
				Ė			
	Demolition of Secondary Clarifier						
7	Remove Existing Mechanical Equipment	1	LS	\$	10,000.00	\$	10,000
8	Demo Concrete Structural Walls to 2' Below Grade	1885	SF	\$	7.50	\$	14,138
9	Fill Structure with Fill	3686	CY	\$	25.00	\$	92,150
	Demolition of Chlorine Contact Chamber/Headworks						
10	Remove Existing Mechanical Equipment	1	LS	\$	7,500.00	\$	7,500
11	Demo Concrete Structural Walls to 2' Below Grade	800	SF	\$	4.00	\$	3,200
12	Fill Structure with Fill	592	CY	\$	25.00	\$	14,800
	Demolition of Sludge Drying Beds						
13	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
14	Demo Concrete Structural Walls to 2' Below Grade	11687	SF	\$	4.00	\$	46,748
15	Fill Structure with Fill	1200	CY	\$	25.00	\$	30,000
				T		т	
	Demolition of Sludge Pump Station						
16	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
17	Demo Concrete Structural Walls to 2' Below Grade	680	SF	\$	7.50	\$	5,100
18	Fill Structure with Fill	151	CY	\$	25.00	\$	3,775
	Demolition of Influent Pump Station						
19	Remove Existing Mechanical Equipment	1	LS	\$	10,000.00	\$	10,000
20	Demo Concrete Structural Walls to 2' Below Grade	84	SF	\$	7.50	\$	630
21	Fill Structure with Fill	64	CY	\$	25.00	\$	1,600
	Demolition of Blower Facility						
22	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
23	Demo Structure	480	SF	\$	7.50	\$	3,600
24	Demo Slab	480	SF	\$	7.50	\$	3,600
				Ħ			,

PROJECT NAME	Wylie WWTP Demolition	DATE	9/8/2021
CLIENT	NTMWD	GROUP	1153
% SUBMITTAL	Conceptual	PM	Clayton Barnard

ESTIMATED BY	QC CHECKED BY	FNI PROJECT NUMBER
		WLE20563

ITEM	DESCRIPTION	QUANTITY	UNIT	ı	UNIT PRICE	TOTAL
	Demolition of Chlorine Storage Facility					
25	Remove Existing Mechanical Equipment	1	LS	\$	1,500.00	\$ 1,500
26	Demo Structure	288	SF	\$	7.50	\$ 2,160
27	Demo Slab	288	SF	\$	7.50	\$ 2,160
	Bioxide Feed Chemical Containment					
28	Fiberglass Containment w/ Concrete Slab	400	SF	\$	25.00	\$ 10,000
29	Chemical Injection Assembly	1	LS	\$	65,000.00	\$ 65,000
30	Electrical Power Service	1	LS	\$	25,000.00	\$ 25,000
		SUBTOTAL				\$ 607,067
		CONTINGENC	Υ		15%	\$ 91,060
		SUBTOTAL				\$ 698,127
		MOBILIZATIO	N		5%	\$ 34,906
		SUBTOTAL				\$ 733,033
		OH&P			18%	\$ 131,946

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

864,979

NOTES:

PROJECT TOTAL (2021 COSTS)

- 1 FNI OPCC classified as an AACE Class 4 Estimate with accuracy range or -20 to + 30.
- 2 FNI OPCC does not include costs associated with engineering fees, permits, surveying, etc.



nnovative approaches Practical results Outstanding service

OPINION OF PROBABLE CONSTRUCTION COST

PROJECT NAME	Wylie WWTP Demolition	DATE	9/8/2021
CLIENT	NTMWD	GROUP	1153
% SUBMITTAL	Conceptual	PM	Clayton Barnard

ESTIMATED BY	QC CHECKED BY	FNI PROJECT NUMBER
		WLE20563

Demolition of Wylie WWTP - Option 2A Cost for Full Removal Demolition of Aeration Basin 1 Demo Remaining Concrete Structural Walls 3294 SF \$ 4. 4. 2 Fill Structure with Fill 366 CY \$ 25. Demolition of Waste Sludge Holding Basin 2 Demo Remaining Concrete Structural Walls 4587 SF \$ 7. 3 Fill Structure with Fill 510 CY \$ 25. Demolition of Secondary Clarifier 3 Demo Remaining Concrete Structural Walls 11207 SF \$ 7. 4 Fill Structure with Fill 1246 CY \$ 25. Demolition of Chlorine Contact Chamber/Headworks 4 Demo Remaining Concrete Structural Walls 4630 SF \$ 4. 5 Fill Structure with Fill 514 CY \$ 25. Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 0 SF \$ 4. 6 Fill Structure with Fill 0 CY \$ 25. Demolition of Sludge Pump Station 6 Demo Remaining Concrete Structural Walls 877 SF \$ 7. 7 Fill Structure with Fill 98 CY \$ 25. Demolition of Influent Pump Station 98 CY \$ 25. Demolition of Influent Pump Station 98 CY \$ 25. Demolition of Influent Pump Station 98 CY \$ 25. Demolition of Influent Pump Station 98 CY \$ 25. Demolition of Influent Pump Station Structure Pump Sta	0 \$ 0 \$ 0 \$	9,150 34,403 12,750
Demolition of Aeration Basin1Demo Remaining Concrete Structural Walls3294SF\$\$2Fill Structure with Fill366CY\$25.2Demo Remaining Concrete Structural Walls4587SF\$7.3Fill Structure with Fill510CY\$25.3Demo Remaining Concrete Structural Walls11207SF\$7.4Fill Structure with Fill1246CY\$25.Demolition of Chlorine Contact Chamber/Headworks4630SF\$4.5Fill Structure with Fill514CY\$25.Demolition of Sludge Drying Beds5Demo Remaining Concrete Structural Walls0SF\$4.6Fill Structure with Fill0CY\$25.Demolition of Sludge Pump Station0CY\$25.0Demo Remaining Concrete Structural Walls877SF\$7.7Fill Structure with Fill98CY\$25.	0 \$ 0 \$ 0 \$ 0 \$	9,150 34,403 12,750
1 Demo Remaining Concrete Structural Walls 2 Fill Structure with Fill 366 CY \$ 25. Demolition of Waste Sludge Holding Basin 2 Demo Remaining Concrete Structural Walls 3 Fill Structure with Fill 510 CY \$ 25. Demolition of Secondary Clarifier 3 Demo Remaining Concrete Structural Walls 4 Fill Structure with Fill 11207 SF \$ 7. 4 Fill Structure with Fill 1246 CY \$ 25. Demolition of Chlorine Contact Chamber/Headworks 4 Demo Remaining Concrete Structural Walls 5 Fill Structure with Fill 514 CY \$ 25. Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 6 Fill Structure with Fill 0 CY \$ 25. Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 6 Fill Structure with Fill 9 SF \$ 4. Fill Structure with Fill 9 SF \$ 7. Fill Structure with Fill 9 SF \$ 7. Fill Structure with Fill 98 CY \$ 25.	0 \$ 0 \$ 0 \$ 0 \$	9,150 34,403 12,750
2 Fill Structure with Fill Demolition of Waste Sludge Holding Basin 2 Demo Remaining Concrete Structural Walls 3 Fill Structure with Fill Demolition of Secondary Clarifier 3 Demo Remaining Concrete Structural Walls 4 Fill Structure with Fill Demolition of Chlorine Contact Chamber/Headworks 4 Demo Remaining Concrete Structural Walls 5 Fill Structure with Fill Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 6 Fill Structure with Fill Demolition of Sludge Pump Station 6 Demo Remaining Concrete Structural Walls 877 SF \$ 7.	0 \$ 0 \$ 0 \$ 0 \$	9,150 34,403 12,750
Demolition of Waste Sludge Holding Basin2Demo Remaining Concrete Structural Walls4587SF\$7.3Fill Structure with Fill510CY\$25.Demolition of Secondary Clarifier3Demo Remaining Concrete Structural Walls11207SF\$7.4Fill Structure with Fill1246CY\$25.Demolition of Chlorine Contact Chamber/Headworks4Demo Remaining Concrete Structural Walls4630SF\$4.5Fill Structure with Fill514CY\$25.Demolition of Sludge Drying Beds5Demo Remaining Concrete Structural Walls0SF\$4.6Fill Structure with Fill0CY\$25.Demolition of Sludge Pump Station6Demo Remaining Concrete Structural Walls877SF\$7.7Fill Structure with Fill98CY\$25.	0 \$	34,403 3 12,750
2 Demo Remaining Concrete Structural Walls 4587 SF \$ 7. 3 Fill Structure with Fill 510 CY \$ 25. Demolition of Secondary Clarifier 3 Demo Remaining Concrete Structural Walls 11207 SF \$ 7. 4 Fill Structure with Fill 1246 CY \$ 25. Demolition of Chlorine Contact Chamber/Headworks 4 Demo Remaining Concrete Structural Walls 4630 SF \$ 4. 5 Fill Structure with Fill 514 CY \$ 25. Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 0 SF \$ 4. 6 Fill Structure with Fill 0 CY \$ 25. Demolition of Sludge Pump Station 6 Demo Remaining Concrete Structural Walls 877 SF \$ 7. 7 Fill Structure with Fill 98 CY \$ 25.	0 \$	12,750
3 Fill Structure with Fill 510 CY \$ 25.0 Demolition of Secondary Clarifier 3 Demo Remaining Concrete Structural Walls 11207 SF \$ 7. 4 Fill Structure with Fill 1246 CY \$ 25.0 Demolition of Chlorine Contact Chamber/Headworks 4 Demo Remaining Concrete Structural Walls 4630 SF \$ 4.0 5 Fill Structure with Fill 514 CY \$ 25.0 Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 0 SF \$ 4.0 6 Fill Structure with Fill 0 CY \$ 25.0 Demolition of Sludge Pump Station 877 SF \$ 7.0 7 Fill Structure with Fill 98 CY \$ 25.0	0 \$	12,750
Demolition of Secondary Clarifier 3 Demo Remaining Concrete Structural Walls 11207 SF \$ 7.	0 \$,
3 Demo Remaining Concrete Structural Walls 4 Fill Structure with Fill 5 Demolition of Chlorine Contact Chamber/Headworks 4 Demo Remaining Concrete Structural Walls 5 Fill Structure with Fill 5 Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 6 Fill Structure with Fill 7 Demolition of Sludge Pump Station 6 Demo Remaining Concrete Structural Walls 7 Fill Structure with Fill 98 CY \$ 25.		
4 Fill Structure with Fill 1246 CY \$ 25. Demolition of Chlorine Contact Chamber/Headworks 4 Demo Remaining Concrete Structural Walls 4630 SF \$ 4. 5 Fill Structure with Fill 514 CY \$ 25. Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 0 SF \$ 4. 6 Fill Structure with Fill 0 CY \$ 25. Demolition of Sludge Pump Station 6 Demo Remaining Concrete Structural Walls 877 SF \$ 7. 7 Fill Structure with Fill 98 CY \$ 25.		
Demolition of Chlorine Contact Chamber/Headworks 4 Demo Remaining Concrete Structural Walls 4630 SF \$ 4. 5 Fill Structure with Fill 514 CY \$ 25. Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 0 SF \$ 4. 6 Fill Structure with Fill 0 CY \$ 25. Demolition of Sludge Pump Station 877 SF \$ 7. 6 Demo Remaining Concrete Structural Walls 877 SF \$ 7. 7 Fill Structure with Fill 98 CY \$ 25.	0 \$	
4 Demo Remaining Concrete Structural Walls 5 Fill Structure with Fill 5 Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 6 Fill Structure with Fill 7 Demolition of Sludge Pump Station 6 Demo Remaining Concrete Structural Walls 7 Fill Structure with Fill 98 CY \$ 25.		31,150
5 Fill Structure with Fill 514 CY \$ 25. Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 0 SF \$ 4. 6 Fill Structure with Fill 0 CY \$ 25. Demolition of Sludge Pump Station 6 Demo Remaining Concrete Structural Walls 877 SF \$ 7. 7 Fill Structure with Fill 98 CY \$ 25.		
Demolition of Sludge Drying Beds 5 Demo Remaining Concrete Structural Walls 0 SF \$ 4. 6 Fill Structure with Fill 0 CY \$ 25. Demolition of Sludge Pump Station 877 SF \$ 7. 7 Fill Structure with Fill 98 CY \$ 25.	- '	,
5 Demo Remaining Concrete Structural Walls 6 Fill Structure with Fill 0 CY \$ 25. Demolition of Sludge Pump Station 6 Demo Remaining Concrete Structural Walls 7 Fill Structure with Fill 98 CY \$ 25.	0 \$	12,850
6 Fill Structure with Fill 0 CY \$ 25. Demolition of Sludge Pump Station 6 Demo Remaining Concrete Structural Walls 877 SF \$ 7. 7 Fill Structure with Fill 98 CY \$ 25.		
Demolition of Sludge Pump Station 877 SF 7. 7 Fill Structure with Fill 98 CY \$ 25.	0 \$	-
6 Demo Remaining Concrete Structural Walls 877 SF \$ 7. 7 Fill Structure with Fill 98 CY \$ 25.	0 \$	-
7 Fill Structure with Fill 98 CY \$ 25.		
	0 \$	6,578
Demolition of Influent Pump Station	0 \$	2,450
7 Demo Remaining Concrete Structural Walls 629 SF \$ 7.	0 \$	4,718
8 Fill Structure with Fill 70 CY \$ 25.	0 \$	1,750
SUBTOTAL	\$	231,546
CONTINGENCY 15%	\$	34,732
SUBTOTAL	\$	266,278
MOBILIZATION 5%	\$	13,314
SUBTOTAL	\$	279,592
OH&P 18%	\$	50,327

PROJECT TOTAL (2021 COSTS)

329,918

Ś

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

- 1 FNI OPCC classified as an AACE Class 4 Estimate with accuracy range or -20 to + 30.
- 2 FNI OPCC does not include costs associated with engineering fees, permits, surveying, etc.



Innovative approaches
Practical results
Outstanding service

PROJECT NAME	Wylie WWTP Demolition	DATE	9/8/2021
CLIENT	NTMWD	GROUP	1153
% SUBMITTAL	Conceptual	PM	Clayton Barnard

ESTIMATED BY	QC CHECKED BY	FNI PROJECT NUMBER
		WLE20563

ITEM	DESCRIPTION	QUANTITY	UNIT		UNIT PRICE		TOTAL
		· ·		•			
Demolit	ion of Wylie WWTP - Option 3		1			ı	
	Demolition of Aeration Basin						
1	Remove Existing Mechanical Equipment	1	LS	\$	15,000.00		15,000
2	Demo Concrete Structural Walls to 2' Below Grade	6531	SF	\$	4.00		26,124
3	Fill Structure with Fill	6485	CY	\$	25.00	\$	162,125
	Demolition of Waste Sludge Holding Basin						
4	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00		5,000
5	Demo Concrete Structural Walls to 2' Below Grade	571	SF	\$	7.50	\$	4,283
6	Fill Structure with Fill	1075	CY	\$	25.00	\$	26,875
	Demolition of Secondary Clarifier						
7	Remove Existing Mechanical Equipment	1	LS	\$	10,000.00	\$	10,000
8	Demo Concrete Structural Walls to 2' Below Grade	1885	SF	\$	7.50	\$	14,138
9	Fill Structure with Fill	3686	CY	\$	25.00	\$	92,150
	Demolition of Chlorine Contact Chamber/Headworks						
10	Remove Existing Mechanical Equipment	1	LS	\$	7,500.00	\$	7,500
11	Demo Concrete Structural Walls to 2' Below Grade	800	SF	\$	4.00		3,200
12	Fill Structure with Fill	592	CY	\$	25.00	-	14,800
12	i iii Structure with i iii	332	Ci	7	23.00	7	14,000
	Demolition of Sludge Drying Beds						
13	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00		5,000
14	Demo Concrete Structural Walls to 2' Below Grade	11687	SF	\$	4.00	\$	46,748
15	Fill Structure with Fill	1200	CY	\$	25.00	\$	30,000
	Demolition of Sludge Pump Station						
16	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
17	Demo Concrete Structural Walls to 2' Below Grade	680	SF	\$	7.50	\$	5,100
18	Fill Structure with Fill	151	CY	\$	25.00		3,775
	Demolition of Influent Pump Station						
19	Remove Existing Mechanical Equipment	1	LS	\$	10,000.00	\$	10,000
20	Demo Concrete Structural Walls to 2' Below Grade	84	SF	\$	7.50		630
21	Fill Structure with Fill	64	CY	\$	25.00	\$	1,600
	Demolition of Blower Facility						
22	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
23	Demo Structure	480	SF	\$	7.50		3,600
24	Demo Slab	480	SF	\$	7.50		3,600
	Demolition of Chlorine Storage Facility						

25	Remove Existing Mechanical Equipment	1	LS	\$ 1,500.00	\$ 1,500
26	Demo Structure	288	SF	\$ 7.50	\$ 2,160
27	Demo Slab	288	SF	\$ 7.50	\$ 2,160
	Bioxide Feed Chemical Containment				
28	Fiberglass Containment w/ Concrete Slab	400	SF	\$ 25.00	\$ 10,000
29	Chemical Injection Assembly	1	LS	\$ 65,000.00	\$ 65,000
30	Electrical Power Service	1	LS	\$ 25,000.00	\$ 25,000
	Muddy Creek Interceptor Relocation				
31	Remove Existing Manholes	4	EA	\$ 1,500.00	\$ 6,000
32	Remove Existing Interceptor Lines	791	LF	\$ 10.00	\$ 7,910
33	30-Inch Interceptor	430	LF	\$ 250.00	\$ 107,500
34	5-Foot Diameter Manhole	4	EA	\$ 30,000.00	\$ 120,000

SUBTOTAL		\$ 848,477
CONTINGENCY	15%	\$ 127,272
SUBTOTAL		\$ 975,749
MOBILIZATION	5%	\$ 48,787
SUBTOTAL		\$ 1,024,536
OH&P	18%	\$ 184,416

PROJECT TOTAL (2021 COSTS)

1,208,952

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

- 1 FNI OPCC classified as an AACE Class 4 Estimate with accuracy range or -20 to + 30.
- 2 FNI OPCC does not include costs associated with engineering fees, permits, surveying, etc.



Innovative approaches
Practical results
Outstanding service

PROJECT NAME	Wylie WWTP Demolition	DATE	9/8/2021
CLIENT	NTMWD	GROUP	1153
% SUBMITTAL	Conceptual	PM	Clayton Barnard

ESTIMATED BY	QC CHECKED BY	FNI PROJECT NUMBER
		WLE20563

ITEM	DESCRIPTION	QUANTITY	UNIT	Į	UNIT PRICE		TOTAL
Demolit	ion of Wylie WWTP - Option 4						
Demone	Demolition of Aeration Basin						
1	Remove Existing Mechanical Equipment	1	LS	\$	15,000.00	\$	15,000
2	Demo Concrete Structural Walls to 2' Below Grade	6421	SF	\$	4.00	\$	25,684
3	Fill Structure with Fill	6485	CY	\$	25.00	\$	162,125
		3,00		т.		т	
	Demolition of Waste Sludge Holding Basin						
4	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
5	Demo Concrete Structural Walls to 2' Below Grade	571	SF	\$	7.50	\$	4,283
6	Fill Structure with Fill	1075	CY	\$	25.00	\$	26,875
	Demolition of Secondary Clarifier						
7	Remove Existing Mechanical Equipment	1	LS	\$	10,000.00	\$	10,000
8	Demo Concrete Structural Walls to 2' Below Grade	1885	SF	\$	7.50	\$	14,138
9	Fill Structure with Fill	3686	CY	\$	25.00	\$	92,150
- 10	Demolition of Chlorine Contact Chamber/Headworks		1.0		7.500.00	•	7.500
10	Remove Existing Mechanical Equipment	1	LS	\$	7,500.00	\$	7,500
11	Demo Concrete Structural Walls to 2' Below Grade	800	SF	\$	4.00	\$	3,200
12	Fill Structure with Fill	592	CY	\$	25.00	\$	14,800
	Demolition of Sludge Drying Beds						
13	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
14	Demo Concrete Structural Walls to 2' Below Grade	11687	SF	\$	4.00	\$	46,748
15	Fill Structure with Fill	1200	CY	\$	25.00	\$	30,000
	Demolition of Sludge Pump Station						
16	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
17	Demo Concrete Structural Walls to 2' Below Grade	680	SF	\$	7.50	\$	5,100
18	Fill Structure with Fill	151	CY	\$	25.00	\$	3,775
	Demolition of Influent Pump Station						
19	Remove Existing Mechanical Equipment	1	LS	\$	10,000.00	\$	10,000
20	Demo Concrete Structural Walls to 2' Below Grade	84	SF	\$	7.50	\$	630
21	Fill Structure with Fill	64	CY	\$	25.00	\$	1,600
	Demolition of Blower Facility						
22	Remove Existing Mechanical Equipment	1	LS	\$	5,000.00	\$	5,000
23	Demo Structure	480	SF	\$	7.50	\$	3,600
24	Demo Slab	480	SF	\$	7.50	\$	3,600
	Demolition of Chlorine Storage Facility			<u> </u>			
25	Remove Existing Mechanical Equipment	1	LS	\$	1,500.00	\$	1,500

26	Demo Structure	288	SF	\$ 7.50	\$ 2,160
27	Demo Slab	288	SF	\$ 7.50	\$ 2,160
	Bioxide Feed Chemical Containment				
28	Fiberglass Containment w/ Concrete Slab	400	SF	\$ 25.00	\$ 10,000
29	Chemical Injection Assembly	1	LS	\$ 65,000.00	\$ 65,000
30	Electrical Power Service	1	LS	\$ 25,000.00	\$ 25,000
	Muddy Creek Interceptor Relocation				
31	Remove Existing Manholes	4	EA	\$ 1,500.00	\$ 6,000
32	Remove Existing Interceptor Lines	791	LF	\$ 10.00	\$ 7,910
33	30-Inch Interceptor	430	LF	\$ 250.00	\$ 107,500
34	5-Foot Diameter Manhole	4	EA	\$ 30,000.00	\$ 120,000
	ALKAGEN FILL STATION				
35	Fill Station and Control Panel Pad	1	LS	\$ 10,500.00	\$ 10,500
36	Chemical Feed Line	70	LF	\$ 400.00	\$ 28,000
	PAVING				
37	Concrete Pavement	681	SY	\$ 95.00	\$ 64,695

SUBTOTAL		\$ 951,232
CONTINGENCY	15%	\$ 142,685
SUBTOTAL		\$ 1,093,917
MOBILIZATION	5%	\$ 54,696
SUBTOTAL		\$ 1,148,613
OH&P	18%	\$ 206,750

PROJECT TOTAL (2021 COSTS)

1,355,363

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

- 1 FNI OPCC classified as an AACE Class 4 Estimate with accuracy range or -20 to + 30.
- 2 FNI OPCC does not include costs associated with engineering fees, permits, surveying, etc.



Innovative approaches
Practical results
Outstanding service

PROJECT NAME	Wylie WWTP Demolition	DATE	9/8/2021
CLIENT	NTMWD	GROUP	1153
% SUBMITTAL	Conceptual	PM	Clayton Barnard

ESTIMATED BY	QC CHECKED BY	FNI PROJECT NUMBER
		WLE20563

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
Demolit	ion of Wylie WWTP - Option 5				
1	Demolition of Aeration Basin				
2	Remove Existing Mechanical Equipment	1	LS	\$ 15,000.00	\$ 15,000
3	Demo Concrete Structural Walls to 2' Below Grade	6421	SF	\$ 4.00	\$ 25,684
4	Fill Structure with Fill	6485	CY	\$ 25.00	\$ 162,125
5					
6	Demolition of Waste Sludge Holding Basin				
7	Remove Existing Mechanical Equipment	1	LS	\$ 5,000.00	\$ 5,000
8	Demo Concrete Structural Walls to 2' Below Grade	571	SF	\$ 7.50	\$ 4,283
9	Fill Structure with Fill	1075	CY	\$ 25.00	\$ 26,875
10					
11	Demolition of Secondary Clarifier				
12	Remove Existing Mechanical Equipment	1	LS	\$ 10,000.00	\$ 10,000
13	Demo Concrete Structural Walls to 2' Below Grade	1885	SF	\$ 7.50	\$ 14,138
14	Fill Structure with Fill	3686	CY	\$ 25.00	\$ 92,150
15					
16	Demolition of Chlorine Contact Chamber/Headworks				
17	Remove Existing Mechanical Equipment	1	LS	\$ 7,500.00	\$ 7,500
18	Demo Concrete Structural Walls to 2' Below Grade	800	SF	\$ 4.00	\$ 3,200
19	Fill Structure with Fill	592	CY	\$ 25.00	\$ 14,800
20					
21	Demolition of Sludge Drying Beds				
22	Remove Existing Mechanical Equipment	1	LS	\$ 5,000.00	\$ 5,000
23	Demo Concrete Structural Walls to 2' Below Grade	11687	SF	\$ 4.00	\$ 46,748
24	Fill Structure with Fill	1200	CY	\$ 25.00	\$ 30,000
25					
26	Demolition of Sludge Pump Station				
27	Remove Existing Mechanical Equipment	1	LS	\$ 5,000.00	\$ 5,000
28	Demo Concrete Structural Walls to 2' Below Grade	680	SF	\$ 7.50	\$ 5,100
29	Fill Structure with Fill	151	CY	\$ 25.00	\$ 3,775
30					
31	Demolition of Influent Pump Station				
32	Remove Existing Mechanical Equipment	1	LS	\$ 10,000.00	\$ 10,000
33	Demo Concrete Structural Walls to 2' Below Grade	84	SF	\$ 7.50	\$ 630
34	Fill Structure with Fill	64	CY	\$ 25.00	\$ 1,600
35					
36	Demolition of Blower Facility				
37	Remove Existing Mechanical Equipment	1	LS	\$ 5,000.00	\$ 5,000
38	Demo Structure	480	SF	\$ 7.50	\$ 3,600
39	Demo Slab	480	SF	\$ 7.50	\$ 3,600
40					
41	Demolition of Chlorine Storage Facility				
42	Remove Existing Mechanical Equipment	1	LS	\$ 1,500.00	\$ 1,500

43	Demo Structure	288	SF	\$ 7.50	\$	2,160
44	Demo Slab	288	SF	\$ 7.50	\$	2,160
45						
46	Bioxide Feed Chemical Containment					
47	Fiberglass Containment w/ Concrete Slab	400	SF	\$ 25.00	\$	10,000
48	Chemical Injection Assembly	1	LS	\$ 65,000.00	\$	65,000
49	Electrical Power Service	1	LS	\$ 25,000.00	\$	25,000
50						
51	Muddy Creek Interceptor Relocation					
52	Remove Existing Manholes	4	EA	\$ 1,500.00	\$	6,000
53	Remove Existing Interceptor Lines	791	LF	\$ 10.00	\$	7,910
54	30-Inch Interceptor	430	LF	\$ 250.00	\$	107,500
55	5-Foot Diameter Manhole	4	EA	\$ 30,000.00	\$	120,000
56	ALKAGEN FILL STATION					
57	Fill Station and Control Panel Pad	1	LS	\$ 10,500.00	\$	10,500
58	PAVING					
59	Concrete Pavement	1250	SY	\$ 95.00	\$	118,750
		CLIDTOTAL			Ċ	077 207

SUBTOTAL		\$ 977,287
CONTINGENCY	15%	\$ 146,593
SUBTOTAL		\$ 1,123,880
MOBILIZATION	5%	\$ 56,194
SUBTOTAL		\$ 1,180,074
OH&P	18%	\$ 212,413

PROJECT TOTAL (2021 COSTS)

1,392,487

\$

The Engineer has no control over the cost of labor, materials, equipment, or over the Contractor's methods of determining prices or over competitive bidding or market conditions. Opinions of probable costs provided herein are based on the information known to Engineer at this time and represent only the Engineer's judgment as a design professional familiar with the construction industry. The Engineer cannot and does not guarantee that proposals, bids, or actual construction costs will not vary from its opinions of probable costs.

- 1 FNI OPCC classified as an AACE Class 4 Estimate with accuracy range or -20 to + 30.
- ${\bf 2} \ \ {\bf FNI} \ \ {\bf OPCC} \ does \ not \ include \ costs \ associated \ with \ engineering \ fees, \ permits, \ surveying, \ etc.$