



Proposal to City of Youngsville La for Abutment Repair on Walk Bridge at Recreation Sports Complex

To: City of Youngsville
Tim Robichaux
Youngsville La 70592

9/1/2024

Durable Piling Restoration, LLC is pleased to propose Repairs on Abutment Wall on walkway bridge at the Sports Complex

Scope of work:

- Add 3"x12"x30' Abutment boards and wing walls at end of walkway near building
- Remove existing concrete and handrails
- Remove existing material and replace with fabric and 6-10 stone
- Replace concrete approximately 4"x 21'x30' from existing concrete to bridge to wingwalls sloping toward water

Durable Piling to supply the following items:

All materials, equipment and labor as needed for repairs

City of Youngsville shall supply

Closing of Bridge and traffic control during construction

Access to work site

Dumpster trailer or dump truck for disposal and hauling off of existing materials

Tax exemption certificate

Total Cost, \$46,680.00

Note; Durable shall remove existing rail with caution

Railing may have to be repaired with new material should existing materials not Remain usable

Price does not include Bonding

Respectfully submitted,
Peter DeCuir President
Durable Piling Restoration, LLC
318 305 7751 peter@durablepiling.com

ACCEPTED BY _____

NAME _____

TITLE _____