

City of Youngsville

P.O. Box 592

305 Iberia Street

Youngsville, LA 70592

(337) 856-4181 * Fax (337) 856-8863

City Engineer: 337-573-4488

MAYOR Ken Ritter

CHIEF ADMINISTRATIVE OFFICER Sally M. Angers

CITY CLERK Nicole Guidry

CITY ENGINEER Clint Simoneaux

August 3, 2022

Honorable Ken Ritter Mayor City of Youngsville P.O. Box 592 Youngsville, LA 70592

Subject: Foster Grove Preliminary Plat Review

Dear Mayor Ritter:

The above referenced preliminary plat has been submitted and reviewed for general compliance with the requirements for development in the City of Youngsville.

I recommend the City of Youngsville to approve this Preliminary Plat with the following comments.

SPECIFIC PLAT REVISIONS

- A. I recommend no waivers to the revisions included in the ADRC Report.
- B. Legal description does not match the plat.
- C. Setbacks for Multifamily low density developments are 20' on all sides of the development.
- D. Add note: A perimeter fence is required where a development fronts a public street, park, or other public property.
- E. Add a note: Sidewalks are required along all city streets.

PLAT/SUBDIVISION CONDITIONS

- 1. I recommend waivers to condition #5 & 15 in the ADRC report and replace with Youngsville's ordinances.
- 2. I recommend no waivers to the remaining conditions included in the ADRC Report.
- 3. Per ordinance, where development fronts a public park a perimeter fence is required. A perimeter fence is to be at minimum 6' high with brick or stucco columns every **50 feet.**

The City of Youngsville is an Equal Opportunity Employer <u>info@youngsvillela.gov</u> www.youngsville.us **CITY COUNCIL**

Kayla Menard Reaux Lindy Bolgiano Matt Romero Kenneth Stansbury Shannon Bares

- 4. Each dwelling is to have an attached enclosed garage.
- 5. 4 unique floor plans are required per development with at least 2 unique floor plans per multiple-unit building. Mirrored floor plans do not constitute a unique floor plan.
- 6. Where a multi-story dwelling is adjacent to a single-family residential dwelling, Bahama/Bermuda shutters are required on the windows located on the second and third story.
- 7. The developer is reminded that heritage live oak trees are protected under ordinance 120-7.
 - a) A permit for removal of a heritage live oak trees should only be granted as a last resort when all other efforts to save the tree(s) by redesign of building placement and site plans have failed.
 - b) The city is empowered to issue or deny the permit, within 30 days of the date of the application, based upon review of the condition of the heritage live oak tree, location, site conditions and any additional supportive materials required to be submitted as part of the application.
 - c) Any heritage live oak tree that is removed in accordance with this section shall be replaced with an equal number of inches of live oak tree.
- 8. The developer is reminded that all newly constructed homes must be elevated 18" above the center line of the road or 1' above the BFE, whichever is higher.
- 9. The review of this Preliminary Plat is for general conformance with overall development requirements. The developer must submit detailed engineering plans for review and approval by the appropriate authority prior to construction. It is the responsibility of the developer and/or the developer's engineer to notify, coordinate, and ultimately adjudicate any review comments to the satisfaction of the appropriate authority. This would include any individual permits that may be required for construction activities.
- 10. Approval of the Preliminary Plat does not imply that utility services necessary to serve the development currently exist, or if they do exist have the capacity to serve the planned development. Any such evaluation and determination would take place by the respective utility during the detailed review of the engineering plans.
- 11. If desired in the future, the owner/developer is responsible for any required sewer infrastructure to convey sewer from the development to the City of Youngsville Sanitary Sewer Treatment Plant or the nearest location with available capacity as determined by the City. The available capacity of the sewer system at the point of discharge from the development into the City sewer system shall be evaluated by the City Engineer during the detailed review of engineering plans. The City reserves the right to require the developer to contribute funds towards the upgrade of existing lift station(s) and collection lines that may result from the addition of the development's sewage discharge to the overall system.
- 12. If desired in the future, the owner/developer shall utilize the City water system as the source of water for the development. The available capacity of the existing water system in the area relative to the proposed development's consumption of City water shall be evaluated during the detailed review of engineering plans. The City reserves the right to require the owner/developer to contribute funds towards the City's water distribution system to provide the requested water services to the development.

- 13. Submittal of a drainage impact analysis shall be submitted to the City for review and approval prior to construction. Please note that this subdivision is subject to the 25-year detention requirements.
- 14. All signage shall conform to the City Sign Ordinance. The proposed signage will be evaluated when the required sign permit application is submitted for review.
- 15. Any changes to the Preliminary Plat made after this initial review may require a resubmittal of the Preliminary Plat.
- 16. The owner/developer is reminded that the final design and all construction activities associated with the development of this plat, including required submittals and permits, must comply with the applicable City Ordinances in effect at the time of submittal and the City's Residential Design Development and Resource Guide.
- 17. The Developer is reminded that inspection services are required in the most recent Unified Development Code.
- 18. The Developer is reminded that this letter does not permit the initiation of construction activities.
- 19. The construction plans submitted for detailed review should be a complete set of plans including the: Overall Plan, Preliminary Plat, Grading Plan, Streets Design, Water/Sewer Design, Stormwater Design, and Erosion Control Plan. Plans submitted lacking sufficient detail to enable a detailed review will be returned without being reviewed.
- 20. Additional easements may be required for this development. This will be evaluated during the review of the actual development construction plans.

If you have any questions or need additional information about this, please contact me.

Thanks,

Clint Simonean

Clint Simoneaux, P.E.

City Engineer

cc: Nicole Guidry, City Clerk Christian Armstrong, PLS